

Switchcraft

ENGINEERING DESIGN GUIDE
4th Edition



JACKS & PLUGS



JACK PANELS



PATCH CORDS & MOLDED CABLE ASSEMBLIES



Switchcraft

ABOUT SWITCHCRAFT, INC.

Switchcraft, Inc. was established in 1946 to manufacture jacks, plugs and switches, from its original plant located on West Diversey Street in Chicago. The company moved to a larger facility at 1328 North Halsted Street in 1948, and in 1958, the operation moved to 5555 North Elston Avenue, which is still the headquarters of the corporation.

Switchcraft is a leading supplier of a broad line of components for the audio/video, broadcast, telecommunication, computer, medical, military, appliance, transportation and instrumentation industries.

In the 185,000-square-foot Chicago facility, Switchcraft manufactures electronic and elecromechanical components, including:

- Jacks
- Connectors
- Patch Panels
- Switches
- Molded Cable Assemblies
- Plugs
- Jackfields
- Patch Cords
- Patch Cords
- EAC Power Receptacles

With a basic line of over 5,000 standard products and thousands of variations, Switchcraft is proud to offer a limited lifetime warranty on all products.

Switchcraft markets products both domestically and internationally through a network of manufacturers' representatives and independent distributors.

In 1999, Switchcraft acquired the Conxall Corporation located in Villa Park, Illinois. Conxall was founded in 1971 as a manufacturer of sealed connectors for the marine industry. Today, the company offers a broad line of custom cable assemblies and connectors used in marine, industrial, sensor, communications and transportation applications. For more information contact Conxall at (630) 834-7504, or visit their website at www.conxall.com.

LIMITED LIFETIME WARRANTY

Switchcraft warrants all of its products to be of sound design, good materials and workmanship at the time of manufacture.

Switchcraft will repair or replace at its discretion any product proven to be defective under normal use.

Switchcraft's liabilty under the terms of this warranty is limited to the repair or replacement of defective products which have not been damaged through accident, abuse, misuse or unauthorized repair. Switchcraft shall in no case be liable for special or consequential damages of any nature.

CATALOG SECTIONS

| Connectors | 1-70 |
|-----------------|---------|
| Jacks & Plugs | 79-162 |
| Jack Panels | 163-238 |
| Patch Cords and | |
| Molded Cable | |
| Assemblies | 239-268 |
| | |

Switches 269-318

Index by Part Number . . . 319-328

Swifeherafi

Visit us on the net: www.switchcraft.com

| CONNECTORS AND RECEPTACLES | SL18 Male/Female Receptacles64 | | | |
|--|---|--|--|--|
| Q-G® XLR CONNECTORS1-30 | CB CONNECTORS MICROPHONE CONNECTORS, | | | |
| Q-G® Connector Part Numbering System2 | MINI-CON MINIATURE CONNECTORS65 | | | |
| Professional Series Q-G® Connector Part Numbering System2 | | | | |
| Q-G® Audio Connectors A, AA, AND QGP Series3-4 | HP75BNC SERIES BNC CONNECTORS66-67 | | | |
| Part Numbers - Male Cord Plugs/Female Cord Plugs4 | | | | |
| Q-G® Color Flex Reliefs/Flex Relief5 | EAC RECEPTACLES68-77 | | | |
| AAA XLR Connectors6-7 | | | | |
| P(*)M Gooseneck Plug, P(*)F Microphone Plug, | RAPC322 POWER INLET SOCKET78 | | | |
| R(*)MZ Cord Plug, R(*)FZ Cord Plug8 | | | | |
| D(*)M, D(*)F and D(*)FD Receptacles9 | | | | |
| T(*)F and T(*)FM Cord Plug With On-Off Switch9 | | | | |
| B(*)F Receptacle, C(*)F Receptacle, B(*)M Receptacle, | TACKS AND DITIOS | | | |
| C(*)M Receptacle10 | JACKS AND PLUGS | | | |
| E Series Receptacles | | | | |
| EH Series Receptacles | JACK SCHEMATICS79-80 | | | |
| | | | | |
| PQG® Receptacles17-18 PD Series - Plastic Panel Mount19-21 | 1/4" LONG FRAME TELEPHONE JACKS81-85 | | | |
| | 1/4" Jack Blocks86 | | | |
| Y3F, Y3FPC, Y3FDPC and Y3MPC Receptacles | | | | |
| F Series Receptacles | BANTAM TYPE® JACKS87-90 | | | |
| Q-G® Adapters, Accessories | TT-JAX® (.173") Telephone Jacks Bantam Type®87-88 | | | |
| Q-G® Wall Plate Receptacles | TT-JAX® (.173") Telephone Twin Jacks Bantam Type®89 | | | |
| Q-G® Connector-Adapters27-28 | TT-JAX® (.173") Telephone Triple Jacks Bantam Type®90 | | | |
| S*FM Audio Connector-Adapter | RTT Series Miniature Telephone Jacks, | | | |
| Audio "Y" Adapters | Right Angle, PC Mount91-92 | | | |
| DMX Adapter29 | .177" Enclosed Jacks93 | | | |
| Q-G® Connector-Adapter Receptacles | | | | |
| Z Matching Transformers, Series M(*)M, Series L(*)MN30 | LITTEL JAX® 2- AND 3-CONDUCTOR, | | | |
| TIN II O CO LIN II I TUDE CON II ECTORO | 1/4" PHONE JACKS94-109 | | | |
| TINI Q-G® MINIATURE CONNECTORS31-37 | Hi-D Jax® 2- and 3-Conductor96-99 | | | |
| Tini Q-G® Audio Adapters31 | Spring Lock PC Terminals for Hi-D Jax®100 | | | |
| TB(*)M AND TB(*)MB Receptacle, TLP(*) Looping Plug, Straight | SN Series, RA Series Right-Angle Phone Jacks101-105 | | | |
| Female Looping Plug, Reverse Gender TQG Series33 | 500 Series Jack Covers106 | | | |
| TRA(*)M PC Mount Male Receptacle34 | Series E (Locking) and Thick Panel Phone Jacks107 | | | |
| TRASM*M, TRAPC*M Series34-36 | 1/4" Extension Jacks and 1/4" Speaker Jacks108 | | | |
| TY(*)F and TY(*)FPC Receptacles,TYEF Escutcheons, | 1/4" Shielded Phone Jacks, SF-Jax® | | | |
| TQG(*)F and TQG(*)M Connector Inserts, TBA(**) | Short Frame Jacks109 | | | |
| Audio Adapter37 | | | | |
| | .141" MINIATURE PHONO JACKS109-111 | | | |
| HPC HIGH POWER AUDIO CONNECTORS38-40 | | | | |
| | 3.5MM DUAL STEREO JACK112-113 | | | |
| EN3TMini WEATHERTIGHT CONNECTOR SERIES41-45 | | | | |
| 2 - 8 pin Cord Connector, 9 - 18 pin Cord Connector | 3.5MM SINGLE MONO AND STEREO JACKS114-118 | | | |
| 2 - 8 pin Panel Connector, 9 - 18 pin Panel Connector44 | | | | |
| 2 - 8 pin Inline Connector, 2 - 8 pin Overmolded Cord | 3.5MM SINGLE MONO JACKS119 | | | |
| and Inline Connector45 | | | | |
| | 2.5MM SINGLE MONO AND STEREO JACKS120 | | | |
| DIN CONNECTORS46-55 | | | | |
| Plugs46-48 | .101" SUBMINIATURE PHONE JACKS121-122 | | | |
| Panel Mount Receptacles48-50 | | | | |
| Right Angle PC Mount Receptacles51-52 | RCA PHONO JACKS AND PHONO JACK SETS123-129 | | | |
| Mini-DIN Right-Angle Receptacles, Right-Angle, PC Mount | NOTT HONG WHO THE FINANCE OF OUT OF THE HEALTH IN 120 120 | | | |
| Receptacles47-53 | RIGHT ANGLE MINIATURE POWER JACKS130-133 | | | |
| SMD Series54 | MOTH ANGLE MINIATORE FOWER GAGRO100-100 | | | |
| DMD Series55 | STRAIGHT MINIATURE POWER JACKS134-135 | | | |
| | STRAIGHT WIINIATURE POWER JACKS154-155 | | | |
| USB CONNECTORS56-57 | VJ SERIES VIDEO JACKS136 | | | |
| | VO GENTEO VIDEO GAGNO100 | | | |
| IEEE 1394 FIREWIRE CONNECTORS58-59 | MVJ SERIES VIDEO JACKS137 | | | |
| 0.044.05 | 107 | | | |
| SLIM-LINE CONNECTORS60-64 | MIL-TYPE 1/4" PHONE PLUGS138-141 | | | |
| Cord Plugs60 | Littel Plug® Phone Plugs139 | | | |
| Slim-Line Connector Part Numbering System, Cable Clamp and | 100 | | | |
| Strain Relief | MIL-TYPE 1/4" EXTENSION JACKS142 | | | |
| SL40-SL41 Male/Female Cord Plugs | | | | |
| SL10-SL17 Male/Female Receptacles63 | | | | |

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information


| TELEPHONE PATCH ADAPTERS | 142 | TT5202000, TT5502000, TT560200021 | 7-218 |
|---|-----------|--|--------|
| | | TT-Jax® (.173") Twin Row and Three Row Jack Panels21 | 9-220 |
| BANTAM TYPE MINIATURE TELEPHONE PLUGS | 143-144 | TT-Jax® (.173") Connectorized Jackfields - Series TT, | |
| | | 2-wire, 4-wire, 6-wire22 | |
| 1/4" COMMERCIAL PHONE PLUGS - | | TT® Lamps and Jewel Assemblies | |
| LITTEL-PLUG® PLUGS | | Longframe Switchboard Switches | |
| Silent-Plug And Lug® Phone Plugs | 148 | Dummy Plugs and Hole Plugs | |
| Audio Loudspeaker and Heavy Duty 1/4" | | TT® (Bantam) Circuit Guard Plugs | |
| Commercial Phone Plugs | 149-150 | Miniature, Dummy Plugs, Hole Plugs | |
| .206" Commercial Phone Plugs | 151 | Designation Strips23 | |
| 1/4" Miti-Plug® Audio Plugs | 152 | Kwik-Change® Designation Strips (Double Height) | 237 |
| 1/4" Flat Plug Phone Plugs | 153 | X-Wide® Vertical Designation Strips | 238 |
| Right-Angle Phone Plugs | 154 | | |
| 1/4" Lock-Extension Jacks And Plugs | | PATCH CORDS AND | |
| | | MOLDED CABLE ASSEMBLIES | |
| 3.5MM HEAVY DUTY STEREO PLUGS | 156 | MOLDED GABLE AGGLMBLILG | |
| | | MOLDED CABLE ASSEMBLIES23 | 0 261 |
| .141" MINIATURE PHONE PLUGS | 157 | Design Materials and Features | |
| | | 3.5MM Molded Cables | |
| .097" SUBMINIATURE PHONE PLUGS | 158 | Power-Plug Battery Charger Plugs and Jacks | |
| | | | |
| AUDIO ADAPTERS | 159 | Power Plugs and Jacks Part Numbering System | |
| | | EN3T MINI Weathertight Overmolded Cable Assemblies Cordette® and Cord Switch Assemblies | |
| RCA PHONO PLUGS | 160-161 | | |
| 1.07.17.101.10.7.20.00 | | Cordette® Switches | |
| MINIATURE POWER PLUGS | 162 | DIN Plugs24 | |
| WINNIATORE TOWERT EGGG | 102 | MIDI Cables | |
| | | Miniature, Shielded, Molded Tini Q-G® Plugs | 250 |
| | | Molded Cable Assemblies for Multi-Pin Interconnection | 054 |
| JACK PANELS, PATCH PANELS, PATCH | KITS AND | Part Numbering System | |
| JACKFIELDS | | Standard Multi-Pin Interconnection Cables | |
| | | Micro Plug® Subminiature Phone Plugs | |
| AUDIO PATCHBAYS | 163-190 | Tini Plug® Miniature Phone Plugs | |
| Professional Punchdown Terminal (PPT) | | Phono Plugs and Phono Extension Jacks | |
| Front Access MTPFA/TTPFA Series | | Tini-Extension® Jacks | |
| MTP48K Wired Audio Series | | Littel Plug® Phone Plugs25 | 6-257 |
| | | Extension Jax® Phone Jacks | 257 |
| TTP96K Wired Audio Series | | Cable Clamp Bands, "Y" Junctions | 258 |
| MTPH/TTPH Harness Audio Series | | Part Numbering System | 259 |
| MTPBP/TTPBP Backpanel Series | | Standard Cable Guide | 260 |
| EZ NORM Patchbay Series | | Cross Reference Guide | 261 |
| TT96 EDAC Series | | | |
| TTP96K Patchkit Series | | | |
| MT48K/MT52K Patchkit Series | | AUDIO/VIDEO PATCHCORDS262 | 2- 267 |
| MT48/MT52 Patchbay Series | | 1/4" Longframe Telephone Patch Cords, MIL Type 1/4" Patch | |
| TTP96AS Patchbay Series | | Cords | |
| Q-G®XLR Patchbay Series | | Combination Patch Cords and MIL Type | 0_ |
| HPC Patchbay Series | 190 | 1/4" Twin Patch Cords | 263 |
| | | Miniature TT® Braided Patch Cords | |
| RS 422 DATA PATCHBAY SERIES | 191-192 | Miniature TT® Molded Patch Cords | 207 |
| | | and Telephone Couplers | 265 |
| VIDEO PATCHBAYS | 193-201 | | |
| VPP Video Patchbay Series | | Video Patch Cords | 200 |
| MVP Midsize Video Patchbay Series | | Broadcast Series 3-Conductor Bantam TT Patch Cords, | 00= |
| VAP Video/Audio Patchbay Series | | Analog-AES/EBU Audio, and RS422 Patching | 267 |
| MBPK Video/Audio Patchbay Series | | | |
| WBI It video/riddio i diolibay corice | 201 | | |
| TELECOM TYPE JACK PANELS | 202-238 | SWITCHES | |
| | | | |
| Long Frame (1/4") Single Row Telephone Jack Panel | | PUSHBUTTON SWITCHES | |
| Long Frame (1/4") Twin Row Jack Panels | | IBS Series Miniature Keyboard Switches | 269 |
| Long Frame (1/4") Modular Twin Row Jack Panels | | IBS Keyboard Switch Pushbuttons | |
| Long Frame (1/4") Modular 3 Row Jack Panels | 210 | US Series Uniswitch® Switches | |
| TT-Jax® (.173") Jack Panel Series 1600, A1600, | = | BXR Series Box Switch® Switches | |
| B1600, C1600 | 211-214 | Button-Switch® Switches, Tini-Switch® Switches | |
| Modular TT-JAX® (.173") Panels - | | Littel-Switch® Switches | |
| Blank Series TT51, TT53, TT56, TT59 | | Hi-D Switch® PC Mount Switches, DA-Switch Switches | |
| TT Module Inserts - Series TT91, TT92 And TT93. | | Cord-Switch® Cord Switches, Cordette® Cord Switches | |
| Modular TT-Jax® (.173") Jack Panels -Series TT510 |)2000, | Cora-Switches Cora Switches, Coraettee Cora Switches | 210 |

| Push-Lite® Switches and Indicators Series PL9000 - PL® Indicators, Pushbutton/Indic Screens, Color Filter Snap-Insserts, Optional | |
|---|---|
| Mounting Barriers, Light Divider | 278 |
| Part Numbering System | |
| Outline Dimensions | |
| | |
| SLIDE SWITCHES | 282-290 |
| General Purpose Slide Switches | 284-287 |
| Miniature Slide Switches | 288-290 |
| Side-Slide®/Miniature Slide Switches | 290 |
| European Line Voltage Selector Switches | |
| | |
| LEVER SWITCHES | 294-298 |
| | |
| GENERAL PURPOSE STACK SWITCHES | 299-300 |
| | |
| MULTIPLE STATION SWITCHES | 301-302 |
| MULTIPLE STATION SWITCHES Littel® Multi Switch | 301-302 |
| MULTIPLE STATION SWITCHES Littel® Multi Switch | 301-302 |
| MULTIPLE STATION SWITCHES Littel® Multi Switch DW Multi-Switch Tini® DW Multi-Switch | 301-302 303-308 309-311 312-313 |
| MULTIPLE STATION SWITCHES Littel® Multi Switch DW Multi-Switch Tini® DW Multi-Switch IBS Multi-Switch - Series IBS | 301-302 303-308 309-311 312-313 314-315 |
| MULTIPLE STATION SWITCHES Littel® Multi Switch DW Multi-Switch Tini® DW Multi-Switch | 301-302 303-308 309-311 312-313 314-315 |
| MULTIPLE STATION SWITCHES Littel® Multi Switch DW Multi-Switch Tini® DW Multi-Switch IBS Multi-Switch - Series IBS | |

Q-G® CONNECTORS



SECTIONALIZED VIEW - A3F Plug to B3M Receptacle



DESIGN FEATURES

CONSTRUCTION: Sturdy, die-cast zinc with satin nickel finish or Black-Velvet[®] finish to withstand hard use – even abuse. Vel-Tone non-reflective finish on QGP connectors only.

INSERT INSULATION: High-impact, molded thermoplastic provides high dielectric strength, and superior insulation resistance.

LOCKING: Latchlock on female plugs and receptacles locks into groove in mating male connector to prevent accidental disconnect. Manual release of latchlock is required to separate connectors. Q-G connectors are also available with FAS-DISCONNECT detent in place of latchlock. QGP has diecast latchlock.

FAS-DISCONNECT: FAS-DISCONNECT detent permits immediate disconnect of locked connectors with a 4-pound (1.8 kg) force. FAS-DISCONNECT connectors are not recommended for use in situations where strong or violent pulls on cable may occur and cause accidental disconnect. Available on Q-G connectors only.

DUAL PRESSURE PLATES: A*F and A*M Series provides secure cable lock and strain relief for all standard size cables.

FLEX RELIEF: TPR cable flex relief bushings on cord plugs are keyed to shell. Standard bushing opening accepts cables from .21" to .3" diameter Bushings with other openings accommodate cables from .105" to .205" diameter and from .3" to .328" diameter.

CONTACTS: Q-G female connectors are copper alloy, silver-plated, tarnish-resistant; male contacts are copper alloy, silver-plated, tarnish-resistant. Gold-plated female contacts are copper alloy. Male contacts are gold-plated.

WIRING: Large, unique design solder cups make wiring fast and easy. Certain receptacles are also available with PC terminals for use with printed circuit boards.

Grounding and Shielding

Tightening the insert screw establishes continuity between ground terminal, ground contactors and connector housing. Upon engagement with a mating plug or receptacle, the ground circuit is automatically connected to the mating shell through the ground contactor. Any pin or contact can be grounded by "jumping" it to the ground terminal. Contact 1 engages before all other contacts and disengages after all other contacts.

Field-proven Switchcraft Q-G ® (Quick-Ground) 3- through 7-contact audio connectors with ground terminal and ground contactors are available in a wide range of plugs and receptacles for microphones, test equipment, instrumentation, computers, video cameras, mixing consoles, tape recorders, PA and sound reinforcement, stereo systems and many more applications.

Switchcraft Q-G® connectors feature a separate ground-terminal electrically integral with connector shell. Ground continuity between mating plugs is automatically accomplished through exclusive "Dual Point" grounding system. Socket and pin assemblies utilize "wedge-action" to insure firm, reliable positioning in connector shell. Inserts are easily removable for wiring and soldering. High-impact thermoplastic insures long reliable insert assembly life. Female connectors have latch lock feature to hold connectors firmly together. Plugs and receptacles are mechanically keyed for proper mating. Q-G (*) Series 3-, 4-, 5-, 6-, and 7-pin/contact connectors offer 4-, 5-, 6-, 7-, and 8-pin contact versatility when ground-terminal is used. Switchcraft QGP connectors; are compatible with 3- and 4-contact (Neutrik, Amphenol 91-850 and Excellite 91-450 Series, and Cannon XLR-3, XLR-4): 5-contact (Neutrik, Cannon XLR-5 and Amphenol Excellite 91-450 Series).

Captive Design® Insert Screws



Insert screw engages as any conventional screw, except it is lefthand threaded. To disassemble the connector, turn screw counterclockwise down into insert (see illustration).



Insert assembly is now readily removed from shell. Note "Ground Terminal" area – large soldering cups make cable installation fast and easy. Unitized 1-piece insert eliminates possible loss of latchlock and spring.



To reassemble, replace insert assembly into shell, align insert screw under hole in shell and secure insert by turning insert screw clockwise. This "wedges" insert against interior of shell providing a rigid connector assembly and positive electrical continuity between ground terminal and shell (see illustration).

 $\frac{1000}{1000}$

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

Q-G® CONNECTOR PART NUMBERING

| Series | Number of Contacts | Gender | | Options |
|--|-----------------------|-----------------------|-----|--|
| | | | | • |
| A CORD PLUG WITH SCREW CABLE CLAMP | 3-7 | M MALE | | FAS-DISCONNECT (FEMALE CONNECTORS) |
| AA CORD PLUG WITH CRIMP CABLE CLAMP | | F FEMALE | В | BLACK EPOXY FINISH |
| AAA CORD PLUG WITH TWIST ON HANDLE | | | | |
| B FRONT PANEL MOUNT USING NUT | | FM BOTH (S SERIES) | ST | STRAIGHT PC TAILS |
| C FRONT PANEL MOUNT - CIRCULAR | | | RA | RIGHT ANGLE PC TAILS |
| D FRONT PANEL MOUNT - RECTANGULAR | | | М | MOMENTARY SWITCH ACTION (T SERIES ONLY) |
| E MODULAR FRONT PANEL MOUNT | | | PC | PC TERMINALS (Y SERIES ONLY) |
| G WALL PLATE - 1 B SERIES MALE | | | Ν | KNURLED COUPLING NUT (L SERIES ONLY) |
| H WALL PLATE - 2 B SERIES MALES | | | L | FLEX RELIEF FOR .250" TO .328" CABLE O.D. |
| J WALL PLATE - 1 D SERIES FEMALE | | | S | SEE NOTE 1. |
| K WALL PLATE - 2 D SERIES FEMALE | | | AU | GOLD CONTACTS |
| L MICROPHONE ADAPTER - INTERNAL THREAD | | | Ι | HOUSING ONLY |
| M MICROPHONE ADAPTER - EXTERNAL THREAD | | | OP. | TIONS SHOWN IN ORDER OF APPEARANCE |
| N CAP PLUG | | | Z | SCREWLESS STRAIN RELIEF |
| P GOOSENECK MOUNT | | | | |
| QG CONNECTOR INSERT | | | | |
| R RIGHT-ANGLE CORD PLUG | | | | |
| S MALE/FEMALE BARREL ADAPTER | | | | |
| T CORD PLUG WITH ON-OFF SWITCH | | | | |
| W RIGHT-ANGLE PANEL MOUNT | | | | |
| Y REAR PANEL MOUNT | | | | |

NOTE 1: S HAS DIFFERENT DESIGNATIONS DEPENDING ON THE SERIES.
FOR A, AA, AND T SERIES: SMALL FLEX RELIEF FOR .105" TO .205" CABLE OUTSIDE DIAMETER
FOR B, C, AND D SERIES: SANDED FRONT FACE FINISH
FOR G, H, J, AND K SERIES: STAINLESS STEEL WALL PLATE (STANDARD)
FOR N SERIES: SHORTING WIRING INSTALLED
NOTE 2: J, K AND T SERIES AVAILABLE IN FEMALE GENDER ONLY.

G, H, L, M, N, AND W SERIES AVAILABLE IN MALE GENDER ONLY.

PROFESSIONAL SERIES Q-G® CONNECTOR PART NUMBERING SYSTEM

| | Series | Number Of Contacts | | Model |
|------|---|--------------------|----|--------------------------------|
| | PROFESSIONAL SERIES | 3 | 22 | FEMALE CORD PLUGS |
| QGP | PROFESSIONAL SERIES CORD PLUG WITH CRIMP CABLE CLAMP | | 23 | MALE CORD PLUGS |
| AQGP | | | 62 | RECTANGULAR FEMALE PANEL MOUNT |
| | | | 63 | RECTANGULAR MALE PANEL MOUNT |

FAX: 773 792-2129


$\begin{array}{c} \textbf{CONNECTORS \& RECEPTACLES} \\ \textbf{Q-G}^{\circledcirc} \ \textbf{CORD PLUG CONNECTOR} - \textbf{A, AA AND QGP SERIES} \end{array}$

* Please visit the product pages on our website for the most up-to-date product information

Q-G ® CORD PLUG CONNECTORS (continued)



Q-G® AUDIO CONNECTORS A, AA, AND QGP SERIES



QGP connectors (3 contacts only) feature Vel-Tone® non-reflective finish, gray TPR flex relief and plated pins/contacts for the most demanding applications.

Preferred by audio professionals the world over, Switchcraft® QG® connectors feature unsurpassed durability and a choice of finishes and contact platings. Features include:

- High performance inserts in traditional Switchcraft[®] green or black.
- · Solder terminals rotated for easier access and soldering.
- · All metal housing.

AA Series Only

- Rugged 1-piece cable clamp to relieve pulling and twisting stresses on terminations.
- No Screws flex relief retention system.
- Integral bump shell grounding system.

SPECIFICATIONS

ELECTRICAL

Contact Resistance: 50 milliohm maximum, per pole. Current Rating: 3 pole – 15A, 4 pole - 10A, 5 and 6

pole - 7.5A, 7 pole - 5A @ 125VAC.

Insulation Resistance: $1,000 \text{ M}\Omega$, minimum. Dielectric Withstanding Voltage: 1,000 V (rms).

Capacitance: 2 pF between pins and 4 pF between pins

and shell, maximum (AA3M and AA3F).

MECHANICAL

Insertion/Withdrawal Forces: 7 pound maximum, 5 pound nominal, insertion; 7 pound maximum,

5 pound nominal, withdrawal.

Wire Size: #12 wire gauge solid; #14 wire gauge stranded (3 contact). #14 wire gauge solid; #16 wire gauge stranded (4 contact). #16 wire gauge solid; #18 wire gauge stranded (5 and 6 contact). #18 wire gauge solid; #20 stranded (7 contact). (Q-G and QGP).

MATERIAL Q-G CONNECTORS (A AND AA SERIES)

Shell: Die-cast zinc. Satin nickel finish, black velvet.

Insert Insulation: Molded thermoplastic.

Socket Contacts: Silver-plated copper alloy tarnish-resistant;

bifurcated on 3-contact type. Gold is available

Pin Contacts: Silver-plated copper alloy. Resists tarnishing, and provide excellent electrical conductivity. Gold is available.

Latchlock: High-strength die-cast zinc. Latch Release: Steel, nickel-plated. Latch Detent: Formed stainless steel.

Insert Screw: Stainless steel.


Flex Relief: TPR (thermoplastic rubber).

QGP CONNECTORS

Shell: Die-cast zinc, non-reflective gray Vel-Tone® finish.

Socket Contacts: Gold-plated copper alloy Pin Contact: Gold-plated copper alloy


FACE VIEW OF PIN (MALE) INSERTS




Q-G® CORD PLUG CONNECTORS (continued)




AA(*)F CORD PLUG



AA(*)FD CORD PLUG



AA(*)M CORD PLUG



PART NUMBERS - FEMALE CORD PLUGS

| Advanced Q-G® Cord Plugs, Series AA(*)F and AQGP | | | | | | | | |
|--|------------------------------------|-------------------------------------|---------------|---------------|---------------|---|--|--|
| AA3F | AA3FB | ♦ AA3FBAU ♦ AA3FD ♦ AA3FL ♦ AQGP322 | | | | | | |
| _ | _ | _ | AA3I | _ | 3 | | | |
| ♦AA4F | ♦AA4FB | _ | ♦AA4FD | _ | 4 | | | |
| ♦AA5F | ♦AA5FB | _ | ♦AA5FD | ♦AA5FL | _ | 5 | | |
| ♦AA6F | ♦ AA6F ♦ AA6FB — ♦ AA6FD ♦ AA6FL — | | | | | | | |
| ♦AA7F | ♦AA7FB | _ | ♦AA7FD | ♦AA7FL | _ | 7 | | |
| | on special of | order only; cont | act Switcher | aft for price | and delivery. | | | |

PART NUMBERS - MALE CORD PLUGS

| Advanced Q-G® Cord Plugs, Series AA(*)M and AQGP | | | | | | | |
|--|------------------------------------|---|---------------|---|---|--|--|
| AA3M | AA3MB | | | | | | |
| ♦ AA4M | - | _ | ♦AA4ML | ı | 4 | | |
| ♦ AA5M | ♦ AA5MB | _ | ♦AA5ML | ı | 5 | | |
| ♦ AA6M | _ | _ | ♦AA6ML | ı | 6 | | |
| ♦AA7M | ♦AA7M — — ♦AA7ML — 7 | | | | | | |

All above part numbers have black flex relief installed. Contact Switchcraft for color flex relief.

A(*)F CORD PLUG

A(*)FD CORD PLUG

A(*)M CORD PLUG

*Number of insert contacts or pins must be specified to complete part number.




Straight female cord plug with standard latchlock. Available in 3-7 pin versions.





Straight female cord plug with FAS-DIS-CONNECT detent.



Straight male cord plug.







PART NUMBERS - FEMALE CORD PLUGS

| S | Standard Q-G® Cord Plugs, Series A(*)F and QGP | | | | | | | | |
|-------------------|--|----------|---------|----------|------------|--------|--|--|--|
| Satin | | | Fas- | Large | | | | | |
| Nickel | Black | Finish | Dis- | Flex | | Insert | | | |
| Finish | Silve | r1 Gold1 | Connect | Relief 2 | QGP Series | | | | |
| Contacts | | | | | | | | | |
| A3F | A3FB | A3FBAU | ♦A3FD | A3FL | QGP322 | 3 | | | |
| A3FS ³ | _ | _ | _ | _ | _ | 3 | | | |
| A4F | A4FB | A4FBAU | ♦A4FD | A4FL | _ | 4 | | | |
| A5F | A5FB | A5FBAU | ♦A5FD | ♦A5FL | _ | 5 | | | |
| A6F | A6FB | A6FBAU | _ | _ | _ | 6 | | | |
| A7F | A7FB | A7FBAU | _ | _ | _ | 7 | | | |

- Contact plating.
- 2. Accepts cables from .25" (6.35 mm) to .328" (8.33 mm) diameter
- 3. Accepts cables from .105" (2.7 mm) to .205" (5.2 mm)
- ♦ Available on special order only; contact Switchcraft for price and delivery.

PART NUMBERS - MALE CORD PLUGS

| Standard Q-G [®] Cord Plugs, Series A(*)M and QGP | | | | | | | |
|--|----------|--------|---------------------|------------|----------|--|--|
| Satin | | | Large | | | | |
| Nickel | Black | Finish | Flex | | Insert | | |
| Finish | Silver 1 | Gold 1 | Relief ² | QGP Series | Contacts | | |
| A3M | A3MB | A3MBAU | A3ML | QGP323 | 3 | | |
| A3MS ³ | _ | _ | _ | _ | 3 | | |
| A4M | A4MB | A4MBAU | A4ML | _ | 4 | | |
| A5M | A5MB | A5MBAU | ♦A5ML | _ | 5 | | |
| A6M | _ | A6MBAU | _ | _ | 6 | | |
| A7M | _ | A7MBAU | _ | _ | 7 | | |

All above part numbers have black flex relief installed. Contact Switchcraft for color flex relief.

♦ Available on special order only; contact Switchcraft for price and delivery.

DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

Q-G® CONNECTORS (continued)

Q-G® COLOR FLEX RELIEFS

Rainbow color cable strain relief bushings can be specified to match or complement equipment decors or code individual or grouped connections for quick recognition. On special order, tan, pink and dark blue are available. Bushings accommodate cables from .21" to .30" diameter. Prepackaged, 25 per bag.

| Part N | lumbers | Flex | Flex |
|-----------------|----------------|--------|--------|
| 3 Pins/Contacts | | Relief | Relief |
| Female | Male | Color | Only |
| A3F | A3M | Black | SR00 |
| ♦ A3F01 | ♦ A3M01 | Brown | SR01 |
| ♦ A3F02 | ♦ A3M02 | Red | SR02 |
| ♦ A3F03 | ♦ A3M03 | Orange | SR03 |
| ♦ A3F04 | ♦ A3M04 | Yellow | SR04 |
| ♦ A3F05 | ♦ A3M05 | Green | SR05 |
| ♦ A3F06 | ♦ A3M06 | Blue | SR06 |
| ♦ A3F07 | ♦ A3M07 | Violet | SR07 |
| ♦ A3F08 | ♦ A3M08 | Gray | SR08 |
| ⊘A3F09 | ♦ A3M09 | White | SR09 |

[♦] Special order only; contact Switchcraft for price and delivery.

Q-G® FLEX RELIEF

Flex relief bushing with small opening accommodates cables from .105" (2.7 mm) to .205" (5.2 mm). Standard size bushing accepts cables from .210" (5.3 mm) to .300" (7.6 mm) outside diameter. Bushing with large opening accommodates cables from .300" (7.6 mm) to .328" (8.3 mm). Larger cables are often needed for multiple-conductor instrumentation. Code letter "L" in last or second to last digit in part number indicates plug with large bushing. Code letter "S" in last or second to last digit in part number indicates plug with smaller bushing.

SWITCHCRAFT PART NUMBER \(\text{K255} \)

Package of 100 cable clamp screws.

♦ Special order only; contact Switchcraft for price and delivery.





Standard Cables .210 to .300 (5.3) (7.6)

> Large Cables .300 to .328 (7.6) (8.3)

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

AAA CONNECTORS



AAA SERIES Q-G® TWIST CONNECTOR

Switchcraft introduces the AAA Series or Q-G® Twist XLR connectors. The Q-G® Twist Series is available in male or female cord plug, 3 through 7 pins or contacts. The unique features are the easy twist on combination handle/strain relief, and the reduced number of parts to assemble. With the insert built into the front shell, and the strain relief preloaded into the handle, the end user has only two parts to assemble – slide the handle onto the cable, solder the terminations, and twist on the handle. As the handle is tightened, the strain relief tightens around the outer jacket of the cable. A ramp on the strain relief keeps it from rotating around the cable jacket and twisting the cable. The strain relief was designed to accommodate the most popular cable sizes. A rugged die-cast metal handle insures optimum protection, and increases signal shielding. Popular options include black and gold finishes, as well as a lower cost plastic handle version.

SPECIFICATIONS ELECTRICAL

Contact Resistance: 50 milliohm maximum, per pole. Current Rating @ 125VAC:

3 pole – 15A 4 pole –10A

5 & 6 pole – 7.5A

7 pole – 5A

Insulation Resistance: 1,000 M Ω , minimum. Dielectric Withstanding Voltage: 1,000 V (rms) Capacitance: \leq 3 pF between pins and \leq 6 pF

between pins and shell, maximum

MECHANICAL

Insertion/Withdrawal Forces: 10 lbs. maximum, 8 lbs. nominal / 7 lbs. maximum, 5 pounds nominal.

Wire Size: 3 Contact

#12 wire gauge solid #14 wire gauge stranded

FEATURES AND BENEFITS

- Only two pieces to assemble
- · Easy twist on handle reduces assembly time
- · Rugged die-cast metal handle
- Accepts cable OD's (.100" .285")
- · Black finish available
- Gold-plated pins/contacts available
- Lower cost plastic handle version available

APPLICATIONS

- Audio
- Medical
- Instrumentation
- Process Controls

4 Contact

#14 wire gauge solid #16 wire gauge stranded

5 & 6 Contact

#16 wire gauge solid #18 wire gauge stranded

7 Contact

#18 wire gauge solid #20 wire gauge stranded

MATERIAL

Shell: Die-Cast zinc with nickel finish or black chrome. **Handle:** Die cast with nickel finish or black chrome.

Also black thermoplastic handle available. **O Ring:** TPR (Thermoplastic rubber). **Insert Insulation:** Molded thermoplastic.

Socket Contacts: Silver plated copper alloy tarnish resistant; bifurcated on 3 and 4 contact types. Gold is available.

Pin Contacts: Silver plated copper alloy. Resists tarnishing, and provides excellent electrical conductivity. Gold is available.

Latch lock: High strength die cast zinc.

Strain Relief: TPR

Flex Relief: TPR (Thermoplastic rubber)


CONNECTOR PART NUMBER SCHEME

| Series | Pins/Contacts | Gender | Handle Material | Housing Finish | Terminal Finish | Z |
|--------|---------------|-----------|-----------------|-------------------|--------------------|-------------------|
| AAA | 3-7 pins | F: Female | P: Plastic | B: Black | AU: Gold | New Strain Relief |
| | 3-7 pins | M: Male | Blank: Metal | Blank: Nickel | Blank: Silver | |

DIMENSIONS ARE FOR REFERENCE ONLY

(mm

AAA CONNECTORS (continued)




Q-G® CONNECTORS (continued)



R(*)FZ CORD PLUG

Right angle, female cord mount plug, latching. New style incorporates an insert that can rotate every 45° for added flexibility in tight applications. Also utilizes the new strain relief system with twist-on handle.




| Part Number | Insert Contacts |
|-------------|-----------------|
| R3FZ | 3 |
| R4FZ | 4 |
| R5FZ | 5 |
| R6FZ | 6 |
| R7FZ | 7 |

Accepts cable O.D.'s .100"-.285" For black finish, add "B" suffix. For black/gold finish, add "BAU" suffix.

R(*)MZ CORD PLUG

Right angle, male cord mount plug, latching. New style incorporates an insert that can be rotated every 45° for added flexibility in tight applications. Also utilizes the new strain relief system with twist-on handle.





| Part Number | Insert Pins |
|-------------|-------------|
| R3MZ | 3 |
| R4MZ | 4 |
| R5MZ | 5 |
| R6MZ | 6 |
| R7MZ | 7 |

Accepts cable O.D.'s .100"-.285" For black finish, add "B" suffix. For black/gold finish, add "BAU" suffix.

P(*)F MICROPHONE PLUG

Female microphone plug for gooseneck mount. Fits standard gooseneck with external 5/8-27 thread. Microphone plugs directly into connector. (Gooseneck not supplied.)






- 1. Satin Nickel Finish. (standard)
- 2. Large flex relief accepts cable from .25" to .328" diameter. (optional)
- 3. Gold-plated contacts. (optional)
- ♦ Available on special order only; contact Switchcraft for price and delivery.

P(*)M GOOSENECK PLUG

Male plug for gooseneck mount. Fits standard gooseneck with internal 5/8-27 thread. Use on gooseneck with microphone plug on opposite end. Plugs directly into female receptacle. (Gooseneck not supplied.)





| Part Number 1 | Insert Pins |
|---------------|-------------|
| P3M | 3 |
| ⊘P4M | 4 |
| ⊘P5M | 5 |

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

Q-G® CORD PLUG CONNECTORS AND RECEPTACLES




T(*)F AND T(*)FM CORD PLUG WITH ON-OFF SWITCH




| | Part Number | Part Number | Insert Contacts |
|---|--------------|---------------|-----------------|
| | T3F | ♦T3FL | 3 |
| | ♦T3FM | ♦T3FLM | 3 |
| | ⊘T4F | ∜T4FL | 4 |
| | ♦T4FM | ♦T4FLM | 4 |
| L | | <u> </u> | |

T(*)F Straight female cord plug with DPDT (2-C) locking on-off switch; standard latchlock.


T(*)FM Straight female cord plug with SPDT (1-C) momentary on-off switch; standard latchlock. Slide switches rated 500 mA, 125V (AC or DC). Mounting screws are supplied.






D(*)M, D(*)F AND D(*)FD RECEPTACLES









Studio quality black and gold Q-G® receptacle with black housing and gold contacts is designed for low/stable contact resistance and withstands corrosion where highest quality is required for recording and broadcast studio equipment, consoles, and other applications.

D(*)M SERIES – Male receptacle for panel or chassis mounting. Special rectangular flange permits close spacing on crowded panels, has two .136" (3.45mm) diameter countersunk holes for #5-40 flat head mounting screws (not supplied). Mounts from front of panel or chassis in .766" (19.45) diameter hole. Satin nickel finish (Series D*M) or black finish (Series D*MB, or D*MBAU).

D(*)F SERIES – Female receptacle for panel or chassis mounting. Flange has two .136" (3.45 mm) diameter countersunk holes for #5-40 flat head mounting screws (not supplied). Mounts from front of panel or chassis in .953" (24.21 mm) diameter hole. Series D(*)F has standard latchlock; Series D(*)FD has FAS-DISCONNECT detent. Satin nickel finish (Series D*F and D*FD) and "Black-Velvet" finish (Series D*FBAU).

| Nickel | Black Finish | | | | |
|--------|--------------|--------|---------------|-------------------------|------|
| Finish | Silver | Gold | Detent | QGP Series ¹ | Pins |
| D3M | D3MB | D3MBAU | _ | QGP363 | 3 |
| D4M | D4MB | D4MBAU | _ | _ | 4 |
| D5M | D5MB | D5MBAU | _ | _ | 5 |
| D6M | D6MB | D6MBAU | _ | _ | 6 |
| D7M | D7MB | D7MBAU | _ | _ | 7 |
| D3F | D3FB | D3FBAU | D3FD | QGP362 | 3 |
| D4F | D4FB | D4FBAU | ⊘D3FDB | _ | 4 |
| D5F | D5FB | D5FBAU | _ | _ | 5 |
| D6F | D6FB | D6FBAU | ⊘D6FDB | _ | 6 |
| D7F | D7FB | D7FBAU | _ | _ | 7 |

- * Number of insert contact or pins must be specified to complete part number.
- \Diamond Available on special order only; contact Switchcraft for price and delivery.
- 1 Non-reflective gray finish, gold-plated pins.

NCE ONLY $\frac{\ln}{(m)}$




B(*)F RECEPTACLE

Panel-mount female receptacle. Mounts with spanner nut from front of panels up to .4375" (11.11 mm) thick. Slot in threaded part of housing permits non-turn mounting. Requires 1.25" (31.75 mm) diameter minimum mounting hole. Spanner nut is die-cast zinc with satin nickel finish (Series B*F) or black finish (Series B*FB).



| Part No.1 | Part No. 2 | Insert Contacts |
|-----------|------------|-----------------|
| B3F | B3FB | 3 |
| B4F | _ | 4 |
| B5F | _ | 5 |
| B6F | _ | 6 |
| B7F | _ | 7 |




B(*)M RECEPTACLE

Panel-mount male receptacle. Mounts with locknut from front of panels up to .250" (6.35 mm) thick. Requires .812" (20.64 mm) diameter mounting hole. For non-turning mounting, can be keyed to "D" shaped panel hole, or S3519 mounting adapter can be used. Satin nickel finish (Series B*M) or black finish (Series B*MB).



| Part No.1 | Part No. ² | Insert Pins |
|-----------|-----------------------|-------------|
| B3M | B3MB | 3 |
| B4M | _ | 4 |
| B5M | _ | 5 |
| B6M | _ | 6 |
| B7M | _ | 7 |




C(*)F RECEPTACLE

Female receptacle for panel or chassis mounting. Flange has three .140" (3.57 mm) diameter holes for #5-40 mounting screws (not supplied). Mounts from front of panel or chassis in 0.953" (24.21 mm) diameter hole.



| Part No.1 | Part No. ⁵ | Insert Contacts | |
|-----------|------------|-----------------|--|
| C3F | ♦QGP326 | 3 | |
| C4F | _ | 4 | |
| C5F | _ | 5 | |
| C6F | _ | 6 | |
| C7F | _ | 7 | |

♦ Special order only. Contact Switchcraft.




C(*)M RECEPTACLE

Male receptacle for panel or chassis mounting. Flange has three .140" (3.57 mm) diameter holes for #5-40 mounting screws (not supplied). Mounts from front of panel or chassis in .766" (19.45 mm) diameter hole.



| Part No. 1 | Part No.⁵ | Insert Pins |
|------------|-----------|-------------|
| C3M | ♦QGP327 | 3 |
| C4M | _ | 4 |
| C5M | _ | 5 |
| C6M | _ | 6 |
| C7M | _ | 7 |



- 1. Satin nickel finish. (standard) 2. "Black-Velvet" finish. (optional) 3. Gold-plated contacts. (optional) 4. Fas-disconnect detent. (optional)
- 5. Non-reflective gray finish, gold-plated pins. (standard)

DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

E SERIES RECEPTACLES



Right Angle

PC Terminals

E Series Q-G® Receptacles are available with quick release inserts. Quick insert release is accomplished by turning screw lock from front of insert. Insert can then be removed from the rear. For PC board applications, insert can be removed/assembled to the housing while soldered to the PC board.

Straight PC

Terminals

FEATURES

• Replaces Neutrik D Series

Conical Spring Solder Terminals

- 3-pin contact; male and female types
- Both male and female fit in same panel cutout
- Choice of 4 terminations; solder cups, conical springs, straight or right angle PC terminals.
- Inserts and housings can be specified separately
- Quick release inserts for ease of removal
- Locking receptacles
- Protected ground clip minimizes scooping damage
- Insert lock detent resists disassembly from shock or vibration during normal handling and transportation
- Silver and gold-plated contacts available
- Rugged metal shells; black or satin nickel finishes
- Through-the-shell ground connection and all-metal shells for greater shielding effectiveness
- Compatible with Switchcraft Q-G ®, QGP and other connectors with similar configurations

QUICK RELEASE INSERT

In two simple steps, inserts can be released while housing stays fastened to the panel.

- With a small screwdriver, twist insert locking screw from front of insert.
- 2. Remove insert from the rear of the housing.

TERMINALS

Four terminations are available on E Series receptacles:

- Conical Spring Solder terminals conical spring on each pin holds wire in place providing constant pressure during soldering process. This effectively acts as a third hand, assuring a high quality solder termination. Housing mounts to panel.
- Straight PC terminals direct termination to PC board. Housing mounts to panel.

E Series receptacles can be specified as complete assemblies, or as separate inserts and housings. Stocking separate inserts and housings offer considerable cost and time savings by minimizing inventory and maximizing configuration possibilities.

Solder cup

- **3. Right-angle PC terminals** direct termination to PC board at a right-angle. Housing mounts to panel.
- 4. SC Solder cup

SPECIFICATIONS

ELECTRICAL

Contact Resistance: 50 milliohms maximum, per pole.

Current Rating: 15A

Insulation Resistance: $2 \times 10^6 \text{ M}\Omega$ Dielectric Resistance: 1,000 V rms

Capacitance: 10 pF

MECHANICAL

Insertion/Withdrawal Forces: 7 pounds maximum/ 5 pounds nominal insertion; 7 pounds maximum/

5 pounds nominal withdrawal. **Life:** 10,000 operations (minimum).

ENVIRONMENTAL

Thermal Range: -55° C to +85° C

Humidity: Meets MIL-STD-202F, method 106E. Thermal Shock: Meets MIL-STD-202F, method 107D. Salt Spray: Meets MIL-STD-202F, method 101D.

MATERIAL

Shells: Die-cast; satin-nickel or Black Velvet.

Inserts: Glass-filled thermoplastic.

Socket Contacts: Copper alloy, silver- or gold-plated. **Pin Contacts:** Copper alloy, silver- or gold-plated.

Latch Release: Steel, nickel-plated. Insert Locking Cam: Die-cast zinc.

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

E SERIES PART NUMBERING SYSTEM

CONNECTOR PART NUMBER SCHEME

| Series | Pins/ Contacts | Gender | Fas-disconnect Option | Termination Style | Housing Finish | Terminal Finish | Mounting Hole Options |
|--------|-------------------|--------|--------------------------|---|---------------------------|--------------------|--|
| E | 3-5 pins | | Blank: Standard | ST: Straight PC terminals RA: Right angle PC terminals SC: Solder cups Blank: Conical springs* | B: Black Blank: Nickel | | M3: M3 x 0.5 thread 440: #4-40 thread Blank: Counter- sunk hole |

HOUSING ONLY PART NUMBER SCHEME


| Series | Pins/ Contacts | Housing Finish | Mounting Hole Options |
|--------|-------------------|-------------------|--------------------------|
| E | F: Female | B: Black | M3: M3 x 0.5 thread |
| | M: Male | Blank: Nickel | 440: #4-40 thread |
| | | | Blank: Counter-sunk hole |

INSERT ONLY PART NUMBER SCHEME

| Series | Pins/ Contacts | Gender | Fas-disconnect Option | Termination Style | Housing Finish | Terminal Finish |
|--------|-------------------|----------------------|--|--|-------------------|---------------------------|
| E | 3-5 pins | F: Female M: Male | D: Fas-disconnect Blank: Standard locking | ST: Straight PC terminals RA: Right angle PC terminals SC: Solder cups Blank: Conical springs* | | AU: Gold Blank: Silver |


^{*3-}pin only

E SERIES






E SERIES (continued)



DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

E SERIES (continued)






EH SERIES RECEPTACLES


The EH Series consist of different styles of popular connectors in our E Series housing. This allows the end user to punch one single hole size and populate wall plates, gang assemblies with different types of connectors. Connector styles include BNC feed-throughs, RCA feed-throughs, USB feed-throughs, IEEE 1394 Firewire feed-throughs, BNC to solder cup, and RCA to BNC.


FEATURES


- Utilizes same panel cut-out as E Series QG connectors
- Rugged metal shells
- Available with a wide variety of popular feed-through connectors











| Part Number | Description | |
|-------------|----------------------|--|
| EHBNC2 | BNC to BNC | |
| EHBNCSC | BNC to solder cup | |
| EHRCA2 | RCA to RCA | |
| EHRCABNC | RCA to BNC | |
| EHUSB2 | USB to USB | |
| EH13942 | IEEE1394 to IEEE1394 | |
| EHCAT62 | Cat6 to Cat6 | |

DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

PQG® RECEPTACLES . The state of the state of













PQG3FRA112

PQG3MRA112

PQG3FST112

PQG3MST112

Q-G® 3 pin/contact PC receptacles offer economy, reliability and performance in amplifiers, audio mixing boards, and other outboard gear. Choose receptacles with just the right combination of standard and optional bonus features to tailor the PQG series to your exact needs.

STANDARD FEATURES

- UL 94V-0 plastic materials.
- Circuit #1 "makes" first and "breaks" last during connect/disconnect.
- · Positive mechanical polarization.
- · Minimum PC board space required.
- Integral PC board locating posts.
- Mating/unmating cycles in excess of 10,000.
- Mates with Switchcraft Q-G and other compatible connectors.

OPTIONAL FEATURES

- Positive latch lock or FasDisconnect (female only).
- Shell-to-ground terminal.
- Mounting Plates:
 - A. Backup Mounting Plate with two, M3 x 0.5 threaded holes for faster, more rugged mounting to equipment panel/chassis.
 - B. "Tri-Mounting" Plate...plus two bifurcated pcb retainers with snap-in terminals which perform three valuable functions:
 - 1. Provide ground connection from panel to PCB.
 - 2. Hold connector securely to PCB during wave-soldering.
 - 3. Add strength between panel/chassis and PCB during soldering by "wicking" solder through the PCB and up sides of retainers to assure continuity.
 - C. Two panel grounds are integral with mounting plate.

SPECIFICATIONS

Housing: Black, glass-filled thermoplastic, UL 94V-0. Flange mounting holes are .128 inch diameter Socket Contacts: Copper alloy, electrotinned. Pin Contacts: Copper alloy, electrotinned. Latch Release: Steel, nickel-plated.

Mounting Plate: Copper alloy.

Shell-to-Ground Terminals: Copper alloy, electrotinned.


Latches: Copper alloy, nickel-plated.


Insertion/Withdrawal Forces: 2 pound (nominal). Contact Resistance: .05 ohms per pole (maximum). Dielectric Withstanding Voltage: 1,000 V rms for 1 minute.

Insulation Resistance: 10⁴ MΩ @ 500 V DC. Current Capacity: 10A maximum (carry only).

Operating Temperature: -30°F to 185°F (-34°C to 85°C).

Mechanical Life: 10.000 cycles @ 10 cpm.







PQG® SERIES PART NUMBERING SYSTEM

P Q G SERIES

PQG-

Composite QG

3 PINS/

CONTACTS

3

GENDER
F - Female

M - Male

PC TERMINALS

RA - Right Angle, Bottom Exit

ST - Straight Rear Exit

LATCHING

0 - None1 - Latch Lock

2 - Fas-Disconnect (female only)

GROUND TERMINAL

0 - None 1 - Installed


2


MOUNTING PLATE

0 - None


1 - Plate with two, M3 x 0.5 threaded holes


2 - Plate with two, M3 x 0.5 threaded holes, panel grounds and PCB retainers







No. PQG3FRAXXX














PANEL OPENING

DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

Q-G® AUDIO RECEPTACLES FOR PC/PANEL MOUNT

PD SERIES - PLASTIC PANEL MOUNT



Switchcraft offers the PD Series (plastic panel mount) audio connectors with a wide variety of 3-pin/contact, male and female types and many terminals for combined PC/panel mount. Female types offer larger contact area for higher ratings and longer life. Panel mounting may be at users option, either front or rear. New PD series connectors mate with Switchcraft Q-G and other compatible types.

PD SERIES FEATURES

- 3 pins/contacts
- Male and female
- Straight and right-angle terminals
- PC or PC/panel mount
- Front or rear panel mount
- Special PC/solder terminal type with exits at 0° (down, 90° (right), 180° (top), and 270° (left)
- · Rugged molded black glass-filled thermoplastic housings.

SPECIFICATIONS

Housing: Black molded thermoplastic, glass-filled.


Ground Pin: Copper alloy.

Stamped Terminals/Contacts: Copper alloy, electrotinned. **Screw Machine Terminals/Pins:** Copper alloy, silver-plated.

BIFURCATED PC TERMINALS

Bifurcation configuration for PC terminals on selected connectors offers these advantages.

- 1. Provides convenient snap-in retention for mounting.
- 2. Holds connector securely to PCB during wavesoldering.
- Adds strength to all terminal connections by solder "wicking" through PCB and up sides of terminals.



BIFURCATED HOLD-DOWN FEATURE FOR ALL PC TERMINALS

PD SERIES PART NUMBERING SYSTEM



3 PINS/







SERIES PD

PD3MS1

3-pin male.

PC terminals.

Front mount.

straight (rear exit)

CONTACTS

GENDER F - Female M - Male

FEMALE RA RL

RR

RU

S

MALE - Right-angle, Bottom Exit

Right-angle,

- Right-angle,

Right Exit

- Right-angle,

Bottom Exit,

Long Screw

Mach. Term. RMS - Right-angle, Bottom Exit, Short Screw

Mach. Term.

- Straight, Rear Exit - Solder Cup

Top Exit

RML - Right-angle,

Left exit

RML - Right-angle, Bottom Exit, Long Screw Mach. Term.

RMS - Right-angle, Bottom Exit, Short Screw Mach. Term.

Straight,

Rear Exit - Solder Cup 1 - Front Mount .11" (2.8 mm) diameter flange mounting holes

2 - Rear Mount .091" (2.3 mm) diameter flange mounting holes


3 - Front Mount .126" (3.2 mm) diameter flange mounting holes

TERMINALS

Blank= Silver terminals


AU= Gold terminals







PD3MRML2 3-pin male, right angle (bottom exit) long screw machine terminals. Panel mount holes not countersunk.




PD3FRL1 3-contact female, right-angle (left exit) PC/solder terminals. **Ground lug. Front** panel mount.




Bifurcated PCB Terminals

PD3FRA1 3-contact female, right-angle (bottom exit) PC/solder terminals. Ground lug. Front panel mount.



Numbers PD3FRA1, 2, and 3; PD3FRL1, 2, and 3; PD3FRR1, 2 and 3; PD3FRU1, 2 and 3 (Typical)




Numbers PD3FS1, 2, and 3 (Typical)


DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)


PD SERIES (continued)




Numbers PD3FRMS1, 2, and 3 (Typical)




Numbers PD3FRML1, 2, and 3 (Typical)



Numbers PD3MRML1, 2, and 3 (Typical)



Numbers PD3MRMS1, 2, and 3 (Typical)



Numbers PD3MS1, 2, and 3 (Typical)

Q-G ® RECEPTACLES

* Please visit the product pages on our website for the most up-to-date product information

SERIES Y(*)F, Y(3)FPC, Y(*)FD, Y(3)FDPC AND Y(3)MPC RECEPTACLES





Y3FPC

Series Y(*)MPC. Male receptacle for panel or chassis mounting escutcheon. PC terminals and standoffs. Rear of panel mount in .750 inch diameter hole. Maximum panel thickness: 25 inches (6.35 mm); .156 inches (3.96 mm) if YEM escutcheon is used.

Series Y(*)FPC. Female receptacle for panel or chassis mounting. PC Terminal and standoffs. Rear of panel mount in .875 inch (22.22 mm) diameter hole.

Series Y(*)F. Female receptacle for panel or chassis mounting. Rear of panel mount in .875 inch (22.22 mm) diameter hole.


Series Y(*)FD, Y(*)FDPC. Female receptacles. Same as Y(*)F and Y(*)FPC, respectively, except with FAS-DISCONNECT detent.

Series YEF Escutcheons. Trim escutcheons provide distinctive panel appearance and can also color code connections. Available in black (standard), red. green, white. and yellow. Other colors possible on special order where production quantities warrant.

ASSEMBLY/MOUNTING

All receptacles are rear-of-panel mount (units with PC terminals also mount/terminate to PC board). Flange fastens to chassis/panel with two #4-40 machine screws (not supplied). Use of escutcheons is optional.

Install latch release lever (Series Y(*)F and Y(*)FPC) after receptacle is fastened to chassis/panel. Insert lever in slot from front and press inward until it locks (snaps) into place. To remove lever, depress rear of lever (with screwdriver) through opening at top rear of housing and pull lever straight out.



RECEPTACLES


| Part Nu | umbers | | | |
|----------------------------------|-------------------------------|--------------------|----------------------------------|----------------|
| Female Latchlock [†] | Female Detent [†] | Insert Contacts | Part Number Male [†] | Insert Pins |
| Y3F | Y3FD | 3 | Y3MPC | 3 |

†Suffix letters "PC" indicate PC terminals; all others have solder lugs.

ESCUTCHEONS


| Part Number | Color | Part Number | Color |
|-------------|-------|-------------|--------|
| ♦YEF01 | Red | YEF04 | Blue |
| YEF02 | Black | ♦YEF05 | White |
| ♦YEF03 | Green | ♦YEF08 | Yellow |

SPECIFYING NOTE: YEM02 escutcheon can be ordered on special order; contact





YEF02 **ESCUTCHEONS**



F SERIES RECEPTACLES





Switchcraft now offers the F Series. Available in male and female, the receptacles can be mounted from the rear of the panel. Features include an all metal housing with a ferrite disk for added EMI/RMI shielding. Both male and female connectors can be mounted vertical or horizontal to the PC board. All connectors have a PC-board retention feature to hold the connectors firmly to the PC board prior to soldering.

F SERIES FEATURES

- Replaces Cannon XLM-Series
- 3-pin contact; male and female types

See the chart below for part numbers.

- Both male and female fit in same panel cutout
- Locking receptacles
- Silver-plated contacts
- Rugged metal shells; satin nickel finishes
- Through-the-shell ground connection and all-metal shells for greater shielding effectiveness
- Compatible with Switchcraft Q-G[®], QGP and other connectors with similar configurations
- Added EMI/RFI ferrite shield

| Part Number | Terminals | Contacts | Housing | Туре |
|----------------|----------------|----------|--------------|------|
| F3MSTF | Straight | | Satin Nickel | M |
| F3FSTF | Straight | Silver | | F |
| F3MRAF | Right Angle | Silver | | М |
| F3FRAF | Trigite Aligie | | | F |

SPECIFICATIONS:

ELECTRICAL

Contact Resistance: 50 milliohms maximum, per pole.

Current Rating: 15A

Insulation Resistance: 1,000 M Ω Dielectric Resistance: 1,000 V rms

Capacitance: 2 to 4 pF

MECHANICAL

Insertion/Withdrawal Forces: 7 pounds maximum/nominal

Insertion: 7 pounds maximum withdrawal. **Life:** 10,000 operations (minimum).

ENVIRONMENTAL

Thermal Range: -55° C to +85° C

Thermal Shock: Meets MIL-STD-202F, method 107D Salt Spray: Meets MIL-STD-202F, method 101D (for 16 hrs.)

MATERIAL

Shells: Die-cast; satin-nickel plated **Inserts:** Glass-filled thermoplastic.

Socket Contacts: Copper alloy, silver-plated.
Pin Contacts: Copper alloy, silver-plated.
Latch Release: Steel, nickel-plated.

TERMINALS


Two terminations are available on F-Series receptacles:

1. Straight PC-terminals – direct termination to PC-board.

Housing mounts to panel.

Right Angle PC terminals – direct termination to PC-board at right angle. Housing mounts to panel.

F SERIES RECEPTACLES (continued)





Q-G® ADAPTERS, ACCESSORIES



Q-G® CONNECTOR INSERTS



Male and female Q-G ® inserts with 3-7 pins/contacts, fit appropriate plug and receptacle housings. Female inserts available with standard latchlock or FAS-DISCONNECT detent mating, and with solder or PC terminals. Intended for replacement, or building into equipment such as microphones and transducers.

| Standard Latchlock | FAS-* DISCONNECT | Male Inserts | Insert Pins/ Contacts |
|-----------------------|---------------------|-----------------|-----------------------------|
| _ | ♦ QG3FDPC | _ | 3 |
| QG3F | QG3FD | QG3M | 3 |
| QG4F | QG4FD | QG4M | 4 |
| QG5F | QG5FD | QG5M | 5 |
| QG6F | QG6FD | QG6M | 6 |
| QG7F | QG7FD | QG7M | 7 |
| | I | 1 | I |

^{*}Suffix letters "PC" indicate PC terminals; all others (except "S") have solder lugs.


Note: Add suffix "BAU" for black insert with gold-plated contacts.

W(*)M RECEPTACLE



| Part Number | Insert Pins |
|-------------|-------------|
| W3M | 3 |
| W4M | 4 |

Right-angle male panel receptacle. Mounts with two, #5-40 machine screws.




SHORTING PLUG




| Part Number | Insert Pins |
|-------------|-------------|
| ♦N3MS | 3 |

[♦] Available on special order only; contact Switchcraft for price and delivery.

3-pin plug shorts out unused hi-Z microphone inputs or other sensitive circuits (shorting jumper installed between pins 2 and 3). 6" (152.4 mm) chain fastened to end pin to prevent plug loss. Switchcraft can install special wiring for a nominal extra charge.





^{**}Suffix letter "S" indicates locking PC terminal and plastic housing. ♦ Special order only. Contact Switchcraft.

Q-G® WALL PLATE RECEPTACLES

G(*)M WALL PLATE RECEPTACLE



Wall plate with one B3M or B4M male receptacle mounted (in "D"-shaped hole to prevent turning) on standard single electrical outlet box. Cover mounting screws included.

| Part Number | Finish | Insert Pins |
|----------------|-----------|----------------|
| G3MS | Stainless | 3 |
| ⊘G4MS | Steel | 4 |

♦ Special order only. Contact Switchcraft.

J(*)F WALL PLATE RECEPTACLE



Wall plate with one, D3F or D4F female receptacle. Mounts on standard single electrical outlet box. Cover mounting screws included.

| Part Number | Finish | Insert Pins |
|----------------|-----------|----------------|
| J3FS | Stainless | 3 |
| ♦J4MS | Steel | 4 |

♦ Special order only. Contact Switchcraft.



H(*)M WALL PLATE RECEPTACLE



Wall plate with two, B3M or B4M male receptacles mounted (in "D"-shaped holes to prevent turning) standard single electrical outlet box. Cover mounting screws included.

| Part Number | Finish | Insert Pins |
|----------------|-----------|----------------|
| ♦Н3MS | Stainless | 3 |
| ♦H4MS | Steel | 4 |


♦ Special order only. Contact Switchcraft.



Wall plate with two, D3F or D4F female receptacles. Mounts on standard single electrical outlet box. Cover mounting screws included.

| Part Number | Finish | Insert Pins |
|----------------|-----------|----------------|
| K3FS | Stainless | 3 |
| ⊘K4FS | Steel | 4 |

♦ Special order only. Contact Switchcraft.



4.5 [114,3]

Q-G® CONNECTOR-ADAPTERS





Switchcraft Q-G © Connector-Adapters, designed to solve common interconnection problems, are ideally suited to the interconnection of microphones, mixers, amplifiers, public address and sound reinforcement equipment, broadcast equipment, and any other component that does not have an appropriate mating connector. All are completely shielded, and incorporate the high quality and outstanding design features of the Switchcraft line of Q-G Audio Connectors, including:

- 1. Separate ground terminal.
- 2. Ground Contactors.
- 3. Captive Design® Insert Screw
- 4. High impact Thermoplastic Insulation.

MATERIAL SPECIFICATIONS PHONE JACK AND PLUG TERMINATIONS

Shell: Copper alloy, nickel-plated. **Insulation:** Paper-base phenolic.

Plug Tip and Sleeve: Copper alloy, nickel-plated.

Phone Pin and Plug Housing: Copper alloy, nickel-plated.

Phono Plug Insulation: Rigid plastic.

Phono Jack Housing: Steel, copper alloy-plated,

tarnish-resistant.

Phono Jack Pin Receptacle: Brass, silver-plated, copper alloy.

Phono Jack Insulation: Thermoplastic.

321. Phono plug to 3-contact female audio-connector (Switchcraft® A3F).


322. Phono jack to 3-contact female audio-connector (Switchcraft® A3F).


323. Phono plug to 3-pin male audio-connector (Switchcraft A3M).


324. Phono jack to 3-pin male audio-connector (Switchcraft® A3M).


383A. Three-contact female audio-connector (Switchcraft® A3F) to standard .250" (6.35 mm) diameter 3-conductor extension phone jack.


384A. Three-pin male audio connector (Switchcraft® A3M) to standard .250" (6.35 mm) diameter 3-conductor extension phone jack.














DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm


Q-G® AUDIO CONNECTOR-ADAPTERS


386A: Three-contact female audio connector (Switchcraft® A3F) to standard .250" (6.35 mm) diameter 3-conductor phone plug.

387A: Three-pin male audio connector (Switchcraft[®] A3M) to standard .250" (6.35 mm) diameter 3-conductor phone plug.


389: Three-contact female audio connector (Switchcraft® A3F) at both ends. Pre-wired contacts: 1 to 1, 2 to 2, 3 to 3.


390: Three-pin male audio connector (Switchcraft® A3M) at both ends. Prewired pins: 1 to 1, 2 to 2, 3 to 3.












S*FM AUDIO CONNECTOR-ADAPTER AUDIO "Y" ADAPTERS






Male-female connector conversion has male Q-G® insert at one end and corresponding female Q-G® insert at the other. Designed to accept internally connected transformer, attenuator, or other circuitry inline with microphone input. Includes 1.50" (38.1 mm) long x .594" (15.08 mm) diameter of usable internal volume.

| Part Number | Female Insert | Male Insert | Insert Pins/Contacts |
|--------------|------------------|----------------|-------------------------|
| S3FM | QG3F | QG3M | 3 |
| ♦S4FM | QG4F | QG4M | 4 |
| ♦S5FM | QG5F | QG5M | 5 |

Available on special order only; contact Switchcraft for price and delivery.





Series 391Q Y-Adapters can combine or split typical audio signals using a combination of Switchcraft Q-G® A3F and A3M cord plugs. Outputs of two microphones can conveniently be connected in parallel and connected to a single input using a 391Q23 Y-Adapter. Cabling is 2-conductor shielded, 2-foot long gray jacket with molded Y-junction at center point. Mates with Switchcraft Q-G® and QGP® connectors.

| | Q-G [®] Cord Plug Part Numbers | | |
|----------------|---|--------|--------|
| Part Number | Plug A | Plug B | Plug C |
| 391Q13 | A3F | A3M | A3M |
| ⊘391Q23 | A3F | A3M | A3F |
| ⊘391Q33 | A3F | A3F | A3F |
| 391Q43 | A3M | A3F | A3F |
| ♦391Q53 | A3M | A3F | A3M |
| ⊘391Q63 | A3M | A3M | A3M |

Note: "Y" adapters may use either series A(*) or AA(*) plugs.

♦ Available on special order only; contact Switchcraft for price and delivery.

DMX ADAPTER

Switchcraft introduces our new series of DMX adapters. The DMX adapters were developed for use in the theater lighting industry. The adapters allow the end user to use standard 3 pin XLR cable assemblies in connecting DMX equipment. The adapters are available in 3 pin male to 5 pin female and 5 pin male to 3 pin female. All are wired "straight through."

FEATURES AND BENEFITS

- · Nickel-plated die-cast housing increases durability
- Pre-wired for immediate use
- Available in two configurations

APPLICATIONS

- Theater lighting
- Any DMX application

SPECIFICATIONS

Shell: Die-cast zinc, satin nickel finish **Insert Insulation:** Molded thermoplastic **Socket contacts:** Silver-plated copper

alloy, tarnish-resistant


Pin contacts: Sliver-plated copper


alloy, tarnish-resistant

ORDERING INFORMATION

S3F5M 3 pin female to 5 pin male S5F3M 5 pin female to 3 pin male







S5F3M 5 PIN FEMALE TO 3 PIN MALE DMX ADAPTER



Q-G® CONNECTOR-ADAPTER RECEPTACLES




Adapter receptacles mount directly to microphones or similar equipment to provide highly reliable 3-, 4- and 5-pin Switchcraft Q-G® connections. Adapter shell and coupling nut are brass, satin nickel finish.

SERIES L(*)MN


Male has plain cylindrical shell with knurled, internally threaded collar to engage external 13/16-27 threads on microphone body.





Z MATCHING TRANSFORMERS





Series 9000 Line Matching Transformers offer low-loss interconnections between high and low impedance equipment. Exclusive mu-metal shielding protects against spurious electrostatic and RF fields. Units are bi-directional and can be used as follows:


- Low to hi, such as professional low impedance microphones to high impedance amplifiers. Stereos, cassette recorders, public address systems, and mixers.
- Hi to low, such as high impedance microphones or electronic instruments to low impedance amplifiers or mixers.

Designed to mate with Switchcraft Q-G $^{\circ}$ connectors. Available with various terminations; see chart.

SERIES M(*)N

Male with shell having 13/16-27 external threads to engage equipment with internally threaded body. Terminals extend out rear (threaded end) to permit wiring without disassembly.





| Part Numbers | | |
|--------------|--------------|--------|
| Series | Series | Insert |
| L(*)MN | M(*)M | Pins |
| ⊘L3MN | ⊘М3М | 3 |
| ♦L4MN | ⊘M4M | 4 |
| ♦L5MN | ♦ M5M | 5 |

SPECIFYING FEATURES

- Plug-in impedance changes
- Fully wired
- Connections bi-directional (low to high impedance or high to low impedance)
- Rugged die-cast housings
- Mu-metal shielding

MATERIAL SPECIFICATIONS

Shell: Die-cast zinc shell, nickel-plated with black non-glare metalized foil label.

Shielding: Mu-metal.

Dimensions: Diameter–.75" (19.05 mm) nominal Length – 3" (76.2 mm) nominal (Part Number 92XX); 3.375" (85.73 mm) nominal (Part Number 91XX).

ELECTRICAL SPECIFICATIONS

Frequency Response: Flat–20 Hz to 20 kHz ± 2 decibels Impedance: High–50 K ohms (nominal); Low–150 ohms (nominal) Voltage Step Ratio (Input Power Level); Low to High: +29 decibels (typical); high to low: -29 decibels (typical)

| Part Number | Switchcraft Connector | | |
|----------------|--|--|--|
| ♦9115 | Lo Z: 3-contact Q-G [®] female, A3F | Hi Z: 2-conductor phone plug, 1/4" finger diameter, right angle handle, 4" extension (shielded) cable | |
| ♦9129 | Lo Z: 3-contact Q-G® female, A3F | Hi Z: 2-conductor phono plug, right angle handle, 4 inch extension (shielded) cable | |
| 9144 | Lo Z: 3-contact Q-G® female, A3F | Hi Z: 2-conductor phone plug, | |
| 9244 | Lo Z: 3-pin Q-G® male, A3M | 1/4" finger diameter | |

 \Diamond Available on special order only; contact Switchcraft for price and delivery.

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

TINI Q-G® MINIATURE CONNECTORS

Series TA(*)F, TA(*)FB, TA(*)FL and TA(*)FLB – Straight female cord plug

Series TA(*)M, TA(*)MB, TA(*)ML and TA(*)MLB -

Straight male cord plug

Series TB(*)M and TB(*)MB - Chassis/panel mount male receptacle

Series TY(*)F and TY(*)FPC — Chassis/panel, female receptacle, choice of solder lugs or P.C. terminations.

Series TLP – Looping Plugs Series TBA(* *) – Audio Adapters

Series TRA(*)M – PC Mount Male Receptacles

Series TRG(*) - Reverse Gender Panel Mount, Cord Mount

DESIGN FEATURES

STYLE – Streamlined, miniaturized with nickel-plated metal and contrasting black plastic parts. Designed for light weight and unobtrusiveness. Also available in conductive black chrome finish.

CONSTRUCTION – Metal parts are rugged die-cast or precision machined with nickel-plating; plastic parts are molded of high dimensional-stability thermoplastic. Advanced design assures minimum weight consistent with strength and durability of cord plug housings of .413" (10.5 mm) diameter Weight: Series TA(*)F plug = .25 ounce (7 g); Series TA(*)M = .3 ounce (8.5 g).

INSERTS — Precision molded of thermoplastic for high mechanical and dielectric strength. Contacts and terminals are precision formed and plated for intimate contact and low resistance connections. Terminal numbers are molded on rear of male insert and on face of female insert for easy identification (except 6-pin male insert). Inserts can be supplied for OEM installation in microphones and instrumentation for optimum connecting reliability. For cord plugs, inserts can also be supplied for replacements.

LATCHLOCK – Positive latch system assures high integrity, vibration-resistant mating and transfer of shielding connection between housing, combined with simple, easy fingertip release.

STRAIN RELIEF – Rugged internal clamp holds cable tightly, while making a secure, low resistance connection between cable shield and housing.



FLEX RELIEF – Protects by minimizing cable bending stress at point of cable entry. Maximum recommended cable diameter is .115" (2.92 mm) when flex relief is used. By omitting flex relief (Series T(*)FL and T(*)ML only), cable up to .170" (4.32 mm) diameter can be used.

ASSEMBLY – Connector parts are mechanically keyed for simple assembly.

POLARIZATION – Mating male and female connectors are also mechanically keyed (latch and groove) so that it is impossible to mate them incorrectly.

"SCOOP-PROOF" FEATURE – Fully recessed pins on male plugs and receptacles cannot be "scooped", bent or damaged by accidental mismating with mating connector.

COLOR ESCUTCHEONS – Attractive color escutcheons, Series TYEF, are recommended for use with Series TY(*)F and TY(*)FPC receptacles (when rear mounted) for attractive panel trim, as well as color coding one or more connectors. Colors are: red, black, gray, green, blue, white and yellow.

CUSTOM Tini Q-G® CABLE ASSEMBLIES — On special order where production quantities warrant, Switchcraft can supply assembled and tested Tini Q-G® cables.

MOUNTING

Panel/Chassis Thickness:

Series TB(*)M: .25" (6.35 mm) maximum

Series TY(*)F:

Front—.375" (9.5 mm) maximum Rear—.093" (2.3 mm) maximum

Series TY(*)FPC:

Front—.312" (7.9 mm) maximum Rear—.093" (2.3 mm) maximum


TINI Q-G ® AUDIO ADAPTERS


Series TA Tini Q-G ® audio adapters have been designed to adapt Tini Q-G ® connections to standard audio connectors. Tini Q-G ® adapters convert to Switchcraft Q-G ® and QGP connectors and similar full-size connectors.





| Part Number | Tini Q-G [®] End Mates With | Q-G [®] End Mates With |
|---------------|---|------------------------------------|
| ♦ TA01 | TA3F | A3M |
| ♦TA02 | TA4F | A4M |
| ♦TA03 | TA5F | A5M |
| ♦TA04 | TA3F | A3F |
| ♦TA05 | TA4F | A4F |
| ♦TA06 | TA5F | A5F |







SPECIFICATIONS: (3 – 5 CORD MOUNT ONLY)

ELECTRICAL

Contact Resistance: .010 ohms maximum after life

(and after salt spray).

Current Rating (Carry Only): 5 A, 125 V AC (4 A, 125 V AC

on 5 circuit) based on 30°C maximum.

Insulation Resistance: 510,000 megohms minimum @ 500 V DC (initial); 10,000 megohms minimum (after humidity test).

Dielectric Strength: 1,000 V (rms).

MECHANICAL

Life: 5,000 operations minimum

Insertion/Withdrawal Forces (after life): 6.1 lb./2.77 kg after

life, insertion; 5.6 lb/2.54 kg, withdrawal.

Solderability Standard: Meets EIA RS-186-9E.

Mechanical Shock: Meets MIL-STD-202, method 213B.

Vibration: Meets MIL-STD-202, method 201A.

Wire Size: #22 wire gauge solid; #24 wire gauge stranded.

ENVIRONMENTAL

Thermal Range: -55°C to + 85°C.

Humidity: Meets MIL-STD-202, method 106D. Thermal Shock: Meets MIL-STD-202, method 107D. Salt Spray: Meets MIL-STD-202, method 101.

MATERIAL

Housing, Plugs and Male Receptacles: Copper alloy, nickel-plated. Female Receptacle—Die-cast zinc, nickel-plated. Black Tini Q-G® Housing: Copper alloy, black chrome-plated. Pin and Socket Contacts: Copper alloy, silver-plated. Flex Relief: Molded black thermoplastic elastomer.

Latch Button: Molded black thermoplastic.
Release Lever and Mounting Washer: Steel, nickel-plated.
Standoff/Ground Terminal and Cable Clamp:

Steel, electrotinned.

Inserts and Insulating Spacer: Molded, high strength

thermoplastic.

Latch (Female): Copper alloy, nickel-plated. **Mounting Nut:** Copper alloy, nickel-plated.

SPECIFICATIONS:

(6 - 8 Cord Mount and all Receptacles and Adapters)

ELECTRICAL

Contact Resistance: .010 ohm maximum after life. Current Rating (Carry only): 1.5A, 125 VAC, based

on 30° maximum

Insulation Resistance: 510,000 M Ω minimum

@ 500 VDC (initial).

Dielectric Strength: 250 V rms.

MECHANICAL

Life: 2,000 operations

Insertion/Withdrawal Forces (after life): -13 pound

insertion; –13 pound maximum withdrawal **Solderability Standard:** Meets EIA RS-186-9E.

Wire Size: 28 wire gauge stranded.

MATERIAL

Housings, Plugs and Male Receptacles: Copper alloy,

nickel-plated.


Socket Contacts: Copper alloy, silver-plated. **Pin Contacts:** Copper alloy, electrotinned.

Flex Relief and Latch Button: Molded thermoplastic. Ground Terminal: Copper alloy, electrotinned.

Inserts and Insulating Spacer: Molded high strength

thermoplastic, UL 94 V-0.


Latch (Female): Copper alloy, nickel-plated. Mounting Nut: Copper alloy, nickel-plated. Ferrite: 43 material, shielded head. Frame: Molded thermoplastic, UL 94 V-0.



STRAIGHT FEMALE CORD PLUG

| Part Number | Insert Contacts | Part Number | Insert Contacts ² |
|--------------------|--------------------|--------------------|------------------------------|
| TA3F | 3 | TA4FLB* | 4 |
| TA3FB* | 3 | TA5F | 5 |
| TA3FL ¹ | 3 | TA5FL ¹ | 5 |
| TA3FLB* | 3 | TA5FLB* | 5 |
| TA4F | 4 | TA6FL ¹ | 6 |
| TA4FB* | 4 | TA7FL | 7 |
| TA4FL ¹ | 4 | TA8FL | 8 |

- 1 Flex relief omitted for larger diameter cable
- 2. Add AU to Part Number for Gold Contacts.
- * B indicates black housing



STRAIGHT MALE CORD PLUG

| Part Number | Insert Pins | Part Number | Insert Pins |
|--------------------|----------------|--------------------|----------------|
| TA3M | 3 | TA5M | 5 |
| TA3MB* | 3 | TA5ML | 5 |
| TA3ML | 3 | TA5MLB* | 5 |
| TA4M | 4 | TA6ML ¹ | 6 |
| TA4MB* | 4 | TA7ML | 7 |
| TA4ML ¹ | 4 | TA8ML | 7 |

- 1. Add AU to Part Number for Gold Contacts.
- * B indicates black housing

♦ Available on special order only; contact Switchcraft for price and delivery.

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

TINI Q-G® MINIATURE CONNECTORS (continued)





TB(*)M AND TB(*)MB RECEPTACLE





Male receptacle for chassis/panel mounting. Specially designed flange permits close (front) mount on crowded panels. Mounting hardware supplied. Available with PC terminals. Call factory for details.






| Part Number | Insert Pins | Part Number | Insert Pins |
|----------------|----------------|----------------|----------------|
| TB3M | 3 | TB5MB* | 5 |
| TB3MB* | 3 | TB6M | 6 |
| TB4M | 4 | TB7M | 7 |
| TB4MB* | 4 | TB8M | 8 |
| TB5M | 5 | | |

* B indicates black housing

TLP(*) LOOPING PLUG



Looping plug is designed for circuit testing. Other inserts and wiring patterns are possible; contact Switchcraft.



STRAIGHT FEMALE LOOPING PLUG

| Part Number | Insert Contacts |
|-------------|-----------------|
| ♦TLP4 | 4 |
| ∜TLP6 | 6 |

[♦] Available on special order only; contact Switchcraft for price and delivery.

^{*} Number of insert contacts or pins must be specified to complete Part Number.




REVERSE GENDER TQG SERIES


Same specifications as the original TQG Series, however, the latch is on the male cord mount. Available in 4 pin only.



TRGS4F



| Part Number | Insert Pins | Description |
|----------------|----------------|-------------------------|
| TRGS4F | 4 | Panel mount female |
| TRG4M | 4 | Cord mount male w/latch |




TINI Q-G® MINIATURE CONNECTORS (continued)

TRA(*)M PC MOUNT MALE RECEPTACLE


The TRA(*)M low profile male receptacles mount in minimum space from the rear of panel or chassis, and feature space-saving right-angle construction and PC type terminals. The TRA3M is a cost-effective choice for audio equipment, medical instrumentation, computer equipment and test/measurement applications. Also available with 6 pins.

| Part Number | Insert Pins |
|-------------|-------------|
| TRA3M | 3 |
| TRA6M | 6 |
| TRA6MF* | 6 |

*F designates ferrite shielding







TRASM*M, TRAPC*M SERIES

Switchcraft introduces an expansion of its popular TQG Series of connectors. The TRASM*M and TRAPC*M offers low profile, right angle PC board mount connectors. The TRASM*M versions are true surface mount connectors, while the TRAPC*M versions are through-hole PC mount connectors. Both versions are available in 3-8 pins. All plastic connectors, the TRASM*M and TRAPC*M series have flats on the top of the connectors to facilitate pick and place assembly. As an added option, a non-threaded bushing version is also available.

FEATURES AND BENEFITS

- Low profile, compact design reduces PC board space
- Mates with TQG female cord plugs
- Rated at 5A for 3-6 pins, 3A for 7 and 8 pin versions

MARKETS

- Wireless microphone systems
- Medical Instrumentation
- Test Instrumentation

SPECIFICATIONS

MATERIALS

Housing: Thermoplastic **Contacts:** Brass, tin-plated

Nut and Washer: Brass, nickel-plated

TRASM3M

TRAPC3MS




ELECTRICAL

Current Rating: 5A for 3-5 pins, 1.5A for 6-8 Contact Resistance: 10 m Ohm max Insulation Resistance: 100 m Ohm min Dielectric Withstanding Voltage: 250VAC

Mechanical Life: 2,000 cycles

TINI Q-G® CONNECTORS ORDERING INFORMATION




See next pages for drawings


DIMENSIONS ARE FOR REFERENCE ONLY


Inch (mm)


TINI Q-G ® MINIATURE CONNECTORS (continued)

TRASM*M, TRAPC*M SERIES










REAR VIEW (CONFIG. 3 THRU HOLE SHOWN)

> Inch (mm

CONNECTORS & RECEPTACLES

TINI Q-G ® MINIATURE CONNECTORS (continued)

TRASM*M, TRAPC*M SERIES




RECOMMENDED PC BOARD LAYOUTS

TINI Q-G ® MINIATURE CONNECTORS (continued) ®




TY(*)F AND TY(*)FPC RECEPTACLES




Female receptacle mounts in minimum space from front or rear panel or chassis. Terminals are solder lugs, Series TY(*)F, or P.C., Series TY(*)FPC. All receptacles have separate ground lug.


| Part Number | Insert Contacts | Part Number | Insert Contacts | |
|----------------|--------------------|----------------|--------------------|--|
| TY3F | 3 | TY5F | 5 | |
| TY3FPC | 3 | TY5FPC | 5 | |
| TY4F | 4 | | | |
| TY4FPC | 4 | | | |

MOUNTING HOLE DETAIL SERIES TY(*)F, TY(*)FPC




COMBINED P.C./PANEL MOUNTING





TYEF ESCUTCHEONS





Trim escutcheons in seven colors for use with Series TY(*)F and TY(*)FPC receptacles, are recommended for rear mount receptacles. Escutcheons must be ordered separately.

| Part Number | Color |
|-------------|--------|
| ♦TYEF01 | Red |
| TYEF02 | Black |
| ♦TYEF03 | Green |
| ♦TYEF04 | Blue |
| ♦TYEF05 | White |
| ♦TYEF08 | Yellow |
| ♦TYEF11 | Gray |

TQG(*)F AND TQG(*)M **CONNECTOR INSERTS**



Male and female inserts with 3, 4, 5 or 6 pins/ contacts. For replacement (cord plugs only) or build-into equipment, such as microphones, transducers and instruments.

Male Inserts


| Part Number | Insert Pins |
|---------------|-------------|
| TQG3M | 3 |
| TQG4M | 4 |
| TQG5M | 5 |
| ♦TQG6M | 6 |

Female Inserts

| Part Number | Insert Contacts |
|-------------|-----------------|
| TQG3F | 3 |
| TQG4F | 4 |
| TQG5F | 5 |
| ♦TQG6F | 6 |

TBA(**) AUDIO ADAPTER





3-6 pin male-to-male adapter is designed for through-bulkhead or cable expansion usage. Adapter is prewired pin 1 to pin 1, pin 2 to pin 2, etc. Mounting nuts are supplied for each threaded end. Panel hole diameter required is .45"; maximum panel thickness is .25" (6.35 mm).

| Part Number | Insert Pins |
|-------------|-------------|
| ♦TBA03 | 3 |
| ♦TBA04 | 4 |
| ♦TBA05 | 5 |
| ♦TBA06 | 6 |

♦ Available on special order only; contact Switchcraft for price and delivery. DIMENSIONS ARE FOR REFERENCE ONLY

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

HPC SERIES PANEL MOUNTS AND CORD PLUGS









HPCPR41F

HPCP41F

HPCP410RA

HPCI4F

HPCC4F

HPCC4RAF

HPC SERIES

Switchcraft recently introduced a complete line of panel mount speaker connectors that are completely compatible with the Neutrik® Speakon® 4 pole series. We are now introducing a complete line of cable mounts as well. The complete HPC Series offers both panel mount and cord mount connectors.

The HPC panel mounts have been updated with new silver-plated contact materials that boost the contact ratings to 30A per UL 1977 on PC mount versions, 50A per UL 1977 on Faston® versions. They are still available with either 0.100" depth flanges or 0.200" depth flanges. The 0.200" depth flange allows for rear mounting of the HPC Series, and proper mating of all cord plugs. The panel mount versions are available with either 0.187" or 0.250" Faston® terminals, and either straight or right angle PC mount terminals. The right angle PC mount version also has, as an option, a mounting post which allows the connector to snap onto the PC board for wave soldering.

The HPC cord plugs are available in either straight, right angle, or as an in-line. The in-line version mates with either the straight or right angle cord plug, allowing the end user to extend cable runs. All cord plugs are compatible with Speakon® panel mounts. The in-line mates with our HPC cord plugs, as well as Speakon® cord plugs. The unique feature of the HPC series cord plugs are the "push to lock" feature, similar to the connection of an XLR connector. The HPC cord plugs, when mated to either HPC panel mounts or Speakon® panel mounts do not require a 1/4" turn to engage. Simply push the connector in until it locks. To disengage, push forward on the latch lever and pull the connector out. This feature eliminates the need to remember to turn the connector to make contact. All HPC cord plugs utilize 0.250" Faston® terminals, which allow for easy assembly, and make it easy to change cord plugs. To change from a straight cord plug to an in-line cord plug, back off the strain relief nut, twist off the handle, disconnect the Faston® terminals, fasten the new cord connector, twist on the handle and the strain relief. Barbs on the handle keep the handle from vibrating loose from the front shell.

Both HPC panel mounts and cord plugs incorporate a built-in gasket, which allows them to meet IP 25 harsh environment ratings, as well as IEC 529 and IEC 1010-1 safety ratings.

FEATURES AND BENEFITS

- Completely compatible with Neutrik® Speakon® 4 pole connectors
- 30A rating per UL 1977 on PC mount versions
- 50A rating per UL 1977 on Faston® versions
- Panel mounts have two different Faston® terminal sizes, 0.187" and 0.250"
- Panel mounts offered with two different flange depths, 0.100" and 0.200"
- 0.200" depth flange offers easy rear mounting

- Right angle or straight PC board terminals on panel mounts
- Built in gasket gives all HPC connectors IP 25 environmental ratings
- All HPC Series meet IEC 529 and IEC 1010-1 safety ratings
- Cord plug versions offer "push to lock" design, no 1/4" turn to engage
- Cord plug versions accept 10 AWG wire, 0.560" cable OD max

APPLICATIONS

- Loudspeakers
- Power audio amplifiers

SPECIFICATIONS

Materials

Housings: Thermoplastic UL 94V-O rated Seal Rings: Thermoplastic rubber Contacts: Silver-plated over copper alloy

ELECTRICAL

PC Terminals Current Rating: 30A per UL 1977

Faston® Terminals Current Rating: 50A RMS w/10AWG

wire, normal ambient, per UL 1977

Voltage Rating: 1,500 AC RMS, Per Mil-Std 202 Method 301

Insulation Resistance: > 2T Ohms

Contact Resistance: 1m Ohm, 1.5mOhm after 1,000

insertion/withdrawals

MECHANICAL

Shock: Mil-Std 202, Method 213B Cond.K Vibration: Mil-Std 202, Method 201A Life: 1,000 insertion/withdrawals Cable Range: 0.560" OD max

ENVIRONMENTAL

Salt Spray: Mil-Std 202, Method 101D Cond. B Thermal Shock: Mil-Std 202, Method 107G Temperature Limits: -55 C to +85 C


Moisture Resistance: Mil-Std 202, Method 106E Life@Ambient Temperature: Mil-Std 202, Method 108A


Touch Proof: IEC 65 and 1010-1 **Weather Tightness:** IEC 529, IP 25


CORD MOUNT ORDERING INFORMATION


| Part Number | Description |
|-------------|-----------------------|
| HPCC4F | Straight Cord Plug |
| HPCI4F | Inline Cord Plug |
| HPCC4RAF | Right Angle Cord Plug |

















DIMENSIONS FOR REFERENCE ONLY

[2.36]

MOUNTING HOLES OPTION [0]

Korea

EN3™ MINI WEATHERTIGHT CONNECTOR SERIES

GENERAL FEATURES AND BENEFITS

- Great all-purpose connector "weather" or not sealing feature is required.
- Superior leakage protection. Contact area is double-sealed for excellent moisture and chemical resistance when mated to Switchcraft's connectors.
- Integral O-ring and gasket. O-ring is molded onto cord housing assembly and gasket is molded onto panel housing assembly to prevent leakage and eliminate need for additional O-rings and gaskets.
- Reduced part count for reduced labor to assemble.
- No Grommets. Cable clamp assembly features living hinges, which snap easily onto and support the cable.

 Thermoplastic rubber body simulates closed entry contact
- system to prevent probe damage or accidental loss of spring retention due to misaligned or bent pins.
- Abrasion-resistant thermoplastic boot provides strain relief and accepts cable diameter .195" to .265".

 • Housing rated UL 94V-O against flammability.
- Panel connector shell features a positioning keyway to prevent misalignments and a polarizing single "D" design for proper panel mounting and to prevent rotational movement.
- 2-18 pins.
- Exceeds Coast Guard specifications for water tightness (CFR 46 Part 110.20).
- Optional cap covers panel housing assembly when not in use.
- Exceeds enclosure rating IP16/IP18 when not mated or covered and IP66/IP68 when mated or covered (IEC 529)
- Exceeds enclosure rating 6P at 1000V when mated or covered (NEMA 250).

MATING INSTRUCTIONS FOR A CORD CONNECTOR TO A PANEL MOUNT OR IN-LINE CONNECTOR

First, align the notched keyway on both the panel mount or in-line and cord connector. Then, push the cord connector onto the mating connector. Grasp the coupling ring between the slots, push it toward the panel mount connector and rotate it clockwise nearly one half a turn. Continue rotating until you feel the coupling ring ride over the locking "bump". This is the locked position. The cord connector is not securely in place unless this procedure is followed.

APPLICATIONS

Process Control Communications Marine Electronics Transportation

Medical Instrumentation General Industrial Electronics

Geothermal Instrumentation Harsh Environments

MATERIALS

Cord and panel connector shells, contact locking disk, and cable clamp assembly: Thermoplastic polymer glass fiber, flame retardant

Coupling ring: Nylon

Rear boot and connector shell interior: Thermoplastic rubber Contacts: Copper base alloy gold-plated over nickel underplate

SPECIFICATIONS **MECHANICAL**

Shock: Mil-Std 202 Method 213B, condition K

Vibration: Mil-Std 202 Method 201


Life: 600 insertion/withdrawal cycles (minimum)

ELECTRICAL

Voltage Rating (sea level): Tested at 600 VRMS Insulation Resistance: 100 megohms (minimum) at 77° F

Contact Resistance: 5 milliohms (maximum)

Current Rating: 3.0 Amps (#26 contact)— 9 through 18pin 6.5 Amps (#20 contact)— 7 and 8 pin 7.5 Amps (#20 contact)— 2 through 6 pin 13.0 Amps (#16 contact) - 2 and 3 pin



ENVIRONMENTAL

Temperature Limits: -40°C to +65°C (non-operating) Moisture Resistance: Mil-Std 202 Method 106F Insulation Resistance: Mil-Std 202 Method 302 condition B

Thermal Shock: Mil-Std 202 Method 107G Salt Spray: Mil-Std 202 Method 101D condition B

RATINGS


IP16/IP18 CFR 46 Part 110.20

IP66/IP68 **UL 94V-O**

NEMA 250 (6P)

Patent 5,485,673 File 36049

EN3™ Weathertight Connector Current Carry Capability (per UL 498 Standard)



| Dielectric Withsta | |
|--------------------|----------|
| number of contacts | Voltage |
| #20-2 | 3000 |
| #20-4 | <u> </u> |
| #20-3 — | |
| #16-2 — | 2000 |
| | |
| #20-7, #20-8 | |
| #16-3 — | <u> </u> |
| #20-5, #20-6 — | — 1000 |

CONNECTORS & RECEPTACLES "MINI WEATHERTIGHT CONNECTOR SERIES

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

CRIMP CONTACT INSERTION INSTRUCTIONS



CRIMP TOOLS

| Part Number | Tool Description | |
|-------------|---|--|
| EN3INS16 | Insertion/Extraction Tool for 16 AWG | |
| EN3INS20 | Insertion/Extraction Tool for 20 AWG | |
| EN3CR | Crimp Hand Tool | |
| EN3CRAUTO | Pneumatic Crimp Tool | |
| EN3POS16 | Positioner for 16 AWG contacts and pins | |
| EN3POS20 | Positioner for 20 AWG contacts and pins | |

NOTE: A positioner must be used with the EN3CR and EN3CRAUTO.


CRIMP CONTACT EXTRACTION INSTRUCTIONS




Note: Solder and PC contacts are factory assembled


CORD CONNECTOR ASSEMBLY INSTRUCTIONS

Cord Connector: To assemble the three-part cord connector, first feed the end of the cable through the boot, cable clamp housing, and coupling ring in that order and position as shown in the figure below. NOTE: The coupling ring can also be inserted onto the cord connector from the front. In-line Connector: Feed the end of the cable through the boot and cable clamp housing in the order and position shown.






Next, strip the cable .218" as shown and begin soldering conductors to pins, or insert contacts crimped on wire starting with contact #1 next to the "notch" and following with the remaining conductors counter-clockwise with #6 or #8 conductor in the center.





Push the cable clamp housing forward until it locks into the connector body and snap the two clamps into their compartments.

CORD CONNECTOR **CABLE CLAMPS**



STEP 4

Finally, push the boot all the way forward to seat tightly onto the cable clamp housing.



CORD CONNECTOR




IN-LINE CONNECTOR


Remember: Cord connectors will not mate with each other. For cord-to-cord connection, your customer must order a cord connector plus an in-line connector.

EN3™ MINI WEATHERTIGHT CONNECTOR SERIES (continued)


2 - 8 PIN CORD CONNECTOR



CONTACT ARRANGEMENTS - VIEWED FROM REAR OF CONNECTOR (WIRING SIDE)



9 - 18 PIN CORD CONNECTOR



EN3 Cord Connector Part Number Scheme

| Series | Style | Pins/ Contacts | Gender | Contact Size | Contact Style | Contact Plating | Packaging |
|--------|-------|-------------------|----------------------|---|--|---------------------------------------|--|
| EN3 | С | 2-18 | F: Female M: Male | 16: #16 Leave blank for #20 26: for 9-18 only | C: Crimp P: PC S: Staggered Leave blank for solder | AG: Silver Leave blank for gold | K: Kit Leave blank for bulk packaging |

Notes: 7 & 8 pin not available in cord male

9-18 pin available in either staggered solder or straight solder only

9-18 pin available only with # 26 terminals

AG: Silver plating special order


#16 contact available in 2 & 3 pins only

CONNECTORS & RECEPTACLES


* Please visit the product pages on our website for the most up-to-date product information

EN3™ MINI WEATHERTIGHT CONNECTOR SERIES (continued)


2 - 8 PIN PANEL CONNECTOR



CONTACT ARRANGEMENTS - HOLE LAYOUTS VIEWED FROM FRONT OF CONNECTOR (PCB COMPONENT SIDE)



9 - 18 PIN PANEL CONNECTOR



EN3 Panel Connector Part Number Scheme

| Series | Style | Pins/ Contacts | Gender | Contact Size | Contact Style | Contact Plating | Packaging |
|--------|-------|-------------------|----------------------|---|--|---------------------------------------|--|
| EN3 | Р | 2-18 | F: Female M: Male | 16: #16 Leave blank for #20 26: for 9-18 only | C: Crimp P: PC S: Staggered Leave blank for solder | AG: Silver Leave blank for gold | K: Kit Leave blank for bulk packaging |

Notes:

7 & 8 pin not available in panel female

9-18 pin available in either staggered solder or straight solder only


9-18 pin available only with # 26 terminals

AG: Silver plating special order

#16 contact available in 2 & 3 pins only

EN3™ MINI WEATHERTIGHT CONNECTOR SERIES (continued)

2 - 8 PIN INLINE CONNECTOR



EN3 Inline Connector Part Number Scheme


| Series | Style | Pins/ Contacts | Gender | Contact Size | Contact Style | Contact Plating | Packaging |
|--------|-------|-------------------|----------------------|-----------------------------------|--|---------------------------------------|--|
| EN3 | I | 2-8 | F: Female M: Male | 16: #16 Leave blank for #20 | C: Crimp P: PC Leave blank for solder | AG: Silver Leave blank for gold | K: Kit Leave blank for bulk packaging |

Notes:

7 & 8 pin not available in inline female #16 contact available in 2 & 3 pins only AG: Silver plating special order

2 - 8 PIN OVERMOLDED CORD AND INLINE CONNECTOR

(See Cable Section for More Details.)





DIN CONNECTORS

SPECIFICATIONS ELECTRICAL

Contact Resistance: Cord Plugs and Receptacles; .010 ohms, contact spring/pin .030 ohms, ground clip/shell. Control and Switching Receptacles; .015 ohms, contact

spring/pin; .020 ohms, switch contacts.

Dielectric Withstanding Voltage: 500 V (rms)

Contact Rating: 5-pin; 3A, 34 V DC Leakage Resistance: 10⁵ MΩ

Recommended Wire Size: 22 wire gauge maximum

MECHANICAL INSERTION/WITHDRAWAL FORCES:

| Number of Contacts | Insertion Force pound/N | Withdrawal Force pound/N |
|-----------------------|-------------------------|--------------------------|
| 2 | 3.6/(16) | .45- 2.7/(2-12) |
| 3 | 5.4/(24) | .67- 4.1/(3-18) |
| 4 | 7.2/(32) | .90- 5.4/(4-24) |
| 5 | 9.0/(40) | 1.24- 6.8/(5.5-30) |
| 6 | 10.8/(48) | 1.46- 8.1/(6.5-36) |
| 7 | 12.6/(56) | 1.68- 9.5/(7.5-42) |
| 8 | 14.4/(64) | 1.90-10.8/(8.5-48) |

NOTE: All connectors meet DIN specifications #41524. Din specification numbers (except for 4-pin, 5-pin @ 240°, and 8-pin @ 262°)


MATERIAL

Shell: Die-cast zinc alloy, nickel-plated. **Receptacle Mounting Flange:** Steel.


Receptacle Body: Plastic.
Insert Material: Plastic.
Socket Contacts: Tin-plated.
Pin Contacts: Tin-plated.

Switching Contacts: Silver-plated. Cable Relief Bushing: Soft plastic.

PIN ARRANGEMENTS




CONTACT ARRANGEMENTS



DIN PLUGS

STRAIGHT CORD PLUG with 30° lock ring





Type 05CL5M – typical Male plug with ground key-rib. Unique 30° turn lockring securely fastens two halves of connector. Mates with lock flange female connectors and receptacles. Insert screw holds insert assembly in shell and also retains lockring on shell. Flexible black strain relief with 7/32" diameter cable entry. Heavy duty clamp.


ORDERING INFORMATION

| Part Number | Description | Pin Arrangement |
|-------------|----------------|-----------------|
| 05CL3M | 3 pins at 180° | 2 |
| 05CL5M | 5 pins at 180° | 5 |
| 09CL4M | 4 pins at 210° | 3 |
| 12CL5M | 5 pins at 240° | 4 |
| ♦15CL7M | 7 pins at 270° | 7 |
| ♦15CL8M | 8 pins at 270° | 9 |

 \Diamond Available on special order only; contact Switchcraft for price and delivery.

STRAIGHT CORD PLUG with Shielded Barrel





Type 15GM7M – typical: Male cord plug with shielded barrel and insulated snaplock plastic body. Two piece metal barrel surrounds pin insert to form an electrical shield. The entire insert assembly is held together by snapping the insulated plastic shell over the assembly. The barrel's special metal tab locks the shell in place. Standard color of plastic shell is gray. All-purpose cable clamp.

ORDERING INFORMATION

| SKDEKING IN OKMATION | | | |
|----------------------|--|--------------------|--|
| Part Number | Description | Pin Arrangement | |
| 05GM3M | 3 pins at 180° Gray body and strain relief. | 2 | |
| 05GM5M | 5 pins at 180° Gray body and strain relief | 5 | |
| ◊09GM4M | 4 pins at 210° Gray body and strain relief | 3 | |
| 12GM5M | 5 pins at 240° Gray body and strain relief | 4 | |
| ♦12GM6M | 6 pins at 240° Gray body and strain relief | 6 | |
| 15GM7M | 7 pins at 270° Gray body and strain relief | 7 | |
| 15GM8M | 8 pins at 270° Gray body and strain relief | 9 | |
| ♦20GM8M | 8 pins at 262° Gray body and strain relief | 10 | |

SPECIFYING NOTE: Use letter "JL" in place of "GM" to order same part number with black housing.

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information


DIN PLUGS AND RECEPTACLES

STRAIGHT CORD PLUG with Extended Barrel



TYPE 12BL6M - TYPICAL

Male plug with ground key-rib. Nickel-plated diecast handle. Contact friction coupling. Flexible black strain relief. Heavy duty cable clamp.




ORDERING INFORMATION

| Part Number | Description | Pin Arrangement |
|----------------|--|-----------------|
| ◊03BL2M | 2 pins with insulated switch actuator | 1 |
| 05BL3M | 3 pins at 180° | 2 |
| 05BL5M | 5 pins at 180° | 5 |
| 09BL4M | 4 pins at 210° | 3 |
| 12BL5M | 5 pins at 240° | 4 |
| 12BL6M | 6 pins at 240° | 6 |
| ♦15BL7M | 7 pins at 270° | 7 |
| ♦15BL8M | 8 pins at 270° | 8 |



TYPE 05YL5M - TYPICAL

Right-angle chassis hugging, male plug with flexible strain relief. Unique 8-position barrel gives you a choice of any one of eight different cable entry angles. ground key rib 30° turn lockring securely fastens two halves of connector.



ORDERING INFORMATION

| Part Number | Description | Pin Arrangement |
|-------------|----------------|-----------------|
| ♦05YL3M | 3 pins at 180° | 2 |
| ♦05YL5M | 5 pins at 180° | 5 |
| ♦09YL4M | 4 pins at 210° | 3 |
| ♦12YL5M | 5 pins at 240° | 4 |

RIGHT-ANGLE CORD PLUG with 8 Position Barrel




TYPE 05DL5M - TYPICAL

Right-angle chassis hugging, male plug with flexible black rubber strain relief. Unique 8-position barrel offers a choice of eight different cable entry angles.

ORDERING INFORMATION

| Part Number | Description | Pin Arrangement |
|----------------|----------------|-----------------|
| ◊05DL3M | 3 pins at 180° | 2 |
| 05DL5M | 5 pins at 180° | 5 |
| ⊘09DL4M | 4 pins at 210° | 3 |
| ♦12DL5M | 5 pins at 240° | 4 |
| ♦12DL6M | 6 pins at 240° | 6 |
| ♦15DL7M | 7 pins at 270° | 7 |



 \Diamond Available on special order only; contact Switchcraft for price and delivery.


DIN PLUGS AND RECEPTACLES (continued)

STRAIGHT CORD PLUG with Flush Socket Insert



TYPE 06AL5F - TYPICAL

Female plug with ground contact. Diecast metal shell, nickel-plated. Two contact plug, Part number 04AL2F includes a break circuit switch (1-B) which is opened by engaging the insulated switch actuator of the mating plug or receptacle. Flexible black strain relief.



ORDERING INFORMATION


| Part Number | Description | Contact Arrangement |
|-------------|--------------------|---------------------|
| 06AL5F | 5 contacts at 180° | F |
| ♦13AL5F | 5 contacts at 240° | E |
| ♦13AL6F | 6 contacts at 240° | G |
| ♦15AL7F | 7 contacts at 270° | Н |
| 15AL8F | 8 contacts at 270° | N |

STRAIGHT CORD PLUG with Lock Flange



TYPE 06EL5F - TYPICAL

Female plug with ground contact. Lock flange designed to accept 30° lockring. Insert screw firmly holds insert assembly in shell. Flexible black strain relief with 7/32" diameter cable entry. Heavy duty cable clamp.



ORDERING INFORMATION


| Part Number | Description | Contact Arrangement |
|-------------|--------------------|---------------------|
| ♦06EL5F | 5 contacts at 180° | F |
| 13EL5F | 5 contacts at 240° | E |
| ⊘15EL8F | 8 contacts at 270° | N |

RECEPTACLE with Extended Shell



TYPE 57KD3M - TYPICAL

Male receptacle, 3 pins, with ground key-rib. Diecast extended shell and flange for chassis or panel mounting. Turret terminals.



ORDERING INFORMATION

| Part Number | Description | Pin Arrangement |
|-------------|----------------|-----------------|
| 57KD3M | 3 pins at 180° | 2 |

 \Diamond Available on special order only; contact Switchcraft for price and delivery.




DIN RECEPTACLES (continued)

RECEPTACLE with Closed Circuit Switch



TYPE 59GB3F - TYPICAL

Unique 3 and 5 contact receptacles include a 1-B (closed circuit) switch which is mounted to drawn metal shell. Switch is actuated by the shell of the mating plug. Receptacles also provide complete shielding through the ground contact. Flared solder terminals.



ORDERING INFORMATION

| Part Number | Description | Contact Arrangement |
|-------------|--|----------------------------|
| | 3 contacts at 180° plus closed-circuit switch (Schematic #5) | В |


 \Diamond Available on special order only; contact Switchcraft for price and delivery.

RECEPTACLE for Chassis or Panel Mounting For shielded and extended barrel plugs



TYPE 57GB5F – TYPICAL – FLARED SOLDER TERMINALS

Drawn metal recessed shell with mounting flange and ground contact. Available flared solder terminals. Part Number 58GB3F features two extra blanks in insert for proper mating (5 pins at 180°) plug where applications may require greater connector flexibility. Flared solder terminals standard.



ORDERING INFORMATION

| Part Number | Descriptions | Contact Arrangement |
|----------------|----------------------|---------------------|
| ♦57GB3F | 3 contacts at 180° B | |
| 57GB5F | 5 contacts at 180° | F |
| 60GB4F | 4 contacts at 210° | D |
| 61GB5F | 5 contacts at 240° | E |
| 61GB6F | 6 contacts at 240° | G |
| 62GB7F | 7 contacts at 270° | Н |
| 62GB8F | 8 contacts at 270° | N |

♦ Available on special order only; contact Switchcraft for price and delivery.


DIN RECEPTACLES (continued)

RECEPTACLE for Lockring Plug Flared solder terminals on Part Number 57HB5F



TYPE 61HA5F - TYPICAL

Female receptacle with ground contact. Chassis or panel mount. Diecast bayonet extension shell with mounting flange. Mates with all lockring plugs. such as Part Number 12CL5M. Part Number 55HA2F includes closed-circuit switch (1-B). All receptacles have straight solder terminals, except as noted.



ORDERING INFORMATION

| Part Number | Description | Pin Arrangement | |
|----------------|--|-----------------|--|
| ◊55HA2F | 2 contacts with closed-circuit switch (Schematic #4) | А | |
| 57HB3F* | 3 contacts at 180° | В | |
| 57HB5F* | 5 contacts at 180° | F | |
| 60HA4F | 4 contacts at 210° | D | |
| 61HA5F | 5 contacts at 240° | E | |
| 62HB7F* | 7 contacts at 270° | Н | |
| 62HB8F* | 8 contacts at 270° | N | |


^{*}Flared solder terminals

RECEPTACLE for Printed Circuit Board Mounting



TYPE 57NC5F - TYPICAL

Mounts to printed circuit boards. Special PC type terminals "snap-in" precut boards. See drawing. Tubular metal shell with ground contact. Part Number 58NC3F mates with either 3 pin or 5 pin (at 180°) plugs because of its 2 extra blanks in the contact insert.



ORDERING INFORMATION

| Part Number | Description | Contact Arrangement | |
|----------------|--------------------------------------|---------------------|--|
| 57NC5F | 5 contacts at 180° | F | |
| ⊘58NC3F | 3 contacts at 180° 2 extra blanks | С | |
| ♦60NC4F | 4 contacts at 210° | D | |
| 61NC5F | 5 contacts at 240° | E | |
| | 7 contacts at 270° H | | |
| 62NC8F | 8 contacts at 270° | 0° N | |

[&]quot;C" in part number indicates PC terminals.

[&]quot;A" in part number indicates straight terminal. (solder lug).

[♦] Available on special order only; contact Switchcraft for price and delivery.


 $[\]Diamond$ Available on special order only; contact Switchcraft for price and delivery.

RIGHT-ANGLE RECEPTACLE for Printed Circuit Board Mounting



TYPE 57PC5F-TYPICAL


Mounts to PC boards. Plugs connect at right-angle to mounting surface. Part Number 57PC3F mates with either 3 or 5 pin (at 180°) plugs because of two extra blanks in contact insert. ground contact provides complete shielding through receptacles.





ORDERING INFORMATION


| Part Number | Description | Contact Arrangement |
|----------------|----------------------|---------------------|
| ♦57PC3F | 3 contacts at 180° B | |
| 57PC5F | 5 contacts at 180° F | |
| ♦60PC4F | 4 contacts at 210° | D |
| 61PC5F | 5 contacts at 240° E | |
| 61PC6F | 6 contacts at 240° G | |
| ⊘62PC7F | 7 contacts at 270° | Н |
| 62PC8F | 8 contacts at 270° | N |


 \Diamond Available on special order only; contact Switchcraft for price and delivery.


















* Please visit the product pages on our website for the most up-to-date product information

| Part Number | Description | Contact Arrangement |
|-------------|----------------------|---------------------|
| ♦57PC3FS | 3 contacts at 180° B | |
| 57PC5FS | 5 contacts at 180° F | |
| ♦60PC4FS | 4 contacts at 210° | D |
| 61PC5FS | 5 contacts at 240° | Е |
| 61PC6FS | 6 contacts at 240° | G |
| 62PC7FS | 7 contacts at 270° | Н |
| 62PC8FS | 8 contacts at 270° | N |

SPECIFYING NOTE: Another series of receptacles with a trimmed metal flange .052" (1.32 mm) below housing top is available. Replace suffix "S" with "T" in part numbers above to specify these receptacles or contact Switchcraft. Mounting: #2 or #3 self-tapping screw.


♦ Available on special order only; contact Switchcraft for price and delivery.





RIGHT-ANGLE SHIELDED RECEPTACLE for printed circuit board mounting





TYPE 60PC4FS-TYPICALSimilar to 57PC5F - Typical, except flange surrounding face of insert is metal to provide through-grounding between plug and receptacle and to potential panel/chassis for common grounding.

















DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

DIN RECEPTACLES (continued)

MINI-DIN RIGHT-ANGLE RECEPTACLES

Miniature DIN right-angle connectors are designed for personal computer, video and data communications, medical and instrumentation equipment and systems.

RIGHT-ANGLE, PC MOUNT RECEPTACLES

Available with 3 through 8 contacts, female only, receptacles also have a standard (and separate) ground contact system. Ground terminal can be straight or snap-in type. Snap-in terminals are bifurcated to assure tight hold down on PC board before, during and after soldering. Solder wicking around the terminal strengthens the connection. Additionally, PC terminals are staggered to assure more "hold down" capability during soldering.

Receptacle/plug retention is "friction" type, and a separate outer shield can be specified.

Series SMD*FRAX10: 3 through 8 contacts, female, right-angle PC mount, straight ground terminal, and no outer shield.

Series SMD*FRAX20: Same as SMD*FRAX10, except with bifurcated snap-in ground terminal.

Series SMD*FRAX11: 3 through 8 contacts, female, right-angle PC mount, straight ground terminal, and outer shield.

Series SMD*FRAX21: Same as SMD*FRAX11, except with snap-in ground terminal.

Series DMD*FRAX111: Dual stacked miniature DIN connectors, available in 4, 5, 6, and 8 contacts. Shielded and non-shielded versions available.

Dimensions: .552" (14 mm) wide x .502"

(12.8 mm maximum depth x .642" (16.3 mm) height,

including terminals.





SPECIFICATIONS

Ratings: 1A, 100 VAC; 2A, 12 VDC. Insulation Resistance: 50 M Ω minimum Dielectric Strength: 250 VDC for 1 minute. Contact Resistance: 30 m Ω maximum Insertion/Withdrawal Force: 0.8 to 5 kilograms

Withdrawal Force: 0.8 to 4 kilograms

Contacts/Terminals: Copper alloy, silver or gold-plated

Ground Terminal: Copper alloy, nickel-plated. **External Shield:** Copper alloy, solder-coated. **Body:** Black molded thermoplastic, UL 94V-0.

MINI-DIN RIGHT-ANGLE RECEPTACLES PART NUMBER SCHEME

| Series | Contacts | Style | Shield/Ground | Optional Mounting Screw Hole |
|------------|----------|-------|--|------------------------------|
| SMD-Single | Insert#: | FRA | 110: Unshielded, no snap-in ground | A: Adds screw hole |
| DMD-Dual | 3-8 | | 111: Shielded, no snap-in ground 120: Unshielded, snap-in ground 121: Shielded, snap-in ground | Blank: None |

Note: Dual available in 4,5,6, and 8 only Note: Snap-in ground available on single only

Note: Optional mounting screw hole available on dual only

Note: Special order only, contact factory for details

CONTACT ARRANGEMENTS

(viewed from contact side)













7


8

CONNECTORS & RECEPTACLES


* Please visit the product pages on our website for the most up-to-date product information

DIN RECEPTACLES (continued)

SMD SERIES




RECOMMENDED PC BOARD LAYOUTS (Viewed from component side)





DIN RECEPTACLES (continued)

DMD SERIES



SINGLE AND DUAL STACKED USB CONNECTORS





PHONE: 773 792-2700

Switchcraft introduces single and dual USB connectors. The USB connectors are fast becoming the industry standard for plug and play connectivity between PCs and their peripherals. The DUSB and USB connectors are RAPC mounted, with kinked terminals for snap-in placement to the PC board. Both meet all Universal Serial Bus standards.

FEATURES AND BENEFITS

- Snap-in terminals facilitate wave soldering
- Shielded for reduced EMI/RFI emissions
- · Dual stacked version increases PC board density

APPLICATIONS

- Personal Computer
- Data Communications
- Medical Equipment
- Test Equipment
- Instrumentation

SPECIFICATIONS

GENERAL

Voltage Rating: 30 VAC (rms) Max.

Current Rating: Signal application only, 1A Max. per contact

Contact Resistance: 25m ohms Max. initial Temperature Rating: 32°F to 104°F (0°C to 40°C)

Insertion Force: 7.7 lbs Max. (3.5 kg Max.) **Withdrawal Force:** 0.8 lb Min. (0.4 kg Min.)

Life: 1500 cycles

MATERIALS

Body: Black, molded thermoplastic, UL 94V-0

Shell: Copper alloy, tin plated

Contact Terminal: Copper alloy, gold plating in mating area,


tin plating on solder tails, all over nickel plating.

| Part Number | Description |
|-------------------|---------------|
| SUSB Single | USB Connector |
| DUSB Dual Stacked | USB Connector |

Note: Special order only, contact factory for details.

Inch (mm)

SINGLE AND DUAL STACKED USB CONNECTORS (continued)



IEEE 1394 FIREWIRE CONNECTORS



1394SMT



Switchcraft introduces both right angle PC and surface mount versions of IEEE 1394 Firewire connectors. The Firewire connectors are becoming another connector standard used in the upcoming multimedia/computer market. The connectors meet IEEE 1394R-4006N Series standards.

FEATURES AND BENEFITS

- Shielded housings to reduce EMI/RFI emissions
- Mounting posts add stability for wave soldering
- Low profile requires less space

APPLICATIONS

- Multimedia
- Video
- · Personal Computers
- Computer Peripherals

SPECIFICATIONS

GENERAL

Voltage Rating: 40 VAC **Current Rating: 1.5A**

Contact Resistance: 30m Ohms Max. Temperature Rating: -55°C to +105°C


Insertion Force: 6.0 lbs. Max. Withdrawal Force: 4.4 lbs. Min.


Lifecycles: 1,500 Min.

| Part Number | Description |
|-------------|----------------|
| 1394RAPC | IEEE 1394 RAPC |
| 1394SMT | IEEE 1394 SMT |

Note: Special order only, contact factory for details.

IEEE 1394 FIREWIRE CONNECTORS (continued)





CONNECTORS & RECEPTACLES

* Please visit the product pages on our website for the most up-to-date product information

SLIM-LINE CONNECTORS

TYPICAL SL172F REAR MOUNT RECEPTACLE

HEX NUT

Used in mounting rear or front of panel receptacles (supplied standard)

BUSHING Coupler ring on mating plug threads onto bushing and keeps plug/receptacle

from working loose.

FEMALE INSERT* Rugged molded black plastic barrel construction: positively keyed to housing

FLATTED BARREL Keys to inside flat on male insert. Polarizes the connection. Correct mating every time.

PIN TERMINALS Large, rugged plated copper alloy; solder cup type.

CABLE CLAMP

Extra large and rugged clamp protects soldered terminations (also facilitates grounding/ shielding feature when used on receptacle insert)

CORD PLUG HOUSING

TYPICAL SL402M CORD PLUG

Precision-drawn. plated copper alloy with non-glare matte finish.

STRAIN RELIEF SPRING

Provides positive relief from cable wear at opening in plug housing.

LOCK WASHER

Prevents rear or front of panel receptacle from working loose when installed (supplied standard).

REAR OF

PANEL MOUNT

RECEPTACI E

Tough, plated

diecast housing

in D-shape (self-

receptacle types

are: Front of Panel

Mount and Flange

Mount.

keved) hole. Other

with non-reflecting

matte finish. Mounts





(supplied standard)

CONTACT TERMINALS Rugged solder lug type; copper alloy plated

CONTACTS Held captive in insert. Excellent pin retention force Copper alloy plated.

plated copper allov pins are 100% molded-in. *NOTE: Insert fits both plug and receptacle

LATCH SPRING Captive spring locks insert to housing

housings: can be interchanged at

any time.

MALE INSERT*

plastic; keyed to

housing. Durable

Rugged black

COUPLER RING Held captive on plug;

non-reflective matte finish. Threads onto receptacle bushing (or mating plug) to hold connector halves secure from accidental separation.

LATCH DETENT

Latch spring on insert seats in detent to hold insert firmly in housing.

DESIGN FEATURES

Slim-Line® Audio Connectors are a unique series of premium quality connectors featuring interchangeable inserts which allow any plug or receptacle to be male or female. This versatility is valuable in a wide variety of applications: microphones, public address systems, 2-way, CB, ham, and marine radios, audio-visual systems, industrial control and instrumentation, broadcast, security and medical electronics.

APPLICATIONS

Retrofit/Replacement; Slim Line Cord Plug (SL405M) and Receptacle (SL105F) are recommended as a possible choice to replace Switchcraft/DIN plug (12CL5M) and receptacle (55HA5F). Receptacle SL105F fits the same mounting holes as the Switchcraft/DIN receptacle.

Four pin/contact Slim-Line plugs and receptacles are recommended as direct replacements for the original Slim-Line connectors, Series 2504, and for the molded version of the Slim-Line connector, Style ST34.

RECEPTACLES

Three types of receptacles can be specified:

- 1. Flange mount (Series SL10)
- 2. Rear of panel mount (Series SL17)

Receptacles can be specified with same male and female insert combinations as cord plugs. For rear and front of panel mounting types, hex nuts, lock washers, and flat washers are supplied. For flange mount receptacles, mounting holes in flange accept #4 machine screw or .125" (3.18 mm) diameter rivet.

CORD PLUGS

Miniature Cord Plugs feature nickel-plated copper alloy housings with matte finish on exterior parts. Plugs may be specified with inserts having 2-, 3-, 4- and 5-pins (male) or contacts (female), or 2-, 3-, or 4-contact receptacles having shunts (N.C.) on two contacts (special order only). Extra large cable clamp protects against pulling and twisting strains on terminations. Strain relief spring protects against excess cable wear at entry point at rear of housing. Cord plugs accept cables up to .281" (7.14 mm) diameter. Captive coupler ring feature (Series SL40) provides secure mechanical connection and protection against shock and vibration between cord plugs and mating plug (Series SL41) or receptacle.

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

SLIM-LINE CONNECTORS (continued)

INSERTS

Inserts are molded of high-strength plastic, and are completely interchangeable between plug and receptacle housings at any time. Inserts are keyed to housings, and male and female inserts are polarized to prevent mismating.

PIN/CONTACT CONFIGURATIONS:

| Pins | Contacts | Contacts (Shunts) |
|------|----------|-------------------------------------|
| 2 | 2 | 2 (N.C. Shunt on each contact) |
| 3 | 3 | 3 (N.C. Shunts on contacts 1 and 3) |
| 4 | 4 | 4 (N.C. Shunts on contacts 1 and 4) |
| 5 | 5 | _ |

⟨Add an "S" to end of part number for shunts. Special order only.

Insert is installed from front, and the captive latch spring locks insert to housing. To remove insert from receptacle, depress latch spring and apply pressure to rear of insert (**DO NOT APPLY PRESSURE TO TERMINALS**). On cord plugs, depress latch spring and press in on strain relief to free the insert.

GROUNDING/SHIELDING

Housings shield internal connections and provide ground (common) connections without using a pin/contact. On cord plugs, ground lead (or shield) is connected to cable clamp. For receptacles Cable Clamp, **SL04** is ordered separately as a special and installed. If desired, ground/shield connection may then be made to clamp. When mated, a continuous, shielded, low resistance path is made through the connector.

| Part Number | Item |
|---------------|----------------------|
| ⊘SL01 | Hex Nut |
| ♦ SL02 | Lockwasher |
| ♦ SL03 | Flat Washer |
| ⊘SL04 | Cable Clamp |
| ⊘SL05 | Strain Relief Spring |

SPECIFICATIONS

MATERIALS

Receptacle Housings: Die-cast zinc, nickel-plated. Cord Plug Housings: Copper alloy, nickel-plated. Inserts: Glass-reinforced thermoplastic. UL 94 V-0.

Female Contacts: Copper alloy, silver-plated, solder lug type.

Pins: Copper alloy, silver-plated, solder cup type.

Cable Clamp, Strain Relief, and Mounting Hardware:

Steel, plated. Latch: Steel, plated.

ELECTRICAL

Current Rating: 5 Amps carry only.

MOUNTING

Cord Plugs: Plugs accept cables up to .281" (7.14 mm) diameter.

Receptacles: Flange mount type mounts in panels or chassis up to .188" (4.78 mm) thick. .125" (3.18 mm) diameter holes accept #4 machine screws or .125" (3.18 mm) diameter rivets. Rear and front of panel types mount in "D"-shaped hole in panels or chassis up to .219" (5.56 mm) thick. Hex nut (**SL01**), lockwasher (**SL02**), and flat washer (**SL03**) are supplied for mounting.

CABLE CLAMP AND STRAIN RELIEF

Cord Plugs: Plugs are supplied with rugged cable clamps and strain relief springs. Cable clamp serves two valuable functions: to firmly hold cable to prevent pulling or twisting strains on soldered terminations, and as a connecting point for ground (common) or shield when grounding/shielding through the connector is required.

Receptacles: Receptacles are not supplied standard with cable clamp for strain relief. If grounding/shielding feature is desired, separate Cable Clamp, **SL04**, is installed on receptacle insert.


MOUNTING HARDWARE

(Supplied with Series SL17 and SL18 receptacles)


SLIM-LINE CONNECTOR PART NUMBERING SYSTEM

| | SERIES | HOUSING TYPE | | Number of Contacts | Gender | Options |
|----|-----------|--------------|---------------------------------|-----------------------|----------|---------------|
| SL | SLIM-LINE | _ | NONE | 2 | M MALE | S WITH SHUNTS |
| | | 10 | RECEPTACLE, FLANGE MOUNT | 3 | F FEMALE | |
| | | 17 | RECEPTACLE, REAR MOUNT | 4 | | |
| | | 18 | RECEPTACLE, FRONT MOUNT | 5 | | |
| | | 40 | CORD PLUG WITH COUPLING RING | | | |
| | | 41 | CORD PLUG WITHOUT COUPLING RING | | | |

PIN AND CONTACT ARRANGEMENTS



SCHEMATIC CIRCUITS




CONNECTORS & RECEPTACLES


* Please visit the product pages on our website for the most up-to-date product information

SLIM-LINE CONNECTORS (continued)

SL40 CORD PLUG with Coupler Ring









Non-reflective metal shell; coupling ring; 2 through 5 pins (male) or 2 through 5 contacts (female). Also 2-, 3- and 4-contact inserts with two shunted (N.C.) contacts. Efficient cable clamp and strain relief.

SL41 CORD PLUG without Coupler Ring







Non-reflective metal shell; 2 through 5 pins (male) or 2 through 5 contacts (female). Also 2-, 3- and 4-contact inserts with two shunted (N.C.) contacts. Efficient cable clamp and strain relief.

SL MALE CORD PLUGS

| Part Number | Pins | Pin Arrangements |
|-------------|------|---------------------|
| SL402M | 2 | 1 |
| SL403M | 3 | 2 |
| SL404M | 4 | 3 |
| SL405M | 5 | 4 |

SL FEMALE CORD PLUGS

| Part Number | Contact | Contact Arrangements |
|-------------|---------|-------------------------|
| SL402F | 2 | A |
| SL403F | 3 | В |
| SL404F | 4 | С |
| SL405F | 5 | D |

STRAIN RELIEF SPRING Strain Relief Spring Part Number SL05



SL MALE CORD PLUGS

| Part Number | Pins | Pin Arrangements |
|-------------|------|---------------------|
| SL413M | 3 | 2 |
| SL414M | 4 | 3 |
| SL415M | 5 | 4 |

SL FEMALE CORD PLUGS

| Part Number | Contacts | Contact Arrangements |
|-------------|----------|-------------------------|
| SL412F | 2 | Α |
| SL413F | 3 | В |
| SL414F | 4 | С |
| SL415F | 5 | D |

♦ Available on special order only; contact Switchcraft for price and delivery.


SLIM-LINE CONNECTORS (continued)

SL10 RECEPTACLES Flange Mount



SL104F (typical)








SL17 RECEPTACLES Rear of Panel Mount

SL17 and SL18 Receptacles Non-turn panel cut-out

SL175F (typical)








Flange mounted; 2 through 5 pins (male) or 2 through 5 contacts (female). Also 2-, 3- and 4-contact inserts with 2 shunted (N.C.) contacts.

DIA. LOCKWASHER 625-27 UNS-2A THREAD



Rear of panel mount; 2 through 5 pins (male) or 2 through 5 contacts (female). Also 2-, 3- and 4-contact inserts with 2 shunted (N.C.) contacts. Mounting locknut (Part Number SL01), lock washer (Part Number SL02), and flat washer (Part Number SL03) supplied.

SL MALE RECEPTACLES

| | | Pin |
|-------------|------|--------------|
| Part Number | Pins | Arrangements |
| SL102M | 2 | 1 |
| SL103M | 3 | 2 |
| SL104M | 4 | 3 |
| SL105M | 5 | 4 |

SL FEMALE RECEPTACLES

| Part Number | Contacts | Contact Arrangements |
|-------------|----------|-------------------------|
| SL102F | 2 | A |
| SL103F | 3 | В |
| SL104F | 4 | С |
| SL105F | 5 | D |

SL MALE RECEPTACLES

| Part Number | Pins | Pin Arrangements |
|-------------|------|---------------------|
| SL173M | 3 | 2 |
| SL174M | 4 | 3 |
| SL175M | 5 | 4 |

SL FEMALE RECEPTACLES

| | | Contact |
|-------------|----------|--------------|
| Part Number | Contacts | Arrangements |
| SL172F | 2 | A |
| SL173F | 3 | В |
| SL174F | 4 | С |
| SL175F | 5 | D |


 \Diamond Available on special order only; contact Switchcraft for price and delivery.

SLIM-LINE CONNECTORS (continued)

SL18 RECEPTACLES Front of Panel Mount



SL183FS (typical)



Front of panel mount; 2 through 5 pins (male) or 2 through 5 contacts (female). Also 2-, 3- and 4-contact insert with 3 shunted (N.C.) contacts. Mounting locknut (Part Number SL01), lockwasher (Part Number SL02), and flat washer (Part Number SL03) supplied.

SL MALE RECEPTACLES

| | | Pin |
|-------------|------|--------------|
| Part Number | Pins | Arrangements |
| SL182M | 2 | 1 |
| SL183M | 3 | 2 |
| SL184M | 4 | 3 |
| SL185M | 5 | 4 |

SL FEMALE RECEPTACLES


| Part Number | Contacts | Contact Arrangements |
|-------------|----------|-------------------------|
| SL182F | 2 | A |
| SL183F | 3 | В |
| SL184F | 4 | С |
| SL185F | 5 | D |

INSTALLING CABLE CLAMP ON INSERT

To install cable clamp on any insert:

- 1. Position insert approximately as shown in the diagram.
- 2. Hold clamp at approximately 30° angle (as shown). Place tip of clamp center finger into slot under molded ring "A". Note position of notch on insert in relation to slot.
- 3. Press center finger forward into slot and reduce angle of clamp until clamp shoulders seat just ahead of molded barrier on rear of insert "B".

Cable Clamp SL04




CB CONNECTORS

Miniature 3 and 4 circuit connectors for microphone connections in mobile/communications equipment. Cord plug has silver-plated copper alloy contacts, large cable clamp, and strain relief spring.

CB-3F 3-contact female cord plug. Knurled coupling ring has internal metric M16x1 thread. Solder lug terminals accept wires up to #18 AWG. Accommodates cables up to .281" (7.14 mm) diameter.

CB-4F Same as CB-3F. except 4 contacts.




CB-3M 3-pin male receptacle. Housing keys insert of mating plug; bushing with external M16x1 metric thread mates with coupling ring on plug. Cup-type terminals accept wires up to #16 AWG. Mounts in .64" (16.26 mm) diameter hole from front of panels up to .125" (3.18 mm) thick, using washer and locknut supplied. Can also be "D"-hole mounted for non-turn mounting (see drawing). Pin diameter. is .093".

CB-4M Same as CB-3M, except 4 pin.


| Insert | | Dimensions, In. (mm) | | |
|----------|----------|----------------------|--------------|--|
| Part No. | Contacts | Length | Diameter | |
| CB3F | 3 | 1.594 (40.49) | .703 (17.86) | |
| CB3M | 3 | .781 (19.84) | .705 (19.05) | |





MICROPHONE CONNECTORS

Connectors with 5/8-27 threads are designed for use with single conductor microphone cable with .281" (7.14 mm) maximum outside diameter. 44 adapts 2501F to fit standard 2-conductor phone jack. Coupling ring on 2501F is removable for fast change from female to male type. Spring assembled into body, cable braid and spring clamped by hollow set screws .281" (7.14 mm) maximum cable diameter. 2501MP mounts in .390" (9.92 mm) diameter hole.



MINI-CON MINIATURE CONNECTORS

Approximately 1/2 the size of standard microphone connectors. Ideal for miniature lapel microphones, musical instruments and wherever small cable is used. Accepts single-conductor shielded cable up to .187" (4.76 mm) diameter Coupling ring on 5501F removable for guick change of female to male type. Cable is braid spring clamped to body by hollow point set screw.

| Part Number | Description | Mounting Hole, Inches (mm) |
|----------------|-------------|---------------------------------|
| 5501F | Female Plug | _ |
| ♦5501M | Male Plug | _ |
| ♦5501MF | Receptacle | .375 (9.52) (Front of panel) |
| 5501MP | Receptacle | .375 (9.52) (Front of panel) |

⟨Available on special order; contact Switchcraft for price and delivery.









5501MF

5501MP

HP75BNC SERIES BNC CONNECTORS



Switchcraft Inc. introduces a complete line of true 75 Ohm BNC cable mount connectors. This new series was developed for the broadcast industry, or wherever true 75 Ohm impedance BNC's are used. The HP75BNC Series is available in a wide range of styles, to accommodate the most popular types of coaxial cables. All are crimp terminated using standard crimping tools.

PHONE: 773 792-2700

FEATURES AND BENEFITS

- True 75 Ohm impedance
- Gold-plated center pins for increased life
- Available for a wide range of cable types
- Outstanding electrical performance
- Rugged nickel-plated, machined shells

SPECIFICATIONS

Electrical

Characteristic Impedance: 75 Ohms Voltage Rating: 500 Volts RMS

Return Loss: Less than -25 db at 3 GHz **Insulation Resistance:** 5000 Megohms min

MECHANICAL Lifecycles: 500 min

Center Contact Retention: 6 lbs. min Coupling Mechanism: 100 lbs. min Force to Engage: 2.5 lbs. max

ENVIRONMENTAL

Thermal Shock: -65° C to 165° C Moisture Resistance: Mil Std 202

Corrosion: Mil Std 202 Flammability: UL 94-VO Vibration: Mil Std 202

Solvent Resistance: Mil Std 202


FINISH


Body/Bayonet: Nickel-plated copper alloy **Center Conductor:** 50 mi gold-plated copper alloy

ORDERING INFORMATION

| Part Number | Cable Type |
|-------------|---------------|
| HP75BNC1 | Belden #8241 |
| HP75BNC2 | Belden #8281B |
| HP75BNC6 | Belden #1695A |
| HP75BNC7 | Belden #1694A |
| HP75BNC9 | Belden #1505A |
| HP75BNC10 | Belden #1506A |
| HP75BNC12 | Belden #1855A |

HP75BNC SERIES BNC CONNECTORS (continued)







EAC RECEPTACLES

SERIES EAC

Two and three-pin/contact grounding primary power receptacles are designed to meet EN 60 320, as well as applicable UL, CSA, VDE and other specifications. Receptacles feature choice of short, standard or long solder lugs or FASTON ® terminals. Receptacles snap-in or screw mount from the front or rear of panel. Receptacles have orbitally riveted lugs (except EAC233, EAC305, EAC323 EAC325, EAC333, EAC405) for superior mechanical/electrical connections. Extended socket versions permit minimum behind-panel depth.







Receptacles are designed for use in European and domestic instrumentation, power rack mounted devices, test equipment and appliances. Three-pin male receptacles have .125" (3.18 mm) longer center (ground) pin. Ground circuit is established before power circuits "make", and is maintained until after power circuits "break".



DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

EAC RECEPTACLES (continued)

SERIES EAC





SPECIFICATIONS ELECTRICAL

Insulation Resistance: 2 million megohms @ 500 V DC.

Dielectric Strength: 1500 V (rms). **Arcing Test:** Meets UL 498 Standard.

MECHANICAL

Solderability Standard: Meets MIL-STD-202, method 208, EIA RS-186-9E.

ENVIRONMENTAL

Thermal Range: -55° C to +65° C (except EAC45x series). **Salt Spray:** Meets MIL-STD-202, method 101; EIA-RS-186-5E, method 5.

MATERIAL

Shell: EAC307 through EAC327. Black polyester. EAC303, EAC307 through EAC315. UL flammability rating of UL94 V-0, yellow card #E45575.

EAC309 through EAC327, EAC333. Black polyester, UL flammability rating of UL94 V-0, yellow card #E45575.

EAC233, EAC233S, EAC305, EAC325, and EAC333S. Black polycarbonate, UL flammability rating of UL94 V-0, yellow card #E45329.

EAC323, EAC409 through EAC411 Black polycarbonate, UL flammability rating, or equivalent UL94 V-0, yellow card #E33640, or equivalent.

Pins, Contacts and Terminals: Plated copper alloy.

◊EAC227—2-pin male receptacle with standard solder lug terminals, similar to EAC327.

◇EAC233—2-pin, male receptacle with right-angle housing for PC mount. PC terminals project .130" (3.3 mm) to extend through PC board. Rear of panel mount. Two, .136 " (3.45 mm) diameter holes permit fastening to PC board; two additional .136" (3.45 mm) holes are for fastening to panel or chassis, if required.

◊EAC233S—Similar to EAC233, but with two, snap-in retainers through mounting flanges for PC mount.

EAC305—3-contact female receptacle. Front mount with two, #4 screws or .094" (2.38 mm) diameter rivets (not supplied).

EAC309—3-pin male receptacle with standard lug terminals. Mounts from front or rear of panel with two, #5 screws or .125 " (3.18 mm) diameter rivets (not supplied).

EAC311—3-pin male receptacle with FASTON® terminals. Mounts from front or rear of panel with two, #5 screws or .125 " (3.18 mm) diameter rivets (not supplied).

◊EAC315—3-pin male receptacle with long solder lug terminals. Mounts from front or rear of panel with two, #5 screws or .125" (3.18 mm) diameter rivets (not supplied).

⟨EAC319—3-pin male receptacle with short solder lug terminals. Mounts from front or rear of panel with two, #5 screws or .125" (3.18 mm) diameter rivets (not supplied).

⟨EAC323—3-pin male receptacle with short solder lug terminals.
Extended socket housing (mounting flange on rear of receptacle) provides more behind panel clearance. Mounts with two, #4 screws or .094" (2.38 mm) diameter rivets (not supplied).

EAC325—3-contact female receptacle with short solder lug terminals. Extended housing (mounting flange on rear of receptacle) provides more behind panel depth. Mounts with two, #4 screws or .094" (2.38 mm) diameter rivets (not supplied).

EAC327—3-pin male receptacle, similar to EAC319 except with standard solder lugs.

EAC333—3-pin, 10A, 250V male receptacle with right-angle housing for PC mount. PC terminal and hole mounting details are the same as for EAC233. Ground pin is integral with ground solder lug on rear of receptacle.

EAC333S—Similar to EAC333, but with two, snap-in retainers through mounting flanges for PC mount.

⟨**EAC405**—3-contact female receptacle with standard solder lug terminals. Snap-in panel mounting.

EAC409—3-pin male receptacle with standard solder lug terminals. Snap-in panel mounting.

EAC411—3-pin male receptacle with FASTON terminals. Snap-in panel mounting.

EAC413—3-pin male receptacle with FASTON terminals on LINE and NEUTRAL and a solder lug on EARTH GROUND. Snap-in panel mounting.

EAC451—3-contact female receptacle with straight PC terminals for use in "HOT" applications. Snap-in panel mounting.

EAC453—Same as EAC451 except with solder lug terminations.

EAC455—Same as EAC451 except with FASTON terminations.

EAC457—Same as EAC451 except with FASTON power terminations and solder lug ground termination.

♦ Available on special order only; contact Switchcraft for price and delivery.

SWIFCHOFAFF CONNECTORS & RECEPTACLES

* Please visit the product pages on our website for the most up-to-date product information

SERIES EAC (continued)

| Part Number | Pins/ Contacts ¹ | Mounting ² | Terminals | Listings | Ratings | Switchcraft Mating Number ³ | Comments ⁴ | |
|---------------------|--------------------------------|-----------------------|-----------------------|-----------------|---------------------------------|---|--|--|
| ♦EAC227 | М | Front or Rear | Solder Lug | UL CSA | 15 A, 250 V AC | P2392 | _ | |
| ♦EAC233 | М | Rear | PC | UL, CSA, VDE | 15 A, 250V AC 10 A, 250 V AC | P2392 | Semko, Demko, Nemko, SETI, and SEV Approved | |
| ♦EAC233S | M | Rear | PC | UL, CSA, | 15 A, 250 V AC | - P2392 | Semko, Demko, Nemko, | |
| V2/102000 | | rioui | | VDE | 10 A 250 V AC | 1 2002 | SETI, and SEV Approved | |
| EAC305 | F | Front | Solder Lug | UL & VDE | 15 A, 250 V AC | _ | Semko, and SEV Approved | |
| LAGGOO | ' | Tiont | | VDE | 10 A, 250 V AC | | Conno, and OLV Approved | |
| EAC309 | M | Front or Rear | Solder Lug | UL & CSA | 15 A, 250 V AC | P2392 | Demko, Semko, Nemko, | |
| 2710000 | | Tront of Floar | | VDE | 10 A, 250 V AC | 1 2002 | SETI and SEV Approved | |
| EAC311 | М | Front or Rear | FASTON | UL & CSA | 15 A, 250 V AC | P2392 | Semko, Demko, Nemko, | |
| 27.0011 | | Tront or rious | 17101011 | VDE | 10 A, 250 V AC | 1 2002 | SETI and SEV Approved | |
| ♦EAC315 | М | Front or Rear | Solder Lug | UL & CSA | 15 A, 250 V AC | P2392 | Semko, Demko, Nemko, | |
| VEAGGIO | 141 | Tront of rical | (Long) | VDE | 10 A, 250 V AC | 1 2002 | SETI and SEV Approved | |
| ♦EAC319 | M | Front or Rear | Solder Lug (Short) | UL & CSA VDE | 15 A, 250 V AC | P2392 | _ | |
| | | | Solder Lug | UL & CSA | 15 A, 250 V AC | | Mounting flange on rear | |
| ♦EAC323 | M | Front or Rear | (Short) | VDE | 10 A, 250 V AC | P2392 | Semko, Nemko, SETI Approve | |
| | _ | _ | Solder Lug | UL & CSA | 15 A, 250 V AC | | | |
| EAC325 | F | Rear | (Short) | VDE | 10 A, 250 V AC | _ | Mounting flange on rear | |
| | | | | UL & CSA | 15 A, 250 V AC | | Demko, Semko, Nemko | |
| EAC327 | М | Front or Rear | Solder Lug | VDE | 10 A, 250 V AC | P2392 | SETI and SEV Approved | |
| | | _ | | UL, & VDE | 15 A, 250 V AC | | Semko, Demko, Nemko, | |
| EAC333 | М | Rear | PC | CSA | 10 A, 250 V AC | P2392 | SETI, SEV Approved | |
| \=.a | | _ | | UL & VDE | 15 A, 250 V AC | 50000 | Semko, Demko, Nemko, | |
| ♦EAC333S | М | Rear | PC | CSA | 10 A, 250 V AC | P2392 | SETI, SEV Approved | |
| ^=4040= f | _ | 0 1 | 0.11 | UL & CSA | 15 A, 250 V AC | | | |
| ◊EAC405 ⁵ | F | Snap-In | Solder Lug | VDE | 10 A, 250 V AC | _ | _ | |
| E404007 | | 0 1 | 0.11 | UL, & CSA | 15 A, 250 V AC | Doogs | Demko, Semko, Nemko, | |
| EAC409 ⁵ | М | Snap-In | Solder Lug | VDE | 10 A, 250 V AC | P2392 | SETI and SEV Approved | |
| | | | | UL, CSA | 15 A, 250 V AC | 50000 | Semko, Demko, Nemko, | |
| EAC411 ⁵ | М | Snap-In | FASTON | VDE | 10 A, 250 V AC | P2392 | SETI and SEV Approved | |
| | | | Solder Lug/ | UL, CSA | 15 A, 250 V AC | | Semko, Demko, Nemko, | |
| EAC413 ⁵ | М | Snap-In | FASTON | VDE | 10 A, 250 V AC | P2392 | SETI and SEV Approved | |
| | _ | | | UL, & CSA | 15 A, 250 V AC | | | |
| EAC451 ⁶ | F | Snap-In ⁶ | PC | VDE | 10 A, 250 V AC | _ | Rated for use up to 120°C | |
| | _ | | | UL, & CSA | 15 A, 250 V AC | | | |
| EAC453 ⁶ | F | Snap-In ⁶ | Solder Lug | VDE | 10 A, 250 V AC | - | Rated for use up to 120°C | |
| | | | E10=2:: | UL, & CSA | 15 A, 250 V AC | | B | |
| EAC455 ⁶ | F | Snap-In ⁶ | FASTON | VDE | 10 A, 250 V AC | _ | Rated for use up to 120°C | |
| | | | Solder Lug/ | UL, & CSA | 15 A, 250 V AC | | | |
| EAC457 ⁶ | F | Snap-In ⁶ | FASTON | VDE | 10 A, 250 V AC | 1 - | Rated for use up to 120°C | |

¹ M = Male; F = Female.

ending in an even number, you can now buy an identical part number that has a 10 amp European rating in addition to the 15 amp UL and CSA approval. The part number for the new dual rated part is one less than the old part number (eg. EAC310 becomes EAC309, EAC412040 becomes EAC411040, EAC234 becomes EAC233, EAC458050 becomes EAC457050, etc.)

If you have been using a 15 amp rated Switchcraft EAC connector

² F = Front; R = Rear. See mounting drawings for mounting details.

³ Also mates with Belden and other standard cords.

⁴ Semko (Sweden), Demko (Denmark), Nemko (Norway), SETI (Finland), SEV (Switzerland).

⁵ Receptacles are snap-in mount, and can be ordered to accommodate .030, .040, .050 and .060 inch panel thickness. For snug fit in panel or for other specifying assistance, contact Switchcraft.

⁶ Available only for .050 inch and .060 inch panel thickness

[♦] Available on special order only; contact Switchcraft for price and delivery.

UL No. E38829-EAC-309 thru -327 UL No. E65081-EAC-305


CSA Guide 365-E-1, Class 6233, File Card No. LR27474


all others VDE approval No. 3181.


VDE Certificate of Compliance No. 731 (EAC-305, -325, -405),
DIMENSIONS ARE FOR REFERENCE ONLY


EAC RECEPTACLES (continued)


SERIES EAC























Recommended
PC Board Layout
EAC233, EAC333
Figure 10

O7 ±.003
[I.8]
HOLE DIA. (3)


778 CTR. FOR MTG.


Note: Center .07 inch diameter hole not used for 233, 234


Note: Unless otherwise specified, all dimension tolerances are \pm .01" (+0.25 mm)


EAC RECEPTACLES (continued)


SERIES EAC

















Chassis/Panel Opening


Note: Unless otherwise specified, all dimension tolerances are \pm .01" (+0.25 mm)


DIMENSIONS ARE FOR REFERENCE ONLY


Inch (mm)


EAC RECEPTACLES (continued)


SERIES EAC
















EAC RECEPTACLES (continued)

SERIES EAC




EAC RECEPTACLES (continued)


SERIES EAC



EAC RECEPTACLES (continued)


SERIES EAC





EAC RECEPTACLES (continued)

SERIES EAC



RAPC322 POWER INLET SOCKET

Switchcraft introduces the RAPC322, an IEC320 inlet developed as a low power interconnect used in a variety of applications. The RAPC322 is molded from 94-VO rated material, is UL recognized, and meets a wide variety of approvals including CSA and VDE. The RAPC is rated at 2.5A at 250V. Applications for the RAPC322 include notebook computers, medical devices, and data communications products.

FEATURES AND BENEFITS

- · Snap-in feet facilitate wave soldering
- Top and side slots allow chassis to captivate connector
- Conforms to EN 60320-1/2

APPLICATIONS

- Appliance Inlet
- Personal Computer
- Data Communications
- Medical Equipment
- Test Equipment
- Instrumentation

SPECIFICATIONS GENERAL


Current Rating: 5A, UL and CSA 2.5A, VDE and


SEMKO Nominal Voltage: 250V

Temperature Range: - 55°C to 65°C

Dielectric Strength: 2000V @ 1 minute **MATERIALS**

Housing: Black, molded thermoplastic, UL 94V-0 Male Pins: Copper alloy, nickel plated PC Terminals: Copper alloy, tin plated






14.65

.577





JACK SCHEMATICS


FAX: 773 792-2129

Circuit Types: Jacks normally have through circuits, shunt circuits, and/or isolated switching circuits, either individually or in various combinations. The chart below shows schematics of 39 common jacks - many more combinations are possible, but these are the most commonly used. A basic description of the switching action of each jack accompanies each schematic.

Military Identification: Military specifications covering phone jacks use a special code to describe jack functions. Jack schematic descriptions are coded J-1 through J-13 (as appropriate) to coincide with Federal Item Identification Guides for Supply Cataloging. One or more groups of suffix numbers/letters identify isolated switching circuits used. Suffixes identify the switching by industry recognized notation, i.e., 1-A, 1-B, 1-C, 1-D, etc. See chart below.

| Notation | Meaning |
|----------|---|
| 1-A | One, SPST switching circuit. Also known as NO (normally open) or "make" circuit. |
| 1-B | One, SPST switching circuit. Also known as NC (normally closed) or "break" circuit. |
| 1-C | One, SPDT switching circuit. Also known as transfer or "break" before "make" circuit. |
| 1-D | One, SPDT switching circuit. Also known as "make" before "break" circuit. |

NOTE: Number indicates the quantity of circuit - 2-A means 2, A circuits. Terminals locations shown on jack schematics do not necessarily coincide with physical locations on jacks. Not all circuit types available on all jacks.



DIMENSIONS ARE FOR REFERENCE ONLY

Single closed circuit

plus "make" before

"break". Isolated

switching-"make"

before "break"

circuit. (J8-1D).

Single open circuit.

Isolated switching-

(J1-1A-1C).

separate transfer and "make" circuits.

Single closed circuit.

common to isolated

(J4-1B).

switching circuit throw.

Isolated switching "break" circuit. Sleeve

Double closed circuit.

"make" circuit on ring

Isolated switching

spring. (J7-1A).

Double open circuit.

circuits on both tip and

Isolated switching-

separate "make"

ring. (J2-2A).

JACKS AND PLUGS


* Please visit the product pages on our website for the most up-to-date product information

JACK SCHEMATICS

XXVI



Single closed circuit. Isolated switching-"make" before "break" circuit. (J4-1D).



Tip closed; ring open circuits. Isolated switching-two "make" circuits and one "break" circuit. (J10-2A-1B).

XXVIII




Single open (tip) circuit and single closed (ring) circuit. (J9).

XXIX




Double jack, 2-conductors on each side. Tip circuits cross shunted: common sleeve. (J12).


XXX




Single open circuit-"make" before "break". (J11).




Tip closed; ring closed circuits. Isolated switching-"break" before "make" circuit.




Double closed circuit. Separate sleeve "break" circuit.




Single closed circuit. Isolated switching-Two "make" circuits.



Single open circuit. Isolated switching-Two "make" circuits.



Double open circuit. Isolated switching-One "make" and one "break" circuit.




Double closed circuit. Isolated switching-One "make" and one "break" circuit.

XXXVII




Tip closed; ring open circuits. Isolated switching-One "make" circuit.



Double closed circuit. Isolated switching-Two "make" circuits.





Double open circuit. Isolated switching-"break" before "make" circuit.

WIRE-WRAPPING TERMINATIONS

Switchcraft can build complete Jack Panel Assemblies with jacks, lamp jacks and switches with wire-wrapping terminals. If desired, components with solder lugs and wire-wrapping terminals can be installed in the same assembly.

WIRE-WRAPPING TERMINAL DESIGN

Jack springs with integral wire-wrapping terminals are made of special copper alloy for maximum work-life with excellent resistance to corrosion. Shank of terminal accommodates a maximum of three wire connections. Tini-Telephone® phone jacks, lamp jacks and switches with wire-wrapping terminals have slightly higher stack due to greater spacing required for wrapping tool access. Actuator springs and ground lug terminals are .704" long by .060" wide.

WIRE-WRAPPING CONNECTIONS

Use the chart below as a guide to recommended tools to be used with varying terminal thickness and wire gauges.

| Terminal | | Recommended Wire-Wrapping Tool (Gardner-Denver Co. Part Numbers) | | | | |
|----------------|---------|--|-------------------------------|--|--|--|
| Thickness | Wire | Use with 14B1-A | Use with 14B1-A Wrapping Tool | | | |
| (Inches) | Gauge | Wrapping Bit | Sleeve | | | |
| .020 thru .032 | 22 & 24 | 500131 | 18840 | | | |
| .016 | 24 | 500131 | 18840 | | | |
| .016 thru .032 | 26 | 37006 | 17611-2 | | | |

SPECIFYING NOTE: Due to assembly variations containing components (solder lugs, wire-wrapping terminals, or both), these Jack Panel Assemblies are available on special order only. Contact Switchcraft.

JACK MATING DATA

NOTE: See tables for jack/plug mating data



FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

1/4" LONG FRAME TELEPHONE JACKS

JACK MATERIALS

The complete Switchcraft line of standard size panels, jacks, plugs, switches and accessories are rugged, premium quality devices...hand-crafted by experts...100% inspected... and carefully adjusted to meet the traditionally high quality demands of the telephone industry and the military. Tightly controlled incoming inspection, manufacturing methods, and QC procedures assure you of long-life, reliable components. Typical applications where Switchcraft components have been specified for more than five decades are: telephone central office equipment, switchboards, jackfields, test and patch panels, and station equipment; TV and radio broadcasting consoles; PA and communication consoles; telegraph systems and apparatus; multichannel video and audio patching; and data processing equipment, such as computers, telemetry, I/O devices and facsimile.

FRAMES – Jack frames are heavy steel, formed and press welded for added strength. Side member adds to frame rigidity and resistance to shock and vibration. Both "A" and "C" type frames can be supplied. (See next page.)


SPRINGS – A special copper alloy is used for leaf springs because it offers excellent mechanical and electrical characteristics, and good corrosion resistance. The spring alloy has special hardness and ductility, and springs are produced from custom-designed dies. Although normally adjusted to mate with telephone (and MIL-type) plugs, springs can be adjusted to mate with commercial phone plugs.

BUSHINGS – Bushings are copper alloy (except insulated jacks), drilled to accept either a standard (.250" diameter finger) plug or a popular smaller (.206" diameter finger) plug. Series M Hi-D Jax® have a threaded brass bushing, or a molded thermoplastic bushing for insulated mounting.

CONTACTS – Jack design includes "wiping" action of contacts for low resistance connections. The contacts supplied depend on the jack selected. Gold or silver plating is normally offered as an option on tip, ring and/or sleeve springs. Several precious metals and shapes are used on jacks.

Material Shape Description Palladium Welded Best overall combination of life, Crossbar current carrying, and resistance to environment. Also known as WEco #2. Fine silver Riveted. Carries higher current than button-type palladium. Gold alloy Welded Recommended for dry circuit Crossbar Excellent resistance to switching. corrosion and contamination. Also known as WEco #1 Fine silver Riveted. Heavy currents. (Large) button-type Plating Gold or For lower contact resistance Silver (used on through circuit springs). **SOLDER LUGS TERMINALS** – Lugs project out directly from rear of jack and are solder-coated for easy wiring and soldering. Offset lugs can be supplied on special order (except standard on MT-Jax®). Jacks with offset ground lugs are particularly suitable for bussing connections on jack panels. Contact Switchcraft for special order lug requirements.





STRAIGHT SOLDER LUGS

OFFSET SOLDER LUGS


WIRE-WRAPPING TERMINALS — Wire-wrapping eliminates the need for soldering. Each terminal accepts up to three wrapped wires (22 or 24 gauge, 5 wraps each), applied with standard wire-wrapping tools. Terminal base has standoff shoulder which prevents first wrapped wire from accidentally sliding down and shorting against another terminal or adjacent spring. Terminal tips are radiused to facilitate positioning of wire-wrapping tool over terminals. See page 80 for wire-wrapping data.

WIRE-WRAPPING TERMINALS



PRINTED CIRCUIT TERMINALS – Components can be supplied with printed circuit terminals on special order. Terminals can be specified in various lengths to accommodate different thicknesses of single and double sided boards, as well as multilayers, and flat flexible cable and circuitry.

PRINTED CIRCUIT TERMINALS (SPECIAL)




OTHER TERMINALS – Many other special terminal styles are possible. For example, where mounting permits, jacks can be supplied with stacks having right-angle terminals. Contact Switchcraft for special terminals.

CUSTOM COMPONENTS


Only the most popular types of jacks are listed.

Inch (mm

LONG FRAME TELEPHONE JACKS



Details of Typical Buss Wiring of Jacks with Offset Ground Lugs



Long frame jacks are designed especially for high quality communication equipment, and to meet exacting MIL specifications, as well as telephone and communication systems. Many jacks have WEco equivalent types. MT-Jax® phone jacks are offered in four styles: MT-Jax®, WMT-Jax®, XMT-Jax® and YMT-Jax®. Rugged steel frames are produced in specially designed dies, press welded to provide rigidity and dimensional stability required by telephone and communication jack panels - and to meet MIL frame strength tests. "A" and "C" frame styles are available.

TERMINALS – Solder Lug: All MT-Jax[®] have solder lug terminals. Wire-Wrapping Terminals: WMT-Jax® have wire-wrapping terminals. Offset Ground Lugs: XMT-Jax® and YMT-Jax® have ground lugs, which simplify production line wiring time. A single row of jacks can be installed with a single buss wire connected to all ground lugs in a row, or when double rows are mounted on .625" vertical centers with lugs oriented between rows, holes in ground lugs line up so a single buss wire provides connections for both rows. XMT-Jax® have ground lugs oriented away and YMT-Jax® are oriented toward jack frame. See illustration.

MIL STANDARDIZATION - MIL jack types listed have been adjusted for use with plugs specified in Amendment No. 1, MIL-P-642, usually M642/1-1, M642/1-2, M642/2-1, M642/2-2, M642/4-1 or M642/4-2. When applicable, specify the plug you will use; we will adjust with that plug where the item is not a MIL-type. NOTE: MT-Jax® jacks Numbers \(\Delta MT-342B \) and \(\Delta MT-344B \) have shorter bushings, 0.5" long with a hold inside diameter of .21". They will mate with MIL plug M642/5-1 or M642/8-1. M642/5-1 plug (Switchcraft 480) cannot be used with ⟨MT-342B or ⟨MT-344B if these jacks are mounted on standard .625" thick panels. The short jack bushings are recessed .125", and the M642/5-1 is too wide to fit in the panel recess. Use plug M642/8-1 (Switchcraft 484) with a narrower diameter to fit in the recess and mate properly.

CONTACTS – Contacts on shuts and isolated switching circuits are welded crossbar palladium. Welded crossbar gold alloy contacts (WEco #1) are available on special order for dry circuit applications.

SPECIFICATIONS

Frame and Stack Screws: Plated steel, with iridescent iridite finish.

Springs: Copper alloy, spring tempered. Solder lugs are tinned. Bushings: Plated copper alloy standard. Natural brass finish

Insulation: Rigid plastic spacers (MIL-type PBE-P per Specification LP-513). One piece molded through stack. Contacts: Welded crossbar palladium contacts in shunt and isolated switching circuits are standard. Gold alloy (WEco #1) and fine silver are available on special order.

MECHANICAL

Life: Commercial jacks: 10,000 insertion/withdrawal cycles, minimum. Military Jacks: 20,000 insertion/withdrawal cycles, minimum. Mechanical Shock: Military Jacks - Per MIL-STD-202, method 213, Test Condition H (75g).

Vibration: Military Jacks – Per MIL-STD-202, method 213, (10-55 Hz).

ELECTRICAL

Contact Resistance: Commercial Jacks - .030 ohms maximum (initial), .050 ohms maximum (after humidity, durability exposure). Military Jacks - .010 ohms maximum (initial), .020 ohms maximum (after life), .10 ohms maximum (after salt spray).

Insulation Resistance: Commercial Jacks - 10,000 M Ω minimum (initial), 1,000 M Ω minimum (after humidity). Military Jacks – 10,000 M Ω minimum (initial), 1,000 M Ω minimum (after humidity, durability exposure).

Dielectric Withstanding Voltage: 500 V, 60 Hz (rms) AC.

ENVIRONMENTAL

Thermal Range: Commercial Jacks - -55°C to +85°C (non-operating); -20°C to +65°C (operating). Military Jacks --55°C to +85°C (non operating); -40°C to +65°C (operating). Thermal Shock: Commercial Jacks - Per MIL-STD-202, method 107. Military Jacks - Per MIL-STD-202, method 107. Humidity: Commercial Jacks - Per MIL-STD-202, method 106. Military Jacks – 0% to 95% operating and non-operating. Salt Spray: Commercial Jacks - Per MIL-STD-202, method 101. Military Jacks - Per MIL-STD-202, method 101 (48 hours). Moisture Resistance: Military Jacks - Per MIL-STD-202, method 106 (240 hours).

ORDERING – Order jacks by part number. Additional variations in jacks are available on special order. Special circuitry, frames, contacts, natural brass bushings, as other terminals are available.

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

1/4" LONG FRAME TELEPHONE JACKS



MT-JAX® (with WEco Equivalent Jacks)2

| | | | Sche- | Dim. "X" | |
|-----------------------|--------|----------|----------|-------------|----------------|
| Switchcraft | WEco | _MIL | matic | maximum | Mating |
| Part Number | Equiv. | Type1 | Circuit* | Inch (mm) | Plug3 |
| | | 2-CONDU | CTOR 2 | | |
| MT331 | 233A, | | | | |
| | 221E3 | M641/2-8 | 1 | .438 (11.1) | |
| ♦CMT331 | 223C | _ | 1 | .438 (11.1) | |
| ♦WMT331 | 223AM | _ | 1 | .438 (11.1) | |
| ♦WCMT331 | 223CM | _ | 1 | .438 (11.1) | |
| ♦MT332 | 232A, | | | | |
| | 544A4 | _ | II | .5 (12.7) | |
| ♦CMT332 | 232C | _ | П | .5 (12.7) | |
| MT332A | 218A | M641/2-3 | III | .5 (12.7) | |
| ♦CMT332A | 218C | - | III | .5 (12.7) | |
| ♦MT332C | 303A | M641/2-1 | XVIII | .562 (14.3) | |
| MT333 | 215A | M641/2-6 | V | .469 (11.9) | |
| ♦CMT333 | 215C | - | V | .469 (11.9) | |
| ♦ MT333E | 237A | - | IX | .625 (15.9) | M642/4-1 |
| ♦CMT333A | 237C | _ | IX | .625 (15.9) | |
| MT334A | 225A, | | | | M642/4-2 |
| | 234A | _ | XI | .562 (14.3) | or M642/4-3 |
| ♦CMT334A | 225C, | | | | M642/4-3 |
| | 234C | _ | XI | .562 (14.3) | |
| MT334C | 216A | M641/2-5 | XVII | .625 (15.9) | |
| ♦CMT334C | 216C, | | | | |
| | 484C5 | - | XVII | .625 (15.9) | |
| MT334E | 217A | M641/2-7 | XXV | .562 (14.3) | |
| ♦CMT334E | 217C | - | XXV | .562 (14.3) | |
| ♦MT334F | 226A | M641/2-4 | XIX | .562 (14.3) | |
| ♦CMT334F | 226C | - | XIX | .562 (14.3) | |
| ♦MT335 | 236A | - | XIII | .562 (14.3) | |
| ♦CMT335 | 236C | _ | XIII | .562 (14.3) | |
| ♦MT336E ¹⁰ | 438A | - | XXIII | .75 (19.0) | |
| CMT336E | 438C | M641/1-2 | XXIII | .75 (19.0) | |
| ♦MT337 ¹⁰ | 411A | M641/2-9 | XXIV | .75 (19.0) | |
| ♦CMT337 | 411C | M641/1-1 | XXIV | .75 (19.0) | |
| ♦CMT351C | 394C | - | XXXIII | .812 (20.6) | |
| ♦MT352A | 218J | - | III | .5 (12.7) | |
| ♦CMT354F | 361C | - | XXXIV | .75 (19.0) | |

^{*}Refer to page 79 and 80 for schematics.

- 3. Mating plugs and patch cords are contained in the catalog.
- 4. Adjust non-short tip-ring.
- 5. Adjusted for plug M642/1-1 or M642/1-2.
- 6. Actuates differently (insulated "A" off ring instead of tip).
- 7. Same as MIL type M641/2-3 except with offset ground lug.
- Same as MIL type M641/3-1 except with offset ground lug.
 Same as MIL type M641/3-2 except with offset ground lug.
- 10. When mounted on "A" frames, stacks are too high to fit in standard panels with .625" horizontal space add prefix "C" to part number to order jacks with "C" frame.

| Switchcraft | WEco | MIL | Sche- matic | Dim. "X" | Mating |
|------------------------|----------------|-------------------|----------------|-------------|-------------------|
| Part Number | Equiv. | Type ¹ | Circuit* | Inch (mm) | Plug ³ |
| | - | 3-COND | UCTOR | , , | |
| MT332B | 238A | M641/3-1 | IV | .562 (14.3) | |
| ♦CMT332B | 238C | - | IV | .562 (14.3) | |
| WMT332B | 238AM | - | IV | .562(14.3) | |
| ♦WCMT332B | 238CM | - | IV | .562 (14.3) | |
| MT333B | 300A | - | VII | .562 (14.3) | |
| ♦MT334B | 239A | M641/3-2 | XII | .562 (14.3) | |
| ♦CMT334-B | 239C | - | XII | .562 (14.3) | |
| WMT334B | 239AM | - | XII | .578 (14.7) | |
| ♦WCMT334B | 239CM | - | XII | .578 (14.7) | |
| ♦MT336 | 241A | M641/3-4 | XX | .562 (14.3) | |
| ♦CMT336 | 241C | - | XX | .562 (14.3) | |
| ♦WMT336 ¹⁰ | 241AM | _ | XX | .625 (15.9) | |
| ♦WCMT336 | 241CM | - | XX | .625 (15.9) | M642/2-1 |
| ♦MT336A ¹⁰ | 242A | M641/5-5 | XIV | .688 (17.5) | or |
| ♦CMT336A | 242C | - | XIV | .688 17.5) | M642/2-2 |
| ♦WMT336A | 242AM | _ | XIV | .75 (19.0) | |
| ♦WCMT336A | 242CM | - | XIV | .75 (19.0) | |
| ♦MT336B ¹⁰ | 285A | M641/3-6 | XXI | .812 (20.6) | |
| ♦CMT336B | 285C | _ | XXI | .812 (20.6) | |
| MT336C ¹⁰ | 240A | M641/3-3 | XXII | .688 (17.5) | |
| ♦CMT336C | 240C | - | XXII | .688 (17.5) | |
| ♦WMT336C ¹⁰ | 240AM | - | XXII | .75 (19.0) | |
| ♦WCMT336C | 240CM | - | XXII | .75 (19.0) | |
| ♦MT336D¹0 | 280A | - | XXXI | .75 (19.0) | |
| ♦CMT336D | 280C | _ | XXXI | .75 (19.0) | |
| ♦WMT336D¹0 | 280AM | _ | XXXI | .938 (23.8) | |
| ♦WCMT336D | VCMT336D 280CM | | XXXI | .938 (23.8) | |
| ♦MT338 | 267A | - | XXXII | .562 (14.3) | |
| ♦ CMT338 | 267C | - | XXXII | .562 (14.3) | |
| ♦MT339¹º | 284A6 | M641/3-7 | XXVII | .967 (24.6) | |
| ♦ CMT339 | 384C6 | - | XXVII | .967 (24.6) | |
| ♦MT342B | 246A | - | IV | .563 (14.3) | M642/5-1 |

MT-JAX (WITH WECO EQUIVALENT JACKS)²

| Switchcraft Part Number | WEco Equiv. | MIL Type¹ | Sche- matic Circuit* | Dim. "X" maximum Inch (mm) | Mating Plug³ |
|----------------------------|----------------|--------------|----------------------------|----------------------------------|-----------------|
| | | 3-CONDUC | CTOR 2 | | |
| ♦WMT342B | 246 AM | - | IV | .562 (14.3) | |
| MT344B | 248A | - | XII | .625 (15.9) | |
| ♦MT346 | 249A | - | XX | .562 (14.3) | M642/5-1 |
| ♦CMT346 | 249C | ı | XX | .562 (14.3) | |
| ♦MT354B | 248E | ı | XII | .625 (15.9) | |
| ♦MT355 ¹⁰ | 243C | - | XXXV | .812 (20.6)10 | |
| ♦MT356C ¹⁰ | 245A | ı | XXXVI | .938 (23.8)10 | M642/5-1 |
| ♦CMT356C | 245C | _ | XXXVI | .938 (23.8) | or |
| ♦MT357 ¹⁰ | 363A | _ | XXXVII | .75 (19.0)10 | M642/2-2 |
| ♦CMT358 | 290C | ı | XXXVIII | .875 (22.2) | |
| ♦CMT359 | 326C | _ | XXXIX | .75 (19.0) | |

[♦] Special order only; contact Switchcraft.

Many jacks are offered with MIL specifications. Other jacks are made of MIL-spec materials but do not have MIL approval because no MIL type numbers have been assigned.


MT-Jax have nickel-plated copper alloy bushing. WEco equivalent jacks have plain copper alloy bushings (except WEco Number 221E, which has nickel-plated copper alloy bushing).

JACKS AND PLUGS

* Please visit the product pages on our website for the most up-to-date product information

MT-JAX® (Industry Standard - No WEco Equivalent)

| Switchcraft Part Number | MIL Type ¹ | Schematic Circuit* | Dim. "X" maximum Inch (mm) | Mating Plug³ |
|-------------------------------|--------------------------|-----------------------|----------------------------------|-----------------|
| | | 2-CONDUCTOR | ₹² | |
| ♦WMT332A | _ | III | .5 (12.7) | |
| ⊘WCMT332A | - | III | .5 (12.7) | |
| XMT332A | _ | III | .5 (12.7) | |
| ♦YMT332A | _ | III | .5 (12.7) | |
| ♦CMT332C | _ | XVIII | .562 (14.3) | |
| ♦WMT332C | _ | XVIII | .5 (12.7) | |
| ♦ WMT333 | _ | V | .469 (11.9) | |
| ♦WCMT333 | _ | V | .469 (11.9) | |
| ⊘MT333A | _ | VI | .967 (24.6) | |
| ♦WMT333E | _ | IX | .625 (15.9) | MC40/4.4 |
| ♦WMT334A | _ | XI | .562 (14.3) | M642/4-1 |
| ♦WMT334C | _ | XVII | .562 (14.3) | M642/4-2 |
| ♦WMT334E | _ | XXV | .562 (14.3) | or M642/4-3 |
| ♦WMT334F | _ | XIX | .641 (16.3) | IVI642/4-3 |
| ♦ WMT335 ¹⁰ | _ | XIII | .688 (17.5) | |
| ♦WCMT335 | - | XIII | .688 (17.5) | |
| MT335A ¹⁰ | M641/2-2 | XXVI | .75 (19.0) | |
| ♦CMT335A | _ | XXVI | .75 (19.0) | |
| ⊘WMT335A | _ | XXVI | .75 (19.0) | |
| ♦WCMT335A | _ | XXVI | .75 (19.0) | |
| ♦WMT336E ¹⁰ | _ | XXIII | .875 (22.2) | |
| ⊘WCMT336E | _ | XXIII | .875 (22.2) | |
| ⊘CMT341 | - | I | .438 (11.1) | |




MT-JAX® (Industry Standard - No WEco Equivalent)


| Switchcraft Part Number | MIL Type¹ | Schematic Circuit* | Dim. "X" maximum Inch (mm) | Mating Plug ³ | | | | |
|-------------------------------|---------------------------------|-----------------------|----------------------------------|-----------------------------|--|--|--|--|
| | | 3-CONDUCTOR | ₹² | | | | | |
| XMT332B | XMT332B – IV .562 (14.3) | | | | | | | |
| ♦YMT332B | _ | IV | .562 (14.3) | | | | | |
| ♦CMT333B | _ | VII | .562 (14.3) | | | | | |
| ♦WMT333B | _ | VII | .562 (14.3) | M642/2-1 | | | | |
| XMT334B | _ | XII | .562 (14.3) | or | | | | |
| ♦YMT334B ¹⁰ | - | XII | .562 (14.3) | M642/2-2 | | | | |
| ♦WMT336B | - | XXI | .812 (20.6) | | | | | |
| ⊘WCMT336B | _ | XXI | .812 (20.6) | | | | | |
| ⊘MT343B | - | VII | .5 (12.7) | | | | | |
| ⊘CMT342B | - | IV | .562 (14.3) | | | | | |
| ⊘CMT344B | - | XII | .625 (15.9) | | | | | |
| ♦WMT344B | - | XII | .625 (15.9) | M642/5-1 | | | | |
| ⊘MT346A ¹⁰ | _ | XIV | .688 (17.5) | | | | | |
| ⊘MT346B ¹⁰ | _ | XXI | .812 (20.6) | | | | | |
| ⊘MT346C ¹⁰ | _ | XXII | .688 (17.5) | M642/5-1 | | | | |
| ♦CMT346C | - | XXII | .688 (17.5) | or M642/2-2 ¹ | | | | |

*Refer to pages 79 and 80.

♦ Special order only; contact Switchcraft.

- Many jacks are offered with MIL specifications. Other jacks are made of MIL-spec materials but do not have MIL approval because no MIL type numbers have been assigned.
- MT-Jax have nickel plated copper alloy bushing. WEco equiv. jacks have plain copper alloy bushings (except WEco No. 221E, which has nickel plated copper alloy bushing).
- Mating plugs and patch cords are contained in this catalog.
- Same as MIL type M641/2-3 except with offset ground lug.
- Same as MIL type M641/3-1 except with offset ground lug.
- Same as MIL type M641/3-2 except with offset ground lug.
- When mounted on "A" frames, stacks are too high to fit in standard panes with .625" horizontal space add prefix "C" to part number to order jacks with "C" frame.





1/4" LONG FRAME TELEPHONE TWIN JACKS





High quality telephone jacks are essentially doubled versions of MT-Jax®. Twin-Jax® are used in Switchcraft Series 2400, 2600 and JP® Jack Panels and other standard jack panels. Twin-Jax® have direct WEco equivalents.

MT388 AND WMT388

Frame mounting ears are on 1.375" centers, and bushings are on .625" centers. Jacks are double, 2-conductor type with a crossover wiring feature. If a mating plug is inserted in either bushing, crossover contacts are opened (see schematic). MT388 (solder lugs) is equivalent to WEco jack 410A, 410C and 410D. WMT388 (wire-wrapping) is equivalent to WEco 410AM.

MT389 AND WMT389

Double, 3-conductor jacks with both the tip and ring circuits interconnected (crossover wired) so if a plug is inserted in either jack, common circuits are opened (see schematic). MT-389 (solder lugs) is equivalent to WEco 482A. WMT389 (wire-wrapping) is equivalent to WEco 482AM and 482BM.

SPECIFICATIONS

Frame and Stack Screws: Steel, plated with iridescent

iridite finish.

Springs: Copper alloy, spring tempered. Solder lugs are

solder coated.

Bushings: Nickel-plated copper alloy.

Contacts: Welded crossbar palladium in shunt circuits. **Insulation:** Rigid plastic (MIL-type PBE-P, per MIL Specification LP-513C). Extruded plastic insulating tubing

through stack.

ORDERING


Order by part number from table.


| Part Number ¹ | Adjusted for Plug | Dim. "X" max. Inch (mm) |
|-----------------------------|---|----------------------------|
| MT388 | WEco types 298B and 347B MIL types M642/9-1 and M642/1-1 | .562 (14.3) |
| ♦WMT388 | Switchcraft types 411, 412, 413, 420 | .562 (14.3) |
| MT389 | WEco type 310 MIL types M642/2-1 and M642/2-2 | .594 (15.1) |
| WMT389 | Switchcraft types 414 and 482 | .562 (14.3) |


♦ Special Order only; contact Switchcraft.

1. Number MT388 is equivalent to MIL-type M641/11-1

Complete data for telephone and MIL-type plugs are contained in this section.
 Mounting Screws: #6-32, Part Number P10725, can be ordered separately.
 Contact Switchcraft. (Screws not supplied with jacks).







PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

1/4" JACK BLOCKS

DUAL-JAX BLOCK®





Dual-Jax Blocks are ideal where limited jack connections are needed but larger jack panels are not required. Designed for broadcasting, intercom and PA systems, switchboards, and commercial, industrial and military communications equipment. Dual-Jax Blocks mount in panels or chassis, either singularly or in multiples. Four countersunk holes accommodate four #8-32 screws (not supplied) for block mounting. Blocks can be supplied without jacks, or with MT-Jax® installed. Many other jacks including, T-Jax®, T-Switch® switches and lamp jacks can be installed. Jacks with wire-wrapping terminals or offset lugs can also be supplied. By drilling additional holes, Twin-Jax® may also be used. Contact Switchcraft for any special order items.

SPECIFICATIONS

Block: Molded black thermoplastic.

Screws: #6-20 plated steel, QQ-P-416, Type II,


Class 2 (for jack mounting).

ORDERING

Order by part number from table.

| Part Number | Description |
|--------------|-------------------------------|
| 2300 | Block, without jacks. |
| 2331 | Two, MT331 MT-Jax installed. |
| 2332A | Two, MT332A MT-Jax installed. |
| 2332B | Two, MT332B MT-Jax installed. |
| ⊘2333 | Two, MT333 MT-Jax installed. |

♦ Special order only; contact Switchcraft for price and delivery. Mounting Screws: #6-20, P1544, can be ordered separately, contact Switchcraft.



FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

TT-JAX® (.173") TELEPHONE JACKS BANTAM TYPE®



STEEL FRAME



DIE-CAST FRAME (special order only)

TT36FM **FRONT MOUNT**



WTT636C THREADED BUSHING

FEATURES

- Steel (standard) or die-cast frames (special order).
- · 2-or 3-conductors.
- Palladium crossbar welded contacts are standard in switching circuits. Fine silver or gold alloy contacts are available on special order.
- Series TT30, TT30FM and TT600 solder lugs; Series WTT-30, WTT30FM and WTT600FM -wire-wrapping terminals. Bussing solder lugs are available on special order.
- Series TT30 and WTT30 jacks mounts in Series 1600, A1600, B1600 and C1600 jacks panels.
- Series TT30FM and WTT30FM jacks mount in Series TT51, TT52, TT55 and TT56 jack panels.
- Series TT600 and WTT600 jacks mount in .25" diameter holes in panels up to .281" thick. Mounting centers: .438".
- Add "N" for nickel-plated frame and "Y" or for offset solder lugs.

SWITCHCRAFT VS. MIL NUMBERS

| Jack Number | MIL Spec. Number | | | |
|-------------|---|--|--|--|
| TT32B | MIL Spec. Number 641/19-2 641/19-6 641/19-4 641/19-8 641/19-10 641/19-1 641/19-5 641/19-3 641/19-7 641/19-9 | | | |
| TT32BFM | 641/19-6 | | | |
| TT34B | 641/19-4 | | | |
| TT34BFM | 641/19-8 | | | |
| TT36C | 641/19-2 641/19-6 641/19-4 641/19-8 641/19-10 641/19-1 641/19-5 641/19-3 641/19-7 | | | |
| WTT32B | 641/19-1 | | | |
| WTT32BFM | 641/19-5 | | | |
| WTT34B | 641/19-3 | | | |
| WTT34BFM | 641/19-7 | | | |
| WTT36C | 641/19-9 | | | |

| Part Numbers, Jack with Solder Lugs | | | | | Dim. "X" | | Typical | |
|-------------------------------------|---------------------------|-----------------|-------------------|----------------|----------|----------------------|---------|-------------------|
| Serie | Series TT30 Series TT30FM | | Series TT600 | | Max. | | Mating | |
| Steel | Die Cast | Steel | Die Cast | Steel | Schem.1 | In (mm) ² | Cond. | Plug ³ |
| TT31 | ♦TT31DC | TT31FM | ♦TT31FMDC | TT631 | I | .422 (10.7) | 2 | TT251 |
| TT32A | ♦TT32ADC | TT32AFM | ♦TT32AFMDC | TT632A | III | .406 (10.3) | 2 | TT251 |
| TT32B | ♦TT32BDC | TT32BFM | ♦TT32BFMDC | ♦TT632B | IV | .578 (14.68) | 3 | TT253 |
| TT32C | ♦TT32CDC | ♦TT32CFM | ♦TT32CFMDC | ♦TT632C | XVIII | .422 (10.7) | 2 | TT251 |
| TT33 | ♦TT33DC | TT33FM | ♦TT33FMDC | ♦TT633 | V | .578 (14.7) | 2 | TT251 |
| ♦TT33B | ♦TT33BDC | ♦TT33BFM | ♦TT33BFMDC | ♦TT633B | VII | .484 (12.3) | 3 | TT253 |
| TT34A | ♦TT34ADC | ♦TT34AFM | ⊘TT34AFMDC | ♦TT634A | ΧI | .547 (13.9) | 2 | TT251 |
| TT34B | ♦TT34BDC | TT34BFM | ⊘TT34BFMDC | TT634B | XII | .578 (14.68) | 3 | TT253 |
| TT34C | ♦TT34CDC | TT34CFM | ♦TT34CFMDC | ♦TT634C | XVII | .547 (13.9) | 2 | TT251 |
| TT34F | ♦TT34FDC | _ | ı | _ | XIX | .609 (15.5) | 2 | TT251 |
| TT35 | ♦TT35DC | ♦TT35FM | ♦TT35FMDC | ♦TT635 | XIII | .609 (15.5) | 2 | TT251 |
| TT36 | ♦TT36DC | ♦TT36FM | ♦TT36FMDC | ♦TT636 | XX | .609 (15.5) | 3 | TT253 |
| TT36A | ♦TT36ADC | TT36AFM | ♦TT36AFMDC | TT636A | XIV | .625 (15.9) | 3 | TT253 |
| TT36B | ♦TT36BDC | - | ı | _ | XXI | .703 (17.9) | 3 | TT253 |
| TT36C | ♦TT36CDC | TT36CFM | ♦TT36CFMDC | ♦TT636C | XXII | .625 (15.9) | 3 | TT253 |

| Part Numbers, Jack with Wire Wrapping Terminals | | | | Dim. "X" | | Typical | | |
|---|------------------|------------------|--------------------|----------------|---------|----------------------|-------|-------------------|
| Series | s WTT30 | Series | WTT30FM | Series WTT600 | | Max. | | Mating |
| Steel | Die Cast | Steel | Die Cast | Steel | Schem.1 | In (mm) ² | Cond. | Plug ³ |
| WTT31 | ♦WTT31DC | WTT31FM | ♦WTT31FMDC | WTT631 | I | .422 (10.7) | 2 | TT251 |
| WTT32A | ⊘WTT32ADC | WTT32AFM | ⊘WTT32AFMDC | WTT632A | Ш | .406 (10.3) | 2 | TT251 |
| WTT32B | ♦WTT32BDC | WTT32BFM | ⊘WTT32BFMDC | WTT632B | IV | .578 (14.68) | 3 | TT253 |
| ⊘WTT32C | ⊘WTT32CDC | ⊘WTT32CFM | ⊘WTT32CFMDC | ♦WTT632C | XVIII | .422 (10.7) | 2 | TT251 |
| WTT33 | ♦WTT33DC | WTT33FM | ♦WTT33FMDC | ♦WTT633 | V | .578 (14.7) | 2 | TT251 |
| ⊘WTT33B | ⊘WTT33BDC | ⊘WTT33BFM | ⊘WTT33BFMDC | ♦WTT633B | VII | .484 (12.3) | 3 | TT253 |
| ♦WTT34A | ⊘WTT34ADC | ⊘WTT34AFM | ⊘WTT34AFMDC | ♦WTT634A | ΧI | .547 (13.9) | 2 | TT251 |
| WTT34B | ♦WTT34BDC | WTT34BFM | ♦WTT34BFMDC | WTT634B | XII | .578 (14.68) | 3 | TT253 |
| _ | _ | _ | _ | ⊘WTT634C | XVII | .547 (13.9) | 2 | TT251 |
| ♦WTT35 | ♦WTT35DC | ♦WTT35FM | ♦WTT35FMDC | ♦WTT635 | XIII | .609 (15.5) | 2 | TT251 |
| ♦WTT36 | ♦WTT36DC | ♦WTT36FM | ♦WTT36FMDC | ⊘WTT636 | XX | .609 (15.5) | 3 | TT253 |
| ♦WTT36A | ♦WTT36ADC | ♦WTT36AFM | ⊘WTT36AFMDC | ♦WTT636A | XIV | .625 (15.9) | 3 | TT253 |
| WTT36C | ♦WTT36CDC | WTT36CFM | ♦WTT36CFMDC | ♦WTT636C | XXII | .625 (15.9) | 3 | TT253 |

[♦] Special order only.

^{1.} See schematic diagrams.

^{2. &}quot;X" dimension of die cast frame jacks may be slightly greater.

^{3.} See Mating Plugs Section.

TT-JAX® (.173") TELEPHONE JACKS BANTAM TYPE®



SPECIFICATIONS

Frame: Plated (steel or zinc diecast).

Stack Screws: Steel plated.

Bushing: Plated (brass or steel).

Tip and Ring Springs: Copper alloy.


Contact Spring: Copper alloy.

Contacts: Welded crossbar palladium. Other alloys in

various sizes available on special order.

Insulation: Rigid plastic with plastic tubing through

stack assembly.



MOUNTING HARDWARE

Series TT30: #3-48 x 1/4"; mounting screws, P10834,

can be ordered separately.


Series TT30FM: Supplied with one #3-48 x 1/4" fil.


head machine screw, steel-plated.


Series TT600: Supplied with one P1975, nickel-plated copper alloy locknut, and one S3997, steel, nickel-plated wash-


er.


NOTE: Dimensional drawings show panels with steel frame jacks. Overall dimensions for steel or die-cast frame jacks are the same, except as noted.











DIMENSIONS ARE FOR REFERENCE ONLY


Inch (mm)

TT-JAX® (.173") TELEPHONE TWIN JACKS BANTAM TYPE®



FEATURES

- Steel or die-cast frames. (Special order only).
- Twin, 3-conductor jacks on .312" centers, inter-connected so circuit is opened when a mating plug is inserted in one side of the jack. Palladium welded crossbar contacts are standard in switching circuits.
- Solder lugs or wire-wrapping terminals.
- TT89, TT89C, WTT89 and WTT89DC jacks mount in Series 1700 jack panels.
- TT89FM, TT89FMDC, WTT89FM and WTT89FMDC jacks mount in Series TT59, TT60, TT61 and TT62 jack panels.



SPECIFICATIONS

Frame: Plated (steel or diecast zinc).

Stack Screws: Steel-plated.

Bushing: Plated (steel or copper alloy).

Tip, Ring and Contact Springs: Copper alloy.

Contacts: Welded crossbar palladium. Other alloys in

various sizes available on special order.

Insulation: Rigid plastic with plastic tubing through

stack assembly.

Mounting Hardware: #3-48 x 1/4" mounting screws, P10834, can be ordered separately for TT89, TT89DC, WTT89 and WTT89DC jacks. Two mounting screws, P25424, are supplied with TT89FM, TT89MDC, WTTFM and WTT89FMDC jacks.

NOTE: Dimensional drawings show panels with steel frame jacks. Overall dimensions for steel or die-cast frame jacks are the same.

| DIM "A" | JACK TYPE | | WIRE WRAP TERMINAL | SOLDER TERM | IINAL |
|-------------------|-----------------------------|--|--------------------|-------------|------------------|
| 0.117 [3.0] DIA | REAR MOUNT | | | 1000 | \ |
| #3-48 THREAD | FRONT MOUNT | T | O OLEE | = -70 | 0 |
| 0.18 TYP | - | <u> </u> | | 4 | |
| Local | | 3.063 [77.8] MAX WIRE WRAP 2.563 [65.1] MAX SOLDER LU | 3 | • | |
| , ce | DIM 'A' | | A T. | _ ,650 | |
| | SEE TABLE | 1 | 1 0 | | |
| 10 | | W | | | 8 |
| 0.812 0.312 | が . L | | | - To | |
| 0.812 0.312 [7.9] | 0025 | | | | 1.26 MAX [32] |
| 16 | 0.25 | 1 00 m | 1 10 | | |
| 1 | 1 | | - 0 | | |
| TT. | 0.177 [4.5] I.D 0.375 | | TT1 TT1" | | |
| | i.D 0.375 | | period period | 4 | |

| Solder Lugs | | Wire-Wrapping Terminals | | | Typical Mating |
|-------------|-----------|-------------------------|------------|-------------|----------------|
| Steel | Die Cast | Steel | Die Cast | Conductors | Plug¹ |
| TT89 | ∜TT89DC | WTT89 | ♦WTT89DC | Twin | TT263 |
| TT89FM | ∜TT89FMDC | WTT89FM | ♦WTT89FMDC | 3-conductor | TT263 |

- 1. See Mating Plugs Section.
- ♦ Special order only

PHONE: 773 792-2700


* Please visit the product pages on our website for the most up-to-date product information

TT-JAX® (.173") TELEPHONE TRIPLE JACKS BANTAM TYPE®




FEATURES

- · Steel or die-cast frames.
- TT95 Tri-Jax® Jacks: three, 3-conductor jacks on one frame. Twin jacks, (on .312" centers, LINE & EQUIPMENT functions), have strapped shunts installed. The third jack (MONITOR) is unwired. See TT95 schematic.
- TT96 Tri-Jax Jacks: Same as TT95 jacks, except third jack (MONITOR) has tip and ring springs, respectively, jumpered to tip and ring springs of top (LINE) jack.
- Selection of solder lugs or wire-wrapping terminals.
- Palladium welded crossbar contact are standard in switching circuits.
- TT95, TT95DC, WTT95 and WTT95DC jacks mount in Series B1700 jack panels.
- TT95FM, TT95FMDC, TT96FM, TT96FMDC and wire-wrapping versions mount in Series TT53, TT54, TT57 and TT58 jack panels.



TT95 SCHEMATIC



TT96 SCHEMATIC

| Solder Lugs | | Wire-Wrapping Terminals | | | | Tunioni Matina |
|-------------|-----------|-------------------------|------------|------------|-----------|-------------------------|
| Steel | Die Cast | Steel | Die Cast | Conductors | Schematic | Typical Mating Plug' |
| TT95 | ∜TT95DC | WTT95 | ØWTT95DC | 3 | TT95 | TT253 |
| TT95FM | ∜TT95FMDC | WTT95FM | 0WTT95FMDC | Plus | TT95 | and |
| TT96FM | ♦TT96FMDC | WTT96FM | 0WTT96FMDC | Twin-3 | TT96 | TT263 |

♦ Special order only

SPECIFICATIONS


Frame: Plated (steel or diecast)
Stack Screws: Stainless Steel Plated.
Bushings: Plated (steel or copper alloy).

Contact Springs: Copper alloy.

Contacts: Welded crossbar palladium. Other precious metal

alloys in various sizes available on special order.

Mounting Hardware: #3-48 x 1/4" mounting screws, P10834, can be ordered separately for rear mount jacks. Two mounting screws, P25424, are supplied with front mount jacks.




DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

MINIATURE TELEPHONE JACKS, RIGHT ANGLE, PC MOUNT





Right-angle miniature phone jacks provide low-profile packaging. Single and twin 3-conductor jacks provide plug-jack access to communication circuits for patching and/or testing. Tips and rings are shunted. These jacks mate with Switchcraft miniature TT® plugs and patch cords.

Jacks are designed for right-angle mounting on .062" (1.6 mm) maximum thickness PC boards. Snap-on covers in colors are available and can be installed or removed in the field without special tools. Covers and jacks may be ordered in different colors for color coded circuits.

SPECIFICATIONS ELECTRICAL

Dielectric Withstanding Voltage: 500 V AC Contact Resistance: $.020 \Omega$ maximum (initial),

.030 Ω maximum (after life test).

Insulation Resistance: $10^{10} \Omega$ at 500 V DC (initial).

MECHANICAL

Shock: MIL-STD 202 Method 213. **Vibration:** MIL-STD 202 Method 201.

Insertion Force: 7 pounds maximum (31.14 N). Withdrawal Force: 1.5 pounds minimum (6.67 N).

Life: 10,000 cycles.

MATERIALS

Housing: Thermoplastic UL 94V-0. **Springs:** Copper alloy, plated.

Contacts: Gold alloy (WEco #1) crossbar.


ENVIRONMENTAL

Temperature Limits: -55°C to +85°C

(non-operating).

Thermal Shock: MIL-STD 202 Method 107. Salt Spray: MIL-STD 202 Method 101. Humidity: MIL-STD 202 Method 106, less

steps 7A and 7B.



ORDERING INFORMATION

| Jack Part No. | Cover Part No. | Color | Schem. | Cond. | Typical Mating Plug ² |
|---------------------|-------------------|--------|--------|-------|-------------------------------------|
| RTT34B01 | ⊘P286301 | Red | | | |
| RTT34B02 | P286302 | Black | | | |
| RTT34B04 | ⊘P286304 | Blue | XII | 3 | TT-253 |
| RTT34B05 | P286305 | White | | 3 | 11-200 |
| ⊘RTT34B07 | ⊘P286307 | Orange | | | |
| \Diamond RTT34B08 | ⊘P286308 | Yellow | | | |
| RTT8701 | ⊘P286401 | Red | | | |
| RTT8702 | P286402 | Black | | | |
| RTT8704 | ⊘P286404 | Blue | Twin | Twin | TT 000 |
| RTT8705 | P286405 | White | XII | 3 | TT-263 |
| ⊘RTT8707 | ⊘P286407 | Orange | | | |
| ♦RTT8708 | ⊘P286408 | Yellow | | | |

- 1. See schematic diagrams on pages 79 and 80.
- 2. See Mating Plugs Section.
- ♦ Special order only; contact Switchcraft for price and delivery.

ORDERING

- 1. Order jacks and covers separately from table.
- 2. Covers can be ordered assembled on special order.
- To order RTT jack with cover installed, add the letter C after RTT in part number. Special order only.
- 4. To order RTT jack with Snap-in terminals, add the letter S to the end of the part number. Special order only.
- 5. For all special orders items, contact Switchcraft.


RTT JACK PART NUMBERING SYSTEM


| Series | Cover | Option | Circui | try | Jack | Color |
|----------------------------|--------|----------------------|--------|---------------------|------|--------|
| RTT Right Angle TT Jack | Blank- | No Cover Standard | 34B- | XII | 01- | Red |
| | C- | Cover Supplied | 87- | Two XII Circuits | 02- | Black |
| | | | | | 04- | Blue |
| | | | | | 05- | White |
| | | | | | 07- | Orange |
| | | | | | 08- | Yellow |


DIMENSIONS ARE FOR REFERENCE ONLY


Inch (mm


MINIATURE TELEPHONE JACKS, RIGHT ANGLE, PC MOUNT (continued)














FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

.177" ENCLOSED JACKS

Two- and 3-conductor Unijax® jacks have advanced features of Hi-D Jax® jacks including chassis/panel and PC mounting and .177" bushing that mates with a variety of tini-telephone® plugs and patchcords. Bushing diameter is .281" inside diameter; panel thickness is .125". Mounts in rows or arrays on .469" centers.

SPECIFICATIONS MECHANICAL

Insertion/Withdrawal: 2-conductor, 1.25 pounds nominal, 3 pounds maximum insertion. 3-conductor, 1.5 pounds nominal, 3 pounds maximum insertion. 2-conductor, 3 pounds nominal, 1.5 pounds minimum withdrawal. 3-conductor, 3 pound nominal,

Life: 10,000 insertion/withdrawal cycles minimum.

ELECTRICAL

Contact Resistance: .10 ohms maximum. Insulation Resistance: $1.000 \text{ M}\Omega$ minimum.

Dielectric Withstanding Voltage: 500 V AC maximum.

MATERIAL

Housing: Thermoplastic.

1.5 pounds minimum withdrawal.

Mounting Bushing: Nickel-plated copper alloy. Tip and Ring Springs: Copper alloy, silver-plated.

Integral contacts.


Shunt Springs: Copper alloy, silver-plated

integral contacts.

Hardware: Supplied with one, Number P2060 nickel-plated copper alloy locknut, and one, Number P2061 nickel-plated copper alloy washer.

Sleeve Terminal: Steel, tin-plated.





TWO CONDUCTOR PART NUMBERS

| Part Number | Description | Jack Schematic ¹ | Typical Mating Plug² |
|----------------|-----------------------|--------------------------------|----------------------------|
| UJ1 | Open circuit | 1 | TT251 |
| UJ2A | Single closed circuit | III | TT251 |

THREE CONDUCTOR PART NUMBERS

| UJ2B | Double Open circuit | IV | TT253 |
|------|-----------------------|-----|-------|
| UJ4B | Double closed circuit | XII | TT253 |

- 1. See jack schematics on pages 79 and 80.
- 2. See Mating Plugs Section.

1/4" PHONE JACKS



LITTEL-JAX® COMMERCIAL PHONE JACKS 2- AND 3-CONDUCTOR

Littel-Jax phone jacks mate with standard commercial phone plugs and are available with .25" and .21" inside diameter bushings.

MIL LITTEL-JAX® PHONE JACKS 2- AND 3-CONDUCTOR MIL-SPEC, MIL-J-641 (E)

MIL jacks mate with MIL-type phone plugs with .25" (6.35mm) or .21" (5.34mm) diameter bushings. Numbers C11 and C12B have a non-turn locating pin which keys the jack to the mounting surface. For low contact resistance applications, jack number C12A has fine silver contacts on shunts and tip springs.

MOUNTING

Chassis/Panel: See Mounting Data drawing below; smallhole is required only for jacks numbers C11 and C12B with non-turn locating pin.

Maximum Panel Thickness: .156" (4mm) for standard .276" (7mm) long bushing; .25" (6.35mm) for .375" (9.5mm) long bushing.

NOTE: For panels thicker than .25" see Thick Panel Phone Jax. **Insulated Mount:** See drawing. S1028 flatwasher and **Part Number S1029** shoulder washer must be ordered separately for mounting in .437" diameter hole.

NOTE: See Hi-D Jax® for jack specifically designed for insulated mounting without additional washers.

PC Board Mounting: See Recommended PC Board Layout drawing below for jacks with PC terminals. Recommended PC board thickness is .062".

Mounting Centers: 1.188" (30mm) recommended. Centers may vary with jack selected, for example, Number 11 mounts on .813" (20.6mm) and 14B mounts on 1.125" (28.6mm) minimum centers.

PREFIX OPTIONS CIRCUITRY Blank- 1/4" Commercial Jack 1-Littel Jax® C-Accepts Mill Plug 2A-Ш FA-.205" Faston Terminals 2B-IV FAL-.205" Faston Terminals ٧ 3and .375" Long Bushing L-.375" Long Bushing 3A-VI PC-PC Terminals VII S-Accepts .206 Diameter Plugs 3F-IX 4B-XII

TWO CONDUCTOR PART NUMBERS

| Part Number | Description | Jack Schematic ¹ | Typical Mating Plug |
|----------------|--|--------------------------------|---------------------------|
| 11 | Open circuit | I | 250 |
| C11 | MIL Number M641/6-1 | I | 440 |
| FA11 | .205 inch FASTON terminal | I | 250 |
| FAL11 | .375 inch long bushing .205 FASTON terminal | I | 250 |
| L11 | .375 inch long bushing | 1 | 250 |
| 12A | Tip shunt | III | 250 |
| C12A | MILNumber M641/12-1 | III | 440 |
| L12A | .375 inch long bushing | III | 250 |
| PC12A | PC board mount | III | 250 |
| 13 | Isolated "make" circuit | V | 250 |
| 13A | Transfer circuit | VI | 250 |
| 13E | Isolated "break" circuit | IX | 250 |

THREE CONDUCTOR PART NUMBERS


| 12B | Double open circuit | IV | 267 |
|------|--|-----|-----|
| L12B | .375 inch long bushing | IV | 267 |
| C12B | MIL number M641/5-1, .250 inch inside diameter | IV | 480 |
| 13B | Tip shunt | VII | 267 |
| 14B | Double closed circuit | XII | 267 |


PART NUMBERS (.210" INSIDE DIAMETER BUSHING)

| S11 | 2 conductor | I | S250 |
|------|-------------|-----|------|
| S12A | 2 conductor | III | S250 |
| S12B | 3 conductor | IV | S267 |
| S13B | 3 conductor | VII | S267 |


Refer to jack schematics on pages 79 and 80. Other circuits are available; contact factory.


STEREO JACK CONNECTIONS





Locating Pin.





DIMENSIONS ARE FOR REFERENCE ONLY

(mm

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

1/4" PHONE JACKS (continued)

LITTEL-JAX® COMMERCIAL PHONE JACKS - 2- AND 3-CONDUCTOR AND MIL LITTEL-JAX® PHONE JACKS - 2- AND 3-CONDUCTOR MIL-SPEC, MIL-J-641 (E)

SPECIFICATIONS MECHANICAL

Life: Commercial Jacks: 10.000 insertion/withdrawal cycles, minimum. Military Jacks: 20,000 insertions/

withdrawals, minimum.

Mechanical Shock: Military Jacks: Per MIL-STD 202,

method 213, Test Condition H (75g).

Vibration: Military Jacks: Per MIL-STD-202,

method 213, (10-55 Hz).

Insertion/Withdrawal Forces: (see charts below)

COMMERCIAL JACKS

| Plug Diameter (inches) | .210 | .250 |
|------------------------|-------|-------|
| Insertion (maximum) | 7 lb. | 7 lb. |
| Withdrawal (minimum) | 1 lb. | 1 lb. |

MILITARY JACKS

| Part Number | C11 | C12A | C12B |
|----------------------|-------|-------|---------|
| Insertion (maximum) | 6 lb. | 7 lb. | 6 lb. |
| Withdrawal (minimum) | 2 lb. | 3 lb. | 1.5 lb. |
| Withdrawal (maximum) | 7 lb. | 7 lb. | 5 lb. |

ELECTRICAL

Contact Resistance: Commercial Jacks - .030 ohms maximum (initial), .050 ohms maximum (after humidity, durability exposure). Per MIL-STD-202E. Military Jacks -.010 ohms maximum (initial), .020 ohms maximum (after life), .10 ohms maximum (after salt spray).

Insulation Resistance: Commercial Jacks - 10,000 M Ω minimum (initial), 1,000 M Ω minimum (after humidity). Military Jacks - 10,000 M Ω minimum (initial), 1,000 M Ω minimum (after humidity, durability exposure).

Dielectric Withstanding Voltage: 500 V, 60 Hz (rms) AC. Contact Rating: 1 A, 25 V DC.

ENVIRONMENTAL

Thermal Range: Commercial Jacks; -55°C to +85°C (non-operating); -20°C to +65°C (operating). Military Jacks; -55°C to +85°C (non-operating); -40°C to+65°C (operating). Thermal Shock: Commercial Jacks - Per MIL-STD 202, method 107. Military Jacks - Per MIL-STD 202, method 107. Humidity: Commercial Jacks - Per MIL-STD 202, method 106. Military Jacks - 0% to 95% operating and non-operating. Salt Spray: Commercial Jacks - Per MIL-STD 202, method 101. Military Jacks - Per MIL-STD 202, method 101 (48 hours). Moisture Resistance: Military Jacks - Per MIL-STD 202, method 106 (240 hours).

MATERIAL

Mounting Bushing: Nickel-plated copper alloy.

Insulation: Rigid plastic.

Springs: Special copper alloy. Integral contacts are standard in the isolated switching circuits; fine silver contacts


in C12A switching circuit.


Sleeve Terminal: Copper alloy.


Hardware: Supplied with one Number P10001 copper alloy nickel-plated hex nut, and one Number 51022 steel nickel-plated washer - except copper alloy nickel-plated washer Number S10451 supplied on C11, C12A and C12B.


*Commercial jacks feature integral contacts. Integral contacts should not be used where low contact resistance is a requirement.


Littel Jax® Jacks












PC-12A 12B, C12B S-12B, SC-12B



13E

14B

DIMENSIONS ARE FOR REFERENCE ONLY

13B, S-13B

JACKS AND PLUGS

1/4" ENCLOSED TELEPHONE JACKS











Series M11

Series MNS11

Series MS11*

Series MN11*

Compactly constructed jacks permit direct cross-patching with Switchcraft, WEco and MIL-type telephone plugs and patch cords. Series M Hi-D Jax® offer a choice of solder lugs or PC terminals. Both insulated and metal bushings can be specified, as well as .21" inside diameter sleeves for narrow plug fingers. Maximum contact resistance is .1 ohm. Springs are made of a special gold-plated copper alloy. Welded cross bar gold alloy contacts are available on special order.

SERIES M-11* HI-D JAX®

Two- and 3-conductor type mate with .25" diameter finger plugs. Tip and ring springs are gold-plated. Shunts (if used) have welded crossbar palladium contacts. Ring springs (where used with shunts) have welded crossbar palladium contacts. Tip springs (when used) do not have a contact welded to the spring. Bushing has 3/8-32-NEF-2 thread; locknut and flat washer for mounting are supplied.

SERIES MN-11* HI-D JAX®

Same as Series M-11* except threaded bushing is molded thermoplastic for insulated mounting. Continuous sleeve contact assures positive sleeve connection without exposed metal on front of panel.

SERIES M113 AND M114 HI-D JAX®

The versatile 3-conductor M113 and M114 feature springs which accept a wide variety of 1/4" plug designs. Self-aligning PC terminals allow for easier insertion into a printed circuit board. Also feature a metric thread mounting.

SPECIFICATIONS

MATERIALS

Mounting Bushing: Series M11*, MS11* - Nickel-plated copper alloy. Series MN11*, MNS11* - Molded thermoplastic.

Housing: Molded thermoplastic, UL 94V-0.

Springs: Copper alloy.

Contacts (mil-type): Tip and Ring Springs are gold-plated. Shuntsprings (where used) are welded crossbar palladium. Welded crossbar gold alloy contacts are available on special order.

Contacts (commercial): Tin-plated integral contacts.

Sleeve Terminal: Steel, tin-plated.

Hardware: Supplied with one **P10001** copper alloy, nickel-plated locknut and one **S10221** steel,

www.switchcraft.com

nickel-plated washer.

MECHANICAL

Life: 10,000 insertion/withdrawal cycles, minimum.

Insertion/Withdrawal Forces: Nominal plug retention on 2-conductor jack is .75 pounds with .5 pounds minimum. Nominal plug retention on 3-conductor jack is 2 pounds with 1.5 pounds minimum. With double tips, the nominal is 1.5 pounds and 1 pound minimum.

Maximum Recommended Mounting Torque: 6" -lb. for thermoplastic bushing.

Mounting Torque (for Spring Lock PC Terminal): 8" -pound for thermoplastic bushings.

ELECTRICAL

Contact Resistance: .020 ohms maximum (initial), .050 ohms maximum (after humidity, durability exposure). Per MIL-STD-202E.

Insulation Resistance: 10,000 M Ω minimum (initial),

1,000 M Ω minimum (after humidity).

Dielectric Withstanding Voltage: 500 V, 60 Hz (rms) AC. Contact Rating: 0.25, 48 VDC make and break, 3A carry only.

ENVIRONMENTAL

Thermal Range: -55°C to +85°C (non-operating);

-20°C to +65°C (operating).

Thermal Shock: Per MIL-STD 202, method 107. Humidity: Per MIL-STD 202, method 106. Salt Spray: Per MIL-STD 202, method 101.

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

1/4" ENCLOSED TELEPHONE JACKS (CONTINUED)

SERIES MS11* HI-D JAX®

3-conductor with .21" inside diameter sleeve. Mates with plugs having .206" diameter finger. Protects against accidental insertion of .25" diameter finger plugs. Gold-plated tip and ring springs. Welded crossbar palladium contacts on shunt springs standard. Bushing has 3/8-32-NEF-2 thread; locknut and flat washer for mounting are supplied.

♦SERIES MNS11* HI-D JAX®

Same as Series MS11* except bushing is molded thermoplastic.

♦ TWIN M11* HI-D JAX®

Two Series M11* Hi-D Jax strapped on .625" centers. Mates with Switchcraft® Twin Plugs. 411, 412 and 413. MIL-type Littel-Plug® phone plugs, 420, 430 and 440 (2-conductor) and 482 and 483 (3-conductor) are also recommended for mating with this series.

ORDERING INFORMATION

Order by part number from table.

| | 2-CONDUCTOR | | | |
|-------------------------------|----------------------------|---|------------------|----------------------------|
| Part Number Solder Lugs | Part Number PC Terms | Description | Sche- matic** | Typical Mating Plug* |
| M111 | _ | .25" I.D. sleeve, metal bushing. | | |
| MN111 | - | .25" I.D. sleeve, molded thermoplastic bushing. | I | |
| ⊘M112A | ⊘M112APC | .25" I.D. sleeve, metal bushing. | | |
| MN112A | ⊘MN112APC | .25" I.D. sleeve, molded thermoplastic bushing. | III | 420 |
| M113E | _ | .25" I.D. sleeve, metal bushing. | | |
| MN113E | _ | .25" I.D. sleeve, molded thermoplastic bushing. | IX | |

[♦] Special Order only; contact Switchcraft.

| | 3-CONDUCTOR | | | |
|-------------------------------|----------------------------|---|-----------------------------|--|
| Part Number Solder Lugs | Part Number PC Terms | Description | Sche- matic ¹ | Typical Mating Plug ² |
| M112B | · M112BPC | .25" inch I.D. sleeve, metal bushing. | mano | 9 |
| ML112B | _ | .25" inch I.D. sleeve, .375 inch long metal bushing. | | |
| MN112B | · MN112BPC | .25 inch I.D. sleeve, molded thermoplastic bushing. | IV | 482 |
| MNL112B | _ | .25 inch I.D. sleeve, .375 inch long metal bushing. | | |
| M113B | _ | .25 inch I.D. sleeve, metal bushing. | | |
| MN113B | MN113BPC | .25 inch I.D. sleeve, molded thermoplastic bushing. | VII | 482 |
| | M113BPC1M | .25 inch I.D. sleeve, molded thermoplastic bushing, metric hardware | | 482 |

| | 3-CONDUCTOR | | | |
|-------------------------------|----------------------------|---|-----------------------------|--|
| Part Number Solder Lugs | Part Number PC Terms | Description | Sche- matic ¹ | Typical Mating Plug ² |
| MNL113B | - | .25 inch I.D. sleeve, .375 inch long metal bushing. | | 482 |
| M114B | · M114BPC | .25 inch I.D. sleeve, metal bushing. | VII | |
| | M114BPC1M | .25 inch I.D. sleeve, metal bushing, metric hardware. | XII | 482 |
| MN114B | · MN114BPC | .25 inch I.D. sleeve, molded thermoplastic bushing. | | 480, 484 |

- \Diamond Special order only; contact Switchcraft for price and delivery.
- 1 See schematics, pages 79 and 80.
- 2 Number(s) specified are not necessarily the only mating plug(s). See Plugs Section.

Other mating plugs are contained in this plug section.

^{**} See pages 79 and 80.

1/4" ENCLOSED PHONE JACKS (continued)

HI-D® JAX 2- AND 3-CONDUCTOR







SERIES 113

PC TERMINAL VIEW

SERIES N113

Hi-D Jax® 2- and 3-conductor enclosed phone jacks are ideal for panel/chassis and PC board mounting. Unitized molded housing protects springs, provides mechanical and electrical reliability, minimizes leakage and provides low capacity between springs. Mounts on .625" minimum centers in rows or arrays. .25" or .21" inside diameter bushing types, metal or thermoplastic bushings (for insulated mounting). Insulated Hi-D Jax® jacks are specifically designed for in-circuit (insulated) mounting from mounting surface and have fully protected enclosed internal sleeve feature. Solder lugs or PC terminals may be selected.

MOUNTING

Jacks mount in a single .375" diameter hole on .625" minimum centers. Series 11*, N11*, NS11* and S11* mount in panels up to .156" thick. Series L11* and NL11* (long bushing) mount in panels up to .25" thick. Jacks with PC terminals mount on PC boards up to .094" thick. Formed "shoulders" on each terminal provide stable stand-off mount. Threaded bushing permits mechanical connection to equipment panel. Mounting hardware is supplied. Also available is a grounding spur bushing, which allows for positive grounding of the bushing to the chassis. Contact factory for details.

SERIES 11* - 2- and 3-conductor types, threaded metal bushing .276" long. .25" inside diameter bushings.

SERIES L11* - Same as Series 11*, except bushing is .375" long for mounting in panels up to .25" thick.

SERIES N11* - Same as Series 11*, except bushing is molded thermoplastic for insulated mounting.

SERIES NL11* - Same as Series N11*, except bushing is .375" long for insulated mounting in panels up to .25" thick.

SERIES S11* - Same as Series 11*, except bushing has .21" inside diameter. Smaller diameter protects against accidental insertion of plugs with .25" diameter fingers.

♦ SERIES NS11* - (SPECIAL ORDER ONLY) - Same as Series N11*, except bushing is .21" inside diameter.

113BPC1M AND 114BPC1M - Versatile, 3-conductor 113BPC1M and 114BPC1M feature springs which accept a wide variety of 1/4" plug designs. Self-aligning PC terminals allow for easier insertion into a printed circuit board. Also feature a metric thread mounting.

TWO CONDUCTOR PART NUMBERS

| | Solder Lug Part Number | PC Terminals Part Number | Description | Jack Schematic ¹ | Typical Mating Plug ² |
|---|------------------------------|-----------------------------|-------------------------------|--------------------------------|--|
| | 111 | 111PC | Open circuit | I | 250 |
| | N111 | N111PC | Insulated bushing | I | 250 |
| | NL111 | - | .375 " long insulated bushing | I | 250 |
| ١ | 112A | 112APC | Single closed circuit | III | 250 |
| | L112A | ♦L112APC | .375" long bushing | III | 250 |
| | N112A | N112APC | Insulated bushing | III | 250 |
| | NL112A | - | .375" long insulated bushing | III | 250 |
| | 113 | 113PC | Isolated "make" circuit | V | 250 |
| | N113 | - | Insulated bushing | V | 250 |
| | ⊘113D | | Transfer circuit (1-C) | VI 3 | 250 |
| | 113E | 113EPC | Isolated "break" circuit | IX | 250 |

THREE CONDUCTOR PART NUMBERS

| 112B | 112BPC | Double open circuit | IV | 267 |
|--------|----------|-------------------------------|--------|-------|
| L112B | - | .375" long bushing | IV | 267 |
| N112B | N112BPC | Insulated bushing | IV | 267 |
| NL112B | - | .375" long bushing | IV | 267 |
| - | S112BPC | .210" inside diameter bushing | IV | S-267 |
| 113B | 113BPC | Single closed circuit | VII | 267 |
| - | 113BPC1M | Single closed circuit | VII | - |
| L113B | - | .375" long bushing | VII | 267 |
| N113B | N113BPC | Insulated bushing | VII | 267 |
| NL113B | - | .375" long bushing | VII | 267 |
| 113F | 113FPC | Ring circuit closed | XXVIII | 267 |
| 114B | 114BPC | Double closed circuit | XII | 267 |
| | 114BPC1M | Double closed circuit | XII | - |
| L114B | ♦L114BPC | .375" long bushing | XII | 267 |
| N114B | N114BPC | Insulated bushing | XII | 267 |
| NL114B | NL114BPC | .375" long bushing | XII | 267 |

- 1 Other circuits available; contact factory. Schematics pages 79 and 80.
- 2 See Plug Section for other options.
- 3 Two tip springs.
- ♦ Special order only. Contact Switchcraft.

SPECIFYING NOTE: Unless otherwise shown in "Description", jacks have .276" long threaded bushings with .25" inside diameter.

SPECIFICATIONS MATERIAL

Mounting Bushing: Series 11*, L11*, S11* -


Nickel-plated copper alloy.


Series N11*, NL11*, NS11* - Molded thermoplastic


over nickel-plated copper alloy sleeve.


1/4" ENCLOSED PHONE JACKS (continued)


HI-D JAX® 2- AND 3-CONDUCTOR














SPRING LOCK PC TERMINALS FOR HI-D JAX $^\circ$


HI-D JAX® SHOWING SPRING LOCK PC TERMINALS





PARTIAL VIEW SHOWING SPRING LOCK TERMINALS

Tip, ring and sleeve terminals are spring lock type.



RECOMMENDED PC BOARD LAYOUT SPRING LOCK **TERMINALS (COMPONENT SIDE)**

NOTES:

- 1. SERIES 110PC-ALL HOLES TO CLEAR .078" X .016" TERMINAL.
- 2. SERIES 110PCS—TIP, RING & SLEEVE HOLES TO BE .055" DIA. RING SHUNT & TIP SHUNT HOLES TO CLEAR .078" X .016" TERMINAL.

Hi-D Jax® enclosed 1/4" phone jacks offer spring lock PC terminals which close during insertion into PC board. Upon completed insertion, the terminals reopen to securely hold the jack to the PC board during soldering. Solder "fills" the terminals which provides an additional security from loosening. The spring lock terminal is available on all Hi-D Jax® which currently offer PC terminals.

NOTE: Tip and ground terminals can be specified with spring lock terminals (also ring terminal on 3-conductor jacks).

MOUNTING

Jacks mount in a single .375" diameter hole on .625" minimum centers. Series 11*, N11* and S11* mount in panels up to .156 " thick. Series NL11* (long bushing) mount in panels up to .250 " thick. Jacks with PC terminals mount on PC boards up to .094 " thick. Spring lock PC terminals hold jack securely to PC board. Threaded bushing permits mechanical connection to equipment panel. Mounting hardware is supplied. See "RECOMMENDED PC BOARD LAYOUT" for further details.

SERIES 11* - 2- and 3-conductor types, threaded metal bushing .276" long. .250 inch inside diameter bushings.

SERIES N11* - Same as Series 11* except bushing is molded thermoplastic for insulated mounting.

SERIES NL-11* - Same as Series N11* except bushing is .375" long for insulated mounting in panels up to .250" thick.

SERIES S11* - Same as Series 11* except bushing has .210" inside diameter Smaller diameter protects against accidental insertion of plugs with .250" diameter fingers.

SPECIFICATIONS

MATERIAL

Mounting Bushing: Series 11*, S11*: Nickel-plated copper alloy. Series N11*, NL11*: Molded thermoplastic over plated copper alloy sleeve.

ORDERING INFORMATION

| TWO CONDUCTOR PART NUMBERS | | | | |
|----------------------------|--------------------------|-------------------|--|--|
| Part Number | Description | Jack Schematic | Typical Mating Plug ¹ | |
| ♦111PCS | Open circuit | I | 250 | |
| ♦N111PCS | Insulated bushing | I | 250 | |
| ♦112APCS | Single closed circuit | III | 250 | |
| ♦N112APCS | Insulated bushing | III | 250 | |
| 113PCS | Isolated "make" circuit | V | 250 | |
| ♦113EPCS | Isolated "break" circuit | IX | 250 | |
| THE | REE CONDUCTOR PART | NUMBERS | | |
| ∜112BPCS | Double open circuit | IV | 267 | |
| ♦N112BPCS | Insulated bushing | IV | 267 | |
| ♦S112BPCS | .210" I.D. bushing | IV | S267 | |
| ∜113BPCS | Single closed circuit | VII | 267 | |
| ♦N113BPCS | Insulated bushing | VII | 267 | |
| 113FPCS | Ring closed circuit | XXVIII | 267 | |
| ♦114BPCS | Double closed circuit | XII | 267 | |
| ♦N114BPCS | Insulated bushing | XII | 267 | |
| ♦NL114BPCS | .375" long bushing | XII | 267 | |

- 1 See Jack Section for other mating plugs.
- ♦ Special order only. Contact Switchcraft.

1/4" RIGHT-ANGLE PHONE JACKS

SERIES SN37, SN49 AND SN70



SN37A14B with cover Number P2993







SN49A12B







SN49C12B

SN70B12A

SN70C14B

These low-profile phone jacks have "snap-in" PC mounting, right-angle plug insertion and available with 2- and 3-conductor circuits and plastic or metal bushings. Ideal for telecommunications, data processing and other high quality audio connecting applications.

SERIES SN37A - Right-angle PC mount phone jack with molded plastic housing. Only .375" high, this jack features a plain (non-threaded) bushing and accepts commercial standard phone plugs with .25" diameter finger.

Jack circuit selection:

2-conductor • Single open circuit • Shunted tip

3-conductor • Double open circuit • Shunted tip and ring

Jack housing snaps into PC boards (.062" thick) and features molded tension fingers to provide stable mount. Location pin polarizes mounting for correct insertion every time. Clearance between housing facilitates board cleaning without disturbing internal springs. SN37 without tension fingers available on special order.

Molded housing protects internal parts and allows high density packaging. Supplied with "Snap-On" cover.

SERIES SN49A - Similar to Series SN37A, except .492" high and insulated/plain (non-threaded) bushing. "Snap-On" cover available on special order only.

SERIES SN49B - Similar to Series SN37A, except .492" high and insulated threaded bushing. Washer and hex nut for bushing mount supplied. "Snap-On" cover available on special order only.

SERIES SN49C - Similar to Series SN37A, except .492" high and threaded metal bushing. Washer and hex nut for bushing mount supplied. "Snap-On" cover available on special order only.

SERIES SN70B - This series features threaded/insulated bushing and .708" in height. Circuit selection and housing features are same as Series SN49B. "Snap-On" cover not available.

SERIES SN70C - Same as Series SN70B, except bushing is threaded metal type.

SPECIFICATIONS

MECHANICAL

Shock: Per MIL-STD-202, method 213. **Vibration:** Per MIL-STD-202, method 201.

Insertion Force: 8 pounds maximum. **Withdrawal Force:** 1.5 pounds minimum.

Life: 10,000 cycles minimum.

ELECTRICAL

SN49B12B with cover Number P2994

Insulation Resistance: 2 x 106 M Ω at 500 V DC per

MIL-STD-202, method 302 (initial).

Dielectric Withstanding Voltage: 500 V AC.

ENVIRONMENTAL

Thermal Range: -55°C (-67°F) to +85°C (+185°F) Non

operating. -20°C to + 65°C Operating.

Thermal Shock: Per MIL-STD-202d, method 107.

Humidity: Per MIL-STD-202, method 106, less steps 7A and 7B.

Salt Spray: Per MIL-STD-202, method 101.

MATERIAL


Housing and Cover: Black thermoplastic, UL 94V-O. **Contact Springs:** Copper alloy with tin-plated terminals.

Hardware: Nickel-plated copper alloy.

Metal Bushing: Nickel-plated copper alloy.

ORDERING

- 1. Order jacks from tables on page 103.
- 2. For all special order items, contact Switchcraft.



DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

JACKS AND PLUGS RIGHT-ANGLE PHONE JACKS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

1/4" RIGHT-ANGLE PHONE JACKS (continued)

SERIES - RA and RN











Series RA

SERIES RA - 2- and 3-conductor RA Jax® are designed with split terminals which provide two distinct advantages over contemporary jacks:

- 1. Positive retention of jack in PC board during wave soldering.
- 2. Split terminal permits additional solder flow paths up the terminal for better mechanical/electrical connection

Tip spring design facilitates positive retention of differing mating plug tip shapes (industry standard and others).

SERIES RN - Right-angle Hi-D Jax® permits space-saving mounting on PC boards. Available in 2- and 3-conductor types with or without shunt circuits, which can mate with .25" diameter COMMERCIAL or TELEPHONE/MIL plug fingers. Right-angle jack permits tip of mating plug to be inserted parallel with PC board. Can be mounted on PC boards or combined PC board and panel/chassis.

Mounted through .375" diameter holes (locknut and washer supplied) in panels and chassis up to .141" thick. Minimum mounting centers are .625". If insulated mount is desired, mounting with flat, non-conductive washer (not supplied) is recommended.

PC terminals mount on boards up to .125" thick, and hand dip or wave soldering, is recommended. Three separate standoffs fit through board to provide stable mounting. Threaded bushing permits optional fastening to panel or chassis.

SERIES RN110 - 2- and 3-conductor right-angle types mount in PC boards or panel/chassis. Bushing is .278" long.

SPECIFICATIONS

Housing: Thermoplastic. **Bushing:** Integral with housing.

Springs: Copper alloy, silver-plated (also available with selectively gold-plated contact points and selectively tin-plated terminals).

Contacts: Integral, part of shunt springs.

NOTE: Specifications for Mechanical, Electrical and Environmental

are the same for Hi-D® Jax. (page 98)

1/4" RIGHT-ANGLE PHONE JACKS (continued)

ORDERING INFORMATION

| SERIES SN Part Numbers | Description | Jack ² Schematic | Typical Mating Plug ³ | |
|---------------------------|--------------------------------|--------------------------------|--|--|
| SN37A11 ¹ | 2-cond., open circuit | I | 250 | |
| SN37A12A1 | 2-cond., single closed circuit | III | 230 | |
| SN37A12B ¹ | 3-cond., double open circuit | IV | 267 | |
| SN37A14B1 | 3-cond., double closed circuit | XII | 207 | |
| SN49A11 ¹ | 2-cond., open circuit | I | 250 | |
| SN49A12A1 | 2-cond., single closed circuit | III | 200 | |
| SN49A12B1 | 3-cond., double open circuit | IV | 267 | |
| SN49A14B1 | 3-cond., double closed circuit | XII | 201 | |
| SN49B111 | 2-cond., open circuit | I | 250 | |
| SN49B12A1 | 2-cond., single closed circuit | III | 250 | |
| SN49B12B1 | 3-cond., double open circuit | IV | 267 | |
| SN49B14B1 | 3-cond., double closed circuit | XII | 201 | |
| SN49C11 | 2-cond., open circuit | I | 250 | |
| SN49C12A | 2-cond., single closed circuit | III | 250 | |
| SN49C12B | 3-cond., double open circuit | IV | 267 | |
| SN49C14B | 3-cond., double closed circuit | XII | 201 | |
| SN70B11 | 2-cond., open circuit | I | 250 | |
| SN70B12A | 2-cond., single closed circuit | III | 250 | |
| SN70B12B | 3-cond., double open circuit | IV | 267 | |
| SN70B14B | 3-cond., double closed circuit | XII | 201 | |
| SN70C11 | 2-cond., open circuit | I | 250 | |
| SN70C12A | 2-cond., single closed circuit | III | 250 | |
| SN70C12B | 3-cond., double open circuit | IV | 267 | |
| SN70C14B | 3-cond., double closed circuit | XII | 207 | |
| | | | | |

¹ Series SN37A supplied with Part Number P2993 cover. Series SN49A and SN49B can be supplied with Part Number P2994 cover on special order. Contact Switchcraft.

ORDERING INFORMATION

| SERIES RA Part Numbers | Description | Jack ² Schematic | Typical Mating Plug ³ |
|---------------------------|--------------------------------|--------------------------------|--|
| RA49B11 | 2-cond., open circuit | I | 250 |
| RA49B12A | 2-cond., single closed circuit | III | 230 |
| RA49B12B | 3-cond., double open circuit | IV | 267 |
| RA49B14B | 3-cond., double closed circuit | XII | 207 |
| RA49C11 | 2-cond., open circuit | I | 250 |
| RA49C12A | 2-cond., single closed circuit | III | 200 |
| RA49C12B | 3-cond., double open circuit | IV | 267 |
| RA49C14B | 3-cond., double closed circuit | XII | 207 |
| RA70B11 | 2-cond., open circuit | I | 250 |
| RA70B12A | 2-cond., single closed circuit | III | 230 |
| RA70B12B | 3-cond., double open circuit | IV | 267 |
| RA70B14B | 3-cond., double closed circuit | XII | 207 |
| RA70C11 | 2-cond., open circuit | I | 250 |
| RA70C12A | 2-cond., single closed circuit | III | 230 |
| RA70C12B | 3-cond., double open circuit | IV | 267 |
| RA70C14B | 3-cond., double closed circuit | XII | 207 |
| SERIES RN Part Numbers | | | |
| RN111PC | 2-cond., single open circuit | I | 250 |
| RN112APC | 2-cond., single closed circuit | III | 250 |
| RN112BPC | 3-cond., double open circuit | IV | 267 |
| RN113BPC | 3-cond., tip closed, ring open | VII | 267 |
| ⟨RN113FPC | 3-cond., tip open, ring closed | XXVIII | 267 |
| RN114BPC | 3-cond., double closed circuit | XII | 267 |

² See pages 79 and 80.


³ Other mating plugs are available.


♦ Special order only. Contact Switchcraft.


1/4" RIGHT-ANGLE PHONE JACKS (continued)

SERIES SN


JACK SCHEMATICS







RECOMMENDED PC BOARD LAYOUT SERIES SN70B (Component Side)




RECOMMENDED PC BOARD LAYOUT SERIES SN70C (Component Side)


DIMENSIONS ARE FOR REFERENCE ONLY


(mm)

1/4" RIGHT-ANGLE PHONE JACKS (continued)

SERIES RA and RN







DIMENSIONS ARE FOR REFERENCE ONLY

JACK COVERS

Reliable, spring-loaded covers effectively seal front panel bushing openings from dust and dirt when mating plugs are not connected to jack. Series 500 is mounted with conventional threaded bushing jacks. Special locknut (comes with Series 500 jack covers) seals tightly against rubber washer when cover is closed. Series 600 is used with certain type tip jacks. Due to variable jack dimensions, two .031" washers are supplied.

SPECIFICATIONS MATERIAL

Base and Cover: Steel per QQ-S-698; finish per MIL-F-14072 (Sig. C), enamel, semi-gloss. **Axle:** Copper alloy per QQ-W-321, Type 321,

composition B. Plated per QQ-P-416, Type II, Class 3. **Spring:** Stainless steel per QQ-W-432, Type 302. **Hex Nut:** Copper alloy per QQ-B-626, composition 22.

Same plating as axle.

Gasket: Synthetic rubber per MIL-R-6855, Type II,

35-40 Durometer.

Washer (600 only): Steel per QQ-S-698; plated per

QQ-P-416, Type II, Class 3.

Additional Specifications for Numbers 512 and 612: Same as above, except rivet, base, cover and hex nut and washer (Number 612 only) are nickel-plated per QG-N-290.

515








| Color | Part No. | Part No. | Color | Part No. | Part No. |
|---------------|-------------|-------------|-----------|-------------|-------------|
| Olive Drab | 510 | ◊610 | Black | 515 | 615 |
| Bright Nickel | 512 | 612 | Navy Gray | 520 | ◊620 |

[♦] Special order only. Contact Switchcraft.



1/4" PHONE JACKS (continued)

LOCKING PHONE JACKS



SERIES E

Series E jacks provide stable, secure connections in panels where shock/vibration or accidental disconnect may occur. Plug locks-in automatically upon insertion; press "PUSH" tab to unlock and remove plug. Series E jacks have the same front panel appearance as Series E Q-G® audio connectors.

SPECIFICATIONS MECHANICAL

Life: 10,000 cycles minimum.

ELECTRICAL

Insulation Resistance: 2 x 106 M Ω at 500 V DC per

MIL-STD-202, method 302 (initial).

Dielectric Withstanding Voltage: 1,000 V AC (rms).

ENVIRONMENTAL

Thermal Range: -55°C to +85°C (non-operating);

-20°C to +65°C (operating).

Thermal Shock: Per MIL-STD-202, method 107. **Humidity:** Per MIL-STD-202, method 106. **Salt Spray:** Per MIL-STD-202, method 101.

MATERIAL

Shell: Die-cast zinc, with satin nickel-plating. Black chrome over

nickel-plating on special order.

Insert and Latch: Thermoplastic, UL 94V-O. Latch Release: Nickel-plated die-cast zinc. Contact Springs: Tin-plated copper alloy.

| Part Number | Description | Jack Schematic ¹ | Typical Mating Plug ² |
|----------------|------------------------------|--------------------------------|--|
| E111L | 2-cond., open circuit | I | 250 |
| E112BL | 3-cond., double open circuit | IV | 267 |

^{1.} See Jack Schematics, pages 79 and 80

2. See Plugs Section

THICK PANEL PHONE JACKS



Jacks are standard 2- and 3-conductor phone jacks with extra long threaded bushing for mounting in panels/chassis up to 1.25" thick. Metal bushing virtually eliminates hum pick-up, and is ideal for electric guitar and speaker connections. Jacks mate with standard commercial phone plugs. See plug section for mating plugs. Jacks mount in a single .469" diameter hole. Rugged cable clamp protects connections from twisting and pulling stresses.

SPECIFICATIONS

MATERIAL

Mounting Bushing: Nickel-plated copper alloy with knurled flange.

Insulating Spacer: Rigid plastic.

Insulator/Spring Mount: Thermoplastic.


Springs: Copper alloy.


Terminals: Tip: Copper alloy. Ring: (Number **152B** only) copper alloy.

Sleeve: Steel, tin-plated.

Hardware: Supplied with one, Number **P10531** nickel-plated copper alloy hex nut, and one, Number **P14761** nickel-plated copper alloy flat washer.

| Part Number | Description | Jack Schematic | Typical Mating Plug |
|----------------|---|-------------------|------------------------|
| 151 | 2-conductor, open circuit, nickel finish | I | 280 |
| 152 | 2-conductor, open circuit, brass finish | I | 280 |
| 152B | 3-conductor, double open circuit, nickel finish | IV | 297 |
| 153 | 2-conductor, open circuit, gold-plated springs, electro-polish brass finish, 9/16-12 UNC wood threads | I | 280 |
| 154 | 3-conductor, double open circuit, gold finish, no cable clamp | IV | 297 |
| 155 | 3-conductor, double open circuit, black satin finish, no cable clamp | IV | |





PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

1/4" EXTENSION JACKS (IN-LINE)



Extension Jax® jacks are connected to the end of a cable. 2- and 3-conductor jacks mate with standard commercial phone plugs, and have a sturdy cable clamp strain relief, knurled shielded or molded black plastic handles, and a screw type solder terminal. All internal parts are interlocked. Note: See locking phone plugs section.

SPECIFICATIONS

MATERIAL

Body, Sleeve and Shielded Handle: Nickel-plated

copper alloy.


Plastic Handles: Molded black thermoplastic.

Springs: Special copper alloy.

Bushing and Flange: Plated copper alloy.

Insulation: Thermoplastic.

Clamp Terminals: Tin-plated copper alloy.




TWO-CONDUCTOR PART NUMBERS

| Part Number | Description | Mating Plug ¹ |
|----------------|---|-----------------------------|
| 80 | Black handle; screw terminals | 250 |
| 88 | Black handle; solder lugs | 250 |
| 120 | Shielded handle; screw terminals | 250 |
| 121 | Shielded handle; solder lugs; cable clamp | 250 |
| 128 | Shielded handle; solder lugs | 250 |

THREE-CONDUCTOR PART NUMBERS

| Part Number | Description M | |
|----------------|---|-----|
| 131 | Shielded handle; solder lugs | 267 |
| 830 | Black handle; screw terminals | 267 |
| S830 | Similar to No. 830 except, .21" I.D. sleeve | 480 |
| 838 | Black handle; solder lugs | 267 |
| 1230 | Shielded handle; screw terminals | 267 |
| 1238 | Shielded handle; solder lugs | 267 |

1. Other mating plugs are available.



1/4" SPEAKER JACKS

High power 2-conductor speaker jack carries 15A (continuous) audio speaker current levels. Jack Number **Z15J** has positive detent for plug retention. Terminations are solder lug; wires accepted are up to 10 AWG. Red housing indicates high current rating. Recommended mating plugs: 70, 184, 187 series.

SPECIFICATIONS


Housing: Glass reinforced thermoplastic, UL 94V-O. **Tip Spring and Ground Terminals:** Copper alloy. **Bushing and Hardware:** Nickel-plated copper alloy

(hardware supplied).

Heat Rise: 30°C with 15 A continuous carry. **Life:** 10,000 (minimum) with proper plug.

| Part Number | Description |
|-------------|-------------------------|
| Z15J | High power speaker jack |





DIMENSIONS ARE FOR REFERENCE ONLY

1/4" SHIELDED PHONE JACKS





CN12A

Shield is assembled as part of the jack; cover "snaps" into place. Shield is designed for Hi Z circuits. Mounting is through a 3/8" diameter hole in chassis/panel up to .156" thick with hex nut and flat washer (supplied). On special order, jacks with .21 inch inside diameter bushing are available.

SPECIFICATIONS

MATERIAL

Cover and Shield: Copper alloy, nickel-plated. Cable Entry Insulation: Thermoplastic.

3/8-32 THREAD 3/8-32 HEX. LOCKNUT 625 [15.88] DIA. WASHER 25 [6,35] I.D. FOR STD.

TWO CONDUCTOR PART NUMBERS

| Part Number | Description | Jack Schematic ¹ |
|----------------|-----------------------------------|--------------------------------|
| CN11 | Uses Number 11 Littel-Jax® jacks | I |
| ⊘CN12A | Uses Number 12A Littel-Jax® jacks | III |

[♦] Special order only. Contact Switchcraft.

THREE CONDUCTOR PART NUMBERS

| CN12B | Uses Number 12B Littel-Jax® jacks | IV |
|--------|-----------------------------------|-----|
| ⊘CN13B | Uses Number 13B Littel-Jax® jacks | VII |

- 1 See jack schematics on pages 79 and 80.
- 2 See Plug Section for mating information.
- ♦ Special order only. Contact Switchcraft.

SF-JAX® SHORT FRAME JACKS

| Part No. | Cond. | Schematic Number | Typical Mating Plug | MIL Type | Contacts | Rating | Mounting In. (mm) |
|----------------|-------|---------------------|---------------------------|----------------------|----------|--------|-------------------------|
| 24B | 3 | XII | 267 | | | | |
| 25 | 2 | XIII | 250 | | | | |
| | 3 | VII | 267 | | | | .375 (9.52) |
| ◊54A | 2 | ΧI | 250 | | Fine | 3A | hole, mounts in |
| | 3 | XII | 267 | | Silver | 125V | panels up |
| ♦ 55 | 2 | XIII | 250 | | | AC | to .156 (3.96) thick |
| ♦ C-55B | 3 | XV | 482 | JJ-095, M641/14-1 | | | (/ / |

Long spring design reliability with minimum behind-panel depth. Series 50 same as Series 20, except solder lug location requires more depth, but less panel space. Number C55B has MIL type insulation and finish.





SERIES 20

SERIES 50

.141" MINIATURE **PHONE JACKS**




MINIATURE EXTENSION JACK, PHONE JACK NUMBER 125 (EIA STANDARD)

Cable-mounted Tini-Extension Jax® 2-conductor single open circuit jack has built in cable clamp/sleeve terminal. Mates with Tini-Plug® phone plugs and other plugs with .141" diameter fingers and compatible tip shape. Shielded housing/handle is knurled for positive fingertip grip; solder lug terminals.

Body and handle: Nickel-plated copper alloy.

Insulation: Rigid plastic. Springs: Plated copper alloy.



| Part Number | Description | Jack Schematic | Typical Mating Plug |
|----------------|----------------|-------------------|---------------------------|
| 125 | Extension Jack | I | 750 |

DIMENSIONS ARE FOR REFERENCE ONLY

.141" MINIATURE PHONE JACKS









142A

TINI-JAX® MINIATURE PHONE JACKS, NUMBERS 41, 42A, 43A

Tini-Jax 2-conductor phone jacks, (for limited space connecting, mate with miniature phone plugs having .141 "diameter fingers and compatible tip shape) are 1/3 the size of Littel-Jax® and weigh less than 1/8 ounce. Notched insulators interlock internal parts. Unique tip spring shape mates with Switchcraft Tini-Plug® phone plugs. Mounting hole: .250" diameter in panels up to .125" thick (mounting hardware supplied). For insulated mount, order two washers separately, Number **S1564** (swedged fiber washer .312" diameter mounting hole) and number **S2207** (flat phenolic washer).

SPECIFICATIONS MECHANICAL

Life: 5,000 insertion/withdrawal cycles, minimum.

ELECTRICAL

Contact Resistance: .075 ohms maximum. Insulation Resistance: 5,000 $M\Omega$ minimum.

Dielectric Withstanding Voltage: 250 V AC maximum.

Contact Rating: .25A, 48 V DC.

MATERIAL

Mounting Bushing: Nickel-plated copper alloy.

Insulating Spacers: Rigid plastic. **Springs:** Special copper alloy.

Sleeve Terminal: Tin-plated copper alloy.

Hardware: Supplied with one, Number P11501 nickel-plated copper alloy locknut, and one, Number S17901 nickel-plated steel flat washer.

| Part Number | Description | Jack Schematic ¹ | Typical Mating Plug ² |
|----------------|--------------------------|--------------------------------|--|
| 41 | Open circuit | I | 750 |
| 42A | Shunted (closed circuit) | III | 750 |
| 43A | Special transfer circuit | Note 3 | 750 |
| 142A | Shunted (closed circuit) | III | 750 |
| PC142A | Shunted (closed circuit) | III | 750 |

- 1. See jack schematics, pages 79 and 80.
- 2. See Plugs Section for mating information.
- When inserted, plug tip contacts "make" tip spring. Further insertion allows tip to short "make" tip spring and tip spring together. Full insertion opens tip shunt circuit.

TINI-D-JAX® MINIATURE ENCLOSED PHONE JACKS, NUMBERS 142A, PC142A

Tini-D Jax uses Hi-D Jax® construction and mounts on .375" centers. Weight: 3.6 grams. Number 142A mounts through .25" diameter hole in chassis/panel up to .125" thick. Four standoff dimples can be molded into housing to reduce effective length of bushing to .187" (special order). Number **PC142A** has special spring terminals for "snap-in" mounting to PC boards up to .125" thick - ready for hand, wave or dip-soldering.

SPECIFICATIONS MECHANICAL

Life: 5,000 insertion/withdrawal cycles, minimum. **Insertion/Withdrawal:** 15 ounce minimum, 40 ounce maximum, insertion. 12 ounce minimum, 25 ounce maximum, withdrawal.

ELECTRICAL

Contact Resistance: .10 ohms maximum.

Dielectric Withstanding Voltage: 250 V AC maximum.

Shunt Tension: 100 grams minimum.

MATERIAL

Housing: Molded plastic.


Mounting Bushing: Plated copper alloy. **Tip Spring:** Plated copper alloy, bifurcated. **Shunt Springs:** Plated copper alloy.


Sleeve Bracket: Plated steel. Insulator: Rigid plastic.


Hardware: Number 142A supplied with one, Number P1975 nickel-plated copper alloy locknut, and one, Number S3997

nickel-plated steel flat washer.

.141" MINIATURE PHONE JACKS (continued)







JACKS AND PLUGS 3.5MM DUAL STEREO JACK

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

3.5MM DUAL STEREO JACK







UNSHIELDED - 35RAPC7J

SHIELDED - 35RAPC7JS

FEATURES

- 3-conductor, miniature phone jack mates with 3.5 mm finger plugs.
- Saves board space...two jacks in a single vertical mount footprint.
- Ideally suited for infra-red and convection oven soldering 235°C (455°F).
- Board retention pins accommodate PC board thickness range of .050" to .080".
- Single-screw panel mounting hole is standard.
- EMI-RFI shield, optional.
- Housing UL 94V-0 rated against flammability.

APPLICATIONS

- Multi-media workstations
- Headphones/microphone sets
- Interactive TV
- Audio
- Telecommunications
- Medical
- Computer
- Instrumentation

MATERIALS

Housing: Thermoplastic.

Tip and Ring Springs: Silver-plated copper alloy. **Shunt Terminals:** Silver-plated copper alloy. **Sleeve Terminals:** Silver-plated copper alloy.

Shield: Pre-tinned copper alloy.

PERFORMANCE SPECIFICATIONS

Insertion/Extraction Forces, initial: 0.8 to 6 pounds.

Dielectric Withstanding Voltage: 500 VAC.

Insulation Resistance, initial: 100 Megaohms, min.

Contact Resistance: Between plug and jack:

50 milliohms, maximum Between springs and shunts:

30 milliohms, maximum. **Life:** 5000 cycles, minimum.


ORDERING INFORMATION


Part Number:


Shielded - 35RAPC7JS Unshielded - 35RAPC7J

- 1. Order by part number.
- 2. Contact Switchcraft for special order information.

3.5MM DUAL STEREO JACK (continued)







NOTES:

- 1. Shield isolated from terminals 1 and 6.
- 2. Width of all terminals = 0.032" (0.814 mm).
- **3.** Use Camcar Textron S25 T8 TORX pan head "Duro-PT" thread cutting fastener of appropriate length or equivalent.

3.5MM SINGLE MONO AND STEREO JACKS



35RAPC4BV4



35RAPC4BH3



35RAPC2AV



35RAPC2BV4



35RAPC2BHN2



35RAPC2BH3

FEATURES

- 2 and 3 conductor 3.5mm phone jacks
- Right angle PC mount, true SMT versions, and open frame panel mounts
- Wide variety of circuits available
- Mates with all 3.5mm plugs Right angle PC mount available in low profile, horizontal styles

MATERIALS

Housing: Thermoplastic, UL94V-1 Terminals: Silver-plated, copper alloy Bushing: Nickel-plated, copper alloy **Performance Specifications:** Contact Resistance: < 50 milliohms Insulation Resistance: 100 milliohms min. **Dielectric Withstanding Voltage: 250** VAC (35RAPC2BHN2-500 VAC) **Open Frame Versions Materials:**

Housing (35PM2BV2): Thermoplastic, 94V-1 Life: 5000 cycles, min.

Bushing: Nickel-plated, copper alloy

Insulating Washers: Rigid Plastic

Springs: Copper alloy

Sleeve Terminal: Tin-plated, copper alloy Hardware: Supplied with one, P11501 nickel-plated brass locknut, and one, S17901 nickel-plated steel flat washer

Performance Specifications: Contact Resistance: .075 ohms max. Insulation Resistance: 5,000 Mohms

Dielectric Withstanding Voltage: 250 VAC Life: 5000 cycles, min

ORDERING INFORMATION

Part numbers which include the letter "N" designate non-threaded bushings. Part numbers without the letter "N" designate threaded bushing.

| Part Number | Description | Height vs. Width | Bushing |
|-------------|-------------|---------------------|-----------------------|
| 35RAPC2AV | mono | vertical | threaded ³ |
| 35RAPC2AHN2 | mono | horizontal | non-threaded |
| 35RAPC2AHN3 | mono | horizontal | non-threaded |
| 35RAPC2BHN2 | stereo | horizontal | non-threaded |
| 35RAPC2BHN3 | stereo | horizontal | non-threaded |
| 35RAPC3BHN2 | stereo | horizontal | non-threaded |
| 35RAPC3BHN3 | stereo | horizontal | non-threaded |
| 35RAPC4BHN2 | stereo | horizontal | non-threaded |
| 35RAPC4BHN3 | stereo | horizontal | non-threaded |
| 35RAPC2AH3 | mono | horizontal | threaded3 |
| 35RAPC2BH3 | stereo | horizontal | threaded3 |
| 35RAPC3BH3 | stereo | horizontal | threaded ³ |

- 1. Order by part number
- 2. Contact Switchcraft for special ordering information
- 3. Mounting hardware included.

| | | Height vs. | |
|-------------|-------------|------------|--------------|
| Part Number | Description | Width | Bushing |
| 35RAPC4BH3 | stereo | horizontal | threaded3 |
| 35RAPC2AV4 | mono | vertical | threaded3 |
| 35RAPC2BV4 | stereo | vertical | threaded3 |
| 35RAPC3BV4 | stereo | vertical | threaded3 |
| 35RAPC4BV4 | stereo | vertical | threaded3 |
| 35RAPC2AVN4 | mono | vertical | non-threaded |
| 35RAPC2BVN4 | stereo | vertical | non-threaded |
| 35RAPC3BVN4 | stereo | vertical | non-threaded |
| 35RAPC4BVN4 | stereo | vertical | non-threaded |

Replacement Knurl Nut P3345

DIMENSIONS ARE FOR REFERENCE ONLY

3.5MM SINGLE, MONO AND STEREO JACKS (continued)

35RAPC2AV - MONO, VERTICAL, THREADED

MATERIALS

Coil Spring: Steel wire.

Bushing: Nickel-plated copper alloy.
Terminal: Silver-plated copper alloy.
Tip Spring: Silver-plated copper alloy.
Shunt Terminal: Plated copper alloy.

Cover: Thermoplastic, transparent UL 94V-2. **Body:** Thermoplastic, UL 94V-1 black color.

PERFORMANCE SPECIFICATIONS

Contact Resistance: 20 milliohms maximum.


Insulation Resistance:

100 milliohms minimum at 250V DC.

Dielectric Withstanding Voltage: 250V AC.

Life: 5000 cycles, minimum.

Insertion Force: 0.88 pounds - 3.5 pounds. **Withdrawal Force:** 0.88 pounds - 2.64 pounds.



35RAPC2AV4, 35RAPC2BV4, 35RAPC3BV4, 35RAPC4BV4 - STEREO, VERTICAL, THREADED

MATERIALS

Coil Springs: Steel Wire.

Ring Spring: Copper alloy strip, tin alloy plating. Ground Terminal: Copper alloy strip, tin alloy plating.

Bushing: Nickel-plated copper alloy. **Cover:** Thermoplastic, UL 94V-0 black color. **Body:** Thermoplastic, UL 94V-0 black color.

PERFORMANCE SPECIFICATIONS


Contact Resistance: 20 milliohms maximum, initial 50 milliohms maximum, after life.

Insulation Resistance: 50 megohms minimum at 500V DC.

Dielectric Withstanding Voltage: 250V AC.

Life: 5,000 cycles, minimum.

Insertion Force: 0.88 lbs. to 3.50 lbs. **Withdrawal Force:** 0.88 lbs. to 3.10 lbs.



DIMENSIONS ARE FOR REFERENCE ONLY

3.5MM SINGLE, MONO AND STEREO JACKS (continued)

35RAPC2AHN2, 35RAPC2BHN2, 35RAPC3BHN2, 35RAPC4BHN2 - STEREO, HORIZONTAL, NON-THREADED

MATERIALS

Cover: Thermoplastic, UL 94V-1 black color.

Ring Spring: Copper alloy.

Tip Spring: Silver-plated copper alloy. Ground Terminal: Silver-plated copper alloy.

Metal: Copper alloy, nickel plating.

Body: Thermoplastic, UL 94V-0 black color.

PERFORMANCE SPECIFICATIONS

Contact Resistance: 30 milliohms maximum, initial

100 milliohms maximum, after life.


Insulation Resistance: 100 megohms minimum

at 500V DC.

Dielectric Withstanding Voltage: 500V AC.

Life: 5000 cycles, minimum.

Insertion Force: 0.88 pounds - 6.6 pounds. Withdrawal Force: 0.88 pounds - 6.6 pounds.



35RAPC2AH3, 35RAPC2BH3, 35RAPC3BH3, 35RAPC4BH3 - STEREO, HORIZONTAL, THREADED PERFORMANCE SPECIFICATIONS **MATERIALS**

Coil Springs: Steel wire.

Tip Spring: Silver-plated copper alloy. Ring Spring: Silver-plated copper alloy. Ground Terminal: Silver-plated copper alloy. Bushing: Nickel-plated copper alloy.

Cover: Thermoplastic, transparent UL 94V-2.


Body: Thermoplastic, UL 94V-1 black color.

Contact Resistance: 20 milliohms maximum, initial

100 milliohms maximum, after life.

Insulation Resistance: 100 megohms minimum. Dielectric Withstanding Voltage: 250V AC.

Life: 5000 cycles, minimum. Insertion Force: 0.88 lbs. - 3.50 lbs. Withdrawal Force: 0.88 lbs. - 3.10 lbs.



DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

3.5MM SINGLE MONO AND STEREO JACKS

Switchcraft introduces a new series of 3.5mm jacks. These low profile jacks come in a wide variety of circuits, both 2 and 3 conductor versions. Circuits include mono closed, stereo open, stereo tip closed and ring open, and stereo closed. The 35RASMT Series is available on tape and reel only. Contact Switchcraft for exact dimensions of the reels. They're designed for use in today's electronic equipment that features remote speakers, headsets, and headphones. While they are more compact than commonly used PC mount phone jacks, they are still extremely durable. Jacks come on tape and reel, 1K per reel.

FEATURES AND BENEFITS

- SMT mounting
- Tape and reel packaging
- · Wide variety of circuits

APPLICATIONS

- Computer
- Video Cameras
- Personal/Portable Audio Devices
- Multimedia

SPECIFICATIONS

Electrical Current Rating: 3A Contact Resistance: <50 mohms

Insulation Resistance: 100 mohms (min.)

Dielectric Withstanding Voltage: 250VAC @ 1 minute

MECHANICAL Lifecycles: 5,000

Operating Temperature: -25°C to +85°C

MATERIAL

Housing: Black thermoplastic Sleeve, Ring and Tip Terminals:

Copper Alloy, silver-plated

Shunt Terminal: Copper Alloy, Silver-plated



35RASMT

3.5MM SINGLE MONO **AND STEREO JACKS**

Part Number/Description 35RASMT2AHNTR

Mono, closed circuit, on tape and reel

35RASMT2BHNTR

Stereo, dual open circuit, on tape and reel

35RASMT3BHNTR

Stereo, tip closed and ring open circuit, on tape and reel


35RASMT4BHNTR

Stereo, dual closed circuit,

on tape and reel

(See next page for drawings.)


3.5MM SINGLE MONO AND STEREO JACKS (continued)




DIMENSIONS ARE FOR REFERENCE ONLY

3.5 mm SINGLE MONO JACKS









FEATURES

- 2-conductor phone jacks similar to Littel-Jax® phone jacks, but smaller.
- For connecting in limited space
- Mate with 3.5 mm phone plugs
- Notched insulators interlock internal parts
- Mounting hole: .250" diameter in panels up to .125" thick (mounting hardware supplied)
- For insulated mount, order two washers separately, Number S1564 (swedged fiber washer .312" diameter mounting hole) and number S2207 (flat phenolic washer)

SPECIFICATIONS MECHANICAL

Life: 5,000 insertion/withdrawal cycles, minimum

ELECTRICAL

Contact Resistance: .075 ohms maximum Insulation Resistance: $5,000~M\Omega$ minimum

Dielectric Withstanding Voltage: 250V AC maximum

Contact Rating: .25A, 48V DC

MATERIAL

Mounting Bushing: Nickel-plated copper alloy.

Insulating Spacers: Rigid plastic.

Springs: Copper alloy.

Sleeve Terminal: Tin-plated copper alloy.

Hardware: Supplied with one, Number P11501

nickel-plated brass locknut, and one, Number S17901

nickel-plated steel flat washer.

| PART NUMBER | DESCRIPTION | JACK SCHEMATIC ¹ | TYPICAL MATING PLUG |
|----------------|--------------------------|--------------------------------|---------------------------|
| 35PM1 | Open circuit | I | 750 |
| 35PM2A | Shunted (closed circuit) | III | 750 |

^{1.} See jack schematics on pages 79 and 80.

ORDERING INFORMATION

- 1. Order by part number.
- 2. Contact Switchcraft for more information.

2.5MM SINGLE MONO AND STEREO JACKS

Switchcraft introduces a new series of 2.5mm jacks. These low profile jacks come in a wide variety of circuits, both 2 and 3 conductor versions. Circuits include mono closed, stereo open, stereo tip closed and ring open, and stereo closed. The MDSMT Series is available on tape and reel only. Contact Switchcraft for exact dimensions of the reels. They're designed for use in today's electronic equipment that features remote speakers, headsets, and headphones. While they are more compact than commonly used PC mount phone jacks, they are still extremely durable.

A LOW

MDSMT4BRATR

FEATURES AND BENEFITS

- SMT mounting
- · Tape and reel packaging
- · Wide variety of circuits

APPLICATIONS

- Computer
- Video Cameras
- Personal/Portable Audio Devices
- Multimedia

SPECIFICATIONS

Electrical Current Rating: 3A Contact Resistance: <50 mohms

Insulation Resistance: 100 mohms (min.)

Dielectric Withstanding Voltage:

250VAC @ 1 minute

MECHANICAL

Lifecycles: 5,000

Operating Temperature: -25°C to +85°C

MATERIAL


Housing: Black thermoplastic **Sleeve, Ring and Tip Terminals:**

Copper Alloy, silver-plated

Shunt Terminal: Copper Alloy, Silver-plated

2.5MM SINGLE MONO AND STEREO JACKS

Part Number/Description MDSMT2BRATR Stereo, dual open circuit MDSMT2ARATR Mono, closed circuit MDSMT3BRATR Stereo, tip closed and ring open circuit MDSMT4BRATR Stereo, dual closed circuit



DIMENSIONS ARE FOR REFERENCE ONLY

.101" SUBMINIATURE PHONE JACKS













TR2A TR1PC

MDPC2A

SUBMINIATURE PHONE JACKS, TR2A AND TR1PC

Extremely small, rugged, shunted Micro-Jax® 2-conductor jack is 1/4 the size of a standard phone jack and weighs less than 1/20 ounce. Can be wired for open or closed circuit operation. Internally keyed insulators interlock all parts and tip springs grip mating plugs positively. Mates with Switchcraft Micro-Plug® phone plugs. Jacks mount through .190" diameter hole in chassis/panels up to .093" thick. For insulated mounting, a .281" diameter hole and .050" maximum panel thickness applies. Order insulating washer separately. Number **P1617** (flat phenolic washer) and Number **P1618** (swedged fiber washer).

Number TR1PC: 2-conductor closed circuit jack with PC terminals. Open frame and enclosed versions available. Mates with Switchcraft® Micro Plug® numbers 850, 855, and 880.

SUBMINIATURE ENCLOSED PHONE JACKS

Micro-D Jax® 2-conductor jacks have insulated box construction and subminiature size.

Number MDPC2A: 2-conductor closed circuit jack with PC terminals. Mounts to single-, double-sided or multilayer boards either singly or in rows as close as .344" centers (+/- .01 inches). Bushing is .10" inside diameter.

Number MDSL2A: Same as MDPC2A except, 1. solder lugs, 2. bushing is #10-48 threaded (nut and washer supplied), and 3. mount ing centers are .35" or .313". When mounted on .313" centers, sleeves or adjacent jacks may be in intimate contact. Mounts through a .203" diameter hole in chassis/panels up to .063" thick.

SUBMINIATURE RIGHT-ANGLE PHONE JACKS

2-conductor jacks have molded housing which protects all internal parts. Panel/chassis or PC boards mounting in rows, if desired, on .351" centers. PC terminals need only .382" behind-panel clearance.

Number MDPC2ARA: PC terminals mount/terminate directly to PC or multilayer boards. Bushing clears a .156" diameter panel hole.

Number MDSL2ARA: Right-angle solder lugs and #10-48 threaded bushing for chassis/panel mount. Mounts in .203" diameter hole in chassis/panels up to .063" thick.

SPECIFICATIONS - MICRO-JAX® ELECTRICAL:

Contact Resistance: .10 ohms maximum (spring to plug).

Shunt Resistance: .10 ohms maximum.

Dielectric Withstanding Voltage: 250 V AC.

MATERIAL:

Mounting Bushing: Nickel-plated copper alloy.

Insulating Spacers: Rigid plastic.

Shunt Tension: 60 grams minimum.

Springs: Nickel-plated copper alloy. Integral contacts are plated. Tip, Shunt and Sleeve Terminals: Silver-plated copper alloy. Hardware: Supplied with one, P15331 nickel-plated copper alloy hex nut, and one S29571 nickel-plated copper alloy flat washer.

MATERIAL - TR1PC

Threaded Bushing: Nickel-plated copper alloy.

Tip Spring: Copper alloy.

Sleeve/Ground Terminal: Copper alloy tin-lead with nickel underplate.

MDSL2A MDSL2ARA MDPC2ARA

MECHANICAL - TR1PC:

Life: 10,000 insertion/withdrawal cycles, minimum. Insertion/Withdrawal Forces: 11 ounces insertion, 11 ounce minimum withdrawal.

ENVIRONMENTAL - TR1PC:

Thermal Range: -55°C to +85°C (non-operating);

-20°C to +65°C (operating).

Thermal Shock: Per MIL-STD-202, method 107. Humidity: Per MIL-STD-202, method 106. Salt Spray: Per MIL-STD-202, method 101.

SPECIFICATIONS - MICRO-D JAX MECHANICAL:

Life: 10,000 insertion/withdrawal cycles minimum. **Insertion/Withdrawal Forces:** 11 ounce insertion,

11 ounce minimum withdrawal.

ELECTRICAL:

Contact Resistance: .010 ohms maximum (initial), .020 ohms maximum (after humidity, durability exposure), .10 ohms

maximum (after salt spray).

Insulation Resistance: 10,000 M Ω minimum (initial), 1,000 M Ω minimum (after humidity, durability exposure). Dielectric Withstanding Voltage: 500 V AC maximum.

Contact Rating: .125 A, 125 V AC.

ENVIRONMENTAL:

Thermal Range: -55°C to +85°C (non-operating);

-20°C to +65°C (operating).

Thermal Shock: Per MIL-STD-202, method 107. Humidity: Per MIL-STD-202, method 106. Salt Spray: Per MIL-STD-202, method 101.

MATERIAL:

Housing: Glass reinforced plastic. **Insulation:** Rigid plastic. **Mounting Bushing (Micro-D):** Nickel-plated copper alloy.

Mounting Bracket (Right-Angle Micro-D):

Nickel-plated copper alloy.

Tip Spring: Silver-plated copper alloy. **Shunt Terminal:** Silver-plated copper alloy. **Sleeve Terminal (Micro-D):** Steel, tin-plated.

Sleeve Terminal (Right-Angle Micro-D): Silver-plated

copper alloy.

Hardware (Micro-D): Same as Micro-Jax (MDSL2A). Hardware (Right-Angle Micro-D): Hex nut, nickel-plated copper alloy, Number P15331; flat washer, nickel-plated copper alloy S29571; not supplied with MDPC2A.


| Part | Jack | Typical | Part | Jack | Typical |
|-------------------------|---------------------|--------------------------|--------------------------------|---------------------|--------------------------|
| No. | Schem. ¹ | Mating Plug ² | No. | Schem. ¹ | Mating Plug ² |
| TR2A TR1PC MDPC2A | } | 850 | MDSL2A MDPC2ARA MDSL2ARA | } | 850 |

All are 2-Conductor (closed circuit). Note 1.: See Jack Schematics page 79 and 80. Note 2.: See Plugs Section for mating information.


DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

.101" SUBMINIATURE PHONE JACKS



BULKHEAD PHONO JACKS



FEATURES AND BENEFITS

- Front or rear mount configurations
- Durable plated machined brass construction
- All mounting hardware is included

APPLICATIONS

- Audio
- Video
- General Purpose Electronics

OPTIONS

- Front or rear mount solder type receptacles
- Jack to jack bulkhead configuration
- · Insulator colors
- · Gold or nickel plating

(See next page for drawings.)

| | Part Number | Description |
|---|------------------------|--|
| | BPJR01 | Rear mount, black insulator |
| | BPJR01AU | Rear mount, black insulator, gold plated |
| | BPJR02 | Rear mount, red insulator |
| | BPJR02AU | Rear mount, red insulator, gold plated |
| | BPJR03 | Rear mount, white insulator |
| | BPJR03AU | Rear mount, white insulator, gold plated |
| | BPJR04 | Rear mount, yellow insulator |
| | BPJR04AU | Rear mount, yellow insulator, gold plated |
| | BPJR05 | Rear mount, blue insulator |
| | BPJR05AU | Rear mount, blue insulator, gold plated |
| | BPJR06 | Rear mount, green insulator |
| | BPJR06AU | Rear mount, green insulator, gold plated |
| | 3501F | Rear mount, rigid plastic mounting flange |
| | 3501FR | Rear mount, natural insulator |
| | For insulated mounting | , order S1028 and S1029 insulating washers |
| | BPJF01 | Front mount, black insulator |
| | BPJF01AU | Front mount, black insulator, gold plated |
| | BPJF02 | Front mount, red insulator |
| | BPJF02AU | Front mount, red insulator, gold plated |
| | BPJF03 | Front mount, white insulator |
| | BPJF03AU | Front mount, white insulator, gold plated |
| | BPJF04 | Front mount, yellow insulator |
| | BPJF04AU | Front mount, yellow insulator, gold plated |
| | | |
| L | | |

SPECIFICATIONS

Material and Platings Housing:

Nickel or Gold-plated Brass

Contact: Nickel-plated Brass Insulator: ABS

Hardware: Nickel-plated Brass. Switchcraft introduces a complete line of bulkheadmount phono (RCA) jacks to meet the most critical audio, audio/video, and general-purpose electronic applications. These jacks are offered in front and rear mount solder type as well as jack to jack bulkhead configurations. These jacks are available with black, white, blue, green, red, and yellow insulators and nickel or gold plated bodies. All mounting hardware is included.

Housing: Nickel or gold plated, copper alloy (3514PC, 3515PC, 3517PC: Nickel plated, steel)

Terminals: Nickel plated, copper alloy (3515PC: Tin plated,

copper alloy)

Bushing: Nickel-plated, copper alloy (3515PC: Ceramic)


Insulators: Thermoplastic

(3517PC: Ceramic and glass filled thermoplastic)

| Part Number | Description |
|-------------------|--|
| BPJF05 | Front mount, blue insulator |
| BPJF05AU | Front mount, blue insulator, gold plated |
| BPJF06 | Front mount, green insulator |
| BPJF06AU | Front mount, green insulator, gold plated |
| 3501FP | Front Mount, natural insulator |
| 3505F | RF version, uses low-loss nylon insulation |
| For insulated mou | nting, order S2207 and S1564 insulating washers |
| BPJJ01 | Feed through, black insulator |
| BPJJ01AU | Feed through, black insulator, gold plated |
| BPJJ02 | Feed through, red insulator |
| BPJJ02AU | Feed through, red insulator, gold plated |
| BPJJ03 | Feed through, white insulator |
| BPJJ03AU | Feed through, white insulator, gold plated |
| BPJJ04 | Feed through, yellow insulator |
| BPJJ04AU | Feed through, yellow insulator, gold plated |
| BPJJ05 | Feed through, blue insulator |
| BPJJ05AU | Feed through, blue insulator, gold plated |
| BPJJ06 | Feed through, green insulator |
| BPJJ06AU | Feed through, green insulator, gold plated |
| 3503 | Extension jack, shielded handle |
| 3514PC | Vertical PC mount, nickel plated steel bushing |
| 3515PC | Vertical PC mount, ceramic bushing |
| 3517PC | Horizontal PC mount, nickel plated steel bushing |

JACKS AND PLUGS

PHONO JACKS (continued)



PHONO JACKS AND PHONO JACK SETS











PJRAN1X1U03

PJRAS1X1S04

PJRAS1X2S02

PJRAN2X1U02

PJRAS2X1S01









PJRAN3X1U03

PJRAS3X1S01

PJRAS3X2S01

PJRAS2X2S01









PJRAS4X2U01

PJRAS1X3S01

PJRAN3X1U02

Switchcraft, the industry recognized leader in audio-video connectivity, introduces the addition of a comprehensive line of PCB Mount RCA Jacks and Jack Sets. Switchcraft's newest product family addresses the requirements of the most critical audio and audio/video applications. 1, 2, 3, 4, 6, and 8 position jack sets are offered in a variety of color combinations with numerous plating, grounding, shielding, mounting, and justification options.

FEATURES AND BENEFITS

- High temperature plastic housings and long life contacts
- Snap fit PCB contacts and housings
- Low profile footprint
- Numerous options and configurations

APPLICATIONS

- Audio
- Video
- General Purpose Electronics

OPTIONS

- · Right angle and straight PCB mount
- Horizontal and vertical justification

- Shielding and grounding
- Bulkhead mounting screw
- Colors
- Plating

SPECIFICATIONS ELECTRICAL

Temperature Range: -25 to +80°C Rated Voltage: 34V DC or AC Withstand Voltage: 500V Rated Current: 2A DC or AC

Dielectric Strength: 500V AC @ 1 minute

Contact Resistance: <30 mohms Insertion Force*: <29.4N Extraction Force*: 1N to 29.4N

* Depends Upon Mating Plug

MATERIAL AND PLATINGS

Housing: UL94-HB Rated, ABS

Insulators: ABS

Ground Shell and Terminal: Nickel or Gold Plated, Copper Alloy

Terminals: Tin Plated Copper Alloy

NLY Inc

โร่ห์ชี AND Phone: 773 792-2700 * Please visit the product pages on our website for the most up-to-date product information

r loade visit the product pages on our website for the most up to date pr

PHONO JACKS AND PHONO JACK SETS (continued)

1 POSITION PCB MOUNT

| Part Number | Color |
|--------------|--------|
| PJRAN1X1U01 | Black |
| PJRAN1X1U02 | White |
| PJRAN1X1U03 | Red |
| PJRAN1X1U04 | Yellow |
| Call factory | Green |
| Call factory | Blue |
| PJRAS1X1S01 | Black |
| PJRAS1X1S02 | White |
| PJRAS1X1S03 | Red |
| PJRAS1X1S04 | Yellow |
| Call factory | Green |
| Call factory | Blue |
| | |

3 POSITION PCB MOUNT

| Part Number | Color |
|-------------|------------------------------------|
| PJRAN3X1U01 | Red/Yellow/White |
| PJRAN3X1U02 | Red/Green/Blue |
| PJRAS3X1S01 | Red/White/Yellow |
| PJRAS3X1U03 | Red/Green/Blue |
| PJRAS1X3S01 | Red |
| | <u>White</u> Yellow |
| PJRAS1X3S02 | <u>Green</u> <u>Blue</u> Red |

2 POSITION PCB MOUNT

| Part Number | Color |
|-------------|---------------------|
| PJRAN2X1U01 | Red/White |
| PJRAN2X1U02 | White/Red |
| PJRAS2X1S01 | Red/White |
| PJRAS2X1S02 | White/Red |
| PJRAS1X2S01 | <u>Red</u> White |
| PJRAS1X2S02 | <u>White</u> Red |

4, 6, & 8 POSITION PCB MOUNT

| Part Number | Color |
|-------------|--------------------------------------|
| PJRAS2X2S01 | White x 2 Red x 2 |
| PJRAS3X2S01 | White x 3 Red x 3 |
| PJRAS3X2S02 | Red/White/Yellow Red/White/Yellow |
| PJRAS4X2U01 | White x 4 Red x 4 |


COMBINATION PHONO AND S-VIDEO PCB MOUNT

| Part Number | Color |
|-------------|--------------------------------------|
| PJRAN3X1U02 | Red/White/Yellow |
| PJRAS1X3U01 | <u>Yellow</u> <u>White</u> Red |


Ordering Information (Contact factory for color, shielding, grounding, justification options.)

| PJ | RA | S | # | Χ | # | S | 01 | AU |
|--------------|-----------------------------------|-------------------------------|----------------------|----|--------------------|--------------------------------|---------|----------------------|
| Product Type | Justification | Mounting | Positions Horizontal | | Positions Vertical | Shielding | Version | Ground Shell Plating |
| Phono Jack | RA - Right Angle ST - Straight | S - Screw(s) N - No Screws | 1,2,3, or 4 | Ву | 1,2, or 3 | S - Shielded U - Unshielded | | AU/Gold |


PHONO JACKS AND PHONO JACK SETS (continued)




PHONO JACKS AND PHONO JACK SETS (continued)




PHONO JACKS AND PHONO JACK SETS (continued)





RIGHT ANGLE MINIATURE POWER JACKS



SPECIFICATIONS:

Materials: Housing: Thermoplastic

Terminals: RAPC700:

Sleeve: Silver plated copper alloy **Tip:** Nickel plated, copper alloy

RAPC742, RASM742TR, RAPC732OF, RAPC742OF, RAPC752, RAPC752S, RASM752TR, RASM752STR:

Sleeve and tip: Silver plated tin **Shunt:** Silver plated copper alloy

RASM700, RASH700:

Sleeve: Tin plated copper alloy **Tip:** Nickel plated copper alloy)

ELECTRICAL

Current Rating: 3A

(RAPC700, RASH700, RASM700: 5A)

Contact Resistance: <50 mohms
Insulation Resistance: 100 mohms min.
(RAPC700, RASH700, RASM700: 30 megohms

@100V DC)

Dielectric Withstanding Voltage: 250 VAC@ 1 minute

MECHANICAL: Lifecycles: 5,000 min.

| Part Number | Pin Size* | Description |
|-------------|---------------|-------------------------------------|
| RAPC712 | 0.100"/2.5mm | Right Angle, PC mount |
| RASH712 | 0.100"/2.5mm | Right Angle, hybrid mount |
| RASM712 | 0.100"/2.5mm | Right Angle, SMT mount |
| RAPC722 | 0.080"/2.0mm | Right Angle, PC mount |
| RASH722 | 0.080"/2.0mm | Right Angle, hybrid mount |
| RASM722 | 0.080"/2.0mm | Right Angle, SMT mount |
| RAPC732 | 0.050"/1.3mm | Right Angle, PC mount |
| RAPC732OF | 0.050"/1.3mm | Right Angle, PC mount ¹ |
| RASH732 | 0.050"/1.3mm | Right Angle, SMT mount |
| RASM732 | 0.050"/1.3mm | Right Angle, hybrid mount |
| RAPC742 | 0.040"/1.0mm | Right Angle, PC mount |
| RAPC742OF | 0.040"/1.0mm | Right Angle, PC mount ¹ |
| RASM742TR | 0.040"/1.0mm | Right Angle, SMT mount ² |
| RAPC752 | 0.025"/0.65mm | Right Angle, PC mount |
| RAPC752S | 0.025"/0.65mm | Right Angle, PC mount ³ |
| RASM752TR | 0.025"/0.65mm | Right Angle, SMT mount ² |
| RASM752STR | 0.025"/0.65mm | Right Angle, SMT mount ⁴ |


Note: Contact factory for specific information on tape and reel options. *Pin Size (in/mm) 1. Open Frame 2. Tape and Reel. 3. Shielded 4. Tape and Reel, Shielded.


Note: Available with P locating post as an option. Note: Available with tin-plating as a special order.


Note: Available with Hi-temp material, contact factory for details.

DIMENSIONS ARE FOR REFERENCE ONLY

RIGHT ANGLE MINIATURE POWER JACKS (continued)








DIMENSIONS ARE FOR REFERENCE ONLY


JACKS AND PLUGS

Please visit the product pages on our website for the most up-to-date product information

RIGHT ANGLE MINIATURE POWER JACKS (continued)



RIGHT ANGLE MINIATURE POWER JACKS (continued)



JACKS AND PLUGS STRAIGHT MINIATURE POWER JACKS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

STRAIGHT MINIATURE POWER JACKS











FEATURES:

- Automatic switch over from AC to DC permitted by sleeve shunt spring.
- Split center pin shaped to hold mating plug firmly.
- Bushing length available as 0.219" or extended 0.319" to permit use in thicker panels.
- Non-turn mounting possible using standard "D" shape bushing.
- Insulated mounting hardware available.
- Right angle versions offer "kinked" PC terminals for added board retention.

MATERIALS:

Housing: Thermoplastic
Bushing: Plated copper alloy
Terminals: Plated copper alloy

Insulators: Rigid Plastic

Hardware: Supplied with one P2439 nickel plated copper alloy hex nut, and one P2441 nickel plated steel flat washer

ELECTRICAL:

Current Rating: 5A, 12V DC resistive

Contact Resistance: 0.01 Ohms max. (initial), 0.02 Ohms max. (after humidity, durability exposure),

0.10 Ohms max. (after salt spray)

Insulation Resistance: 10,000 Mohms min. (initial), 1,000 Mohms min. (after humidity, durability exposure) Dielectric Withstanding Voltage: 500 VAC max.


MECHANICAL:

Lifecycles: 10,000 cycles min.

| Part Number | Pin Size* | Description | Typical Mating Plug |
|-------------|--------------|--|---------------------|
| 712A | 0.100"/2.5mm | Solder lugs | 760 |
| 712RA | 0.100"/2.5mm | Right angle PC terminals | 760 |
| L712A | 0.100"/2.5mm | Solder lugs, long bushing | 761K |
| L712RA | 0.100"/2.5mm | Right angle PC terminals, long bushing | 761K |
| PC712A | 0.100"/2.5mm | Straight PC terminals | 760 |
| PCL712A | 0.100"/2.5mm | Straight PC terminals, long bushing | 761K |
| 722A | 0.080"/2.0mm | Solder lugs | S760 |
| 722RA | 0.080"/2.0mm | Right angle PC terminals, long bushing | S760 |
| L722A | 0.080"/2.0mm | Solder lugs, long bushing | S761K |
| L722RA | 0.080"/2.0mm | Right angle PC terminals, long bushing | S761K |
| PC722A | 0.080"/2.0mm | Straight PC terminals | S760 |
| PCL722A | 0.080"/2.0mm | Straight PC terminals, long bushing | S761K |
| 732A | 0.050"/1.3mm | Solder lugs | 860 |
| 732RA | 0.050"/1.3mm | Right angle PC terminals | 860 |
| PC732A | 0.050"/1.3mm | Straight PC terminals | 860 |
| 2C1072 | | Jack covers for 712A and 722A | |

Note: For insulated mounting order P2442 phenolic flat washer and S4263 swedged fiber washer.


STRAIGHT MINIATURE POWER JACKS (continued)



VJ SERIES



VJHD*75TX



FEATURES AND BENEFITS

- HD Series meets SMPTE 292M Specifications
- SD Series has a bandwidth from DC to 1.75GHz
- · Jacks feature rugged heavy duty housings

VIDEO JACK SPECIFICATIONS ELECTRICAL

Rated Bandwidth: 2.4 GHz (HD), 1.75 GHz (SD)

Characteristic Impedance: 75 ohms Return Loss: Better than -15 dB Insertion Loss: Better than -.5 dB

Contact Resistance: Less than 20 milliohms

Termination Resistance: 75 W, ±1%

Center Conductor: Accepts .090 pin diameter

MECHANICAL

Mechanical Shock: Per MIL-STD-202,

Method 213, Test condition I

Vibration: Per MIL-STD-202. Method 201 Insertion Force: 12 lbs. maximum Withdrawal Force: 3 lbs. minimum

Life Cycle: 30,000

MATERIAL

Housing: Zinc alloy, nickel plated

Center Contacts: Copper alloy, gold plated Switching Springs: Copper alloy, gold plated

Grounding Contacts:

HD Series - Copper alloy, gold plated SD Series - Copper alloy, nickel plated Insulators: Thermoplastic, UL 94V-0 rated


ENVIRONMENTAL

Operating Temperature: - 40°C to 65°C Storage Temperature: - 55°C to 85°C Thermal Shock: Per MIL-STD-202,

Method 107

Moisture and Humidity:


Per MIL-STD-202, Method 106. The HD Series meets SMPTE 292M specifications for high definition video signaling, covering a bandwidth range from DC to 2.4GHz. The SD Series is perfect for serial digital, with a bandwidth from DC to 1.75GHZ.



SD

*Add "N" for non-normalled version

Non-terminated




VJSD*NTX

NON-NORMALLED **TERMINATED**

NORMALLED **TERMINATED**

NORMALLED NON-NORMALLED NON-TERMINATED NON-TERMINATED




DIMENSIONS ARE FOR REFERENCE ONLY

Inch

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information



Rated Bandwidth: 3.0 GHz Characteristic Impedance: 75 ohms

Characteristic Impedance: 75 ohms
Return Loss: See Typical Return Loss Chart
Insertion Loss: See Typical Insertion Loss Chart
Contact Resistance: Less than 20 milliohms
Termination Resistance: 75 W, ±1%
Center Conductor: Accepts .048 pin diameter

MECHANICAL

Mechanical Shock: Per MIL-STD-202, Method 213, Test condition I

ivietnod 213, Test condition I

Vibration: Per MIL-STD-202, Method 201 Insertion Force: 12 lbs. maximum Withdrawal Force: 3 lbs. minimum

Life Cycle: 30,000

MATERIAL

Housing: Zinc alloy, nickel plated

Center Contacts: Copper alloy, gold plated **Switching Springs:** Copper alloy, gold plated

Grounding Contacts: Copper alloy,

gold plated

BNC Insulators: Teflon

Actuators: Thermoplastic, UL94V-0 rated


ENVIRONMENTAL

Operating Temperature: - 40°C to 65°C Storage Temperature: - 55°C to 85°C Thermal Shock: Per MIL-STD-202,


Method 107

Moisture and Humidity: Per MIL-STD-202, Method 106


| Ordering Information Part | | | | |
|------------------------------------|------|----------------|--|--|
| Number | Jack | Description | | |
| MVJ*75T | HD | Terminated | | |
| MVJ*NT | HD | Non-terminated | | |
| *Add "N" for non-normalled version | | | | |



SMITH CHART (TYPICAL)




RETURN LOSS (TYPICAL)



FREQUENCY (MHz)

RETURN LOSS (TYPICAL)



FREQUENCY (MHz)

DIMENSIONS ARE FOR REFERENCE ONLY



JACKS AND PLUGS


* Please visit the product pages on our website for the most up-to-date product information

MIL-TYPE 1/4" PHONE PLUGS




2-CONDUCTOR






3-CONDUCTOR
























FEATURES

Designed for high quality communication equipment to meet military requirements, This series features one-piece tip rod and one-piece sleeve and plug body, assembled together into a mode as inserts, providing a finished plug with complete continuity of thermoplastic insulation between top rod and plug sleeve. Internal (invisible externally) interlock mechanically engages the metal and plastic components providing a realistic lock to prevent parts shifting. Design and material in accordance with MIL-P-642(A), MIL part number molded or stamped on handle, manufacturer's trademark (as required by MIL specification) appears on plug body.

SPECIFICATIONS

Tip Rod, Body and Screws: Copper alloy, natural finish.

Terminals: Tinned copper alloy.

Insulation: Thermoplastic, per MIL-P-22985, Type II, Class 1. **Handles:** Thermoplastic, Type 6, per MIL-M-20693, Type II. Shielded; machined from copper alloy, nickel-plated.

STRAIN RELIEF CLAMP

For MIL-type Littel-Plug phone plugs. **P2380** conforms to Specification SC-A-7674-F - supplied with Plug Numbers 430, 440, 445 and 470. **P2381** meets Specification MS-35762 - supplied with Plug Number 480 and Extension-Jax® phone jack, Number 820.

DIMENSIONS ARE FOR REFERENCE ONLY

LITTEL PLUG® PHONE PLUGS



FEATURES AND BENEFITS

- 3 conductor plug
- Designed for high quality communication equipment
- One-piece tip rod ensures electrical continuity
- Brass plug finger versions meet MIL specifications
- 'N' and 'NC' suffix versions have nickel-plated plug fingers, excellent for audio applications
- NC" suffix option has rugged, heavy duty cable clamp, solder terminals for easier solderability and assembly. Metal shielded handle
- 'NCP" plastic handle

SPECIFICATIONS

Plug Finger: Brass, natural finish or nickel-plated

Terminals: Brass, electro-tinned

Insulation: Ethyl cellulose, per MIL-P-22835, Type II,

Class 1, or acetal resin


Handles: Plastic-nylon molding plastic, Type 6,

per MIL-M-20693, Type II. Shielded metal handle with red,

black or nickel finish

ORDERING INFORMATION

- 1. Order by part number.
- 2. Contact Switchcraft for more information.
- 3. Mating jacks available.



* Please visit the product pages on our website for the most up-to-date product information

LITTEL PLUG® PHONE PLUGS


| Part Number | Conductors | Terminals | Handle | MIL Part Number | Notes |
|-------------|------------|-------------|----------|--------------------|---|
| 482N | 3 | Screw | Red | None | Plastic handle, nickel plated plug finger |
| 482NC | 3 | Cable Clamp | Shielded | None | Red metal handle, nickel plated plug finger |
| 482NCP | 3 | Cable Clamp | Red | None | Plastic handle,nickel plated plug finger |
| 483N | 3 | Screw | Black | None | Plastic handle, nickel plated plug finger |
| 483NC | 3 | Cable Clamp | Shielded | None | Black metal handle,nickel plate plug finger |
| 483NCP | 3 | Cable Clamp | Black | None | Black plastic handle, nickel plated plug finger |
| 485NC | 3 | Cable Clamp | Shielded | None | Nickel plated handle,nickel plated plug finger |


480 SERIES PART NUMBERING CHART


| Part | 206" dia. | 1/4" dia. | Brass | Nickel | Handle | Red | Black | Nickel | Standard | Large |
|--------|-----------|-----------|--------|--------|----------|--------|--------|--------|-------------|-------------|
| number | finger | finger | finger | finger | Material | handle | handle | handle | cable clamp | cable clamp |
| 480 | • | | • | | Plastic | | • | | • | |
| 482 | | • | • | | Plastic | • | | | • | |
| 482N | | • | | • | Plastic | • | | | • | |
| 482NC | | • | | • | Metal | • | | | | • |
| 482NCP | | • | | • | Plastic | • | | | | • |
| 483 | | • | • | | Plastic | | • | | • | |
| 483N | | • | | • | Plastic | | • | | • | |
| 483NC | | • | | • | Metal | | • | | | • |
| 483NCP | | • | | • | Plastic | | • | | | • |
| 484 | • | | • | | Plastic | • | | | • | |
| 485NC | | • | | • | Metal | | | • | | • |


MIL-TYPE 1/4" TWIN PHONE PLUGS











FEATURES

Design and material strictly in accordance with Specification MIL-P-642(A), MIL part number molded or stamped on handle, manufacturer's trademark (as required in MIL Specification) appears on plug body. Ideal for use in broadcast and recording studios, military, industrial and telephone switchboard applications, instrumentation and telemetry.

Individual plugs, featuring one-piece tip rod and one-piece sleeve and plug body, with complete continuity of thermoplastic insulation between plug elements, are placed into handles to provide a double Twin-Plug® plug (two electrically-independent 2-conductor plugs spaced .625" center-to-center, with self-alignment feature). 411, 414 and 415 Twin-Plug plugs have provision for use of Cord Clamp Number S2674. 412 Twin-Plug has external Cord Anchor.

6-conductor Twin-Plug, 414 and 415, provide two electrically-independent 3-conductor plug fingers spaced on .625" centers. Fingers are insulated from each other and each provides tip, ring and sleeve connections. Black plastic handle is notched to indicate polarity. Accepts standard 6-conductor cables. Handle has provision for use of Cord Clamp, \$2674.

Fingers of 414 are .25" diameter and mate with Switchcraft type MT389 Twin-Jax®, MT333B, MT336 MT-Jax®, and other jacks having .25" inside diameter sleeves and mounted on .625" centers. 415 has a .25" diameter finger and a .206" diameter finger to provide automatic polarization. Fingers mate with Switchcraft MT332B and MT342B MT-Jax, respectively.

STRAIN RELIEF CLAMP

Natural brass. For use only with 411, 414, 415 Twin-Plug, S2674.

SPECIFICATIONS

Tip, Rod, Ring Sleeve, Body, Screws: Copper alloy, natural finish. Number 412 Handle Screws - iridescent iridite overplating.

Terminals: Tinned copper alloy. (Latest MIL Specifications no longer specify terminals; terminal furnished is the type referenced as TM-89).

Insulation: Thermoplastic; per MIL-P-22985, Type II, Class 1. Handle: Thermoplastic on 411, 412, 414 and 415, per MIL-P-22985, Type II, Class 4. Molded black thermoset plastic per MIL-M-14F.

| Part No. | Conductors | Terminals | "Typical Mating Jack1" | Mil No. | Notes |
|----------|------------|-----------|------------------------|-------------------------------|---|
| 411 | 2 | Screw | MT388 | M642/9-1 | Provision for internal cord clamp (not included) |
| 412 | 2 | Screw | MT388 | MILPJ289. Similar to WECo289B | |
| 414 | 3 | Screw | MT389 | | 6-circuit plug, 2 electrically-independent 3 conductor fingers, .25" fingers. Provision for internal cord clamp (not included) Similar to WECo 338A. 425A-3 |
| 415 | 3 | Screw | MT332B &1, MT342B | | 6-circuit plug, 2 electrically-independent 3 conductor fingers, one .25" finger, one .206" finger. Provision for internal cord clamp (not included) |

1. Switchcraft Part Numbers. See Jacks Section for other mating jacks.

JACKS AND PLUGS MIL-TYPE 1/4" EXTENSION JACKS AND TELEPHONE PATCH ADAPTERS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MIL-TYPE 1/4" EXTENSION JACKS • TU



FEATURES

Cable jack meets requirements of Specification MIL-J-641(A), Type Number JJ-026. Mates only with MIL-type plugs PJ-054 and PJ-540.

SPECIFICATIONS


Body and Terminal Screws: Copper alloy, natural finish.

Springs: Punched from special copper alloy.

Stack Insulation: Rigid plastic spacers Rigid plastic tubing.

Handle: Same as plug handle above.

Stack Screws: Stainless steel.





| | Part | | | Typical Mating | | Handle | MIL |
|---|--------|------------|-----------------------|----------------|--------|-------------|-------------|
| N | Number | Conductors | Terminals | Plug¹ | Handle | Part Number | Part Number |
| | 820 | 2 | Screw ^{2, 3} | 430 | Black | M1015 | M641/4-1 |

^{1.} Switchcraft Part Number See Jacks Section for mating jacks. 2. Switchcraft replacement screw. P1070, Terminal P1069 (2 each required)

TELEPHONE PATCH ADAPTERS • 7







FEATURES

Compact patch adapters convert standard full-size phone jacks to standard miniature phone jack connections with maximum convenience and reliability at a minimum cost. Eliminates cross-patching problems and need for combination patch cords with standard phone plug on one end and a miniature phone plug on the other. Adapters are 100% compatible with Switchcraft® telephone type and military phone jacks and miniaturized tini-telephone patching system components, as well as equivalent industry standard phone plugs.

TAD2 - 2-conductor adapter. Plug finger meets specifications for MIL plug PJ-047 (MIL-P-642). Fits Switchcraft T-Jax®, M-Jax®, MIL-approved MT-Jax®, and other industry-standard phone jacks with .250" inside diameter sleeves. The .552" diameter handle accommodates jacks on .625" centers. For quick identification, TAD-2 is stamped on the blue handle - will not wear off with constant use. Miniature 2-conductor jack built into plug body, accepts miniature phone plugs with .173" diameter fingers, such as Switchcraft tini-telephone® plugs, Series TT200 and TT250, and other standard miniature telephone plugs. TAD3 is a 3-conductor version of TAD2. Finger configuration meets requirements of PJ-051 (MIL-P-642). Finger incorporates dead ring to minimize plug and jack wear. Blue handle has diameter of .444".

SPECIFICATIONS

Tip Rod, Ring, Sleeve Body and Screws: Copper alloy, natural finish.

Insulation: Injection-molded plastic. Jack Springs: Formed copper alloy.

Screw, Spring Retaining:

TAD2 - #2-64, steel. Part Number P1616 (one required). TAD3 - #2-64, brass. Part Number P1070 (two required).


Ring Insulations (TAD3 only): Kraft paper sleeve.

Handle: Molded blue thermoplastic with die-stamped identification legend, TAD2 Handle, (Part Number M1487). and Retaining Screw, (Part Number T1677), one required. TAD3 Handle, (Part Number M1488), and Retaining Screw, (Part Number T1990), one required.

^{3.} See previous page for strain relief clamp.

MINIATURE TELEPHONE PLUGS





.173" MINIATURE PHONE PLUGS FEATURES

2- and 3-conductor miniature non-shorting telephone plugs designed for use with TT-Jax®, Unijax®, and other phone jacks with a .176" inside diameter bushing. Approximately 1/2 the size of standard phone plugs, yet retains the uniformity, dependability and quality of MIL-type phone plugs.

TT-Plug® Miniature Telephone Plugs are the first to offer 2- and 3-conductors in an attachable type with twist handles for quick assembly. Series TT250 phone plug is available with red or black handles. Other color handles available on special order. Also available with nickel-plated plug fingers. (Add "N" to part number: 253N, 254N).

The TT253NC and TT254NC offer the same nickel-plated plug fingers as the 'N' versions, but also includes cable clamps and solder terminals for easy assembly.

Plugs feature a one-piece tip rod, ring and a one-piece sleeve with integral plug body, assembled together into a mold as inserts. Providing complete continuity of thermoplastic insulation between tip rod, ring and sleeve. Internal interlock of all parts prevents shifting and shorting under extreme rugged usage.

Internal 12-24 threads in end of plug body are intended for threading over outer jacket of a patch cord to provide a superior cable anchor.

Patch cords such as Switchcraft Series TT700 (or other .216" diameter cable) are easily attached to Series TT250 by screw terminals.

FEATURES AND BENEFITS

- · Designed for pro audio applications
- 3 Conductor
- .173" (4.40mm) plug finger diameter
- One-piece tip rod ensures high reliability
- Complete continuity of thermoplastic insulation between conductors
- Internal keying of all parts preventing shifting and shorting
- Solder terminals for easier termination and assembly
- Large cable clamp for shield termination and strain relief
- Black or red handles

SPECIFICATIONS

Tip Rod, Ring, Sleeve and Body: Copper alloy, natural finish.

Terminals and Terminal Screws: Copper alloy,

natural finish.

Insulation: Thermoplastic. Handle: Molded plastic

| Part Number | Conductors | Terminals | Handle Color | Handle Part Number | Description |
|----------------|------------|-----------|-----------------|-----------------------|-------------------------|
| TT251 | 2 | Screw | Black | T2302 | |
| TT252 | 2 | Screw | Red | T2315 | |
| TT253 | 3 | Screw | Black | T2307 | Mil-type M642/13-1 |
| TT253N | 3 | Screw | Black | T2324 | Nickel-plated plug |
| TT253NC | 3 | Solder | Black | T2324 | Nickel-plated plug, |
| | | | | | tinned solder terminals |
| TT254 | 3 | Screw | Red | T2301 | Mil-type M642/13-2 |
| TT254N | 3 | Screw | Red | T2325 | Nickel-plated plug |
| TT254NC | 3 | Solder | Red | T2325 | Nickel-plated plug, |
| | | | | | tinned solder terminals |
| 2P2003 | 3 | Screw | None | None | |

DIMENSIONS ARE FOR REFERENCE ONLY

(mm

* Please visit the product pages on our website for the most up-to-date product information

.173" MINIATURE TELEPHONE PLUGS BANTAM TYPE

FEATURES

Miniature telephone twin plugs with two 2-conductor or two 3-conductor fingers, designed to mate with TT Twin-Jax®, TT-Jax®, and other phone jacks with a .176" inside diameter bushing and compatible tip and ring springs. Approximately 1/2 the size of standard phone plugs; yet retains uniformity, dependability of high-quality phone plugs. The phone plugs are exceptionally light, small and rugged. Plug fingers can easily be removed and replaced.

- Minimum Space: Plugs fit .313" centers, horizontally or vertically.
- Self-Aligning: Plug fingers compensate for minor variations in jack spacing.
- Polarizing: Handle notches identify location of each finger.
- Tip Monitoring: Handle ports permit probe insertion to monitor tip circuits.
- Terminating and Looping Plugs: OEMs can fabricate cross-wired plugs, i.e., tip-to-sleeve, tip-to-ring, etc., according to individual requirements. OEMs can also wire-in resistors, RCL networks, etc. for standard and special terminating applications. Switchcraft will build looping and terminating TT-Twin Plugs on special order, where quantities warrant.
- Sleeve Plugs: For looping, terminating and single cable applications, sleeve plugs seal off unused handle open-ing(s).
 Sleeve plugs also make a bridged (common) sleeve connection by holding braided shield in place in second plug.On special order, TT-Twin Plugs can be supplied with one 2-conductor finger and one 3-conductor finger.
- Ease of Assembly/Disassembly: Refer to illustration below for assembly/disassembly procedure; no handle retaining screws required. Tip and ring terminations are screw-type screws supplied).

SPECIFICATIONS

Tip Rod, Ring, Sleeve and Body: Copper alloy, natural finish.

Terminals and Terminal Screws: Copper alloy, natural finish.


Insulation: Thermoplastic.

Handle, Sleeve Plugs: Molded plastic.

- DISASSEMBLY: Place plug on edge as shown. Push down and back on metal lip on finger (inside notch) with small screwdriver and slip plug finger out of handle. Turn plug over and repeat for other finger.
- 2. CABLE INSTALLATION: Fold braided shield on cable back over insulation. Insert leads through rear of plug finger, and screw finger (clockwise) onto cable with twisting motion until lead terminations lineup with threaded tip and/or ring openings. Fasten terminals on both fingers with screws provided.
- **3.** To bridge sleeves (common connection), place free end of braided shield in remaining finger sleeve opening. Press sleeve plug firmly in place.

TT261: Two electrically-independent 2-conductor fingers in a black handle. Can be used with single or dual cables for independent tip circuits with common sleeve or separate sleeve circuits.






TT263: 6-circuit plug consists of two electrically-independent 3-conductor fingers with black handle. Can use single or dual cables for two electrically-independent 3-conductor fingers or common tip, ring and/or sleeve circuits.

| | art nber¹ | Cond. | Terminals | Typical Mating Jack ² | Handle | Handle Part Number | MIL Type Number |
|-----|--------------|-------|--------------------|--|--------|--------------------------|--------------------|
| TT: | 261 | 2 | 0 3 | TT31 | Black | T2300-2 | _ |
| TT | 263 | 3 | Screw ³ | TT32B | Black | T2316 | M642/13-3 |

- 1. TT-Twin Plug plugs can be supplied with one, 2-conductor plug finger and one, 3-conductor plug finger in the same handle (on special order).
- 2. Switchcraft Part Numbers. See additional mating jacks in this section.
- Switchcraft Replacement screw P2240, Terminal P2642. 2 each required with 2-conductor twin plugs; 4 each required with 3-conductor twin plugs.
- 4. Replacement Hole Plug Switchcraft T2318 (Black) T2319 (Red).



4. ASSEMBLY: Align grooves in fingers with internal handle ribs and insert fingers into rear of handle. Push fingers in until lips or rear of fingers snap into notches on handle.

DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

1/4" COMMERCIAL PHONE PLUGS

2-CONDUCTOR LITTEL-PLUG® PLUGS




FEATURES

- Heavy duty machined copper alloy handle (shielded versions), tip and body for unsurpassed ruggedness.
- Bright nickel plating on exterior surfaces will not chip or corrode.
- · Solder terminals are tin electroplated for ease of soldering.
- One-piece tip rod staked into tip terminal ensures electrical continuity
- Heavy duty cable clamp provides secure strain relief.
- The proven industry standard phone plug for audio applications. Beware of imitations!
- Shielded handle versions recommended for applications where electromagnetic interference and physical abuse may occur.


SPECIFICATIONS

Sleeve, Tip and Body: Nickel-plated copper alloy. Terminals: Solder lug - Tinned copper alloy. Screw: Tin-plated (screws size 3-48).


Handles: Molded - black or red plastic. Shielded - machined Nickel-plated copper alloy. Tubular insulator inside handle.



No. 280 typical – shown with solder lug terminals, cord clamp and shielded handle.



3-CONDUCTOR LITTEL-PLUG® PLUGS



2-CONDUCTOR PLUGS PART NUMBERS

| Part Number | Terminals | Typical Mating Jack ² | Handle* | Handle Part Number |
|----------------|--|-------------------------------------|-----------------------|-----------------------|
| 240 | Screw ³ | | Black | M1002 |
| ♦C240 | Screw ³ with Cable Clamp | | Black | |
| 245 | Screw ³ | | Red | |
| ♦ C245 | Screw ³ with Cable Clamp | | Red | M1003 |
| 250 | Solder Lug & | | Black | M1002 |
| 255 | Cable Clamp | 11 | Red | ♦M1003 |
| 270 | Screw ³ | | Shielded | |
| ♦ C270 | Screw ³ with Cable Clamp | | Shielded | Handle: T10581 |
| 280 | | | Shielded ¹ | Insulator: |
| 281 | | | Shielded⁴ | A10071 |
| 285 | Solder Lug & Cable Clamp | | Shielded 4, 5 | |
| 288 | Cable Clamp | | Shielded ¹ | |
| 285L | | | Shielded 4, 5, 6 | T2323 |
| 2P1298 | Solder Lug & Cable Clamp | | Without | Handle |
| ♦2P1495 | Screw ³ | | | |

3-CONDUCTOR PLUGS PART NUMBERS

| 260 | Screw | | Black | M1002 |
|---------|-----------------------------|-----|----------|--------------------------------|
| 267 | Solder Lug & | | Black | M1002 |
| 269 | Cable Clamp | | Red | ♦M1003 |
| 290 | Screw ³ | 12B | Shielded | Handle: |
| 297 | Solder Lug & Cable Clamp | | Shielded | T10581 Insulator: A10071 |
| ♦2P1248 | Solder Lug & Cable Clamp | | Without | Handle |

- * Additional plug handle colors available (P2714) green, (M1111) blue, (M1235) gray. Fits any plug on which Numbers M1002, M1003 are standard.
- Wide insulator between tip and sleeve allows use of 2-conductor plug in 3-conductor jack without shorting.
- 2. Switchcraft Part Numbers. See Mating Jacks Section.
- Replacement Screw Part Number P10292 (2-conductor plugs require 2 screws; 3-conductor plugs require 3 screws).
- 4. Unassembled.
- 5. Larger cable clamp to accommodate larger diameter cables.
- Handle has .375" (9.53mm) diameter hole to accommodate larger diameter cables.
- ♦ Special order only. Contact Switchcraft.

Inch (mm)

* Please visit the product pages on our website for the most up-to-date product information

1/4" COMMERCIAL PHONE PLUGS (continued)

Switchcraft® commercial 2- and 3-conductor phone plugs are available with a logo handle in addition to the plain handle. The Switchcraft® name appears prominently on the shielded handle so the plugs can no longer be easily confused with "copycat" plugs found on the market today. Knurling on handles provides a convenient, positive fingertip grip for connect and disconnect. Plugs are available in the following popular variations:

- 1. 1/4" diameter finger, 2-conductors.
- 2. 1/4" diameter finger, 3-conductors.
- 3. .206" diameter finger, 2-conductors.

Plug handles accept cable up to .290" diameter.



SPECIFICATIONS

Sleeve: Tip and Body: Plated copper alloy.

Terminals: Solder lug: Copper alloy, electro-tinned;

Screw: Tin-plated (screw size #3-48).

Handles: Nickel-plated zinc (tubular insulator inside handle).


PART NUMBERS


NOTE: Plugs have 1/4" finger diameter unless otherwise specified.

| Logo Handle | Plain Handle | Description | Typical Mating Jack | |
|----------------|-----------------|---|------------------------|--|
| 2-CONDU | CTORS | | | |
| 570 | 270 | Screw terminals. Shielded handle. | | |
| 580 | 280 | Solder lug & cable clamp. Shielded handle. | | |
| 581 | 281 | Solder lug & cable clamp. Shielded handle. Unassembled. | | |
| 585 | | | | |
| 588 | 288 | Solder lug & cable clamp. Shielded handle. Wide insulator between tip and sleeve makes possible use as a 2-conductor plug in 3-conductor jack without shorting. | | |
| S580 | S280 | Solder lug & cable clamp. Shielded handle. Plug finger has .206" diameter. | S11 | |
| 3-CONDU | CTORS | | | |
| 590 | 290 | Screw terminals. Shielded handle. | 12B | |
| 597 | 297 | Solder lug & cable clamp. Shielded handle. | IZD | |
| 598 | 298 | Solder lug & cable clamp. Shielded handle. Locking feature. | 12B, 133 | |

^{1.} Other mating plugs are available.


^{2.} Replacement screw, Part Number P10292 (2-conductor requires 2 screws; 3-conductor requires 3 screws).








1/4" COMMERCIAL PHONE PLUGS (continued)











2-CONDUCTOR/PLASTIC OR SHIELDED HANDLES

Popular general purpose plug fits all standard jacks. Available in both 2- and 3-conductor types. Two-conductor plugs available with black or red molded plastic, or 3 different lengths of brass nickel-plated (shielded) handles. 2-Conductor Special Military Plugs are also available.

FEATURES

- 1-piece tip rod staked into tip terminal insures tightness of plug.
- All essential conducting members are brass with external parts nickel-plated.
- Terminal screws: broad-headed. In production quantities, screws may be eliminated and terminals hot-tinned for easier soldering of wire leads to terminals (special order).
- Screw terminals have grooves which accommodate 1 or 2 cord tips.
- Thermoplastic handle insert for greater insulation.
- Plugs accept up to .25" maximum diameter cable (parallel or shielded cable).

SPECIFICATIONS

Sleeve, Tip and Body: Nickel-plated copper alloy. **Terminals:** Solder lug: copper alloy, electro-tinned.

Screw: steel, tin-plated.

Handles: Shielded: Nickel-plated copper alloy.

Molded: black or red plastic.

| Part Number | Terminals | Typical Mating Jack ² | Handle | Handle Part Number |
|-------------------------|---|-------------------------------------|-------------------|--|
| 40 | | | Black | M1001 |
| 70 ³ | Screw | | Shielded | Handle: T10141 Insulator: A10063 |
| 160 | (Replacement Screw Part No. P10013) | | Shielded | Handle: T10451 Insulator: A10061 |
| ⊘2P1251 | 2 required | 11 or Z15J | Without Handle | _ |
| 170¹ 182QB 182QBD | | 2130 | Shielded | Handle: T11231 ¹ Insulator: A10064 |
| 184³ | Solder Lug & Cable Clamp | | Shielded | Handle: T10141 Insulator: A11372 |
| 184L⁴ | | Cable Clamp | | Shielded |

- 2-piece shielded handle with built-in cable clamp for .25" diameter cable. Handles: Number T11231, handle; Number T11241, cap; see above for insulating tube; Number T1125, rubber washer.
- 2. Other mating plugs are available.
- Handle has .380" (9.65mm) diameter hole to accommodate .375" diameter cable.
- 4. Handle has .451" (11.51mm) diameter hole to accommodate larger diameter cables.

* Please visit the product pages on our website for the most up-to-date product information

SILENT-PLUG PHONE PLUGS



Silent-Plug plugs have unique circuit-closing device—stops hums, squeals and pops when plug is removed from jack. One-piece tip rod assembly insures plug quality. Utilizes cables up to .25" diameter (parallel or shielded cable). U.S. Patent No. 2,664,475.

SPECIFICATIONS

Sleeve, Tip and Body: Nickel-plated copper alloy.

Terminals: Copper alloy, tin-plated.

Screw: Cadmium plated (screws size 3-48).


Handles: Shielded machined copper alloy nickel-plated.


Tubular insulator inside handle.


2-CONDUCTOR PLUGS

| Part Number | Terminals | Typical Mating Jack | Handle | Handle Part Number |
|----------------|--|------------------------|-----------------------|--|
| 172 | Screw (Replacement Screw Part No. P-1011-3) 2 required | 11 | Shielded | Two-Piece¹ Ins. Tube A-1006-3 |
| 181 182 | Solder Lug and Cable Clamp | | Shielded ² | Two-piece¹ Ins. Tube A-1137-1 T-1014-1 Handle, A-1137-2 Ins. Tube |

1. 2-piece shielded handle with built-in cable clamp for .25" diameter cable. Handles: Number **T1123-1**, handle; Number **T1124-1**, cap; Number **T-1125**, rubber washer. 2. Mylar tube insulation for greater protection.







LUG®-PLUG PHONE PLUGS



Similar to Littel-Plug phone plug. Same molded handles as used on Littel-Plug; metal handle, bright nickel-plated, only 1" long. Fits all standard jacks. See drawing for details.

SPECIFICATIONS

Sleeve, Tip and Body: Nickel-plated copper alloy. **Terminals:** Solder lug: copper alloy, tin-plated.

Screw: plated steel.


Handles: Shielded: Nickel-plated copper alloy.

Molded: black or red plastic.

2-CONDUCTOR PLUGS

| Part Number | Terminals | Typical Mating Jack ¹ | Handle | Handle Part Number |
|----------------|------------|-------------------------------------|-----------|-----------------------|
| 350 | | | Black | M-1002 |
| 2P-1216 | Caldaul | 44 | | |
| 380 | Solder Lug | 11 | Shielded | Handle: T-1060-1 |
| 300 | | | Sillelueu | Insulator: A-1007-2 |

1 Switchcraft part numbers. See Jacks Section for additional mating jacks.




DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

AUDIO LOUDSPEAKER PLUGS





| Part Number | | Cable Relief | Typical |
|-------------|--------|---------------------|-------------------|
| Nickel | Black | Bushing | Typical Mating |
| Finish | Finish | diameter (inch) | Jack ¹ |
| 187 | 187B | .3 to .33 (regular) | |
| 187L | 187BL | .3 to .355 (large) | 11 or Z15J |
| 187D | 187BD | .2 to .30 (small) | |

^{1.} Other mating plugs are available. See Jacks Section.

The 187 series 1/4" phone plugs are similar to the Switchcraft® 184 plugs, except that they offer an attractive tapered handle with a snap-in flex relief. Other features include:

- Larger tip terminal to accommodate wire sizes up to 14 AWG.
- · Choice of Satin nickel or black finish.
- Black flex relief bushing can be specified in three different cable diameter openings for maximum reliability of cable.
- Plug is rated at 15A rms (maximum) for use with audio loudspeaker applications.


SPECIFICATIONS


Sleeve, Tip and Body: Nickel-plated copper alloy. **Terminals: Solder lugs:** tinned copper alloy;

Screw: tin-plated.

Handles: Die-cast zinc. Satin nickel or black finish. **Cable Relief Bushing:** Black (thermoplastic elastomer).

HEAVY DUTY 1/4" COMMERCIAL PHONE PLUGS





- Switchcraft's 188 is more heavy-duty than our competitor's biggest 1/4" commercial phone plugs.
- Large curved tip solder terminal makes it easier to solder to heavy gauge wires.
- Longer sleeve terminal allows more room to make sleeve solder connections.
- Extra-large cable clamp securely grips cable of up to .450" in diameter.
- Will easily accommodate some varieties of four conductor 14 gauge wire and parallel two conductor 12 gauge wire.
- Bendable tab on sleeve terminal makes termination easier by holding down cable while soldering. In addition, such mechanical retention makes for a superior solder connection.
- Will handle up to 15 A. rms (maximum). (continued on next page)

 $\frac{\ln}{(m)}$ YJNC

JACKS AND PLUGS HEAVY DUTY 1/4" COMMERCIAL PHONE PLUGS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

HEAVY DUTY 1/4" COMMERCIAL PHONE PLUGS (continued)

SPECIFICATIONS

Contact Resistance (typical *D.O.M.J.):< 0.020 ohms. Dielectric Withstand Voltage: 500 VAC (minimum). Insulation Resistance @ 500 VDC: 2,000 megohms

Insulation Resistance (after MIL-STD-202 Salt Spray):

1,000 megohms (minimum).

Working Voltage: 250 VAC, 140 VDC.

Current Carry @ Working Voltage For 188 Plug

(typical *D.O.M.J.): 15.0 AMPS.

Current Carry @ Working Voltage For 299 Plug

(typical *D.O.M.J.): 6.0 AMPS. Insert/Withdrawal Force: *D.O.M.J.. Soldering Requirement: ANSI/J-STD-001. Temperature Range: -40° to + 85° Centigrade U.L. Component Recognition File No.: E118169.

Life: *D.O.M.J.

Maximum Cable Size For 188 Plug: 12 AWG stranded, up to .450" diameter.

Maximum Cable Size For 299 Plug: .290" diameter.

MATERIALS

Tip: Nickel-plated copper alloy. Sleeve: Nickel-plated copper alloy. Handle: Nickel-plated copper alloy.

Tip Terminal: Copper alloy, electro tin-plated. Cable Clamp: Copper alloy, electro tin-plated. Insulators For 188 Plug: Thermojet plastic, thermoplastic, thermoplastic film, P.P.O. Insulators For 299 Plug: Thermoplastic,

thermoplastic film, glass epoxy. *D.O.M.J. - Dependent On Mating Jack

Part Maximum Mating Cable Size Number Jack

.290" Diameter

299



Z15J

| 1.188 REF Ø1/4 REF | 2.736 REF | 1.625 REF |
|-----------------------------|--------------|--------------|
| | | |


1/4" COMMERCIAL PHONE PLUGS (continued)


3-CONDUCTOR/PLASTIC OR SHIELDED HANDLES



| Part Number | Terminals | Typical Mating Jack ² | Handle | Handle Part Number |
|----------------------|------------|-------------------------------------|----------|-------------------------------------|
| 60 | | | Black | M1001 |
| ♦90 | | | Shielded | T10451 |
| 190 | Solder Lug | 12B | Shielded | Handle: T10141 Insulator: A10063 |
| 190A,190B & 190BL | | | Shielded | 2-piece ¹ |

- 1. 2-piece shielded handle with built-in cable clamp for .25" diameter cable. Handles: Number T11231, handle; Number T11241, cap; Number A10064, insulating tube; Number T1125, rubber washer.
- 2. Other Mating Plugs are available.\$\(\rightarrow\) Special order only. Contact Switchcraft.





.206" COMMERCIAL PHONE PLUGS

PHONE PLUGS FOR POLARIZED CONNECTIONS



FEATURES

For applications requiring polarization (use of plugs of different sizes) to prevent insertion of incorrect equipment Littel-Plug® phone plugs featuring a sleeve and tip diameter of .206" are available. Mate with Number S128 Extension Jax® and S11 Littel Jax® jacks. Number S260 used interchangeable with Military Type M642/51 (Switchcraft Number 480) plugs. Mate with jacks S12B, S13B, M444, MT342B, MT344B and others.


2-CONDUCTOR PLUGS PART NUMBERS

| | Part Number | Terminals | Typical Mating Jack ¹ | Handle | Handle Part Number |
|---|----------------|--------------|-------------------------------------|-----------|-----------------------|
| ĺ | S250 | | 044 | Black | M1002 |
| | S280 | Solder Lug & | S11 | Shielded | T10581 |
| | 3200 | Cable Clamp | | Sillelueu | A10071 |

3-CONDUCTOR PLUGS PART NUMBERS

| S260 | Screw (Replacement Screw Part No. P10292) 2 required | \$12B | Black | M1002 |
|------|--|-------|-------|-------|
| S267 | Solder Lug & Cable Clamp | | | |

1. Switchcraft® mating jacks



* Please visit the product pages on our website for the most up-to-date product information

1/4" MITI-PLUG® AUDIO PLUGS



Number 174S

TIP TERMINAL

FEATURES

- 2-conductor phone plug with full shielding and resistance to extremely rough usage for electrified audio instruments such as amplifiers, synthesizers power heads and speaker systems requiring high-quality audio plugs.
- 3-WAY CABLE STRAIN/STRESS RELIEF: For hours of trouble-free operation under heavy and abusive use. Plug body internally threaded for screw-on strain relief for cables from .29" to .30" diameter, and an additional clamp for additional relief (and for smaller cables). A heavy copper alloy-plated steel spring at point of entry to plug keeps cable from folding and pinching. Flex relief spring recommended for cables with diameters of .265" maximum only.
- TERMINATING: Tip wire soldered to tip—braid folded back and secured with cable clamp.
- IDENTIFICATION: Customer or OEM name of logo can be applied to plastic handles for a minimal charge for personalization. (Contact Switchcraft for details).
- SPECIAL HANDLE COLORS: Plastic handles molded in custom colors on special order. Contact Switchcraft for details.

1.200 2.250 [57.15] [46.02] .500 [12.70] DIA. HANDLE .250 [6.35] DIA. SLEEVE FLEX RELIEF SPRING No. 174S

SPECIFICATIONS


Tip Rod & Body: Copper alloy. **Handle:** Copper alloy or plastic (black). **Flex Relief Spring:** Plated spring steel.

(Part No. P2848).

Strain Relief Clamp: Plated steel.

(Part No. P2380).

Insulation: Thermoplastic, glass reinforced.



2-CONDUCTOR PLUGS

| Part Number | Handle | Flex Relief | Typical Mating Jack ¹ | Handle Part Number |
|----------------|---------------|-------------|-------------------------------------|-----------------------|
| 173 | Black plastic | U-Clamp | | M1483 |
| 174S | Copper Alloy | Spring | | T2313 |
| 175 | Copper Alloy | None | | T2313 |
| 176S | Black Plastic | Spring | 11 | M1483 |
| 177S | Red Plastic | Spring | | |
| 178 | Black Plastic | None | | M1483 |
| ♦179 | Red Plastic | None | | |

^{1.} Other mating plugs are available.

[♦] Special order only. Contact Switchcraft.

1/4" FLAT PLUG PHONE PLUGS





Series 230



Series S230



FEATURES

- · Ideal where conventional long handled plugs are not suited to design of equipment. "Chassis-hugging" phone plugs allow cables to be brought out at right angles to equipment.
- · Removable plastic cap for easy assembly of wire leads to either screw or solder lug terminals. Adapter clips on types 220 and 225 make it convenient to clamp standard phone tips to terminals.
- Terminals and body of plug mechanically interlocked, eliminating probability of any shifting.
- Cover is black or red plastic; plug body is a rugged assembly of all metal parts.
- · One-piece tip rod staked into tip terminal to insure tightness, no disassembly of tip during use of plug.
- High grade insulation.
- Terminal identification permanently stamped into base plate adjacent to each terminal. Letter "T" denotes tip connection; "R" denotes ring sleeve; "S" terminal is the sleeve or body connection (no identification on types 228, 238).
- · Cover molds designed so customer's name or trademark inserts can be added. Call for details.

SPECIFICATIONS


Tip Rod and Sleeve: Nickel-plated copper alloy.

Terminals: Tinned copper alloy.

Series 220

Handle: Black or red plastic. Numbers 228 and 238,

steel, nickel-plated.



TO<u>.250</u> DIA. CORD No. S-230

RING TERMINAL 238 ONLY TIP TERMINAL No. 238 (typical)

2- OR 3-CONDUCTOR/SHIELDED HANDLE

| Part | | Typical | | | Handle |
|------|----------|-----------------------------|-----------|-----------|----------|
| No. | Terminal | Mating Jack ^{1, 2} | Conductor | Handle | Part No. |
| 228 | Solder | 11 | 2 | Shielded | S3067 |
| 238 | Lug | 12B | 3 | Sillelded | 33007 |

- 1. Nickel plated steel handle. Two screws (Part Number P15823) required to mount handle.
- 2. Other mating plugs are available.
- 3. Accommodates cables from .219" outside diameter to .250" outside diameter Ideal for music equipment use.

3-CONDUCTOR/PLASTIC HANDLE .206" DIAMETER SLEEVE AND TIP

| Part No. | Terminals | Typical Mating Jacks ¹ | Handle | Handle Part No.⁴ |
|----------------|--------------------|--------------------------------------|--------|---------------------|
| 230 | Screw ³ | | Black | M1005 |
| ♦235 | Screw | | Red | |
| 237 | Solder | 12B | Black | M1005 |
| ⊘239 | Solder | | Red | |
| ♦ \$230 | Screw ³ | S12B ² | Black | M1005 |

- 1. Switchcraft Part Number Other mating plugs are available.
- 2. Part Number S230 is the commercial version of military Type PJ068 (Switchcraft Number 480) plug. Mates with S12B, S13B, M444, MT342B, MT344B Jacks and others. Other mating plugs are available. For applications where it is desirable to polarize, use plugs of different sizes to prevent insertion of incorrect equipment. Sleeve and tip diameter of these plugs is .206" Mates with S830, S1230 Extension-Jax® jacks and S12B, S13B Littel-Jax® phone jacks.
- 3. Switchcraft Replacement Part Number P10292. 3 screws required. 4. Three screws (Number P1039) required to mount handle.
- Special order only. Contact Switchcraft.

2-CONDUCTOR/PLASTIC HANDLE

| Part No. | Terminals | Typical Mating Jack¹ | Handle | Handle Part No. ³ |
|-------------|------------|-------------------------|-------------|---------------------------------|
| 220 | Screw | | Black | M1005 |
| 225 | Screw | | Red | M1006 |
| 227 | Solder Lug | 11 | Black | M1005 |
| 229 | Solder Lug | | Red | M1006 |
| 2P1509 | Screw | | Less Handle | _ |

- 1. Switchcraft Part Number; see jack section for additional mating jacks.
- 2. Switchcraft replacement Part Number P10292. 2 screws required per plug. Clips for phone tips. Part Number S1832.
- 3. Three screws (Number P1039) required to mount handle.

RIGHT-ANGLE AUDIO PHONE PLUG

FEATURING 3-PIECE CONSTRUCTION AND FAST TERMINATION/ASSEMBLY

Switchcraft's 2- or 3-conductor right-angle audio phone plugs are designed for OEMs and users of commercial phone plugs. The plugs offer large terminals for easy wiring, and only three pieces to assemble - handle, insulator and finger/housing assembly and rugged reliability for stable, long-term, trouble-free operation.

FEATURES

- Easy Termination: Large terminals accept up to 16 AWG wiring (cables up to .25 inch diameter)
- 3-Piece Assembly: Screw on the handle for quick and easy assembly; minimizes labor costs.
- Rugged: All metal exterior construction.
- Low Profile: Only 1/2 inch wide. Ideal for crowded, multi-channel panels. Right-angle handle minimizes space required behind equipment.
- Knurled Handles: Positive grip during connect/disconnect.
- Rugged Cable Clamp: Isolates pulling and twisting strains.

SPECIFICATIONS

Tip, Rod and Handle: Nickel-plated copper alloy.

Housing/Sleeve: Nickel-plated.
Tip Terminal: Tin-plated copper alloy.
Sleeve (Clamp) Terminal: Tin-plated steel.
Insulation: Thermoplastic.


Dielectric Withstanding Voltage: 500 Vac.

Insulation Resistance: 50,000 Megaohms minimum (initial).

Operating Temperature: -20°C to +65°C.



| Part Number | Description | Typical Mating Jack |
|----------------|------------------------------|---------------------------|
| 236 | 3-conductor 1/4" right-angle | 12B, 13B |
| | commercial plug. | 112B, 113B |
| 226 | 2-conductor 1/4" right-angle | 11, 12A |
| | commercial plug | 111, 112A |



DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm) FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

1/4" LOCK-EXTENSION JACKS AND PLUGS



Number 133

FEATURES

Modified Littel-Plug® phone plug, 2- or 3-conductor, with coupling ring that can be threaded to thread projection of mating panel jack or to threaded end of the Lock-Extension Jax®. Locks connection after plug has been fully inserted into its mating panel jack or Extension Jax®.

Lock-Plug® makes proper contact to mating jack without tightening or attaching coupling ring, when rapid disconnect may be desired. Lock-Plug fits any standard jack with 3/8".-32 thread bushing with .094" of the bushing exposed. Lock-Extension Jax also will mate properly with standard phone plugs, where no "lock" requirement exists.



Number 298

SPECIFICATIONS

Lock-Plug Tip Rod, Body, Handle and Coupling Ring:

Nickel-plated copper alloy.

Terminals: Brass, electro-tinned. Solder lug design,

cable clamp part of sleeve terminal.

Insulation: Rigid plastic.

LOCK-EXTENSION JAX®

Housing (or Sleeve) and Handle:

Nickel-plated copper alloy.

TERMINALS:

Sleeve: Plated steel. Tip and Ring: integral part of tip and ring springs. **Springs:** Spring tempered copper alloy. **Insulation:** Molded thermoplastic insert.


Rigid plastic terminal washer.


LOCK-PLUG

| Part Number | Cond. | Terminals | Typical Mating Jack | Handle Part Number | Notes |
|----------------|-------|-------------------------|---------------------------|-----------------------|--|
| 282 | 2 | Solder | 12A | T40504 | Cimilar to Cuitab auth Numb as 207 Littal Dive |
| 298 | 3 | Lug & Cable Clamp | 12B, 133 | T10581 A10071 | Similar to Switchcraft Number 297 Littel-Plug except with coupling ring. |

LOCK-EXTENSION JAX®

| Part Number | Cond. | Terminals | Typical Mating Plug | Handle Part Number | Notes |
|----------------|-------|-----------------------------------|---------------------------|-----------------------|--|
| 133 | 3 | Solder Lug & Cable Clamp | 298 | T1485 | Sleeve terminal has cable clamp. Similar to Switchcraft [®] Number 131 Extension-Jax [®] . |





3.5 MM HEAVY DUTY STEREO PLUGS



3.5MM STEREO PLUGS **FEATURES**

- · Heavy duty 3.5mm plugs for audio, instrument, other applications.
- Large cable clamps for rugged use.
- Available in straight or right angle.
- · One piece tip rods for added durability.
- Available in nickel, gold, and black finishes.
- · Large solder terminals for easy assembly.
- Standard handle accommodates cable sizes up to 0.290" Optional 'S' versions accommodate cable sizes up to 0.175"


35HDBN - Black Handle, Nickel Plug 35HDBAU - Black Handle, Gold Plug 35HDNAU - Nickel Handle, Gold Plug 35HDNN - Nickel Handle, Nickel Plug

BENEFITS

- One piece tip rod with flat for easy solderability.
- Compliments current line of 3.5 mm jacks.
- Insert molded plug finger.
- · Heavy Duty cable clamp provides better strain relief for larger cables
- Longer cable clamp for easier plug assembly and more room for solder connections
- Knurl on the back of handle provides ergonomic gripping surface to tighten plug
- Tubular insulator included to prevent solder joints from contacting handle
- Longer handle for improved gripping surface and easy plug withdrawal from jack
- Large solder terminal for easy solderability

MARKETS

- Audio
- Consumer electronic equipment
- Broadcast studios
- Home recording equipment
- · Audio cable assembly manufacturers
- Instrumentation
- Test equipment



SPECIFICATIONS

Contact Resistance: <0.020 ohms

Dielectric Withstand Voltage: - 250 VAC (min.)

Insulation Resistance @ 500 VDC: 2,000 megohms (min.)

Working Voltage: - 250 VAC, 140 VDC Current Carry @ Working Voltage: 4 AMPS Insert/Withdrawal Force: - Typical 2.5/2 pounds **Temperature Range:** 0° to 66° Centigrade (operating) Passed MIL-STD-202F Method 107G (Thermal Shock), and

Method 201 (Vibration) Life: - 5000 cycles

Maximum Cable Size: - .250? dia.

MATERIALS

Tip Rod: Copper alloy, tin, or gold-plated Ring: Copper alloy, nickel, or gold-plated Sleeve: - Copper alloy, nickel, or gold-plated Handle: Copper alloy, nickel, or gold-plated

Cable Clamp: - C.R.S., tin-plated Solder Terminal: Copper alloy, tin-plated

Tubular Insulator: Clear plastic

ORDERING INFORMATION

- 1. Order by part number
- Contact Switchcraft for more information

| Part | Description | | |
|-----------|-------------|--------|-----------------------|
| Number | Plug Finger | Handle | Notes |
| 35HDNN | Nickel | Nickel | |
| 35HDNNS | Nickel | Nickel | 0.175" handle opening |
| 35HDBN | Nickel | Black | - |
| 35HDBNS | Nickel | Black | 0.175" handle opening |
| 35HDNAU | Gold | Nickel | - |
| 35HDNAUS | Gold | Nickel | 0.175" handle opening |
| 35HDBAU | Gold | Black | - |
| 35HDBAUS | Gold | Black | 0.175" handle opening |
| 35HDRANN | Nickel | Nickel | Right angle |
| 35HDRABAU | Gold | Black | Right angle |
| 35HDRAAU | Gold | Nickel | Right angle |

DIMENSIONS ARE FOR REFERENCE ONLY

.141" MINIATURE PHONE PLUGS





FEATURES

- Miniature 2-conductor Phone Plug for use with Switchcraft Tini-Jax® miniature phone jacks. About 1/2 the size of Switchcraft Littel-Plug® phone plug. Average net weight, 1/8 ounce.
- Various terminal combinations: (a) Dual purpose sleeve terminal may be clamped over metal braid or shielded cables; provides cable anchor. Easily soldered for perfect electrical connection. (b) Screw terminal design (no cable clamp) for cable. Terminals that can be more suitably connected by screws.
- 1-piece tip rod staked into mating terminals; no disassembly of tip during use of plug. Terminals and body of plug interlocked mechanically.
- Available in black or red plastic handles or brass nickelplated handles for shielding. Can be used with cables up to .188" outside diameter.

SPECIFICATIONS


Sleeve, Tip and Body: Nickel-plated copper alloy. **Terminals:** Copper alloy, electro-tinned. Solder lug or


screw type (Screws #0-80).

Handle: Molded black or red plastic.

Copper alloy, nickel-plated.

| Part Number | Terminals | Typical Mating Jack ¹ | Handle | Part No. |
|----------------|-----------------------------|-------------------------------------|-------------|----------|
| 740 | | | Black | M1055 |
| 745 | Screw ² | | Red | M1056 |
| 750 | 0 - 1 - 1 0 | 41 | Black | M1055 |
| 755 | Solder Lug & Cable Clamp | | Red | M1056 |
| 2P1384 | Cable Clamp | | Less Handle | _ |
| 770 | Screw ² | | Shielded | T13631 |
| 780 | Solder Lug & Cable Clamp | | Shielded | T13631 |





- 1. Other mating plugs are available.
- 2. Switchcraft replacement Part Number P1153. 2 screws required per plug.

Numbers 850, 880

Number 851

FEATURES

- Subminiature, 2-conductor phone plugs are 1/3 the size of standard phone plugs, with the uniformity, dependability, and quality construction of Switchcraft Littel-Plug® and Tini Plug® phone plugs. 50 W soldering with 60/40 solder recommended for terminating.
- Switchcraft's 852, 853, 857, 858, 882 and 883 have a wider insulator between the tip and the sleeve. The wide insulator prevents the tip of the plug from shorting out between the tip spring and the sleeve of the jack during insertion.

Micro-Plug® PLUG - Sleeve terminal incorporates cable clamp. May be clamped over mated braid to anchor shielded cable; solders readily for perfect electrical connection. Terminals and plug body interlocked mechanically. Accommodates cable up to .125" Combined length, handle and tip: 1.106" outside diameter, .250" outside diameter handle.

LOCK Micro-Plug® PLUG - Similar to Micro-Plug plug, with addition of integral threaded collar that fastens to bushing of mating jack to prevent accidental disconnect. Requires at least .05" of exposed and usable thread on jack bushing to lock securely. Ideal for secure connections in critical medical and sensitive scientific instruments. Combined length, handle and tip: 1.046". Various molded cable assemblies incorporating Micro-Plug Subminiature phone plugs with plastic handles are available.

SPECIFICATIONS MATERIALS

Tip, Rod and Body (also integral Coupling Collar on

Lock Micro-Plug): Nickel-plated copper alloy.

Insulation: Molded thermoplastic. **Sleeve Termination and Cable Clamp:**

Tinned copper alloy.

Handle: Anodized aluminum; red, black or natural finish.

MECHANICAL

Life rating: 5,000 insertion/withdrawals.

Insertion/Withdrawal Force: 1 pound (depending on

mating jack).

ELECTRICAL

Insulation Resistance: > 100 megohms Dielectric Withstanding Voltage: 250V AC.

ENVIRONMENTAL

Thermal Range: -55°C to +85°C (non-operating);

-20°C to 65°C (operating).

Thermal Shock: Mil-Std 202, Method 107. Humidity: Mil-Std 202, Method 106. Salt Spray: Mil-Std 202, Method 101.


MICRO-PLUG


| Part Number | Terminals | Mating Jacks ¹ | Handle | Handle Part No. |
|----------------|------------|------------------------------|-------------|--------------------|
| 850 | | | Black | T18623 |
| 852 | | | Black | T18623 |
| 855 | 0-1-11 | TDOA | Red | T18622 |
| 857 | Solder Lug | TR2A | Red | T18622 |
| 880 | | | Natural | T18621 |
| 882 | | | Natural | T18621 |
| 2P1419 | | | Less Handle | _ |

LOCK MICRO-PLUG

| Part Number | Terminals | Mating Jacks ¹ | Handle | Handle Part No. |
|----------------|------------|------------------------------|---------|--------------------|
| 851 | Solder Lug | | Black | T23123 |
| 853 | | TR2A | Black | T23123 |
| 856 | | | Red | T23122 |
| 858 | | INZA | Red | T23122 |
| 881 | | | Natural | T23121 |
| 883 | | | Natural | T23121 |


1. Switchcraft Part Numbers. Other mating plugs are available.





DIMENSIONS ARE FOR REFERENCE ONLY

AUDIO ADAPTERS



Part Number 332A (Not shown): 2-cond. phone jack input to old MC1M-style microphone connector output. Coupling ring can be screwed back to convert female microphone connector to male type. Shielded.

Part Number 336A: 2-conductor phone jack input to a phono plug output. Shielded.

Part Number 336B: 2-conductor phone jack input to phono jack output. Shielded.

Part Number 340: Two 2-conductor phone jack inputs connected in parallel to a 2-conductor phone plug output. Shielded.

Part Number 345A: Phono plug input to a standard 2-conductor phone plug output. Shielded.

Part Number 349A: Phono plug coupler. Phono Extension Jax® input to phono Extension Jax output. Shielded.

♦Part Number 352A: Stereo to monaural adapter.
3-conductor phone jack input to 2-conductor phone plug output. Extra-wide insulator prevents accidental damage should wrong connection be made. Shielded.

Part Number 361A: Phone plug coupler. Standard 1/4" inside diameter phone jack input to standard 1/4" inside diameter phone jack output. Ideal for connecting two cables terminated with 2-conductor phone plugs. Shielded.

Part Number 362A (Not shown): Phone plug coupler. Standard 3-cond. phone jack input to standard 3-cond. phone jack output. Ideal for connecting two cables terminated with 3-conductor phone jacks. Shielded.

Part Number 363: Phone jack coupler. Standard 1/4" 2-conductor phone plugs at each end to connect two cables terminated with phone Extension Jax. Shielded.

Part Number 364A: EIA Standard 2-conductor Tini-Jax® phone jack input to a standard 1/4" 2-conductor phone plug output. Shielded.

Part Number 365: EIA Standard 2-conductor Tini-Jax® phone jack input to a phono plug output. Shielded.

Part Number 370A: 2-conductor EIA Standard Tini-Plug® phone plug (.141" diameter finger) output to phono jack input. Adapts standard phono plug to small Tini-Plug. Shielded

Part Number 374: 2-conductor phone jack input to a 2-conductor EIA Standard Tini-Plug (.141" diameter finger) phone plug output. Adapts standard phone plug to small Tini-Plug.

Part Number 376: EIA Standard Tini-Jax phone jack input to a 2-conductor Micro-Plug (.097" diameter finger) phone plug output. Adapts a Tini-Plug phone plug to a Micro-Plug phone plug.

Part Number 377: Micro-Jax phone jack input to a 2-conductor EIA Standard Tini-Plug (.141" diameter finger) phone plug output. Adapts a Micro-Plug phone plug to a Tini-Plug phone plug.

♦ Special order only. Contact Switchcraft.

* Please visit the product pages on our website for the most up-to-date product information

PHONO PLUGS



FEATURES

- Wide variety of styles for a wide range of applications.
- 3502A and 3502RA Series offer solid pin, large solder cups.
- 3558 Series utilize plastic handles for low cost applications.
- 3507 and 3504M have low-loss nylon insulators for RF applications. Can be used at 1 kW at 30 MHz.
- 3501M and 3501MC have the handle removed for tight spaces
- Options include nickel and gold plated, or black epoxy finishes.

SPECIFICATIONS MATERIALS

Pin: Nickel or gold plated, copper alloy Sleeve: Nickel or gold plated, copper alloy

Handle: Nickel or gold plated, or black epoxy finish, copper alloy

(3558 Series: Thermoplastic) Cable Clamp: Tin, copper alloy Insulator: Rigid Plastic

ELECTRICAL

Current Carry @ Working Voltage (typical *D.O.M.J.): 6A Contact Resistance (typical *D.O.M.J.): < 0.20 Ohms Dielectric Withstanding Voltage: 500 VAC min.


Insulation Resistance @ 500VDC: 2,000 megohms min


Working Voltage: 250VAC, 140VDC


MECHANICAL Life: *D.M.O.J


Temperature Range: -40∞ C to +85∞ C *D.M.O.J. - Dependent On Mating Jack


PHONO PLUGS (continued)


















| Part | Description | Typical | | |
|-----------|-------------|---------|---|-------------|
| Number | Pin | Handle | Notes | Mating Jack |
| 3502A | Nickel | Nickel | | BP Series |
| 3502AAU | Gold | Nickel | | BP Series |
| 3502ABAU | Gold | Black | | BP Series |
| 3502RA | Nickel | Nickel | Right angle | BP Series |
| 3502RABAU | Gold | Black | Right angle | BP Series |
| 3502RAAU | Gold | Nickel | Right angle | BP Series |
| 35581 | Nickel | Plastic | Red handle | BP Series |
| 35582 | Nickel | Plastic | Black handle | BP Series |
| 35585 | Nickel | Plastic | White handle | BP Series |
| 3502 | Nickel | Nickel | | BP Series |
| 3501M | Nickel | | | BP Series |
| 3501MC | Nickel | | Same as 3501M except with cable clamp | BP Series |
| 3504M | Nickel | | Same as 3507 less cable clamp and handle | 3505F |
| 3507 | Nickel | Nickel | For RF applications | 3505F |
| 330F1 | Nickel | | 2 inline jacks to 1 male plug, 4" gray shielded cable | BP Series |
| 330F2 | Nickel | | 1 inline jack, 1 male plug to 1 male plug, 4" gray shielded cable | BP Series |

DIMENSIONS ARE FOR REFERENCE ONLY $\frac{\ln}{(m)}$

* Please visit the product pages on our website for the most up-to-date product information

MINIATURE POWER PLUGS



FEATURES AND BENEFITS

- · 2-conductor power jacks.
- Hollow center pin available in 3 pin diameters and 2 finger lengths (See chart below).
- Locking option available for added security in critical applications.
- Molded plastic handles available in black or red.
- Sleeve terminal serves as cord clamp.

SPECIFICATIONS

Plug Sleeve and Pin: Nickel-plated copper alloy.

Lockring: Nickel-plated copper alloy. **Lockring Thread Size:** 5/16 - 32 UNEF 2B.

Finger Insulator: Molded plastic. Insulating Washers: Rigid plastic.


Sleeve Terminal: Copper alloy, electro-tinned.


Handle: Molded plastic.

Handle Thread Size: 5/16 - 24 UNF 2B. **Electrical:** Current (Carry): 5 amps.

ORDERING INFORMATION

- 1. Order by part number. 2. Contact Switchcraft for more information.
- 3. ♦ Indicates "special order" only.





INSIDE DIAMETER TOLERANCES (PLUGS)

860/865: .050" (.050 - .053)
1.27mm (1.27 - 1.35)
.080" (.080 - .084)
2mm (2.03 - 2.13)
760/765*: .100" (.099 - .103)
2.5mm (2.52 - 2.61)

OUTSIDE DIAMETER TOLERANCES (PLUGS)

860/865: \frac{.150" (.149 - .153)}{3.81mm (3.78 - 3.89)} \text{S760/S765*:} \frac{.218" (.217 - .221)}{5.5mm (5.51 - 5.61)} \text{760/765*:} \frac{.218" (.217 - .221)}{5.5mm (5.51 - 5.61)} \text{

*includes locking (k) versions

PART NUMBERING and MATING CHART (Power plugs/Power jacks)

| Part Number | Inside Diameter | Outside Diameter | Length "L1" | Length "L2" | Locking Feature | Tip Insulator | Handle Color | Handle Part Number | Switchcraft® Mating Jack¹ |
|----------------|--------------------|---------------------|----------------|----------------|--------------------|------------------|-----------------|-----------------------|---|
| 760 | .100" | .218" | .375" | 1.42 | No | Black | Black | M1055 | 712A, RAPC712, RASH712, RASM712, PC712A, RA712A |
| 765 | .100" | .218" | .375" | 1.42 | No | Black | Red | M1056 | 712A, RAPC712, RASH712, RASM712, PC712A, RA712A |
| 760K | .100" | .218" | .375" | 1.7 | Yes | Black | Black | M1055 | 712A, PC712A |
| 761K | .100" | .218" | .475" | 1.8 | Yes | Black | Black | M1055 | L712A, PCL712A |
| 765K | .100" | .218" | .375" | 1.7 | Yes | Black | Red | M1056 | 712A, PC712A |
| 766K | .100" | .218" | .475" | 1.8 | Yes | Black | Red | M1056 | L712A, PCL712A |
| ◊2P1515 | .100" | .218" | .375" | 1.42 | No | Black | No Handle | No Handle | 712A, PC712A |
| S760 | .080" | .218" | .375" | 1.42 | No | White | Black | M1055 | 722A, RAPC722, RASH722, RASM722, PC722A, RA722A |
| S765 | .080" | .218" | .375" | 1.42 | No | White | Red | M1056 | 722A, RAPC722, RASH722, RASM722, PC722A, RA722A |
| S760K | .080" | .218" | .375" | 1.7 | Yes | Black | Black | M1055 | 722A, PC722A |
| S761K | .080" | .218" | .475" | 1.8 | Yes | Black | Black | M1055 | L722A, PCL722A |
| S765K | .080" | .218" | .375" | 1.7 | Yes | Black | Red | M1056 | 722A, PC722A |
| S766K | .080" | .218" | .475" | 1.8 | Yes | Black | Red | M1056 | L722A, PCL722A |
| 2P1624 | .080" | .218" | .375" | 1.42 | No | White | No Handle | No Handle | 722A, PC722A |
| 860 | .050" | .150" | .375" | 1.42 | No | Black | Black | M1055 | RAPC 732, RASH 732, RASM 732 |
| 865 | .050" | .150" | .375" | 1.42 | No | Black | Red | M1056 | RAPC 732, RASH 732, RASM 732 |

¹See pages 130-134.

(mm)

PROFESSIONAL PUNCHDOWN TERMINAL (PPT)

Our Patchbays Now Feature the New Professional Punchdown Terminal (PPT) Our Patchbays Have Just Rounded A New Corner

Actually, the corners we rounded belong to our patchbays' revolutionary, new Professional Punchdown Terminal (PPT), making it perfectly compatible with the industry standard. We realized that achieving a new industry standard meant we couldn't cut any corners to get there.

The PPT design incorporates a split-barrel design and a more rugged, thicker housing to minimize the impact of repeated punchdowns. The split-barrel design eliminates the problems associated with the old "V-shaped" terminal designs. The PPT design distributes pressure evenly across both sides of the terminated wire, causing improved wire retention plus more reliable connections. The serrated teeth in the plastic housing firmly grip the wires, which also greatly improves wire retention. With the PPT, multiple wires can be terminated to a single contact, and a wide range of wire gauges can be used. Look for Switchcraft's PPT in our MTP and TTP Series of audio patchbays, and in our new Backpanel Series.

All Switchcraft audio patchbays incorporate heavy gauge materials and our high quality nickel-plated, steel framed jacks. Gold-plated, crossbar contacts come standard!

MATERIALS

Housing: Thermoplastic (UL 94V-0)


Contacts: High strength copper alloy, tin plated Wire size: Accommodates #22, 24, or 26 AWG,

stranded or solid

| Accessories Part Number | Description |
|-------------------------|---|
| | |
| K459 | PPT replacement kit consists of |
| | 15 of each color* (IDC/IDC) |
| K460 | PPT replacement kit consists of |
| | 15 of each color (IDC/wirewrap) |
| PT1LA | PPT impact punchdown tool |
| PT2B | Replacement bit for PT1LA tool |
| *Colors consist of r | ed, black, white, yellow, blue, and orange. |



FRONT ACCESS MTPFA/TTPFA SERIES



The Front Access Series offers the end user the ease of re-terminating patchpoints from the front of the rack as opposed to the back. A slide out tray allows the user to slide out the punchdown terminals, and reconfigure the unit. An easy release mechanism on either side of the unit allows it to be pushed back into place and easy to grip locking nuts tighten the unit in place.

FEATURES AND BENEFITS

- Easy slide-out tray slides forward for easy re-termination from the front of the rack
- Available with either 48 MT style or 96 TT style jacks in a 1RU space
- Attractive, corrosion resistant nickel-plated, steel frame jacks
- Gold-plated switching contacts reduce contact resistance, improves reliability
- Extra wide designation strips for easy channel identification
- Rugged, attractive black epoxy-finished steel chassis
- Configurations available include normals strapped and normals brought out

SPECIFICATIONS MATERIALS (JACKS)

Frame: Nickel-plated steel **Bushing:** Nickel-plated brass

Tip, Ring and Shunt Springs: Nickel silver with welded contacts

Assembly Screws: Nickel-plated steel Welded Contacts: Gold alloy

PANEL

Frame: C.R.S. black epoxy painted

Designation Strips: Black polycarbonate 94V-0 **Designation Strip Covers:** Clear polycarbonate

Jack Inserts: Thermoplastic 94V-0

MECHANICAL

Life: 30,000 cycles

Insertion Force: 7 lbs. maximum Withdrawal Force: 1 lb. minimum Operating: -20°C to +65°C

ELECTRICAL

Jack Contact Resistance: 30 milliohms initial maximum; 50 milliohms after life


Jack Insulation Resistance: 10,000 megohms maximum Dielectric Withstanding Voltage: 500V at 60 Hz AC Working Voltage: 100 milliamps or less; maximum 56.5 VDC

| Ordering Inform | nation | | |
|-----------------|---------|--------|---------------------------------|
| Part | Type of | No. of | |
| Number | Jack | Jacks | Description |
| TTPFA96K1NS | TT | 96 | 1.75" High, normals strapped |
| TTPFA96K1NO | TT | 96 | 1.75" High, normals brought out |
| MTPFA48K1NS | MT | 48 | 1.75" High, normals strapped |
| MTPFA48K1NO | MT | 48 | 1.75" High, normals brought out |

DIMENSIONS ARE FOR REFERENCE ONLY


Inch (mm)

FRONT ACCESS MTPFA/TTPFA SERIES (continued)



* Please visit the product pages on our website for the most up-to-date product information

MTP48K WIRED AUDIO SERIES



FEATURES AND BENEFITS

- Unit features 48 MT style jacks in either 1RU (1.75"H) or 2RU (3.5"H) spaces
- All versions utilize AES/EBU wiring for complete digital compatibility
- Attractive, corrosion resistant nickel-plated, steel frame jacks
- Gold-plated switching contacts reduce contact resistance, improve reliability
- Rugged, attractive black epoxy-finished steel chassis
- Extra wide designation strips for easy channel identification
- 1RU version configurations include normals strapped and normals brought out
- 2RU version configurations include normals strapped, normals brought out, and sleeve normals brought out

SPECIFICATIONS MATERIALS JACKS

Frame: Nickel-plated steel Bushing: Nickel-plated brass

Tip, Ring and Shunt Springs: Nickel silver

with welded contacts

Assembly Screws: Zinc-plated steel
Welded Contacts: Gold alloy

PANEL

Front Channel: Black anodized aluminum Frame: C.R.S. black epoxy painted

Designation Strips: Black polycarbonate 94V-0 **Designation Strip Covers:** Clear polycarbonate

Jack Inserts: Thermoplastic polyester

MECHANICAL

Life: 30,000 cycles

Insertion Force: 7 lbs. maximum Withdrawal Force: 1 lb. minimum Environmental: O°C to +50°C

ELECTRICAL

Contact Resistance: 30 milliohms maximum initial Insulation Resistance: 10,000 megohms maximum Dielectric Withstanding Voltage: 500 VAC at 60 Hz


Working Voltage: 140 VDC maximum Current Rating: 100 milliamps

| Ordering Information | | | | | | |
|----------------------|---------|--------|---------------------------------|--|--|--|
| Part | Type of | No. of | | | | |
| Number | Jack | Jacks | Description | | | |
| MTP48K1NS | MT | 48 | 1.75" High, normals strapped | | | |
| MTP48K3NS | MT | 48 | 3.5" High, normals strapped | | | |
| MTP48K1NO | MT | 48 | 1.75" High, normals brought out | | | |
| MTP48K3NO | MT | 48 | 3.5" High, normals brought out | | | |
| MTP48K3SNC |) MT | 48 | 3.5" High, sleeve normals out | | | |


DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)

MTP48K WIRED AUDIO SERIES (continued)



TTP96K WIRED AUDIO SERIES



The TTP96K Series was developed with the AES/EBU digital standard in mind. As a standard the TTP96K utilizes 110 Ohm cabling inside.

FEATURES AND BENEFITS

- Unit features 96 TT style jacks in 2RU (3.5"H) space
- Utilizes AES/EBU wiring for complete digital compatibility
- · Attractive, corrosion resistant nickel-plated, steel frame jacks
- Gold-plated switching contacts reduce contact resistance, improve reliability
- · Rugged, attractive black epoxy-finished steel chassis
- Extra wide designation strips for easy channel identification

SPECIFICATIONS MATERIALS JACKS

Frame: Nickel-plated steel Bushing: Nickel-plated brass

Tip, Ring and Shunt Springs: Nickel silver with

welded contacts

Assembly Screws: Zinc-plated steel Welded Contacts: Gold alloy

PANEL

Front Channel: Black anodized aluminum Frame: C.R.S. black epoxy painted

Designation Strips: Black polycarbonate 94V-0 **Designation Strip Covers:** Clear polycarbonate

Jack Inserts: Thermoplastic polyester

MECHANICAL

Life: 30,000 cycles

Insertion Force: 7 lbs. maximum Withdrawal Force: 1 lb. minimum Environmental: O°C to +50°C

ELECTRICAL


Contact Resistance: 30 milliohms maximum initial Insulation Resistance: 10,000 megohms maximum Dielectric Withstanding Voltage: 500 VAC at 60 Hz

Working Voltage: 140 VDC maximum Current Rating: 100 milliamps


| Ordering Information | | | | | | |
|----------------------|---------|--------|-----------------------------|--|--|--|
| Part | Type of | No. of | | | | |
| Number | Jack | Jacks | Description | | | |
| TTP96K3NS | TT | 96 | 3.5" High, normals strapped | | | |

DIMENSIONS ARE FOR REFERENCE ONLY

TTP96K WIRED AUDIO SERIES (continued)



MTPH/TTPH HARNESS AUDIO SERIES



are terminated to our PPT's on the back panel. Primarily used where the back panels must either be mounted into a rack, or brought back to the front for easier access. Custom cable lengths can also be supplied. Contact the factory for details.

FEATURES AND BENEFITS

- Units feature either 48 MT style jacks or 96 TT style jacks on the front panels, to a 4 foot harness, out to a backpanel with PPT's
- All versions utilize AES/EBU wiring for complete digital compatibility
- Attractive, corrosion resistant nickel-plated, steel frame jacks
- Gold-plated switching contacts reduce contact resistance, improve reliability
- Rugged, attractive black epoxy-finished steel frame chassis
- Extra wide designation strips for easy channel identification

SPECIFICATIONS MATERIALS

JACKS

Frame: Nickel-plated steel **Bushing:** Nickel-plated brass

Tip, Ring and Shunt Springs: Nickel silver with

welded contacts

Assembly Screws: Zinc-plated steel **Welded Contacts:** Gold alloy

PANEL

Front Channel: Black anodized aluminum **Frame:** C.R.S. black epoxy painted

Designation Strips: Black polycarbonate 94V-0 **Designation Strip Covers:** Clear polycarbonate

Jack Inserts: Thermoplastic polyester

MECHANICAL

Life: 30,000 cycles

Insertion Force: 7 lbs. maximum Withdrawal Force: 1 lb. minimum Environmental: O°C to +50°C

ELECTRICAL

Contact Resistance: 30 milliohms maximum initial Insulation Resistance: 10,000 megohms maximum Dielectric Withstanding Voltage: 500 VAC at 60 Hz

Working Voltage: 140 VDC maximum Current Rating: 100 milliamps

DIMENSIONS ARE FOR REFERENCE ONLY


Inch (mm)

MTPH/TTPH HARNESS AUDIO SERIES (continued)


| Ordering Information | | | | |
|----------------------|--------------|--------------|--|--|
| Part Number | Type of Jack | No. of Jacks | Description | |
| MTPH48K1NS | MT | 48 | 1.75" High front panel, 4' Harness, | |
| | | | 3.5" High back panel, normals strapped | |
| MTPH48K1NO | MT | 48 | 1.75" High front panel, 4' Harness, | |
| | | | 3.5" High back panel, normals brought out | |
| MTPH48K3NS | MT | 48 | 3.5" High front panel, 4' Harness, | |
| | | | 3.5" High back panel, normals strapped | |
| MTPH48K3NO | MT | 48 | 3.5" High front panel, 4' Harness, | |
| | | | 3.5" High back panel, normals brought out | |
| MTPH48K3SNO | MT | 48 | 3.5" High front panel, 4' Harness, | |
| | | | 3.5" High back panel, sleeve normals brought out | |
| TTPH96K1NS | TT | 96 | 1.75" High front panel, 4' Harness, | |
| | | | 3.5" High back panel, normals strapped | |
| TTPH96K1NO | TT | 96 | 1.75" High front panel, 4' Harness, | |
| | | | 5.25" High back panel, normals brought out | |
| TTPH96K3NS | TT | 96 | 3.5" High front panel, 4' Harness, | |
| | | | 3.5" High back panel, normals strapped | |
| TTPH96K3NO | TT | 96 | 3.5" High front panel, 4' Harness, | |
| | | | 5.25" High back panel, normals brought out | |

See Page 172 for Mechanical Drawings

MTPH/TTPH HARNESS AUDIO SERIES (continued)



MTPH/TTPH HARNESS AUDIO SERIES (continued)



MTPBP/TTPBP BACKPANEL SERIES



The Backpanel Series offers the end user the flexibility of configuring their own patchbay, or to use as a central patchpoint location. The backpanels utilize the PPT punchdown and come with a rugged cable tray.

FEATURES AND BENEFITS

- Allows for custom patchbay configurations or central patching points
- PPTs have IDCs on both sides for easy installation
- · Rugged, attractive black epoxy-finished steel chassis
- · Cable trays allow for mounting and securing terminated cable

SPECIFICATIONS

Panel thickness: .093"

Mounting hole diameter: .187"

Mounting hole spacing (48 IDCs/row): .340" (Horizontal) x .275" (Vertical)

Mounting hole spacing (52 IDCs/row):

.320" (Horizontal) x .275" (Vertical) Wire size: #22, 24, 26 AWG Stranded

or Solid (IDC termination)


MATERIALS

Housing: Thermoplastic (UL 94V-0) Contacts: High strength copper alloy Backpanels: Black Epoxy coated C.R.S. Cable Tray: Black Epoxy coated C.R.S.

| Ordering Information | | | | | | | |
|----------------------|----------------------|--------|-----------------|--|--|--|--|
| Part | Sets of | | | | | | |
| Number | PPT Terminals | Height | Description | | | | |
| MTP48K3BPNS | 48 | 3.5" | T, R, S | | | | |
| MTP48K3PBNO | 48 | 3.5" | T, R, S, TN, RN | | | | |
| MTP52K3BPNO | 52 | 3.5" | T, R, S, TN, RN | | | | |
| MTP24K7 | 24 x 2 | 7.0" | +, -, S | | | | |
| TTP96K3BPNS | 96 | 3.5" | T, R, S | | | | |
| TTP96K5BPNS | 96 x 2 | 5.25" | T, R, S, TN, RN | | | | |

DIMENSIONS ARE FOR REFERENCE ONLY


MTPBP/TTPBP BACKPANEL SERIES (continued)



PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

EZ NORM PATCHBAY SERIES



Easily Normal The Jacks By Rotating To "Full", "Non", Or "Half"

The EZ Norm offers a simplified method for setting up and changing normals to a Bantam/TT patchbay. Simply remove the middle designation strip, and rotate the center cam, using a standard screwdriver. An audible"click" can be heard as you rotate from full normals to no normals to half normals. An opaque marking strip is included to conceal the normal position, if needed.

EZ NORM JACK SPECIFICATIONS MATERIALS:

Housing & Cover: 94V-0 rated thermoplastic Sleeve Collar: Nickel plated copper alloy

Tip, Ring, Shunt, & Sleeve Springs: Nickel Silver with

welded contacts

Welded Contacts: Gold

Cam Switching Springs: Silver plated copper alloy Cam Switching Contacts: Silver plated copper alloy

MECHANICAL

Jack Mechanical Life: 30,000 cycles

Cam Contact Mechanical Life: 30,000 cycles Insertion - Withdrawal Forces: 1 - 4 lbs. Moisture resistance: MIL-STD 202 Method 106 Thermal shock: MIL-STD 202 Method 107 Salt spray: MIL-STD Method 101 (48 hrs.) Vibration: MIL-STD 202 Method 213

ELECTRICAL:

Jack Spring Contact Resistance: 30 milliohm Maximum Cam Switch Contact Resistance: 30 milliohm Maximum

Insulation Resistance: 10,000 Megaohms

Dielectric Withstanding Voltage:

500 VAC (rms) at 60 Hz

Insertion Loss: -0.5dB up to 10 MHz

EZ NORM PATCHBAY OPTIONS


- 1RU can be terminated to EDAC or Cannon DL, solder terminals, or wire-wrap terminals
- 1.5RU can be terminated to EDAC/Cannon DL, solder terminals, wire-wrap terminals, plus 3 pin connectors, or our own PPT Professional Punchdown Terminal
- 2RU Same as above
- All units will be offered with or w/o docking connector
- Unwired units will be offered with either cable tie bar


or cable tray


EZ NORM PATCHBAY SERIES (continued)


Racks

The EZ Norm comes in 3 different rack heights, 1RU, 1.5RU, and 2 RU.











Harness Assembly

The EZ Norm is also offered as a harness assembly, with a standard harness of 4 ft. Custom lengths are available, call Switchcraft® for details.





Front Access

The Front Access option offers a slide-out tray, allowing the end user to re-terminate the patchbay from the front of the rack.

DIMENSIONS ARE FOR REFERENCE ONLY



FEATURES AND BENEFITS

- Attractive, corrosion-resistant, nickel-plated jacks
- Steel frame jacks for superior jack life
- Extra wide labeling strips provide maximum space and two vertical strips, one at each side
- Rugged, attractive black anodized aluminum face will not break
- Two configurations available:
- Normals brought out
- Normalled at jacks
- · Gold switching contacts for long-term reliability
- Jacks paired for easy identification of left and right channels
- Connectorized by EDAC® connectors for ease of termination by customer

SPECIFICATIONS MATERIALS JACKS

Frame: Nickel-plated steel
Bushing: Nickel-plated brass
Tip, Ring and Shunt Springs:
Nickel silver with welded contacts
Assembly Screws: Zinc-plated steel
Welded Contacts: Gold alloy

PANEL

Front Channel: Black anodized aluminum Frame & Cover: C.R.S. black epoxy painted

Designation Strips: Black polycarbonate 94V-0

Designation Strip Covers: Clear

polycarbonate

Jack Inserts: Polyester

EDAC CONNECTOR

Housing: Thermoplastic, UL94V-0 **Contacts:** Gold plated phosphor bronze

MECHANICAL

Life: 30,000 cycles

Insertion Force: 7 lbs. maximum Withdrawal Force: 1 lb. minimum Operating: -20°C to +65°C

ELECTRICAL

Contact Resistance: 30 milliohms maximum initial

Insulation Resistance:10,000 megohms

Dielectric Withstanding Voltage: 500VAC at 60 Hz

Working Voltage: 140VDC Current Rating: 100 milliamps

| EDAC Mating Plugs | |
|--------------------------|-----------------------|
| Part Number | Description |
| 516-090-000-301 | 90 Pin male w/screw |
| 516-090-000-302 | 90 Pin male w/nut |
| 516-120-000-101 | 120 Pin male w/screw |
| 516-120-000-102 | 120 Pin male w/nut |
| 516-290-500 | Terminal solder-style |
| 516-290-590 | Terminal crimp-style |

| Ordering Information | | | | |
|----------------------|---------|--------|------------------------------------|--|
| Part | Type of | No. of | | |
| Number | Jack | Jacks | Description | |
| TT96EDACNO | TT | 96 | Normals Brought Out (120 pin EDAC) | |
| TT96EDACNS | TT | 96 | Normals Strapped (90 pin EDAC) | |


DIMENSIONS ARE FOR REFERENCE ONLY

(mm)

CY

* Please visit the product pages on our website for the most up-to-date product information

TT96 EDAC SERIES (continued)



DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm) DB

JACKS #20 THRU #24
PATTERN CONTINUES TO EF, EH, EJ, EK, EL

19

CF


JACKS #20 THRU #24 PATTERN CONTINUES TO CM,CU,DB

CN

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

TTP96K PATCHKIT SERIES



The TTP96K Patchkit Series offers the end user a rugged cable tray to support rear cabling. Heavy duty construction takes weight off the back of the jacks for increased reliability. Available in 1.75" or 3.5" height versions.

FEATURES AND BENEFITS

- Kit features 96 TT jacks in one rack space (1.75" high) or two rack spaces (3.5" high)
- Jack blocks can be removed from the front for easy soldering
- Dust tray limits dirt, dust and contamination of jack terminals
- Wire management straps are adjustable and reusable
- Attractive, corrosion resistant nickel-plated jacks
- Steel frame jack for superior jack life
- Extra wide labeling strips provide maximum space
- Rugged, attractive black anodized aluminum face will not break or rust
- Three jack configurations available for the exact switching arrangement you need: full normal, half normal, and non-normal (open circuit)
- Fanned solder terminals for easier solder connections
- Gold switching contacts for long-term reliability in normal-through connections

SPECIFICATIONS MATERIALS JACKS

Frame: Nickel-plated steel Bushing: Nickel-plated brass

Tip, Ring and Shunt Springs: Nickel silver

with welded contacts

Assembly Screws: Nickel-plated steel

Welded Contacts: Gold alloy

PANEL

Front Channel: Black anodized aluminum Frame: C.R.S. black epoxy painted

Designation Strips: Black polycarbonate 94V-0 **Designation Strip Covers:** Clear polycarbonate

Jack Inserts: Thermoplastic polyester

MECHANICAL

Life: 30,000 cycles

Insertion Force: 7 lbs. maximum Withdrawal Force: 1 lb. minimum Environmental: 0°C to +50°C

ELECTRICAL

Contact Resistance: 30 milliohms maximum initial Insulation Resistance: 10,000 megohms maximum Dielectric Withstanding Voltage: 500VAC at 60 Hz


Working Voltage: 140VDC maximum Current Rating: 100 milliamps

| Ordering Info | rmation | | |
|----------------|-----------------|-----------------|--------------------------|
| Part Number | Type of Jack | No. of Jacks | Description |
| TTP96K1FN | TT | 96 | 1.75" High, full normals |
| TTP96K1HN | TT | 96 | 1.75" High, half normal |
| TTP96K1NN | TT | 96 | 1.75" High, no normals |
| TTP96K3FN | TT | 96 | 3.5" High, full normals |
| TTP96K3HN | TT | 96 | 3.5" High, half normals |
| TTP96K3NN | TT | 96 | 3.5" High, no normals |

DIMENSIONS ARE FOR REFERENCE ONLY


Inch (mm)

TTP96K PATCHKIT SERIES (continued)



PHONE: 773 792-2700

MT48K/MT52K PATCHKIT SERIES



* Please visit the product pages on our website for the most up-to-date product information

FEATURES AND BENEFITS

- Kit features 48 1/4" longframe jacks in one rack space (1.75" high) or in two rack spaces (3.5" high) or 52 1/4" longframe jacks in one rack space (1.75" high)
- Allows user to add cable and termination panel
- Removable jack panel from the front allows easy soldering of wire connections
- · Jacks have gold switching contacts
- Fanned solder terminals for easier soldering
- Offset ground lugs allow easy bussing of ground with one wire
- Jacks have a nickel-plated frame and assembly screws
- Wire management straps are reusable and adjustable

SPECIFICATIONS MATERIALS JACKS

Frame: Stamped nickel-plated steel Bushing: Nickel-plated brass Tip, Ring and Shunt Springs: Nickel silver with welded contacts Assembly Screws: Nickel-plated steel Welded Contacts: Gold alloy

PANEL

Front Panel: Thermoplastic Frame: C.R.S. black epoxy paint Designation Strips: Black polycarbonate 94V-0 Designation Strip Covers: Clear polycarbonate

MECHANICAL

Life: 30,000 cycles

Insertion Force: 7 lbs. maximum **Withdrawal Force:** 1 lb. minimum

Operating: 0°C to +50°C

ELECTRICAL

Contact Resistance: 30 milliohms maximum initial Insulation Resistance: 10,000 megohms maximum Dielectric Withstanding Voltage: 500VAC at 60 Hz


Working Voltage: 140VDC maximum Current Rating: 100 milliamps

| Ordering Info | | | | |
|---------------|---------|--------|--------|------------------|
| Part | Type of | No. of | | |
| Number | Jack | Jacks | Height | Description |
| MT48K1NS | MT | 48 | 1.75" | Normals strapped |
| MT48K1FN | MT | 48 | 1.75" | Full normals |
| MT48K1HN | MT | 48 | 1.75" | Half normals |
| MT48K1NN | MT | 48 | 1.75" | No normals |
| MT52K1NS | MT | 52 | 1.75" | Normals strapped |
| MT52K1FN | MT | 52 | 1.75" | Full normals |
| MT52K1HN | MT | 52 | 1.75" | Half normals |
| MT52K1NN | MT | 52 | 1.75" | No normals |
| MT48K3FN | MT | 48 | 3.5" | Full normals |
| MT48K3HN | MT | 48 | 3.5" | Half normals |
| MT48K3NN | MT | 48 | 3.5" | No normals |
| MT52K3FN | MT | 52 | 3.5" | Full normals |
| MT52K3HN | MT | 52 | 3.5" | Half normals |
| MT52K3NN | MT | 52 | 3.5" | No normals |


DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)

MT48K/MT52K PATCHKIT SERIES (continued)



MT48/MT52 PATCHBAY SERIES



FEATURES AND BENEFITS

- Units feature either 48 or 52 MT Jax®
- Steel frame jacks for superior jack life
- Attractive, corrosion resistant nickel-plated jacks
- · Gold switching contacts for long-term reliability in normalthrough connections
- · Offset ground terminal for ease in making common ground buss connections
- Fanned solder terminals for easier solder connections
- · Cable tie bar takes the weight of cables off the jacks
- Four jack configurations available for the exact switching arrangement: full normal, half normal, non-normal, and normals strapped

SPECIFICATIONS MATERIALS JACKS

Frame: Steel, nickel-plated Bushing: Brass, nickel-plated Springs: Nickel silver, solder lugs Ground Terminal: Nickel silver,

solder lugs

Switching Contacts: Welded, gold alloy

Insulation: Phenolic spacers, rigid PVC tubing through stack

Screws: Steel, nickel-plated

PANEL

Jack Panel: Thermoplastic Cable Support Bracket: 5/16"

diameter black epoxy painted steel rod

Screws (designation strip): Steel, black zinc-plated Screws (mounting jack): Steel, nickel plated

Kwik-change® Designation Strip: Extruded aluminum, black

anodized

Marking Strip:

White plastic, matte finish Marking Strip Cover: Clear, extruded plastic

MECHANICAL

Life: 30,000 cycles

Insertion Force: 7 lbs. maximum Withdrawal Force: 1 lb. minimum Operating: 0°C to +50°C

ELECTRICAL

Contact Resistance: 30 milliohms maximum initial Insulation Resistance: 10,000 megohms maximum Dielectric Withstanding Voltage: 500VAC at 60 Hz

Working Voltage: 140VDC


maximum

Current Rating: 100 milliamps

| Part | Type of | No. of | |
|--------|---------|--------|------------------|
| Number | Jack | Jacks | Description |
| MT48FN | MT | 48 | Full normals |
| MT48HN | MT | 48 | Half normals |
| MT48NN | MT | 48 | No normals |
| MT48NS | MT | 48 | Normals strapped |
| MT52FN | MT | 52 | Full normals |
| MT52HN | MT | 52 | Half normals |
| MT52NN | MT | 52 | No normals |
| MT52NS | MT | 52 | Normals strapped |

DIMENSIONS ARE FOR REFERENCE ONLY


MT48/MT52 PATCHBAY SERIES (continued)



PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

TTP96AS PATCHBAY SERIES



FEATURES AND BENEFITS

- Unit features 96 TT jacks
- · Attractive, corrosion resistant nickel-plated jacks
- · Steel frame jack for superior jack life
- Extra wide labeling strips provide maximum space
- Rugged cable tie bar takes the weight of cables off the jacks
- Rugged, attractive black anodized aluminum face will not break
- Three jack configurations available for the exact switching arrangement you need: full normal, half normal, and open circuit panel
- Fanned solder terminals for easier solder connections
- Offset ground terminal for ease in making common ground buss connections
- Gold switching contacts for long-term reliability in normal-through connections

SPECIFICATIONS MATERIALS JACKS

Frame: Steel, nickel-plated Bushing: Nickel-plated copper alloy Springs: Copper alloy solder lugs

Ground Terminal: Steel, tin electrodeposited **Switching Contacts:** Welded, gold alloy inlay

over palladium base

Insulation: Rigid plastic spacers, rigid PVC

tubing through stack **Screws:** Steel, plated

PANEL

Frame: Black anodized aluminum **Inserts:** Polyester, glass filled, 94V-0

Cable Support Bar: Cold rolled steel, nickel-plated

Designation Strips: Thermoplastic, 94V-0

Designation Strip Covers: Clear thermoplastic, SE-1 **Marking Strip:** Rigid vinylite

Jack Mounting Screws: Steel, plated

Screws: Steel, black plated

MECHANICAL

Life: 30,000 cycles

Insertion Force: 7 lbs. maximum Withdrawal Force: 1 lbs. minimum Environmental: 0°C to +50°C


ELECTRICAL

Contact Resistance: 30 milliohms maximum initial Insulation Resistance: 10,000 megohms maximum Dielectric Withstanding Voltage: 500VAC at 60 Hz

Working Voltage: 140VDC maximum Current Rating: 100 milliamps

| Ordering Information | | | | | |
|----------------------|---------|--------|--------------|--|--|
| Part | Type of | No. of | | | |
| Number | Jack | Jacks | Description | | |
| TTP96ASFN | TT | 96 | Full normals | | |
| TTP96ASHN | TT | 96 | Half normals | | |
| TTP96ASNN | TT | 96 | No normals | | |


TTP96AS PATCHBAY SERIES (continued)



PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

Q-G® PATCHBAY SERIES



solder cup terminals for easy soldering and the inserts are removable from the back, allowing for easy changes. The one rack unit height version comes with 16 male, or 16 female, or 8 male and 8 female connectors. The two rack unit version comes with 16 male and 16 female connectors. We also offer the unit without connectors, but with the panel cut-outs already punched out. All versions have a rugged cable tie bar, which takes the weight of the cabling away from the solder connections.

FEATURES AND BENEFITS

- Available in 1RU or 2RU versions
- Available with or without the connectors
- E Series connectors are silver-plated, 3 pins/contacts with black finish
- · Cable tie bar takes the weight of the cables off the solder terminations
- Rugged aluminum channel increases durability
- · Silk-screen designation area makes it easy to re-label channels

SPECIFICATIONS MATERIALS CONNECTORS

Housing: Die-cast, black velvet finish Inserts: Glass-filled thermoplastic Pin/Contacts: Copper alloy, silver-plated Latch Release: Steel, nickel-plated Insert Locking Cam: Die-cast zinc

FRAME


Aluminum, black anodized

CABLE TIE BAR

Steel, black epoxy

| Ordering Information | | | |
|----------------------|--------|-----------------------------------|--|
| Part Number | Height | Description | |
| QGPK116FB | 1.75" | 16 female | |
| QGPK116MB | 1.75" | 16 male | |
| QGPK18M8FB | 1.75" | 8 male, 8 female | |
| QGPK332MFB | 3.5" | 16 female(top), 16 male (bottom) | |
| QGPK1B | 1.75" | Blank panel | |
| QGPK3B | 3.5" | Blank panel | |

Q-G® PATCHBAY SERIES (continued)




HPC PATCHBAY SERIES

The HPC Patchbay features a 19" rack unit loaded with HPC Series connectors. Available with either 0.250" Faston terminals or 0.187" Faston terminals. One rack unit height versions come with 12 HPC connectors, two rack unit height versions come with 24 HPC connectors. All versions have a rugged cable tie bar, which takes the weight of the cabling away from the connections.

FEATURES AND BENEFITS

- Available in 1RU or 2RU versions
- · Available with or without connectors
- HPC Series connectors are compatible with Neutrik Speakon® connectors
- Cable tie bar takes weight of the cables off the terminations
- Rugged aluminum channel
- Silk-screen designation area makes it easy to re-label channels




See page 38 for details

MATERIALS


Housing: Thermoplastic UL 94V-O rated Contacts: Silver-plated over copper alloy

FRAME Aluminum, black anodized

CABLE TIE BAR Steel, black epoxy





PHONE: 773 792-2700



| Part Number | Height | Description |
|----------------|--------|-------------------------------|
| HPCPK112F | 1.75" | 12 connectors, 0.250" Fastons |
| HPCPK112F1 | 1.75" | 12 connectors, 0.187" Fastons |
| HPCPK1B | 1.75" | Blank panel |
| HPCPK324F | 3.50" | 24 connectors, 0.250" Fastons |
| HPCPK324F1 | 3.50" | 24 connectors, 0.187" Fastons |
| HPCPK3B | 3.50" | Blank panel |

RS 422 DATA PATCHBAY SERIES





| RS422 Ordering Information | | | | |
|----------------------------|--------|-------------|--------------|--------|
| Part | No. of | Front Panel | Back | Rack |
| Number* | Jacks | Layout | Plane | Height |
| RS422H48N081 | 2 x 8 | Horizontal | 9 Pin D-Sub | 1 |
| RS422V4N081 | 2 x 8 | Vertical | 9 Pin D-Sub | 1 |
| RS422H4N161 | 2 x 16 | Horizontal | 9 Pin D-Sub | 1 |
| RS422H4N162 | 2 x 16 | Horizontal | 9 Pin D-Sub | 2 |
| RS422V4N161 | 2 x 16 | Vertical | 9 Pin D-Sub | 1 |
| RS422V4N162 | 2 x 16 | Vertical | 9 Pin D-Sub | 2 |
| RS422H4N242 | 2 x 24 | Horizontal | 9 Pin D-Sub | 2 |
| RS422V4N242 | 2 x 24 | Vertical | 9 Pin D-Sub | 2 |
| RS422V4N322 | 2 x 32 | Vertical | 9 Pin D-Sub | 2 |
| RS422PH4N081 | 2 x 8 | Horizontal | PPT Punchdow | n 1 |
| RS422PV4N081 | 2 x 8 | Vertical | PPT Punchdow | n 1 |
| RS422PH4N161 | 2 x 16 | Horizontal | PPT Punchdow | n 1 |
| RS422PH4N162 | 2 x 16 | Horizontal | PPT Punchdow | n 2 |
| RS422PV4N161 | 2 x 16 | Vertical | PPT Punchdow | n 1 |
| RS422PV4N162 | 2 x 16 | Vertical | PPT Punchdow | n 2 |
| RS422PH4N242 | 2 x 24 | Horizontal | PPT Punchdow | n 2 |
| RS422PV4N242 | 2 x 24 | Vertical | PPT Punchdow | n 2 |
| RS422PV4N322 | 2 x 32 | Vertical | PPT Punchdow | n 2 |

*Add "N" for non-normalled version See Page 267 for Patchcord Information

FEATURES AND BENEFITS

- Unit Features either 8,16, 24, or 32 TT style jacks on the front Panels, to a 9 pin D-Sub or PPT back Plane.
- All version utilize low capacitance internal wiring for maximum performance of transferring data
- All standard units are available 1 or 2 rack units high (1.5 RU available by request)
- Rugged, attractive black epoxyfinished steel frame chassis

Our standard RS data jackfield series offer a multiple combination of ports, rack heights, and back panel terminations which will easily fit into any television broadcast or video production where custom data patching is required. Custom ports and rack height combinations can be supplied. Contact the factory for details.

SPECIFICATIONS ELECTRICAL


Internal Wiring:

24 AWG Solid TC, foils shield


Nom Capacitance: 11.5 pF/ft between conductors 21.3 pF/ft between one conductor and conductor

connected to the shield **Nom**. Impedance: 110 Ohms

Inch (mm)



RS422V4N322 32 Vertical Paired Jacks Front and Back Views





PHONE: 773 792-2700

RS422H4N242 24 Horizontal Paired Jacks Front and Back Views

| Part | No. of | Front Panel | Back | Rack |
|--------------|--------|-------------|---------------|--------|
| Number | Jacks | Layout | Plane | Height |
| RS422H4N081 | 2 x 8 | Horizontal | 9 Pin D-Sub | 1 |
| RS422V4N081 | 2 x 8 | Vertical | 9 Pin D-Sub | 1 |
| RS422H4N162 | 2 x 16 | Horizontal | 9 Pin D-Sub | 1, 2 |
| RS422V4N162 | 2 x 16 | Vertical | 9 Pin D-Sub | 1, 2 |
| RS422H4N242 | 2 x 24 | Horizontal | 9 Pin D-Sub | 2 |
| RS422V4N242 | 2 x 24 | Vertical | 9 Pin D-Sub | 2 |
| RS422V4N322 | 2 x 32 | Vertical | 9 Pin D-Sub | 2 |
| RS422PH4N081 | 2 x 8 | Horizontal | PPT Punchdown | 1 |
| RS422PV4N081 | 2 x 8 | Vertical | PPT Punchdown | 1 |
| RS422PH4N162 | 2 x 16 | Horizontal | PPT Punchdown | 1, 2 |
| RS422PV4N162 | 2 x 16 | Vertical | PPT Punchdown | 1, 2 |
| RS422PH4N242 | 2 x 24 | Horizontal | PPT Punchdown | 2 |
| RS422PV4N242 | 2 x 24 | Vertical | PPT Punchdown | 2 |
| RS422PV4N322 | 2 x 32 | Vertical | PPT Punchdown | 2 |

DIMENSIONS ARE FOR REFERENCE ONLY



The VPP Series video patchbays offer a wide variety of options for video patching. The HD Series meets SMPTE 292M specifications for high definition video signaling, covering a bandwidth range from DC to 2.4GHz. The SD Series is perfect for serial digital, with a bandwidth from DC to 1.75GHZ. Both come in either terminated or non-terminated, 24 or 26 jacks, 1.75" or 3.5" heights.

FEATURES AND BENEFITS

- HD Series meets SMPTE 292M Specifications
- SD Series has a bandwidth from DC to 1.75GHz
- Black thermoplastic modules insulate jacks from chassis
- Jacks feature rugged heavy duty housings

VIDEO JACK SPECIFICATIONS ELECTRICAL

Rated Bandwidth: 2.4 GHz (HD), 1.75 GHz (SD)

Characteristic Impedance: 75 ohms Return Loss: Better than -15 dB Insertion Loss: Better than -.5 dB

Contact Resistance: Less than 20 milliohms Termination Resistance: 75 W. ±1%

Center Conductor: Accepts .090 pin diameter

MECHANICAL

Mechanical Shock: Per MIL-STD-202, Method 213,

Test condition I

Vibration: Per MIL-STD-202, Method 201 Insertion Force: 12 lbs. maximum Withdrawal Force: 3 lbs. minimum

Life Cycle: 30,000

MATERIAL

Housing: Zinc alloy, nickel plated

Center Contacts: Copper alloy, gold plated Switching Springs: Copper alloy, gold plated

Grounding Contacts:

HD Series - Copper alloy, gold plated SD Series - Copper alloy, nickel plated Insulators: Thermoplastic, UL 94V-0 rated

ENVIRONMENTAL

Operating Temperature: - 40°C to 65°C Storage Temperature: - 55°C to 85°C

Thermal Shock: Per MIL-STD-202, Method 107


Moisture and Humidity: Per MIL-STD-202, Method 106

| Ordering Information | | | | | |
|------------------------------------|---------|--------|--------|-------------|--|
| Part | Type of | No. of | | | |
| Number | Jack | Jacks | Height | Description | |
| VPP24K1HD*75T | HD | 24 | 1.75" | Terminated | |
| VPP24K1HD*NT | HD | 24 | 1.75" | Non-term | |
| VPP24K1SD*75T | SD | 24 | 1.75" | Terminated | |
| VPP24K1SD*NT | SD | 24 | 1.75" | Non-term | |
| VPP26K1HD*75T | HD | 26 | 1.75" | Terminated | |
| VPP26K1HD*NT | HD | 26 | 1.75" | Non-term | |
| VPP26K1SD*75T | SD | 26 | 1.75" | Terminated | |
| VPP26K1SD*NT | SD | 26 | 1.75" | Non-term | |
| VPP24K3HD*75T | HD | 24 | 3.5" | Terminated | |
| VPP24K3HD*NT | HD | 24 | 3.5" | Non-term | |
| VPP24K3SD*75T | SD | 24 | 3.5" | Terminated | |
| VPP24K3SD*NT | SD | 24 | 3.5" | Non-term | |
| VPP26K3HD*75T | HD | 26 | 3.5" | Terminated | |
| VPP26K3HD*NT | HD | 26 | 3.5" | Non-term | |
| VPP26K3SD*75T | SD | 26 | 3.5" | Terminated | |
| VPP26K3SD*NT | SD | 26 | 3.5" | Non-term | |
| *Add "N" for non-normalled version | | | | | |

DIMENSIONS ARE FOR REFERENCE ONLY


Inch (mm


VPP VIDEO PATCHBAY SERIES (continued)




VPP VIDEO PATCHBAY SERIES (continued)

| Ordering-Individual Jacks | | | | |
|------------------------------------|------------------------------|----------------|--|--|
| Part Number | Part Number Type Description | | | |
| VJHD*75TX | HD | Terminated | | |
| VJHD*NTX | HD | Non-terminated | | |
| VJSD*75TX SD Terminated | | | | |
| VJSD*NTX SD Non-terminated | | | | |
| *Add "N" for non-normalled version | | | | |





MVP MIDSIZE VIDEO PATCHBAY SERIES



FEATURES AND BENEFITS

- Midsize video jacks rated from DC to 3 GHz
- 32 midsize jacks mounted either 1RU, 1.5RU or 2RU panel
- Available in terminated or non-terminated configurations

SPECIFICATIONS MATERIAL

Frame: Aluminum, black anodized Designation Strips: Vinylite, white

Designation Strip Covers: Lexan, transparent Jack Inserts: Thermoplastic, UL 94V-0 rated

MIDSIZE VIDEO JACK SPECIFICATIONS **ELECTRICAL**

Rated Bandwidth: 3.0 GHz

Characteristic Impedance: 75 ohms Return Loss: See Typical Return Loss Chart **Insertion Loss:** See Typical Insertion Loss Chart Contact Resistance: Less than 20 milliohms

Termination Resistance: 75 W, ±1% Center Conductor: Accepts .048 pin diameter

MECHANICAL

Mechanical Shock: Per MIL-STD-202.

Method 213, Test condition I

Vibration: Per MIL-STD-202, Method 201 Insertion Force: 12 lbs. maximum Withdrawal Force: 3 lbs. minimum

Life Cycle: 30,000

MATERIAL

Housing: Zinc alloy, nickel plated

Center Contacts: Copper alloy, gold plated Switching Springs: Copper alloy, gold plated Grounding Contacts: Copper alloy, gold plated

BNC Insulators: Teflon

Actuators: Thermoplastic, UL94V-0 rated

ENVIRONMENTAL

Operating Temperature: - 40°C to 65°C Storage Temperature: - 55°C to 85°C

Thermal Shock: Per MIL-STD-202, Method 107


Moisture and Humidity: Per MIL-STD-202, Method 106

| Ordering Information | | | | |
|-------------------------------------|---------|--------|----------------|--|
| Part | Type | | | |
| Number | of Jack | Height | Description | |
| MVP32K1*75T | Midsize | 1.75" | Terminated | |
| MVP32K1*NT | Midsize | 1.75" | Non-terminated | |
| MVP32K3*75T | Midsize | 3.5" | Terminated | |
| MVP32K3*NT | Midsize | 3.5" | Non-terminated | |
| * Add "N" for non-normalled version | | | | |

Note: For 1.5RU (2.62" height), use K2

DIMENSIONS ARE FOR REFERENCE ONLY

MVP MIDSIZE VIDEO PATCHBAY SERIES (continued)



Ν


S E R T

0 Ν


(dB)

MVP MIDSIZE VIDEO PATCHBAY SERIES (continued)


| Ordering Information Part | |
|---------------------------|----------------------|
| Number | Description |
| MVJ*75TX | Terminated |
| MVJ*NTX | Non-terminated |
| *Add "N" for no | on-normalled version |



RETURN LOSS (TYPICAL)



RETURN LOSS (TYPICAL)





FEATURES AND BENEFITS

configurations.

- Combines 13 video jacks and 26 long-frame audio jacks into one patchbay
- Available with either HD Series or SD Series video jacks
- All audio jacks are nickel-plated with steel frames and gold-plated switching contacts
- Audio modules consist of 4 YMT334BN jacks, video modules consist of 2 dual video jacks

VIDEO JACK SPECIFICATIONS ELECTRICAL

Rated Bandwidth: 2.4 GHz (HD), 1.75 GHz (SD)

Characteristic Impedance: 75 ohms Return Loss: Better than -15 dB Insertion Loss: Better than -.5 dB

Contact Resistance: Less than 20 milliohms Termination Resistance: 75 W, ±1%

Ocates Ocasion to Accests 000 six disease

Center Conductor: Accepts .090 pin diameter

MECHANICAL

Mechanical Shock: Per MIL-STD-202,

Method 213, Test condition I

Vibration: Per MIL-STD-202, Method 201 Insertion Force: 12 lbs. maximum Withdrawal Force: 3 lbs. minimum

Life Cycle: 30,000

MATERIAL

Housing: Zinc alloy, nickel plated

Center Contacts: Copper alloy, gold plated Switching Springs: Copper alloy, gold plated

Grounding Contacts:

HD Series - Copper alloy, gold plated SD Series - Copper alloy, nickel plated **Insulators:** Thermoplastic, UL 94V-0 rated

ENVIRONMENTAL

Operating Temperature: -40°C to 65°C Storage Temperature: -55°C to 85°C


Thermal Shock: Per MIL-STD-202, Method 107

Moisture and Humidity: Per MIL-STD-202, Method 106


| Ordering Information | | | |
|----------------------|------------|------------|----------------------------|
| Part | Type of | | |
| Number | Jack | Height | Description |
| VAPK1HD*75T | HD | 1.75" | Terminated |
| VAPK1HD*NT | HD | 1.75" | Non-terminated |
| VAPK1SD*75T | SD | 1.75" | Terminated |
| VAPK1SD*NT | SD | 1.75" | Non-terminated |
| VAPK3HD*75T | HD | 3.5" | Terminated |
| VAPK3HD*NT | HD | 3.5" | Non-terminated |
| VAPK3SD*75T | SD | 3.5" | Terminated |
| VAPK3SD*NT | SD | 3.5" | Non-terminated |
| Modules | | | |
| VMAFN | MT | | 4- YMT334BN jacks |
| VMVHD*75T | HD | | 2- HD terminated jacks |
| VMVHD*NT | HD | | 2- HD non-terminated jacks |
| VMVSD*75T | SD | • | 2- SD terminated jacks |
| VMVSD*NT | SD | • | 2-SD non-terminated jacks |
| *Add "N" for nor | n-normalle | ed version | า |

DIMENSIONS ARE FOR REFERENCE ONLY

VAP VIDEO/AUDIO PATCHBAY SERIES (continued)



MBPK VIDEO/AUDIO PATCHBAY SERIES



The MBPK Series combines audio and video in one convenient patchbay. The patchbay consists of 16 midsize video jacks and 48 TT bantam jacks. Options include 75 Ohm terminated or non-terminated video jacks. All TT bantam jacks have T, R, S, TN and RN solder terminals. Audio jacks have nickel-plated steel frames, gold-plated crossbar switching contacts and flared terminals for easier soldering.

FEATURES AND BENEFITS

Combines 16 midsize video jacks and 48 TT bantam audio jacks

Video jacks are rated from DC to 3.0 GHZ

All audio jacks are nickel-plated with steel frames and goldplated crossbar switching contacts

For non-terminated version, use part no. MBPK1NT

VIDEO JACK SPECIFICATIONS


See page 196 for details

AUDIO JACK SPECIFICATIONS

See page 164 for details

MATERIALS FRAME

Aluminum, black anodized



JACK PANELS LONG FRAME 1/4" TELEPHONE JACK PANELS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

LONG FRAME (1/4") TELEPHONE JACK PANELS



STANDARD SINGLE ROW JACK PANELS SERIES 1200 AND 1400

SERIES 1200

Panels accomodate 24 T-Jax® jacks in standard 1.75 inch x 19 inch racks. Jack openings are on alternate .625 inch and .750 inch spacing; twin plugs cannot be cross-connected between adjacent jack pairs. Includes designation strips (marking strips and transparent plastic covers).

SERIES 1300

Same as Series 1200, except MT-Jax® are used in panel assemblies.

SERIES 1400

Mounts 26 T-Jax®. Openings are on continuous .625 inch centers. Twin plug can be used on any two adjacent jacks. Single designation strip (marking strip, and plastic cover). WEco equivalent is 230B.

SERIES 1400300

Same as Series 1400, except designation strip is Kwik-Change® type which is easier to install and remove and provides larger vertical designation marking area. Strip holder is recessed into top of panel for additional panel strength. 1400301 has single height Kwik-Change® designation strip. 1400315 has a single height Kwik- Change® designation strip along bottom of panel and double height strips above jacks. Top designation strip has .188 inch overhang above 1.75 inch panel height, to help seal small opening between adjacent panels. CAUTION: Because of this overhang, 1400315 cannot be mounted one above another in a rack.

SERIES 1500

Same as Series 1400 except MT-Jax® are used in panel assemblies.

SPECIFICATIONS

Jack Panel: General purpose black phenolic resin

Frame (except 1400300): Plated, steel

End Bracket and Side Strip (1400300 only): Cold rolled

plated Steel

Designation Strip (except 1400300): Clear plastic. "Kwik-Change" Designation Strip (1400300): Extruded aluminum, black anodized and black thermoplastic UL 94V-0.

Marking Strip: White plastic, matte finish.

Marking Strip Cover: Clear extruded plastic.

Screws: #6-32 x .25 inch phillips RHMS (for mounting jacks).


ORDERING

Part number table lists blank panels and popular jack panel assemblies. If you wish to mount components on basic panels, order jacks, lamp jacks, and switches separately. (See appropriate section in this catalog.) For other panel assemblies, provide complete details with your inquiry or order. Switchcraft can build special assemblies to your requirements in small or large quantities. See wire wrapping data. Series 1200 and 1400 are available with holes pre-drilled for vertical designation strips (Series DS320). Add prefix "D" to part numbers for pre-drilled panels: D1200, D1400301, etc.









LONG FRAME (1/4") TELEPHONE JACK PANELS (continued)





| Part Numbers | | Part Numbers | | Description | | |
|-----------------|------------------|----------------------------|--|--------------------|-------------------------------------|--|
| | | y with Jacks older Lugs | Assembly with Jacks With Wire-Wrapping | Number of Jacks | Type of Jacks Installed | |
| Panel Only | Straight | Offset | Terminals | OI DUCKS | Jacks Installed | |
| 1200 | - | - | - | None | | |
| - | 1332A | ◊ X1332A | ⊘W1332A | 24 | MT332A , XMT332A or WMT332A MT-Jax® | |
| - | ◊1332B | ◊ X1332B | - | 24 | MT332B or XMT332B MT-Jax® | |
| - | ◊1334B | ♦X1334B | ⊘W1334B | 24 | MT334B,XMT334B or WMT334B MT-Jax® | |
| 1400 | - | - | - | None | | |
| 1400301 | - | - | - | None | | |
| ◊1400315 | - | - | - | None | | |
| - | 1532A | X1532A | - | 26 | MT332A or XMT332A MT-Jax® | |
| - | ♦1532A301 | - | ⊘W1532A301 | 26 | MT332A or WMT332A MT-Jax® | |
| - | ◊1532B | - | - | 26 | MT332B MT-Jax® | |
| - | ♦1532B301 | ♦X1532B301 | ⊘W1532B301 | 26 | MT332B, XMT332B or WMT332B MT-Jax® | |
| - | ◊1534B | ◊ X1534B | ⊘W1534B | 26 | MT334B, XMT334B or WMT334B MT-Jax® | |
| - | - | - | ⊘W1534B301 | 26 | WMT334B MT-Jax® | |
| - | - | ♦X1542B315 | - | 26 | XMT342B MT-Jax® | |

 $[\]Diamond$ Special order only; contact factory for price and delivery.

Jack Mounting Screws: #6-32, **P10725**, can be ordered separately. Contact Switchcraft.

Legend Cards (Series 1200, 1300) - **A1029 Legend Windows** (Series 1200, 1300) - **A1030**






DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)


^{1.} Prefix "X" denotes offset lugs for buss wiring.

LONG FRAME (1/4") TWIN ROW JACK PANELS






See next page for specific part numbers.







STANDARD TWIN ROW JACK PANELS SERIES 2400, 2600, 2600300, 2700300 - PHENOLIC

Twin row jack panels offer greater jack density - up to 52 jacks per panel. All panels fit standard 19" wide racks. Blank panels or standard assemblies can be ordered from Switchcraft. Series 2600 panels are direct equivalent to WEco #230A.

SERIES 2400

Twin row panel accommodates 48 T-Jax®. Openings are on alternate .625" and .75" centers. Panel is 2.125" high and fits standard 19" racks. Twin plug cannot be cross-connected between jacks in adjacent guads, but may be connected either horizontally or vertically in the same quad. Single designation strip.

SERIES 2500

Same as Series 2400 except MT-Jax® are used.

SERIES 2600

Twin row panel accommodates 52 T-Jax® in standard 1.75" x 19" racks. Jack openings are on continuous centers. Twin plug can be connected to any two adjacent jacks, either horizontally or vertically. Two designation strips. WEco equivalent is #230A.

SERIES 2600300

Same as Series 2600, except designation strips are Kwik-Change® type, providing larger vertical marking area. Top strip holder is recessed into top of panel to provide additional

strength. 2600301 has single height designation strips (one above and below each row of jacks).

2600310

Has a double height strip above top row and a steel reinforcing strip below bottom row. Top strip has .188" overhang above 1.75" panel height, helping seal the small opening between adjacent panels. Note: overhang prevents mounting panel one above another in a rack.

SERIES 2700

Same as Series 2600 except MT-Jax® are used in panel assemblies. The series is available with cable tie bar.

ORDERING

- 1. Order basic panels and popular assemblies by part number from table.
- 2. For special panels provide complete details with your inquiry
- 3. Series 2600 is available with hole pre-drilled for vertical designation strips, Series DS320. Add prefix "D" to part number (D2600301, etc.).
- 4. Jack Mounting Screws: #6-32, P10725, can be ordered separately. Contact Switchcraft.


Inch


LONG FRAME (1/4") TWIN ROW JACK PANELS (continued)

| | ٠. |
|------------|----|
| _ | _ |
| / | 7 |
| / | |
| , | |
| u | |
| , <u> </u> | |
| | |
| • | |
| | |

| | Part Numbers | 3 | Part Numbers | | Description |
|------------|------------------|----------------------------|-------------------------------------|----------|------------------------------------|
| | Solde | th Jacks Having er Lugs | Assembly with Jacks Having Wire- | Number | |
| Panel Only | Straight | Offset ¹ | Wrapping Terminals | of Jacks | Type of Jack Installed |
| 2400 | - | - | - | None | |
| - | ⊘2432A | ◊ X2432A | - | 48 | T332A |
| - | ⊘2432B | ◊ X2432B | - | 48 | T332B |
| - | ⊘2434B | ◊ X2434B | - | 48 | T334B or XMT334B T-Jax® |
| - | 2532A | ◊ X2532A | ⊘W2532A | 48 | MT332A, XMT332A or WMT332A MT-Jax® |
| - | ⊘2532B | ◊ X2532B | - | 48 | MT332B or XMT332B MT-Jax® |
| - | ◊2533 | - | - | 48 | MT333 MT-Jax® |
| - | ⊘ 2533B | - | ⊘W2533B | 48 | MT333B or WMT333B MT-Jax® |
| - | ⊘2534B | X2534B | - | 48 | MT334B or XMT334B MT-Jax® |
| - | ⊘2542B | - | - | 48 | MT342B MT-Jax® |
| - | ◊2544B | - | - | 48 | MT344B, MT-Jax® |
| - | ◊2588 | - | - | 24 | MT388, Twin MT-Jax® |
| - | ◊2589 | - | - | 24 | MT389 Twin MT-Jax® |
| 2600 | - | - | - | None | |
| 2600301 | - | - | - | None | (WEco equivalent #230A) |
| 2600310 | - | - | - | None | |
| - | ⊘2732A | ◊ X2732A | - | 52 | MT332A or XMT332A MT-Jax® |
| - | ⊘2732A301 | ♦X2732A301 | ⊘W2732A301 | 52 | MT332A, XMT332A or WMT332A MT-Jax® |
| - | ⊘2732B | ◊ X2732B | ⊘W2732B | 52 | MT332B, XMT332B or WMT332B MT-Jax® |
| - | ⊘2732B301 | ♦X2732B301 | ⊘W2732B301 | 52 | MT332B, XMT332B or WMT332B MT-Jax® |
| - | ⊘2733B | - | - | 52 | MT333B, MT-Jax® |
| - | ⊘2734B | ◊ X2734B | - | 52 | MT334B or XMT334B MT-Jax® |
| - | ⊘2734B301 | ♦X2734B301 | ⊘W2734B301 | 52 | MT334B, XMT334B or WMT334B MT-Jax® |
| - | ⊘2789 | - | ⊘W2789 | 26 | MT389 or WMT389 Twin MT-Jax® |
| - | - | ◊ X2832A | - | 48 | XT332A |
| - | - | ◊ X2932A | - | 48 | XMT332A |

^{1.} Prefix "X" denotes offset lugs for buss wiring.





[♦] Special order only; contact factory for price and delivery.

JACK PANELS Long Frame 1/4" modular twin row Jack Panels

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

LONG FRAME (1/4") MODULAR TWIN ROW JACK PANELS





SERIES JP122S34B

*Shown with optional jacks, See next page for specific part numbers.



SERIES JP032S32B

*Shown with optional jacks, See next page for specific part numbers.

SERIES JP012000 THROUGH JP122000

Series JP® Modular Jack Panels feature a modular packaging concept. Jacks are mounted on inserts then complete modular insert assemblies are mounted to the panel from the rear. Mounting and wiring are quick and easy. Individual jacks or complete inserts can be removed from the panel with minimum disturbance to wiring and adjacent jacks. JP panels offer three mounting styles (standard rack mount, flush mount, and extension mount), staggered or continuous-center panel openings, two panel lengths (19" and 23"), WEco equivalents, Kwik-Change® designation strips, precision manufactured modular parts, rugged black anodized aluminum frames and quick and easy module or jack removal/installation.

Each module insert has four holes which mount four MT-Jax® or two Twin-Jax®. Each modular jack panel is supplied with two Kwik-Change® designation strips. Mounting strips are integral with panel, and marking strips and clear covers snap into place quickly and easily.

SERIES JP012000

Standard 1.75" x 19" size for console, rack or control panel mounting. Mounts 48 MT-Jax®. Openings are on alternate .625" and .75" centers in each row. A twin plug fits jacks horizontally or vertically in the same guad, but cross-connecting between quads is not possible. Includes 12 black module inserts, insert mounting screws and two Kwik-Change® designation strips.

SERIES JP022000

Same as JP012000, except 23" wide (includes 14 inserts which accommodate 56 MT-Jax®).

SERIES JP032000

Same as JP012000, except with 5.375" extension brackets which permit access to rear of jacks from front of panel. Brackets are supplied mounted to panel.

SERIES JP042000

Same as JP032000, except 23" wide (includes 14 inserts which accommodate 56 MT-Jax®).

SERIES JP052000

Same as JP012000, except designed for flush mounting or standoff mounting. Switchcraft Bracket Kit K107; Contact Switchcraft.

SERIES JP062000

Same as JP052000, except 23" wide (includes 14 inserts which accommodate 56 MT-Jax®).

SERIES JP072000

Same as JP012000, except mounts 52 MT-Jax® and includes 13 black module inserts. Modular equivalent of WEco #230A.

SERIES JP082000

Same as JP072000, except 23" wide (includes 16 inserts which accommodate 64 MT-Jax®). Modular equivalent to WEco #231A.

SERIES JP092000

Same as JP072000, except with 5.375" extension brackets which permit access to rear of jacks from front of panel. Brackets are supplied mounted to panel.

SERIES JP102000

Same as JP092000, except 23" wide (includes 16 inserts which accommodate 64 MT-Jax®).

SERIES JP112000

Same as JP072000, except designed for flush mounting or standoff mounting. Switchcraft Bracket Kit K107; Contact Switchcraft.

SERIES JP122000

Same as JP112000, except 23" wide (includes 16 inserts which accommodate 64 MT-Jax®).

SPECIFICATIONS

Panel and Integral Designation Mounting Strips:

Aluminum alloy, extruded. Black anodized per MIL-A-8625 Module Insert: Molded plastic, matte finish. Black standard; white, red, green, blue or yellow available on special order Marking Strip: White matte finish plastic

Designation Strip Cover: Extruded clear plastic Screws: #6-32 x 5/15", PHMS, for jack mounting; #4-40 x 1/2" phillips PHMS, for module insert mounting Brackets: 5.375", aluminum alloy black anodized finish

(JP032000, JP042000, JP092000, JP102000)

Screws, Mounting Bracket: #6-32, self-tapping supplied.

LONG FRAME (1/4") MODULAR TWIN ROW JACK PANELS (continued)



ORDERING

Order popular assemblies by part number from table. If you wish to mount components on the panels, order blank panels and refer to MODULE INSERTS below. On special order, various combinations of colored inserts mounted in basic panels, as well as many different types of complete assemblies are possible. Provide complete details with your

inquiry or order. Standard mount panels are available with holes pre-drilled for vertical designation strips, Series DS320. Add prefix "D" to part number (JPD012000, JPD022000, JPD072000, JPD082000, etc.).

| Pa | | | |
|-------------------|--|---------------|----------------------|
| Panel Only | Assembly with Jacks Having Solder Lugs | # of Jacks | MT-Jax® Installed |
| JP012000 | - | None | |
| - | ♦JP012S32A | 48 | MT332A |
| - | | 48 | MT332B |
| - | JP012S34B1 | 48 | MT334B |
| ♦ JP022000 | - | None | |
| - | ♦JP022S32A | 56 | MT332A |
| - | ⊘JP022S32B | 56 | MT332B |
| - | ⟨JP022S34B | 56 | MT334B |
| ♦ JP032000 | - | None | |
| - | ♦JP032S32A | 48 | MT332A |
| - | ⊘JP032S32B | 48 | MT332B |
| - | ⟨JP032S34B | 48 | MT334B |
| ♦ JP042000 | - | None | |
| - | ⊘JP042S32A | 56 | MT332A |
| - | ⊘JP042S32B | 56 | MT332B |
| - | ⟨JP042S34B | 56 | MT334B |
| JP052000 | - | None | |
| - | ♦ JP052S32A | 48 | MT332A |
| - | ♦ JP052S32B | 48 | MT332B |
| - | ⟨JP052S34B | 48 | MT334B |
| ♦ JP062000 | - | None | |
| - | ♦JP062S32A | 56 | MT332A |
| - | ♦ JP062S32B | 56 | MT332B |
| - | ♦ JP062S34B | 56 | MT334B |

^{1.} Add a "1" to the part number to specify a cable tie bar.

Mounting Screws: #6-32, P10725 for jack mounting and #4-40, P2435 for insert mounting, can be ordered separately.

MODULE INSERTS







Standard color is black, matte finish plastic. Contact Switchcraft. Inserts are ideal for mounting directly in control panels and chassis where convenient jack connections are required. Applications include test outlets, remote equipment connections and headsets such as those used in telephone and telecommunications equipment.


| Pa | | | |
|-------------------|---|-------------------|----------------------|
| Panel Only | Assembly with Jacks Having Solder Lugs | # of Jacks | MT-Jax® Installed |
| JP072000 | - | None ¹ | |
| - | ⊘JP072S32A | 52 | MT332A |
| - | ⊘JP072S32B | 52 | MT332B |
| - | JP072S34B | 52 | MT334B |
| ♦ JP082000 | - | None ² | |
| - | ⊘JP082S32A | 64 | MT332A |
| - | ⊘JP082S32B | 64 | MT332B |
| - | ⊘JP082S34B | 64 | MT334B |
| ♦ JP092000 | - | None | |
| - | ⊘JP092S32A | 52 | MT332A |
| - | ⊘JP092S32B | 52 | MT332B |
| - | ⊘JP092S34B | 52 | MT334B |
| ♦JP102000 | - | None | |
| - | ⊘JP102S32A | 64 | MT332A |
| - | ⊘JP102S32B | 64 | MT332B |
| - | ⊘JP102S34B | 64 | MT334B |
| ♦JP112000 | - | None | |
| - | ♦JP112S32A | 52 | MT332A |
| - | ♦JP112S32B | 52 | MT332B |
| - | ♦JP112S34B | 52 | MT334B |
| ♦JP122000 | - | None | |
| - | ⟨JP122S32A | 64 | MT332A |
| - | ⊘JP122S32B | 64 | MT332B |
| - | ⊘JP122S34B | 64 | MT334B |


- * Panels with jacks having wire-wrapping terminals are approximately 10% higher in price. Contact Switchcraft.
- 1. Non-modularized equivalent is WEco #230A.
- Non-modularized equivalent is WEco #230A.
 Non-modularized equivalent is WEco #231A.

| Part Number | Description |
|-------------|---|
| JP9942 | Black module insert with four jack openings (less jacks). Includes two, #4-40 machine screws for mounting. |
| JP9922 | Black module insert with two jack openings (less jacks). Includes two, #4-40 machine screws for mounting. |
| JP9902 | Black module insert without holes. Includes two, #4-40 machine screws for mounting. Used where no jacks are needed. |


[♦] Special order only; contact Switchcraft.

LONG FRAME (1/4") MODULAR TWIN ROW JACK PANELS (continued)





LONG FRAME (1/4") MODULAR TWIN ROW JACK PANELS (continued)



JACK PANELS Long Frame (1/4") Modular 3 Row Jack Panels

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

LONG FRAME (1/4") MODULAR 3 ROW JACK PANELS

Four series of cross-connect jack panels are available in 19" and 23" widths. Individual modules are easily dismounted from the front. On special order, panels can be supplied with a variety of standard telephone jacks.

SERIES JP312000 AND JPD312000

2.655" x 19" size for console, rack or control panel mounting. Mounts 24 twin jacks and 24 single jacks. Openings are on .625" centers in each row. A twin plug fits jacks horizontally or vertically in same quad. Bottom row has 24 single jacks. Two Kwik®-Change designation strips are supplied. Series JPD31 has pre-drilled and countersunk holes for mounting vertical designation strips. See "ORDERING".

SERIES JP322000 AND JPD322000

Same as JP312000 and JPD312000, except 23" wide (includes 14 inserts which accommodate 28 twin jacks and 28 single jacks).

MODULE INSERTS

Available with 6 holes or blank faces. See "ORDERING" for colored modules.

ORDERING

Order basic assemblies by part number from table. On special order, various combinations of colored inserts mounted in basic panels, as well as many types of complete assemblies are possible. Provide complete details with your inquiry or order.

Standard mount panels are available with holes pre-drilled for vertical designation strips, Series DS320. Add prefix "D" to part number (JPD312000, JPD322000, etc.). Refer to "DESIGNATION STRIPS".

Mounting Screws: #6-32 **P10725** for jack mounting and #4-40 **P2435** for insert mounting can also be ordered separately. Contact Switchcraft.



SPECIFICATIONS

Panel and Designation Strips: Aluminum alloy, extruded. Black anodized per MIL-A-8625.


Module Insert: Molded plastic, matte finish. Black standard; white, red, green, blue or yellow available on special order.

Marking Strip: White matte finish plastic.

Designation Strip Cover: Extruded clear plastic.


Screws: #6-32 x 5/16" PHMS, for jack mounting; #4-40 x 1/2" phillips FHMS, for module insert mounting.

| Part Number | Description |
|-------------|--|
| JP312000 | 19" wide x 2.625" high panel with 12 black modules installed. Two, full width Kwik® -Change designation strips are included. |
| JPD312000 | Same as JP312000, except holes pre-drilled for mounting vertical designation strips at each side. |
| JP322000 | 23" wide x 2.625" high panel with 14 black modules installed. Two, full width Kwik® -Change designation strips are included. |
| JPD322000 | Same as JP322000, except holes pre-drilled for mounting vertical designation strips at each side. |



TT-JAX® (.173") JACK PANELS SERIES 1600, A1600, B1600, C1600







SERIES 1600 DOUBLE ROW JACK PANELS

Black anodized panel has four inserts (24 single jacks). Double row configuration accommodates 96 total jacks (48 pairs). Jack spacing eliminates cross-patching of adjacent circuits when twin plugs are used. Panel size: 1.75" x 19". Four, Kwik-Change® designation strips for circuit identification supplied.

SERIES A1600 DOUBLE ROW JACK PANELS

Similar to Series 1600, except mounts 104 jacks. Jacks are spaced on .312" centers for maximum jack density. Four, Kwik-Change® designation strips supplied.

SERIES B1600 THREE ROW JACK PANELS

2.625" x 19" panel size yields high density (144 jacks). Jacks are paired for single or twin plugs without cross-patching. Six, Kwik-Change® designation strips supplied.

SERIES C1600 THREE ROW JACK PANELS

Similar to B1600, except maximum jack density (156 jacks). Six, Kwik-Change® designation strips supplied.

SERIES 1700 TWIN ROW JACK PANELS

Standard 1.75" x 19" panel accepts 48 TT-Twin-Jax® jacks. Two, Kwik-Change® designation strips supplied.

SERIES B1700 THREE ROW JACK PANELS

Accepts 48 Tri-Jax® with alternate mounting centers to eliminate cross-patching between adjacent circuits. Panel size: 1.75" x 19". Two, Kwik-Change® designation strips supplied.

SPECIFICATIONS

SERIES 1600, A1600, B1600, 1700, B1700

Panel and Designation Strip: Aluminum alloy, extruded. Per QQ-A-200/8. Black anodized per MIL-A-8625C.

Black thermoplastic UL 94V-0.

Panel Insert: Thermoplastic polyester, UL 94V-0. **Marking Strip:** White matte finish plastic.

Designation Strip Cover: Extruded clear plastic.

ORDERING

- Part number tables list jack panels with the most commonly used jack circuits. Custom jack panels can be built on special order to OEM requirements. Typical special order features are:
 - Lamp jack with incandescent or LED lamps.
 - Solder lug or wire-wrapping terminals.
 - Pre-printed designation strips.
 - TT-Switch® switches with wide switching selection.
- 2. Contact Switchcraft for all special order items.

SPECIFYING NOTE:

Prefix letter "D" on part number indicates panels are drilled for mounting vertical designation strips on both ends. EXAMPLE - D1600, AD1632B, WCD1634B (vertical designation strips not included). Order DS321 for 1.734" high panels; DS350 for 2.069" high panels. See "Designation Strips" section.

The most commonly-used combinations of panels and jacks are listed on following page. 1600, A1600, B1600, C1600 panels can be assembled with many different "bantam type" jacks.



Bussing type terminals which allow you to buss jacks quickly and easily are available on special order.

DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm

JACK PANELS TT-JAX (.173") JACK PANELS

SERIES 1600 AND A1600

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

TT-JAX® (.173") JACK PANELS – SERIES 1600, A1600, B1600, C1600 (continued)

| Jack Data ¹ | Panel Data |
|------------------------|------------|
|------------------------|------------|

| Part Number | Part Number | Quantity | Dimensions | Mount |
|-------------|-------------|----------|------------|----------|
| 1600 | w/o Jacks1 | | | |
| D1600 | w/o Jacks1 | | | |
| 1632A | TT32A | | | |
| D1632A | TT32A | | | |
| 1632B | TT32B | | | |
| D1632B | TT32B | 96 | 19" | Standard |
| W1632B | WTT32B | | X | |
| WD1632B | WTT32B | | 1.734" | |
| 1634B | TT34B | | | |
| D1634B | TT34B | | | |
| W1634B | WTT34B | | | |
| WD1634B | WTT34B | | | |
| A1600 | w/o Jacks1 | | | |
| AD1600 | w/o Jacks1 | | | |
| A1632B | TT32B | | | |
| AD1632B | TT32B | 104 | | |
| A1634B | TT34B | | | |
| AD1634B | TT34B | | | |
| WA1634B | WTT34B | | | |
| | | | | |

SERIES B1600

WTT34B

WAD1634B

| Part Number | Part Number | Quantity | Dimensions | Mount |
|-------------|-------------|----------|--------------------|----------|
| B1600 | w/o Jacks1 | | | |
| BD1600 | w/o Jacks1 | | | |
| B1632B | TT32B | | | Standard |
| BD1632B | TT32B | 144 | 19" x 2.609" | |
| B1634B | TT34B | | | |
| BD1634B | TT34B | | | |
| WBD1634B | WTT34B | | | |
| B1650 | Note 2 | | | |
| BD1650 | Note 2 | | | |
| WB1650 | Note 3 | | | |
| WBD1650 | Note 3 | | | |

- Accepts indicated number of single TT-Jax®, TT-Switches®, TT-Lamp-Jax® or any combination.
- Three-row panel assembly with 96 TT34B Jax (top 2 rows); and 48 TT32B Jax (bottom row).
- 3. Same as Note 2 above, except jacks have wire-wrapping terminals.
- 4. Accepts 48 TT Twin-Jax®.
- 5. Accepts 48 TT Tri-Jax®.
- \Diamond Special order only; contact Switchcraft.

| Jack Data | Panel Data |
|-----------|------------|
|-----------|------------|

SERIES C1600

| Part Number | Part Number | Quantity | Dimensions | Mount |
|-------------|-------------|----------|------------|----------|
| C1600 | w/o Jacks1 | | | |
| CD1600 | w/o Jacks1 | | | |
| C1634B | TT34B | 156 | 19" x | Standard |
| CD1634B | TT34B | | 2.609" | |
| WC1634B | WTT34B | | | |
| WCD1634B | WTT34B | | | |

SERIES 1700

| Part Number | Part Number | Quantity | Dimensions | Mount |
|-------------|-------------|-----------|------------|----------|
| 1700 | w/o Jacks4 | | | |
| D1700 | w/o Jacks4 | | | |
| 1789 | TT89 | 48 | 19" x | Standard |
| D1789 | TT89 | Twin-Jax® | 1.734" | |
| W1789 | WTT89 | | | |
| WD1789 | WTT89 | | | |


SERIES B1700


| Part Number | Part Number | Quantity | Dimensions | Mount | |
|-------------|-------------|-------------|------------|----------|--|
| B1700 | w/o Jacks5 | | | | |
| BD1700 | w/o Jacks⁵ | | | | |
| B1795 | TT95 | | | | |
| BD1795 | TT95 | | " | | |
| WB1795 | WTT95 | 48 Tri-Jax® | 19" x | Standard | |
| WBD1795 | WTT95 | | 1.734" | | |
| B1796 | TT96 | | | | |
| BD1796 | TT96 | | | | |
| WB1796 | WTT96 | | | | |
| WBD1796 | WTT96 | | | | |


PANEL INSERTS

| Part Number | Insert Description | For Panels |
|---------------|-------------------------|--------------------|
| TT505 | Without jacks, 24 holes | A1600, B1600 |
| ♦TT506 | Blank | 1600, B1600, C1600 |
| ♦TT507 | Without jacks, 48 holes | 1700 |
| ♦TT508 | Blank | 1700 |
| ♦TT509 | Without jacks, 26 holes | A1600, C1600 |
| ♦TT511 | Without jacks, 72 holes | B1700 |


TT-JAX® (.173") JACK PANELS -SERIES 1600, A1600, B1600, C1600 (continued)









TT-JAX® (.173") JACK PANELS – SERIES 1600, A1600, B1600, C1600 (continued)





MODULAR TT-JAX® (.173") PANELS - BLANK SERIES TT51, TT53, TT56, TT59



Ten series of blank panels are available in 19" and 23" widths, standard or flush mounting, and double, twin or three row configurations. OEM's can order blank components and individual modules, jacks, switches and lamp jacks for production line assembly according to standard or special front panel configurations. Kwik-Change® designation strips are supplied with panels for custom legend marking.

Flush mounting styles can use extension legs (on special order), for stand-off mounting from front of rack. Contact Switchcraft for Mounting Bracket Kit K107.

SPECIFICATIONS

Panel and Designation Mounting Strip: Aluminum alloy, extruded per QQ-A-200/8. Black anodized per MIL-A-8265C. Marking Strip: Matte finish white plastic. Designation Strip Cover: Extruded clear plastic.

SPECIFYING NOTE: Part numbers in table are for blank panels only.

ORDERING

- 1. Order by part number from table
- Refer to jack section to specify other jacks and components.

| Series Number ¹ | Description ² |
|-------------------------------|--|
| TT51 | 19" double row standard mount panel. Mounts 96 single jacks on 24 modules. |
| TT53 | 19" three row standard mount panel. Mounts 48 Tri-Jax® jacks on 24 modules. |
| TT54 | 23" three row standard mount panel. Mounts 56 Tri-Jax® jacks on 28 modules. |
| TT55 | 19" double row flush mount panel. Mounts 96 single jacks on 24 modules. |
| TT56 | 23" double row flush mount panel. Mounts 112 single jacks on 28 modules. |
| TT58 | 23" three row flush mount panel. Mounts 56 Tri-Jax® jacks on 28 modules. |
| TT59 | 19" twin row standard mount panel. Mounts 48 TT Twin-Jax® jacks on 24 modules. |
| TT60 | 23" twin row standard mount panel. Mounts 56 TT Twin-Jax® jacks on 28 modules. |
| TT61 | 19" twin row flush mount panel. Mounts 48 TT Twin-Jax® jacks on 24 modules. |
| TT62 | 23" twin row flush mount panel. Mounts 56 TT Twin-Jax® jacks on 28 modules. |

- ♦ Special order only. Contact Switchcraft.
- Prefix TTD for standard mounting panels indicates predrilled holes for mounting "X Wide" vertical designation strips. See "Designation Strips" section.
- Each panel includes integral designation mounting strip, marking strips and clear plastic covers.
- 3. Contact Switchcraft for any special order items.

Inch (mm) **JACK PANELS**

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

TT MODULE INSERTS – SERIES TT91, TT92 AND TT93

SERIES TT91

SERIES TT92

SERIES TT-93



















TT91402 (black, 4 hole) (black, 2 hole)

TT91202

TT91002 (black, blank)

TT92402 (black, 4 hole)

TT92202 (black, 2 hole)

TT92002 (black, blank)

TT93602 (black, 6 hole)

TT93302 (black, 3 hole)

TT93002 (black, blank)

Module colors are black or gray (standard); red, green, blue, white and yellow available on special order. Each module has a matte finish front surface and includes two mounting screws (Switchcraft P2348).

SERIES TT91

Choice of blank, two- or four-hole modules for double row panels Series TT51, TT55 and TT56. The following components are used with Series TT91 modules:

- 1. Front mount TT-Jax[®] jacks.
- 2. Front mount TT-Switch® switches Series TT300FM and WTT420FM.
- 3. Front mount TT Lamp Jax® lamp jacks TT420FM and WTT420FM.

SERIES TT92

Blank, two- or four-hole modules for twin row panels Series TT59, TT60, TT61 and TT62. TT Twin-Jax® jacks are used with these modules.

SERIES TT93

Blank, three- or six-hole modules for three row panels Series TT53, TT54, TT57 and TT58. Tri-Jax® jacks are used with these modules.

SPECIFICATIONS

Module: Precision molded thermosetting plastic in colors. Mounting Screws: Black zinc, #3-48 x .312" flat head machine screws.

ORDERING

- 1. Order by part number from tables.
- 2. Contact Switchcraft for any special order items.

SPECIFYING NOTE: The part numbers listed on this page are for modules only. Refer to following page for specifying panel assemblies with components installed.

SERIES TT91 (For Double Row Panels)

| Color | Openings | | | | |
|--------|-----------------|-----------------|-----------------|--|--|
| | 4 | 4 2 Blank | | | |
| Red | TT91401 | ♦TT91201 | TT91001 | | |
| Black | ⊘TT91402 | ♦TT91202 | ♦TT91002 | | |
| Green | TT91403 | ♦TT91203 | TT91003 | | |
| Blue | TT91404 | ♦TT91204 | TT91004 | | |
| White | TT91405 | ♦TT91205 | TT91005 | | |
| Yellow | TT91408 | ♦TT91208 | TT91008 | | |
| Gray | TT91411 | TT91211 | TT91011 | | |

SERIES TT92 (For Twin Row Panels)

| Color | Openings | | | | |
|--------|-----------------|-----------------|----------|--|--|
| | 4 | 4 2 Blank | | | |
| Red | TT92401 | ♦TT92201 | TT92001 | | |
| Black | ♦TT92402 | TT92202 | ♦TT92002 | | |
| Green | TT92403 | ♦TT92203 | TT92003 | | |
| Blue | TT92404 | ♦TT92204 | TT92004 | | |
| White | TT92405 | ♦TT92205 | TT92005 | | |
| Yellow | TT92408 | ♦TT92208 | TT92008 | | |
| Gray | TT92411 | TT92211 | TT92011 | | |

SERIES TT93 (For Three Row Panels)

| Color | Openings | | | | |
|--------|-----------|-----------------|---------|--|--|
| | 4 2 Blank | | | | |
| Red | TT93601 | ♦TT93301 | TT93001 | | |
| Black | TT93602 | TT93302 | TT93002 | | |
| Green | TT93603 | ♦TT93303 | TT93003 | | |
| Blue | TT93604 | ♦TT93304 | TT93004 | | |
| White | TT93605 | ♦TT93305 | TT93005 | | |
| Yellow | TT93608 | ♦TT93308 | TT93008 | | |
| Gray | TT93611 | TT93311 | TT93011 | | |

♦ Special order only; contact factory for price and delivery.

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

MODULAR TT-JAX® (.173") JACK PANELS – SERIES TT5102000, TT5202000, TT5502000, TT5602000



Series TT5102000, TT5202000 (Typical)





Series TT5502000, TT5602000 (Typical) Shown w/mounting bracket K107 (not supplied).

SERIES TT5102000*

Modular double row, 1.75" high x 19" wide, standard mount. Supplied with 24 black modules, designation strips, and covers. Mounts 96 TT-Jax® single jacks, lamp jacks and/or switches.

SERIES TT51020001*

Modular double row, 1.75" high x 19" wide, standard mount. Supplied with 24 black modules, designation strips, and covers. Mounts 96 TT-Jax® single jacks, lamp jacks and/or switches. Comes supplied with cable tie bar.

SERIES TT5202000*

Similar to TT5102000, except 23" wide. Supplied with 28 black modules, designation strips, and covers. Mounts 112 TT-Jax® single jacks, jack lamps and/or switches.

SERIES TT5502000

Modular double row, 1.75" high x 19" wide, flush mount. Supplied with 24 black modules, designation strips, and covers. Panels can be mounted flush with rack/control panel surface, or use with extension legs for standoff mounting with easy access to rear of jacks for testing/monitoring. Mounts 96 TT-Jax® single jacks, lamp jacks and/or switches.

SERIES TT5602000

Similar to TT5502000, except 23" wide. Supplied with 28 black modules, designation strips, and covers. Mounts 112 TT-Jax® single jacks, jack lamps and/or switches.

ORDERING

- 1. Order part number from table
- 2. Contact Switchcraft for any special order items.
- 3. Separate components can be ordered.
- * Prefix TTD indicates panel is pre-drilled with countersunk holes for mounting "X-Wide" vertical designation strips. See "DESIGNATION STRIPS" section.


| | Jack Data | Panel Data | | | | |
|-------------------------|-------------------|------------------|-----|---------------|---------------|--|
| Part Number | Part Number | Part Number Qty. | | Mount | Modules | |
| TT5102000 | without jacks | 0 | | | | |
| ♦TT5102S31 | TT31FM | | | | | |
| ♦TT5102W31 | WTT31FM | | | | | |
| TT5102S32A | TT32AFM | | | | | |
| TT5102W32A | WTT32AFM | | | | | |
| TT5102S32B ² | TT32BFM | 96 | 19" | Stan- | 24 | |
| TT5102W32B | WTT32BFM | | | dard | (Black) | |
| ♦TT5102S33B | TT33BFM | | | | | |
| ♦TT5102W33B | WTT33BFM | | | | | |
| TT5102S34B ² | TT34BFM | | | | | |
| TT5102W34B | WTT34BFM | | | | | |
| TTD5102000 | without jacks | 0 | | | | |
| TTD5102S31 | | |] | | | |
| Through | Note ¹ | 96 | | | | |
| TTD5102W34B | | | | | | |
| TT5202000 | without jacks | 0 | | | | |
| TTD5202000 | without jacks | 0 | | | | |
| TT5202S31 | | | | | | |
| Through | Note ¹ | | | | | |
| TT5202W34B | | 112 | 23" | Stan- dard | 28 (Black) | |
| TTD520231 | | ''' | 20 | daru | (Diaok) | |
| Through | Note ¹ | | | | | |
| TTD5202W34B | | | | | | |
| TT552000 | without jacks | 0 | | | | |
| TT5502S31 | | | | | 24 | |
| Through | Note ¹ | 96 | 19" | Flush | (Black) | |
| TT5502W34B | | | | | | |
| TT5602000 | without jacks | 0 | | | | |
| TT5602S31 | | | | | 28 | |
| Through | Note ¹ | 112 | 23" | Flush | (Black) | |
| TT5602W34B | | | | | | |


- ♦ Special order only; contact Switchcraft for price and delivery.
- 1 Complete panel part number with jacks installed can be constructed as shown for Series TT51.
- 2. Add a "1" to part number to specify cable tie bar.

Inch (mm

MODULAR TT-JAX® (.173") JACK PANELS -SERIES TT5102000, TT5202000, TT5502000, TT56020000 (continued)







| | Jack Panel Dimensions - inch (mm) | | | | | |
|--------------|-----------------------------------|--------------|--------------|----------------|--|--|
| Series | | | | | | |
| Number | Α | В | С | D | | |
| TT51 | 19 (482.6) | 18.3 (465.1) | 1.013 (25.7) | - | | |
| ♦TT52 | 23 (584.2) | 22.3 (566.7) | 1.648 (41.9) | - | | |
| TT55 | 19 (482.6) | 18.3 (465.1) | 1.013 (25.7) | 17.125 (435) | | |
| TT56 | 23 (584.2) | 22.3 (566.7) | 1.648 (41.9) | 21.125 (536.6) | | |

 $[\]Diamond$ Special order only; contact Switchcraft for price and delivery.

TT-JAX® (.173") TWIN ROW AND THREE ROW JACK PANELS




Series TT5902000



Series TT6102000



Series TT5302000, TT5402000 (Typical)



SERIES TT5902000*

Modular twin row, 1.75" high x 19" wide, standard mount. Supplied with 24 black modules, designation strips, and covers. Mounts 48 TT Twin-Jax® twin jacks.

SERIES TT6002000*

Similar to TT5902000, except 23" wide. Supplied with 28 black modules, designation strips, and covers. Mounts 56 TT Twin-Jax® twin jacks.

SERIES TT6102000

Modular twin row, 1.75" high x 19" wide, flush or standoff mount. Supplied with 24 black modules, designation strips, and covers. Mounts 48 TT Twin-Jax® twin jacks.

SERIES TT6202000

Similar to TT6102000, except 23" wide. Supplied with 28 black modules, designation strips, and covers. Mounts 56 TT Twin-Jax® twin jacks.

SERIES TT5302000*

Modular three row, 1.75" high x 19" wide, standard mount. Supplied with 24 black modules, designation strips, and covers. Designed for LINE, EQUIP and MONITOR patch connections. Mounts 48 Tri-Jax® triple jacks.

SERIES TT5402000*

Similar to TT5302000, except 23" wide. Supplied with 28 black modules, designation strips, and covers. Mounts 56 Tri-Jax® triple jacks.

SERIES TT5702000

Modular three row, 1.75" high x 19" wide, flush or standoff mount. Supplied with 24 black modules, designation strips, and covers. Mounts 48 Tri-Jax® triple jacks.

SERIES TT5802000

Similar to TT5702000, except 23" wide. Supplied with 28 black modules, designation strips, and covers. Mounts 56 Tri-Jax® triple jacks.

ORDERING

- 1. Order part number from table
- 2. Contact Switchcraft for any special order items.
- *Prefix TTD indicates panel is pre-drilled with countersunk holes for mounting "X-Wide" vertical designation strips. See "**DESIGNATION STRIPS**" section.

| | Jack Data | | Panel Da | ıta | |
|--------------------------|----------------------|------|----------|---------------|---------------|
| Part Number | Part Number | Qty. | Width | Mount | Modules |
| TT-000000 | | | | | |
| TT5902000 | without jacks | 0 | | | |
| TT5902S89 | TT89FM | 48 | | | |
| TT5902W89 | WTT89FM | _ | 19" | | |
| TTD5902000 TTD5902S89 | without jacks | 0 | | | |
| TTD5902W89 | TT89FM WTT89FM | 48 | | | |
| TT6002000 | WITOSFIVI | | | Stan- dard | 24 (Black) |
| TTD6002000 | without jacks | 0 | | duru | (Black) |
| TT6002S89 | | | 1 | | |
| TT6002W89 | Note ¹ | 56 | 23" | | |
| TTD6002S89 | | | 1 | | |
| TTD6002W89 | Note ¹ | 56 | | | |
| TT6102000 | None | 0 | | | |
| TT6102S89 | | | 19" | | |
| TT6102W89 | Note ¹ | 48 | | | |
| TT6202000 | without jacks | 0 | | Flush | 28 |
| TT6202S89 | , | | 23" | | (Black) |
| TT6202W89 | Note ¹ | 56 | | | |
| TT5302000 | without jacks | 0 | | | |
| ♦TT5302S95 | TT95FM | | 1 | | |
| TT5302W95 | WTT95FM | 10 | 19" | | |
| ♦TT5302S96 | TT96FM | 48 | | Stan- dard | 24 |
| TT5302W96 | WTT96FM | | | | (Black) |
| TTD5302000 | without jacks | 0 | 1 | | |
| TTD5302S95 | | | | | |
| Through | Note ² | 48 | | | |
| TTD5302W96 | | | | | |
| TT5402000 | without jacks | 0 | | | |
| TTD5402000 | without jacks | | | | |
| TT5402S95 | Note ² | | | | |
| Through | Through | | | | |
| TT5402W96 | | 56 | 23" | Stan- dard | 28 (Plack) |
| TTD5402S95 | Note ² | | | ualu | (Black) |
| Through | | | | | |
| TTD5402W96 | | | | | |
| TT5702000 | without jacks | 0 | - | | |
| TT5702S95 | | 48 | 19" | Flush | 24 |
| Through | Note ² | 10 | | 1 10011 | (Black) |
| TT5702W96 | data a . ot de edice | | | | |
| TT5802000 TT5802S95 | without jacks | 0 | - | | |
| Through | Noto2 | FC | 00" | Elizah | 20 |
| | Note ² | 56 | 23" | Flush | 28 (Black) |
| TT5802W96 | | | | | (Diaon) |

- ♦ Special order only; contact Switchcraft for price and delivery.
- Complete panel part number with jacks installed can be constructed as shown for Series TT59 or TTD59.
- Complete panel part number with jacks installed can be constructed as shown for series TT53.

(mm)

JACK PANELS TT-JAX® (.173") TWIN ROW AND THREE ROW JACK PANELS


PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

TT-JAX® (.173") TWIN ROW AND THREE ROW JACK PANELS (continued)




Series TT5902000 and TT6002000 (Typical)




| | Jack Panel Dimensions - inch (mm) | | | | | |
|--------|-----------------------------------|--------------|--------------|----------------|--|--|
| Series | | | | | | |
| Number | Α | В | С | D | | |
| TT59 | 19 (482.6) | 18.3 (465.1) | 1.013 (25.7) | - | | |
| TT60 | 23 (584.2) | 22.3 (566.7) | 1.648 (41.9) | - | | |
| TT61 | 19 (482.6) | 22.3 (566.7) | 1.013 (25.7) | 17.125 (435) | | |
| TT62 | 23 (584.2) | 22.3 (566.7) | 1.648 (41.9) | 21.125 (536.6) | | |

Series TT6102000 and TT6202000 (Typical)




Series TT5302000 and TT5402000 (Typical)



| | Jack | Panel Dimens | sions - inch (ı | mm) | | |
|--------------|------------|--------------|------------------------------|--------|---------|--|
| Series | | | | | | cont. |
| Number | Α | В | С | |) | |
| TT53 | 19 (482.6) | 18.3 (465.1) | 1.013 (25.7) | | • | ATTACHMELE STANDOFFS 63 Not Supplied |
| TT54 | 23 (584.2) | 22.3 (566.7) | | | - | \$ \$100 MER. |
| TT57 | 19 (482.6) | 22.3 (566.7) | | | | |
| ◊TT58 | 23 (584.2) | 22.3 (566.7) | 1.648 (41.9) | 21.125 | (536.6) |) |
| | | | s TT5702000 02000 (Typica | | 1 1 127 | ASS. ASS. |

TT-JAX® (.173") CONNECTORIZED JACKFIELDS – SERIES TT, 2-WIRE, 4-WIRE, 6-WIRE





2-WIRE TT-CONNECTORIZED JACKFIELDS, SERIES TT

Contains 48, 2-wire circuits. Arrangements include: LINE-DROP or Signal E/M, or LINE-DROP-MON. Available with MONITOR jack row. On rear panel, LINE connectors are receptacles and DROP connectors are plugs. LINE and DROP circuits may be isolated from each other for separate monitoring. On special order, 48 circuits LINE/COMBINATION DROP/MON or 96 circuits, LINE/DROP or Signal E/M may be specified.

2-WIRE TT-CONNECTORIZED PC JACKFIELD, SERIES TTPC

Same as 2-Wire TT-connectorized jackfields above, except all connections are machine-soldered on a double-sided PC board instead of hand wired.

4-WIRE TT-CONNECTORIZED JACKFIELDS, SERIES TT

4-Wire jackfields have 24, 4-wire circuits for MOD-DEM/EQ IN-EQ OUT/MON patching, or may be used for other 4-wire patching applications. Can be supplied with or without MONITOR jack row. On rear panel, MOD AND EQ IN connectors are receptacles and DEM and EQ OUT connectors are plugs.

6-WIRE TT-CONNECTORIZED JACKFIELDS, SERIES TT

6-Wire jackfields contain 48, 6-wire circuits for MOD-DEM/EQ IN EQ OUT/MON/SIG LINE/SIG EQ patching with toll test boards. Available with or without MONITOR jack row. On rear panel, MOD, EQ IN and SIG LINE connectors are receptacles and DEM, EQ OUT and SIG EQ connectors are plugs. The following can be specified on special order: 12 circuits, DEM-MOD/EQ IN-EQ OUT/MON/SIG E/M; 48 circuits, signal E/M leads separated; 48 circuits for D3 channel banks.

ORDERING

- 1. Order by part number from tables.
- 2. Contact Switchcraft for any special order items.

JACK PANELS TT-JAX® (.173") CONNECTORIZED JACKFIELDS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

TT-JAX® (.173") CONNECTORIZED JACKFIELDS -SERIES TT, 2-WIRE, 4-WIRE, 6-WIRE (continued)



SPECIFICATIONS

Panel and Integral Designation Strip: Aluminum alloy, extruded per QQ-A-200/8. Black anodized per MIL-A-8265. Modules: Precision-molded thermosetting plastic. Black

standard. Other colors on special order.

Mounting Screws: Black zinc, #3-48 x 312" flat head machine screw.

TT-Jax® Jacks: See jacks section for TT-Jax® specifications.

Marking Strip: Matte finish white plastic.

Vertical Designation Strip: Extruded aluminum, black

anodized.

Back Frames: Cold rolled steel, zinc-plated with iridescent tarnish-resistant finish.

Screws, Nuts and Lockwashers: Steel, clear iridite

tarnish-resistant finish over zinc-plating.

Connectors: 50-pin micro/pierce plugs and receptacles.


Cable Tie Bar: Aluminum hexagon alloy. 6061-T6, clear iridite

finish per MIL-C-5541 (not hinged versions only).

Cables: 25 pair, 24 AWG solid copper wire, tinned and annealed, covered with insulating grade thermoplastic jacket.

Cable Ties: Thermoplastic, locking-non-releaseable,

30 pounds minimum loop tensile strength.




TT-JAX® (.173") CONNECTORIZED JACKFIELDS (continued)



PART NUMBERS

 Compose part numbers from data below to specify your jackfield...or use the table to order popular jackfields. **SPECIFYING NOTE:** Any jackfield can be manufactured with AMP CHAMP connectors. Contact Switchcraft.




TYPICAL PART NUMBERS

| O MUDE LACKEIEL DO | |
|--------------------|---|
| 2-WIRE JACKFIELDS | |
| Part Number | Description |
| TT2W48VCF1 | Hinged front panel. |
| TT2W48VCN1 | Front panel NOT hinged. |
| TT2W48MCF1 | Same as TT2W48VCF1, except with MONITOR jack row. |
| TT2W48MCN1 | Same as TT2W48VCN1, except with MONITOR jack row. |
| 4-WIRE JACKFIELDS | |
| Part Number | Description |
| TT4W24MCF1 | Hinged front panel with MONITOR jack row. |
| TT4W24MCN1 | Front panel NOT hinged with MONITOR jack row. |
| TT4W24VCF1 | Same as TT4W24MCF1, except no MONITOR jack row. |
| TT4W24VCN1 | Same as TT4W24MCN1, except no MONITOR jack row. |
| 6-WIRE JACKFIELDS | |
| Part Number | Description |
| TT6W48MCF1 | Hinged front panel with MONITOR jack row. |
| 16J1055 | Hinged front panel with MONITOR jack row. |
| TT6W48MCN1 | Front panel NOT hinged with MONITOR jack row. |
| TT6W48VCF1 | Same as TT6W48MCF1, except no MONITOR jack row. |
| TT6W48VCN1 | Same as TT6W48MCN1, except no MONITOR jack row. |


TT-JAX® (.173") CONNECTORIZED JACKFIELDS (continued)




TYPICAL CIRCUIT ARRANGEMENTS - 2-WIRE




TYPICAL CIRCUIT ARRANGEMENTS - 4-WIRE







TYPICAL CIRCUIT ARRANGEMENTS - 6-WIRE



TT-JAX® (.173") CONNECTORIZED JACKFIELDS (continued)









TT-JAX® (.173") CONNECTORIZED JACKFIELDS (continued)










TT-JAX® (.173") CONNECTORIZED JACKFIELDS (continued)










| | | (| CONNE | TABLE | | | |
|-----------|------------|------|-------|--------------|---------------|------|---|
| TO PLUG | CONNECTO | R | PIN | TO RECEPTAGE | CLE CONNE | CTOR | P |
| | T | TI | 26 | | MOD. | т | 1 |
| CKT. I | DEM. | RI | 1 | CKT. I | MICID. | R | Г |
| | REPEATED | | | R | EPEATED | | |
| | T | TI | 49 | | MOD. | T | Г |
| CKT, 24 | DEM. | P(I) | 24 | CKT. 24 | MOD. | R | Γ |
| | 200 | TI | 26 | | MOD. | Ŧ | Г |
| CKT. 25 | DEM. | RI | 1 | CKT. 25 | mou. | R | Γ |
| | REPEATED | | | - | EPEATED | | _ |
| CKT. 48 | DEM. | Τı | 49 | CKT, 48 | MOD. | т | Γ |
| UN 1. 40 | UEM. | RI | 24 | UN 1. 40 | | R | Ī |
| ave . | F0 017 | T | 26 | av= . | F0 W | TI | Γ |
| CKT. I | EQ. OUT | R | T | CKT. I | EQ. IN | R) | Ī |
| | REPEATED | | | F | EPEATED | | • |
| ~ | EQ. OUT | Т | 49 | ~~~ | | TI | Γ |
| CKT. 24 | EQ. 001 | R | 24 | CKT, 24 | EQ.IN | Ri | T |
| CKT. 25 | EQ. OUT | т | 26 | CKT. 25 | EQ. IN | Tì | Γ |
| UN 1. 20 | E4.001 | R | 1 | J W | Da. = 1 | RI | Γ |
| | REPEATED | | | F | EPEATED | | |
| CKT. 48 | EQ. QUT | T | 49 | CKT. 48 | EQ. IN | TI | Γ |
| UN 1. 40 | 52.001 | R | 24 | CK1. 40 | Ca. 114 | Ri | Γ |
| CKT. I | SIG. EQ. | É | 26 | CKT. I | SIG. LINE | E | Γ |
| CK I. I | 310. EQ. | М | | L CK I. I | SIG. LINE | M | ŀ |
| | REPEATED | | | F | EPEATED | | |
| CKT. 24 | SIG. EQ | E | 49 | CKT, 24 | SIG. LINE | € | L |
| UM 1. 2-7 | Gro. EQ | M | 24 | | Service Comme | M | L |
| CKT 25 | SIG. EQ | Ε | 26 | CKT. 25 | SIG. LINE | E | L |
| CAL ZO | SIG. EM | М | 1 | L CR 1. 25 | ore. Line. | M | Ĺ |
| | REPEATED | | | F | EPEATED | | |
| CKT. 48 | SIG. EQ. | £ | 49 | CKT, 48 | SIG. LINE | E | L |
| Un 1. 70 | J 543. EU. | M | 24 | w | | M | Γ |


TT-JAX® (.173") CONNECTORIZED JACKFIELDS





TT-Jax® (.173") CONNECTORIZED JACKFIELDS





TT® LAMPS AND JEWEL ASSEMBLIES





SERIES TT-450 LAMPS

Red LED and series dropping resistor are molded into compact cartridge with bi-pin terminals for use with TT Lamp-Jax® lamp jacks. Colored bezels are molded in for color coding of functions; colors are black, red, green, white and yellow. On special order, blue or other colors are available.

Standard voltages are 6, 24 and 48 V (DC only). No tools are required for lamping/relamping. Simply slip TT-LED into lamp jack with (+) terminal up. If it doesn't light, remove it, rotate it 180°, and reinsert it into jack.

SPECIFICATIONS

Housing: Molded black plastic. Bezel: Molded plastic in colors.


LED: Red illumination.


Pins: T-1 3/4 bi-pin configuration.

| Part | | Bezel | Part | | Bezel |
|---------|---------|-------|----------|---------|--------|
| Number | Voltage | Color | Number | Voltage | Color |
| TT45106 | 6 | | ♦TT45406 | 6 | |
| TT45124 | 24 | Red | ♦TT45424 | 24 | Blue |
| TT45148 | 48 | | ♦TT45448 | 48 | |
| TT45206 | 6 | | TT45506 | 6 | |
| TT45224 | 24 | Black | TT45524 | 24 | White |
| TT45248 | 48 | | TT45548 | 48 | |
| TT45306 | 6 | | TT45806 | 6 | |
| TT45324 | 24 | Green | TT45824 | 24 | Yellow |
| TT45348 | 48 | | TT45848 | 48 | |

ORDERING

- 1. Order by part number from table.
- 2. For special order items, such as other LED colors, voltages, lamps with 25% reduced power consumption, etc., contact Switchcraft.





FLASHING/STEADY ON LEDS

Yellow, green and red LEDs are 2-pin cartridge plug-ins which operate from a 48 VDC supply. When 48 V is applied, LED flashes for 30 seconds, then changes to steady "On" condition.


SPECIFICATIONS

Body: Thermoplastic, UL 94V-0 rated. LED Colors: Yellow, green or red.

| Part Number | Description | |
|-------------|----------------------------|--|
| 15J9068 | Red flashing/continuous | |
| 15J9076 | Yellow flashing/continuous | |
| 15J9077 | Green flashing/continuous | |
| 15J9078 | Amber flashing/continuous | |

TT-JEWEL ASSEMBLY







Panel with TT-Jewel Assemblies and TT-Switches installed

Jewel assemblies use bi-pin lamp and act as lighted jewel and lamping/relamping tool. Simply slip bi-pin lamp in brass collar and insert lamp with pins in vertical plane. Lamp automatically seats properly. Jewel is molded plastic in colors; sleeve is brass.

| Part Number | Color | Part Number | Color | |
|-------------|-------|--|--------|--|
| TT401 | Red | TT408 | Yellow | |
| TT403 | Green | TT413 | Amber | |
| TT404 | Blue | TT510 | Black* | |
| TT405 | White | *Used as hole plug where no jack is installed. | | |

LAMPS

| Part Number | Description |
|-------------|---|
| P2290 | 6.3 V, GE No. 7377. |
| P2315 | 6.3 V, GE No. 7381. Avg. life: 50K hrs. @ 200 mA. |
| P2316 | 28 V, GE No. 7387. Avg. life: 25K hrs. @ 40 mA. |
| P2456 | 24 V, GE No. 7001. |

LONGFRAME SWITCHBOARD SWITCHES

SERIES 11000 and 11200

Premium quality, long frame switches, designed especially for jack panel mounted switching. Standard actuations are push-lock/pull-release, 2-position turn button and 3 position turn button. Many contact forms available. Mounts in Switchcraft Jack Panels Series 1200, 1400, 2400, 2600, 2800, modular JP® jack panels, and other standard telephone jack panels. Part numbers in table indicate "A" frame. For same switch with "C" frame, add prefix "C" to part number. Many circuit forms not shown in tables are available on special order. Long leaf springs have no forms at point of flexing, which insures long life. Welded crossbar palladium contacts rated at 2A 200W maximum are standard. Fine silver (for higher currents) or gold alloy (dry circuit to 1A) contacts are available on special order. Contact Switchcraft.

SPECIFICATIONS

Frame, Screws and Twin Nut: Steel, plated.

Springs, Pressure Plate and Terminals: Copper alloy.

Solder lugs are tin-dipped.

Contacts: Welded crossbar palladium are standard. Fine silver or gold alloy are available on special order.


Insulation: Rigid plastic. Extruded plastic tubing through stack.


Knob: Molded black plastic. Turn-key type faced with white arrow.

Bushing: Copper alloy, nickel-plated.

ORDERING

- 1. Order by part number from table.
- 2. For special order items, contact Switchcraft.





| Part Nu | mbers | Circuit |
|---------|-----------|---------|
| Locking | Momentary | Circuit |

PUSHBUTTONS - SERIES 11000


| ◊11001L | ♦11001 | 1-A |
|-----------------|----------------|-----|
| ⊘11002L | ⊘11002 | 1-B |
| 11003L | 11003 | 1-C |
| ⊘W11003L | ⊘W11003 | 1-0 |
| ♦11003DL | ⊘11003D | 1-D |
| ♦11004L | ◊11004 | 2-A |
| ⊘11005L | ⊘11005 | 2-B |
| 11006L | 11006 | 2-C |
| ♦W11006L | ⊘W11006 | 2-0 |
| ♦11006DL | ⊘11006D | 2-D |
| ⊘11008L | ⊘11008 | 4-A |
| ⊘11009L | ⊘11009 | 3-C |
| ⊘11012L | 11012 | 4-C |
| ⊘W11012L | ⊘W11012 | 4-0 |
| | | |

TURN BUTTONS - SERIES 11200

| ⊘11201 | 1-A |
|----------------|---|
| | 1-B |
| 11203 | 4.0 |
| ⊘W11203 | 1-C |
| ⊘11203D | 1-D |
| ♦11204 | 2-A |
| ♦11205 | 2-B |
| 11206 | 2-C |
| ⊘W11206 | 2-0 |
| ♦11206D | 2-D |
| | 4-A |
| ⊘11209 | 3-C |
| 11212 | 4-C |
| ⊘W11212 | 4-0 |
| | ↑11202 11203 ♦W11203 ♦11203D ♦11204 ♦11205 11206 ♦W11206 ♦11206D ♦11208 ♦11209 11212 |

[♦] Special order only; contact Switchcraft.

Mounting Screws: #6-32, P10725, can be ordered separately. Contact Switchcraft. (Screws not supplied with switches.)



DUMMY PLUGS AND HOLE PLUGS










When inserted into a standard size telephone jack, the dummy plug actuates springs like a normal plug, except no signal is conducted through since the plug is made of non-conducting plastic. Dummy plugs can also be used to plug-up unused jacks to prevent accidental insertion of an incorrect plug.

SERIES 491: 3-conductor with .206" diameter finger. Mates with MT342B and MT344B MT-Jax®, Series M Hi-D Jax®, and other standard telephone jacks having .21" inside diameter

SERIES 492: 3-conductor with .25" diameter finger. Mates with 3-conductor MT-Jax® and Series M Hi-D Jax®, and other standard telephone jacks have .25" inside diameter sleeves.

SERIES 493: 2-conductor with .25" diameter finger. Mates with 2-conductor MT-Jax®, Series M Hi-D Jax®, and other standard telephone jacks having .25" inside diameter sleeves.


| Part Number | Descri | ption | ngeable h | |
|----------------|------------|-------|--------------|-------|
| Number | Conductors | Color | WEco | Trimm |
| 49101 | 3 | Red | _ | _ |
| 49102 | 3 | Black | _ | _ |
| 49105 | 3 | White | _ | _ |
| 49201 | 3 | Red | 258F | 558D |
| 49202 | 3 | Black | 258C | 558C |
| 49205 | 3 | White | 258E | 558E |
| 49301 | 2 | Red | 165F | 556D |
| 49302 | 2 | Black | 165C | 556C |
| 49305 | 2 | White | 165E | _ |





PLASTIC HOLE PLUG Hole Plug P1801

Used to seal off unused holes in jack panels, Series 1200, 1400, 2400, 2600 and JP012000 through JP122000. Constructed of dimensionally stable molded black plastic.



DIMENSIONS ARE FOR REFERENCE ONLY



TT® (BANTAM) CIRCUIT GUARD PLUGS

APPLICATION

Circuit guard plugs snap into TT-Jax® (bantam) jacks eliminating accidental or unauthorized insertion of a plug into a critical circuit. The circuit guards plugs do not actuate the jack springs. These plugs seal the jack bushing and provide an additional means of circuit identification.

Circuit guard plugs are available in three different designs: Series TT512, Series TT513 and Series TT514. All three designs are molded thermoplastic and are available in the following colors: red, black, green, blue, white or yellow.

SERIES TT512

TT512 circuit guard plugs cover an individual jack opening and insert to an virtually flush position with the front panel.

SERIES TT513

TT513 circuit guard plugs are similar to the Series TT512 except the button extends .219" from the front of the panel for easier removal.

SERIES TT514

TT514 circuit guard plugs cover both the IN and OUT jacks of two adjoining circuits while leaving the monitor jacks exposed for circuit testing. The four jack circuit guard plugs also include a matte finish white plastic marking strip and a clear extruded plastic window for additional designation.


SPECIFICATIONS

TT512 and TT513: Molded thermoplastic in colors. TT514: Base: Molded thermoplastic in colors. Marking Strip: Matte finish white plastic.

Cover: Clear extruded plastic.


ORDERING

- 1. Order by part number from table.
- 2. Contact Switchcraft for any special order items.



| Part Number | Part Number | Part Number | Color |
|-------------|-------------|-------------|--------|
| TT5121 | TT5131 | TT5141* | Red |
| TT5122 | TT5132 | TT5142* | Black |
| TT5123 | TT5133 | TT5143* | Green |
| TT5124 | TT5134 | TT5144* | Blue |
| TT5125 | TT5135 | TT5145* | White |
| TT5128 | TT5138 | TT5148* | Yellow |

^{*}Includes base, marking strip & cover.



JACK PANELS Miniature, Dummy Plugs, Hole Plugs

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MINIATURE, DUMMY PLUGS, HOLE PLUGS



Terminating, dummy and looping plugs are designed for use with Tini-Telephone® Jacks. TT-Phone Plugs are also recommended for use on other miniature telephone jacks with same bushing inside diameter and compatible tip and/or ring spring configurations.

TT-TERMINATING PLUGS

TT-Phone Plug terminating plugs are used to terminate a circuit with a specific resistive load. A precision 1/2 watt, \pm 1% resistor is molded into the handle of each terminating plug. See "PLUG SCHEMATICS" for resistor wiring. Resistance value is marked on plug handle. Other resistance values are available on special order.

TT-DUMMY PLUGS

TT-Phone Plug dummy plugs are designed to be inserted into phone jacks to actuate shunt and isolated switching circuits.

TT-LOOPING PLUGS

TT-Phone Plug looping plugs are used to loop or patch adjacent jack circuits. See "PLUG SCHEMATICS" for wiring.

TT-HOLE PLUG

TT-Hole Plugs are used to close off unused openings in all Switchcraft TT-Jack Panels. Molded of black plastic with brass sleeve

ORDERING

- 1. Order by part number from table.
- 2. Contact Switchcraft for any special order items.

SPECIFICATIONS

Series TT200 Tip Rod, Ring and Sleeve:

Brass per QQ-B-626.


Handle: Molded PVC, ivory or black.

Series TT515: Molded of dimensionally stable plastic

in black, red or white.

| Part No. | Description | Schematic | Color |
|---------------|--------------------------------------|-----------|-------|
| ♦TT201 | 2-conductor terminating-135 Ω | 1 | Gray |
| ♦TT202 | 2-conductor terminating-600Ω | 1 | Gray |
| TT203 | 3-conductor terminating-135 Ω | 2 | Gray |
| TT204 | 3-conductor terminating-600 Ω | 2 | Gray |
| TT205 | 2-conductor dummy | 5 | Gray |
| TT206 | 3-conductor dummy | 6 | Gray |
| ♦TT207 | 2-conductor twin looping | 3 | Gray |
| TT208 | 3-conductor twin looping | 4 | Gray |
| TT209 | 2-conductor twin dummy | 5 | Ivory |
| TT210 | 3-conductor twin dummy | 6 | Ivory |
| TT510 | Hole Plug | - | Black |
| TT5151 | 2- or 3-conductor dummy | _ | Red |
| TT5152 | 2- or 3-conductor dummy | _ | Black |
| TT5155 | 2- or 3-conductor dummy | _ | White |

[♦] Special order only; contact Switchcraft for price and delivery.



DESIGNATION STRIPS



Designation strips with protective covers are supplied with all tini-telephone® jack panels, jackfields and certain standard jack panels. Replacement kits and individual parts are also available. Legends can be marked in pencil, ink, or lettering transfers. Kwik-Change® is the name of all horizontal strips. See illustration.

Three types of designation strips are available as accessories:

- 1. Kwik-Change single height.
- 2. Kwik-Change double height.
- 3. X-Wide vertical.

KWIK-CHANGE® DESIGNATION STRIPS (SINGLE HEIGHT)

Two types of single height designation strips are available:

- 1. SERIES 1600, A1600, B1600, C1600, 1700, B1700, 1400300, 2600300, JP012000 through JP122000
 - · Extruded aluminum mounting strip
 - · Four mounting screws
 - Marking strips
 - Clear plastic strip covers

Mounting strips are fastened with four mounting screws provided. Marking strip slides into the clear plastic cover, and cover is snapped into place on the mounting strip. Legends can be marked in pencil, ink, lettering transfers, typewriter, etc.

SPECIFICATIONS

(Used on panels 1600, A1600, B1600, C1600, 1700, B1700)

Mounting Strip: Extruded aluminum black anodized

Cover: Clear extruded plastic.

Marking Strip: White matte finish plastic.

Screws: Copper alloy, plated.

(Used on panels 1400300, 1600300)

Mounting Strip: Aluminum alloy, extruded, black anodized.

Cover: Clear extruded plastic.


Marking Strip: White matte finish plastic.


Screws: Steel, plated.

SERIES TT51 through TT62, TT-Connectorized (2-, 4- and 6-Wire), JP012000 through JP122000, TTPC and DSX panels. Mounting strips are extruded as part of the panel. Otherwise, use is the same as above.

ORDERING

Order by part number from table.





DESIGNATION STRIPS (continued)

SINGLE HEIGHT DESIGNATION STRIPS

| Dest No | B. a. antartia a | E D I. |
|----------|--|---|
| Part No. | Description | For Panels |
| TT501 | Kits (single height) includes: 1-mounting strip (8.375" long) 1-cover 1-marking strip sheet (5 strips per sheet) 4-mounting screws | 1600, 1700 (Alternate spacing) |
| TT502 | Marking Strip sheet (used with Kit TT501 & TT521) | _ |
| TT503 | Cover (used with Kit TT501 and TT504) | _ |
| TT504 | Kits (single height) includes: 1-mounting strip (8.375" long) 1-cover 1-marking strip sheet (5 strips per sheet) 4-mounting screws | A1600, C1600 (Continuous spacing) |
| TT519 | Kit (single height) includes: 2-covers (9.61" long) 1- marking strip sheet (5 strips per sheet) | TT52, TT54 TT56, TT58 TT60, TT62 (23" Panels) |
| TT520 | Marking strip sheet (used with Kit TT519) | _ |
| TT521 | Kit (single height) includes: 2-covers (8.25" long) 1- marking strip sheet (5 strips per sheet) | TT51, TT53 TT55, TT57 TT59, TT61, Connectorized Jackfields (2-, 4- and 6 wire) |

| Part No. | Description | For Panels |
|----------|--|------------------------------------|
| DS301 | Kit (single height) includes: 1-mounting strip (17" long) 1-cover 1-marking strip sheet (5 strips per sheet) 4-mounting screws | 1400301, 2600301 |
| DS302 | Cover (used with Kit DS301) | _ |
| DS303 | Marking strip sheet (used with Kit DS301 and DS316). | _ |
| DS306 | Marking strip sheet (used with Kit DS307 and DS308). | - |
| D\$307 | Kit (single height) includes: 2-covers (16.5" long) 1-marking strip sheet (5 strips per sheet) | JP012000, JP032000, JP052000 |
| D\$308 | Kit (single height) includes: 2-covers (19.5" long) 1-marking strip sheet (5 strips per sheet) | JP022000, JP042000, JP062000 |
| DS316 | Kit (single height) includes: 2-covers (16.25" long) 1- marking strip sheet (5 strips per sheet) | JP072000 JP092000, JP112000 |
| DS317 | Marking strip sheet (used with Kit DS318). | - |
| DS318 | Kit (single height) includes: 2-covers (20" long) 1- marking strip sheet (5 strips per sheet) | JP082000 JP102000, JP122000 |

KWIK-CHANGE® DESIGNATION STRIPS (DOUBLE HEIGHT)

Double height strips allow larger legends. Can be factory installed on Series 1600, B1600, 1700 and B1700 panels, or may be ordered separately for customer installation.

- Series 1600/B1600: Four strips can be mounted, two above each row of jack openings.
- Series 1700: Two strips can be mounted, two above or two below (special order) the double row of jack openings.
- Series B1700: Two strips can be mounted (side-by-side) above top row of jacks.

NOTE: When TT516 kits are mounted above top row of jacks on Series 1600, B1600 and B1700, strips will overhang top edge of panel by .156 inches For most applications, the strips help seal the normal opening between adjacent panels. Series B1700 panel mounting screws may have to be loosened to facilitate removal of the panel above it in this type of installation.

SPECIFICATIONS


Mounting Strip: Black thermoplastic UL 94V-0.

Cover: Clear plastic.

Marking Strip: Matte finish white plastic. **Mounting Screws:** Copper alloy, plated.

ORDERING


- 1. Order by part number from table.
- To order double height strips installed on panels, contact Switchcraft.



 $Y = \frac{\text{Inch}}{(\text{mm})}$

DIMENSIONS ARE FOR REFERENCE ONLY

KWIK-CHANGE® DESIGNATION STRIPS (DOUBLE HEIGHT)



DOUBLE HEIGHT DESIGNATION STRIPS

| Part No. | Description | For Panels |
|----------|--------------------------------|------------|
| DS311 | Kit (double height) includes: | 2600310, |
| | 1-mounting strip (17" long) | 1400315 |
| | 1-cover | |
| | 1-marking strip sheet | |
| | (3 strips per sheet) | |
| | 4-mounting screws | |
| DS312 | Cover (used with Kit DS311) | _ |
| DS313 | Marking strip sheet (used with | _ |
| | Kit DS311) | |

| Part No. | Description | For Panels | | |
|----------|--------------------------------|--------------|--|--|
| TT516 | Kit (double height) includes: | 1600, B1600, | | |
| | 1-mounting strip (8.375" long) | 1700, B1700 | | |
| | 1-cover | | | |
| | 1-marking strip sheet | | | |
| | (3 strips per sheet) | | | |
| | 4-mounting screws | | | |
| TT517 | Marking strip sheet (used with | _ | | |
| | Kit TT516) | | | |
| TT518 | Cover (used with Kit TT516) - | | | |


X-WIDE® VERTICAL DESIGNATION STRIPS


X-Wide designation strips mount on either side (or both) of standard 19" and 23" wide panels and do not interfere with horizontally mounted strips. Each kit contains two mounting brackets which easily fasten with mounting screws provided. Marking strips and clear plastic covers slide into place. Each kit fits onto both sides of a jack panel. X-Wide strips are used on the following panels:

| UNDRILLED | PREDRILLED |
|-----------------------------------|-----------------------------|
| 1600, A1600, 1700 B1700, TT51 | D1600, D1700, BD1700, |
| through TT62, 2-, 4- & 6-Wire | TTD51 through TTD62, 2- 4 & |
| TT-Connectorized Jackfields, 2- & | 6-Wire TT-Connectorized |
| 4-Wire TTPC Connectorized | Jackfields, 2 & 4-Wire TTPC |
| Jackfields, 1200, 1400, 1400320, | Connectorized Jackfields. |
| 2600,and 2600320. | |

SPECIFYING NOTES: Each kit fits both sides of a jack panel (Standard height 1.75". Also available in 3.5 inch and 5.25 inch heights.


Prefix letter"D" indicates panels have been predrilled countersunk holes to facilitate mounting X-Wide strips. Series 1200, 1400, & 2600 can be predrilled on special order.






Inch (mm)

X-WIDE® VERTICAL DESIGNATION STRIPS



X-WIDE VERTICAL DESIGNATION STRIPS

| Part No. | Description | For Panels |
|----------|--|--|
| DS321 | Kit (.75 x 1.75 inches) includes: 2-mounting brackets 2-marking strips 2-covers 4-mounting screws, nuts and lockwashers | 1600, A1600 1700, B1700 TT51 thu TT54, TT59 thru TT62, 2- & 4-Wire TTConnectorized Jackfields, 2-, 4- & 6-Wire TTPC Conntectorized Jackfields |
| D\$322 | Kit (.75 x 3.5 inches) includes: 2-mounting brackets 2-marking strips 2-covers 8-mounting screws, nuts and lockwashers | Same as DS321 (Mounted in pairs) |
| D\$323 | Kit (.75 x 5.25 inches) includes: 2-mounting brackets 2-marking strips 2-covers 12-mounting screws, nuts and lockwashers | 6-Wire TT- Connectorized and panels for DS321 |
| D\$350 | Kit (.75 x 2.265 inches) includes: 2-mounting brackets 2-marking strips 2-covers 4-mounting screws, nuts and lockwashers | B1600, C1600 |
| DS351 | Kit (.75 x 1.75 inches) includes: 1-marking strip 1-cover (Used on all 1.75 inch height connectorized jackfields except next to hinge) | 2-, 4- & 6-Wire Connectorized Jackfields, TTPC Connectorized Jackfields |
| DS352 | Kit same as DS351except narrow width. To be used next to hinge. | Same as DS351 |
| DS353 | Kit (.75 x 5.25 inches) includes: 1-marking strip 1-cover | 6-Wire TT- Connectorized Jackfields |



ORDERING

- 1. Order by part number from table.
- 2. To order X-Wide® strips installed on panels, contact Switchcraft.

DESIGN MATERIALS AND FEATURES

Molded cable assemblies offer many advantages over conventionally-fabricated cables:

- Improved wiring strain relief.
- Proper match of cable diameter to handle.
- Sealed junction: Less exposed area; less contamination due to moisture, dust, dirt.
- · Lower weight and smaller size.
- 100% shielding on selected types.
- Color to match/complement equipment decor.
- Legends, color codes, ribs, dot, customer logo/indicia can be added.
- All molded cables are 100% tested for continuity, shorts and voltage breakdown (250 or 500V).
- All Switchcraft® molded assemblies are UL recognized.

OEM COST SAVINGS

Molded cable assemblies generally cost less than your in-house conventionally-fabricated assemblies. Specific advantages are elimination of:

- 1. Your evaluation, ordering, incoming inspection, and stocking of individual parts.
- 2. Your plant/equipment needs for in-house fabrication.
- 3. Your tooling/labor costs
- 4. Your production line QA/QC.

MOLDED CABLE RELIABILITY

In a series of OEM-conducted tests of Switchcraft versus non-molded, fabricated cables, Switchcraft cables were shown to be superior.

- Fabricated cables broke at lower pull forces: OEM types 24 to 34 pounds, molded cables 37.5 to 41 pounds (molded cables did not break at terminations; the cable itself broke about one to two feet back from the connector).
- Fabricated cables suffered broken wires at low pull-out force limits. Molded cables had cable breaks before cable pulled out of the handle, in most instances. And this failure occurred, as previously noted, at higher pull-out forces.

Strengthened molded cable assemblies out-performed fabricated assemblies, and in fact, the crimp molding process makes it stronger than the wire itself.

SPECIAL ORDER ITEMS

- Customer logo
- Panel Relief Bushing. Specify panel thickness and exact point on cable where bushing is to be installed. Standard panel opening is .50" (12.7 mm) diameter. Double flatted in panels up to .125" (3.18 mm) thick.
- Molded Cable Clamp Bands or Y-Junctions. (Refer to page 258.)
- Special Termination (see separate chart). Contact Switchcraft for specials and provide complete details.

TYPES OF PLASTICS

Thermoplastics used for molded cable assemblies, have excellent electrical and mechanical properties, are economical, convenient for molding, and can be provided in an array of colors. They have electrical characteristics far higher than required, and provide dimensional stability, abrasion and abuse resistance, and can be molded with a smooth mirror-like finish or matte or semi-matte finishes.

WIRE AND CABLE

Switchcraft provides over 100 types of wire and cable from which molded cable assemblies are manufactured. Basically, 30 different cables are used for standard tooling. There are no additional charges where standard tooling exists.

Tooling is designed so cable entry openings on molded plastic handles fit tightly to the outside diameter of the cable. The tighter fit holds cable secure and is more resistant to abuse than if a larger opening were used.

DESIGN AND FABRICATING TECHNIQUES

Switchcraft's engineering staff is supported by a complete tool and die making facility, as well as a fully equipped and staffed molding department to fill all of Switchcraft's plastic molding requirements.

The molding department uses injection molders of semi-automatic, multiple-cavity type to obtain high production rates.

MANUFACTURING SEQUENCE (EXAMPLE)


Step 1: The 1-piece tip rod is firmly staked into the phone plug finger assembly, making a complete and mechanically secure assembly. (Refer to Figure 1) The staking process, using precision manufactured parts, keeps the tip rod assembly from working loose and causing mechanical and electrical problems later.

Step 2: Cable center conductor is soldered to tip rod; then the tubular bridge sleeve is slid forward, bringing the cable shield in contact with the circular notch around rear of tip rod assembly.

Step 3: Bridge sleeve is crimped tightly to tip rod assembly and cable. Center conductor is completely isolated from potential pulling strains, and shield makes a firm, low resistance connection with plug sleeve.

Step 4: A dimensionally stable plastic handle/body of the proper color, size and shape is molded into place. Features are depressions for finger grip, cable entry opening customized to cable diameter to minimize wear on cable, and handle/body molded in one place.

From start to finish, Switchcraft's molded cables are designed and built with maximum quality and reliability. There is virtually no limit to the type and characteristics of special molded cables that Switchcraft can build to special order. For all special orders, consult Switchcraft.



NLY Inc

PATCH CORDS & MOLDED CABLE ASSEMBLIES 3.5MM MOLDED CABLE ASSEMBLIES

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

3.5MM MOLDED CABLES







35HRXXX35 36HRXXX36 35HRXXX84

FEATURES AND BENEFITS

- · Choose plug-to-plug or plug-to-stripped and tinned leads
- 3.5 mm plugs available as straight or right-angle
- Available in mono and stereo
- NOM.29 GA jacketed conductors (red and white) with copper spiral shield
- Cable O.D. 3.0 mm nom./.118" nom.
- Black cable

ORDERING INFORMATION

- 1. Order by part number.
- 2. Contact Switchcraft for custom requirements.

SPECIFICATIONS

PLUGS

35 - Stereo

36 - RA Stereo

Tip, Ring and Sleeve: Brass with nickel-plate

Flex Life: 5000 cycles minimum Plug Insulator: ACETAL

PART NUMBERING SYSTEM

32 - Mono H - Black 33 - RA Mono

R - 3.0 mm nom. 2-conductor wire with spiral copper shield

Length (feet) 036 (3) 072 (6) 144 (12)


0.50

32 - Mono 33 - RA Mono 35 - Stereo

36 - RA Stereo 84 - Stripped and tinned

- Straight Cut Off

0.125





Inch (mm)


Our Locking Power Plugs

* Please visit the product pages on our website for the most up-to-date product information

MOLDED CABLE ASSEMBLIES With Power-Plug Battery Charger Plugs and Jacks







SPECIFICATIONS

PLUG

Sleeve: Copper alloy, nickel-plated.
Pin: Silver-plated copper alloy.
Finger Insulator: Plastic.
Insulating Washers: Rigid plastic.

Insulating Washers: Rigid plastic.
Sleeve Terminal: Steel, tin-plated.
Molded Handle: Plastic.

JACK

Bushing: Brass, nickel-plated copper alloy.

Washers: Rigid plastic.

Pin, Springs, and Terminals: Plated copper alloy.

Housings: Thermoplastic.

CABLE

We will build assemblies on cable furnished by you, .156" (3.96 mm) outside diameter, or on cable we purchase to your specifications. Jacket must have temperature rating of 60° C minimum. Optional mold available for larger cable; order as ST760L or ST765L.

DESIGN FEATURES

- ST760, ST760L, RA760 accepts .08" (2.03 mm) diameter pin.
- ST765, ST765L, RA765 accepts .099" (2.54 mm) diameter pin.
- RA712A:
- Mates with ST765, ST765L, and RA765.
- 2 conductor.
- Mounts in .313" diameter hole in panels up to .125" thick.
- Pin outside diameter is .108" .112" split pin.
- · Automatic switchover from AC to DC.
- RA722A:
- Mates with ST760, ST760L, and RA760.
- Pin outside diameter is .086" .090" split pin.
- Molded-in cable clamp sleeve terminal (RA plugs only).
- For use with sockets similar to those used on portable radios, tape recorders, television receivers and appliances which feature AC adapters and/or battery chargers.
- Available with terminations of another ST760, RA760 stripped and tinned ends, spade lugs, alligator clips, and more on special order.
- Jacks available with extended bushing for use with Switchcraft locking power plugs 761K, 766K, S761K, and S766K on special order.

See ordering guide on next page.

PATCH CORDS & MOLDED CABLE ASSEMBLIES ORDERING GUIDE

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MOLDED CABLE ASSEMBLIES WITH POWER PLUGS AND JACKS PART NUMBERING SYSTEM

TO CREATE A PART NUMBER

- 1. Identify Terminations (both ends)
- 2. Indicate Color and Type of Cable
- 3. Select the Length of Assembly

DC POWER CABLE ASSEMBLIES

| Туре | Termir | nation | Color | Cable* | Len | Length (feet) | | Termi | nation | |
|--------|--------|--------|---------|--------|-----|---------------|---|-------|--------|---|
| | | | | | | | | | | |
| ST760 | 4 | 7 | G-Gray | С | 0 | 1 | 8 | (1.5) | 4 | 7 |
| ST765 | 4 | 8 | H-Black | K | 0 | 2 | 4 | (2) | 4 | 8 |
| ST760L | 5 | 7 | | | | | | | 5 | 7 |
| ST765L | 5 | 8 | | | | | | | 5 | 8 |
| ST760K | 7 | 3 | | | | | | | 7 | 3 |
| ST765K | 7 | 4 | | | | | | | 7 | 4 |
| RA760 | 5 | 2 | | Υ | 0 | 3 | 6 | (3) | 5 | 2 |
| RA765 | 5 | 3 | | Z | 0 | 4 | 8 | (4) | 5 | 3 |
| RA712A | 7 | 1 | | | 0 | 7 | 2 | (6) | 7 | 1 |
| RA722A | 7 | 2 | | | 1 | 2 | 0 | (10) | 7 | 2 |
| | | | | | | | | | 8 | 4 |
| | | | | | | | | | 9 | 0 |

^{*}See "Cable Types" chart on page 260. **Note:** Some configurations will be special orders. Contact Switchcraft.

TYPICAL STANDARD PART NUMBERS

| STRAIGHT 2-CONDUCTOR .100 PIN POWER PLUG (#48) TO: | | | | | | | |
|--|---|---|-----------|--|--|--|--|
| Termination (other end) Cable Length (feet) Part Number | | | | | | | |
| (power plug) #48 | С | 6 | 48HC07248 | | | | |
| (stripped wires) #84 | С | 6 | 48HC07284 | | | | |
| (blunt cut) #90 | С | 6 | 48HC07290 | | | | |
| (power jack .100 pin) #71 | K | 6 | 48HK07271 | | | | |

^{1.} All cables listed here are black.

EN3™ MINI WEATHERTIGHT OVERMOLDED CABLE ASSEMBLIES



FEATURES AND BENEFITS

- Dual purpose handle provides flex relief and finger grip design for easy insertion and withdrawal.
- · Available in both cord and in-line versions.
- 2 through 8 pin configurations.
- Superior leakage protection. Contact area is double-sealed for excellent moisture and chemical resistance.
- Integral O-ring and gasket. O-ring is molded onto cord housing assembly and gasket is molded onto panel housing assembly to prevent leakage and eliminate need for additional copper case o-rings and gaskets.
- Thermoplastic rubber body simulates closed entry contact system to prevent probe damage or accidental loss of spring retention due to misaligned or bent pins.
- Housing rated UL 94V-O against flammability.
- Exceeds Coast Guard specifications for water tightness (CFR 46 Part 110.20).
- Exceeds enclosure rating IP16/IP18 when not mated or covered and IP66/IP68 when mated or covered (IEC 529).
- Exceeds enclosure rating 6P at 1000V when mated or covered (NEMA 250).

APPLICATIONS

- Process Control
- Communications
- Marine Electronics
- Transportation
- Medical Instrumentation
- General Industrial Electronics
- Geothermal Instrumentation

MATERIALS

Connector shells, contact locking disk:

Thermoplastic polymer glass fiber, flame retardant

Coupling ring: Nylon

Connector shell interior: Thermoplastic rubber Contacts: Copper base alloy gold-plated over

nickel underplate

PART NUMBERING GUIDE* Example:

| 1st Termination | Color | Cable | Length in Inches | 2nd Termination |
|--------------------|-------|-------|------------------|--------------------|
| 503 | Н | Α | 072 | 184 |

*In most instances the multi-conductor cable will be used – found on page 252.

The overmolded EN3™ cable can accept nominal cable O.D.'s up to .300.

Tooling charges may apply for customer specified cable.



SPECIFICATIONS MECHANICAL

Shock: Mil-Std 202 Method 213B, condition K

Vibration: Mil-Std 202 Method 201

Life: 600 insertion/withdrawal cycles (minimum)

ELECTRICAL

Voltage Rating (sea level): Tested at 600 VRMS

Insulation Resistance: 100 megohms (minimum) at 77° F

Contact Resistance: 5 milliohms (maximum) Current Rating: 7.5 Amps (#20 contact);

13.0 Amps (#16 contact)

ENVIRONMENTAL

Temperature Limits: -40°C to +65°C (non-operating) **Moisture Resistance:** Mil-Std 202 Method 106F

Insulation Resistance: Mil-Std 202 Method 302 condition B

Thermal Shock: Mil-Std 202 Method 107G Salt Spray: Mil-Std 202 Method 101D condition B

RATINGS

IP16/IP18 IP66/IP68 NEMA 250 (6P) CFR 46 Part 110.20 UL 94V-O Patent 5,485,673 File 36049

OVERMOLDED STYLE NUMBER #20 CONTACT SIZE

| Number of Pins | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|----------------|-----|-----|-----|-----|-----|-----|-----|
| Male Cord | 502 | 503 | 504 | 505 | 506 | _ | _ |
| Female Cord | 512 | 513 | 514 | 515 | 516 | 517 | 518 |
| Male Inline | 522 | 523 | 524 | 525 | 526 | 527 | 528 |
| Female Inline | 532 | 533 | 534 | 535 | 536 | _ | _ |

OVERMOLDED STYLE NUMBER #16 CONTACT SIZE

| Number of Pins | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|----------------|-----|-----|---|---|---|---|---|
| Male Cord | 552 | 553 | _ | _ | _ | _ | _ |
| Female Cord | 562 | 563 | _ | _ | _ | _ | _ |
| Male Inline | 572 | 573 | _ | _ | _ | _ | - |
| Female Inline | 582 | 583 | _ | _ | _ | _ | _ |

Note: 9-18 versions can also be molded. Contact factory for details.

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

CORDETTE® AND CORD SWITCH ASSEMBLIES



FEATURES AND BENEFITS

- Momentary, 0.5 A switching combined with 1-piece molded plastic body qualifies Cordette for all types of commercial and industrial usage.
- Available with molded-on Cordette switch or assembled Cord switch (ED series).
- Cable features PVC outer jacket and withstands rugged use.

SPECIFICATIONS STYLE 97


Body: Series ED900

Housing: Die-cast zinc, satin nickel-plated.

Switch Body and Insert Bushing: H.H. Brass, nickel-plated.

Insulation: XXXP paper-base phenolic. Cable Relief Bushing: Black neoprene. Pressure Plates: Stainless steel.

Cable Relief Screws: Steel, nickel-plated.



| DESCRIPTION | 1st Term | Housing & | CABLE | Cab | le Length | (ln.) | 2nd Term | Circuitry | Button Color |
|----------------------|----------|-------------|-------------|-------|-----------|-------|----------|------------------|----------------------|
| Example: | Code | Cable Color | CODE | Х | Х | Χ | Code | | |
| Std. Cordette (921K) | 99 | G | V | 0 | 7 | 7 | 84 | Std 1A (No Code) | Std. Black (No Code) |
| ED903 Series | 97 | | | | | | | 1 - 1B | H - Black |
| Standard Cable | | G-Gray | V (W1230-1) | .250" | PVC | 18GA | 06 | 2 - 1C | R - Red |
| Type for 1/4" Plugs | | H-Black | V (W1230-2) | .250" | PVC | 18GA | 07 | 3 - AB | W - White |
| | | B-Beige | V (W1230-4) | .250" | PVC | 18GA | | | |
| | | W-White | V (W1230-5) | .250" | PVC | 18GA | | | |
| Standard Cable | | G-Gray | D (W1032-1) | .109" | PVC | 25GA | 61 | | |
| Types for Tini® and | | H-Black | D (W1032-2) | .109" | PVC | 25GA | 50 | | |
| Micro Plugs | | W-White | D (W1032-3) | .109" | PVC | 25GA | 51 | | |
| | | H-Black | E (W1065-2) | .100" | PVC | 26GA | | | |


DIMENSIONS ARE FOR REFERENCE ONLY


Inch (mm)

MOLDED CABLE ASSEMBLIES WITH CORDETTE® SWITCHES



ST900 **Termination Code: 99**







SPECIFICATIONS SWITCH

Housing: White plastic (standard).

Molded Body: Gray plastic (standard) with contrasting trim

and gray pushbutton.

Contacts: Integral, copper alloy, hard gold-plated form 1-A, 0.5 A, 50 W maximum, AC, non-inductive load. Not recommended for high voltage circuits.

Insulation: Thermoplastic UL 94V-0.

Button Color: Black (standard). Other colors available on

special order.

CABLE

Standard Unshielded—Type W-1230.

Note: See Standard Cable Chart on page 260 for details. We will build assemblies on cable furnished by you, .27" (6.68 mm) outside diameter, or on cable we purchase to your specifications. Jacket must have temperature of 60° C minimum. ST900 (#99)

Button stroke only .063" (1.6 mm). Cable leads soldered directly to switch terminals. Standard button is with 1-A switching. Use termination number "99" with all cable numbering charts except multi-pin interconnection. Use code "198" for multi-pin interconnections.

See Switch Section of Switchcraft's Engineering Design Guide for more details on the ST900.

| Part Number | Description |
|-------------|---|
| 921 | Cordette Switch, phone jack termination |
| 921K | Same as 921, plus 6-foot, 2 conductor cable with stripped and tinned leads. |

SPECIAL ORDER FEATURES

- 1-B, 1-C, or 1-A + 1-B switching.
- Red, green, blue, white or yellow pushbuttons.
- Legends
- Other body colors
- ST-900 Custom-molded to any of a large selection of cables. Also many cable terminations, i.e., phone plugs, extension jacks, phono plugs, spade lugs, alligator clips, stripped and tinned leads, etc.

PATCH CORDS & MOLDED CABLE ASSEMBLIES MULTIPIN INTERCONNECTORS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MOLDED CABLE ASSEMBLIES WITH DIN PLUGS

STYLES RA300 AND ST300 APPLICATIONS

- Computer
- Data Communications
- Instrumentation
- Medical Systems
- Process Controls
- MIDI (Musical Instrument Digital Interface)

FEATURES

- Long life
- 7 different pin configurations: versatile circuitry
- Fully molded plugs sealed against contamination (moisture, dust, dirt)
- Fully shielded: plugs with interference protection/ common ground-shield
- · Strain relief: protects internal wire connections
- Flex relief: molded integral with handle for extra protection. No exit stress failures
- Locking: 30° twist locking for anti-vibration protection and ease of engagement
- Straight and coil cords: stock and custom styles, colors, lengths
- Shielded or unshielded cables: stock and custom styles, colors, lengths
- Molded through-panel cable relief: extra cable protection
- Custom wiring/ keying: gives extra choice in mounting and circuit selection
- Custom contact plating: precious and other metals
- Custom logo: your identification on molded plugs
- 100% tested for continuity, shorts, appearance, voltage breakdown (250 or 500 V)

COMPLETE SHIELDING SYSTEMS

Switchcraft also offers shielded DIN receptacles for use with shielded molded cable assemblies. Together they provide a valuable design tool to suppress EMI interference to permit you to meet strict requirements of FCC Docket 20780.

ORDERING

- 1. Order by part number from guide on page 251.
- 2. For special order items, contact Switchcraft with details. **SPECIFYING NOTE:** See Connector Section of Switchcraft's Engineering Design Guide for mating receptacles.





Style ST324

Termination Code: 324



Switchcraft DIN molded cable assemblies meet increased demand for modern, field-tested connections for a wide range of electrical/electronic applications. Connectors are DIN (Deutsche Industrie Norm) circular type, male or female (locking or non-locking) with 3 to 8 pins/contacts. Units are molded and protected with a rugged handle, and are fully shielded and equipped with advance design cable relief. Switchcraft cable assemblies and mating receptacles adhere to strict requirements of FCC Docket 20780 and offer fully shielded links for data and instrumentation applications of all kinds.

SHIELDING EFFECTIVENESS

Effectiveness of shielding is frequency-dependent; as frequency increases, more shielding is required to maintain comparable shielding effectiveness. The chart below delineates shielding effectiveness with molded cable assemblies with 100% foil shield cables and shielded DIN connectors.

| Frequency Range MHz | Shielding Effectiveness, dB |
|---------------------|-----------------------------|
| 30-500 | -30 |
| 60-400 | -20 |
| 500-800 | -10 |

MOLDED CABLE ASSEMBLIES WITH DIN PLUGS (continued)

STYLES RA300 AND ST300 **SPECIFICATIONS ELECTRICAL**

Contact Resistance: Cord Plugs and Receptacles.

.010 ohms, contact spring/pin; .030 ohms, ground clip/shell.

Control and Switching Receptacles: .015 ohms, contact spring/pin; .020 ohms, switch contacts. Dielectric Withstanding Voltage: 500 V (rms).

Leakage Resistance: 10⁵ MΩ

MECHANICAL Life: 5000 cycles

| Insertion/Witho | Insertion/Withdrawal Forces: | | | | | | |
|--------------------|------------------------------|--------------------------|--|--|--|--|--|
| Number of Contacts | Insertion Force pound/N | Withdrawal Force pound/N | | | | | |
| 2 | 3.6/(16) | .45-2.7/ (2-12) | | | | | |
| 3 | 5.4/(24) | .67-4.1/ (3-18) | | | | | |
| 4 | 7.2/(32) | .90–5.4/ (4–24) | | | | | |
| 5 | 9.0/(40) | 1.24-6.8/ (5.5-30) | | | | | |
| 6 | 10.8/(48) | 1.46-8.1/ (6.5-36) | | | | | |
| 7 | 12.6/(56) | 1.68–9.5/ (7.5–42) | | | | | |
| 8 | 14.4/(64) | 1.90–10.8/ (8.5–48) | | | | | |

PLUG MATERIALS

Pin Contacts: Silver-plated, copper alloy. Insulating Washer: Thermoplastic.

Locking Plug Housing: Nickel-plated, die-cast zinc alloy.

Other Housings: Plated steel.

Molded Handle: Flexible thermoplastic. Strain relief

matte finish.

NOTE: All connectors meet DIN specifications. Din specification numbers (except for 4-pin, 5-pin 240°)

will be furnished on request.

ORDERING

- 1. See table below for termination descriptions. Termination code is the same number as the plug style (e.g. termination code for a ST305 is 305).
- 2. See page 251 for ordering guide.

PART NUMBERS - MOLDED CABLE ASSEMBLIES

PATCH CORDS & MOLDED CABLE ASSEMBLIES

MULTIPIN INTERCONNECTIONS

| Part Number | Description | Term. A | Term. B |
|---------------------|---|------------|------------|
| ⟨305KD084184 | Black coil cord. 15" (381 mm) retracted; 78.74" (2 m) extended. 5 pin male with other end stripped and tinned on cable number W-1301-2. | ST305 | _ |
| ♦305HJ084184 | Black cable cord. 7 feet (2.13 m) in length. 5 pin male with other end stripped and tinned on cable number W-1279-2. | ST305 | _ |
| ♦306HK042306 | Black cable cord. 39.37" (1 m) in length. 6 pin male to 6 pin male on cable number W-1289-2. | ST306 | ST306 |
| ♦306HK084306 | Black cable cord. 78.74" (2 m) in length. 6 pin male to 6 pin male on cable number W-1289-2. | ST306 | ST306 |

 $[\]Diamond$ Special order only; contact Switchcraft.

FOIL SHIELD CABLES - STRAIGHT

| Part Number | Color | Length, inch (mm) |
|-------------|-------|---------------------------|
| W-1279-2 | Black | Length must be specified. |
| W-1289-2 | Black | Longar must be specified. |

| | Part Numbers-Male (pins) | | | | | | | |
|--|--------------------------|--------|--------|--------|--------|--------|--------|--|
| | 3@180° | 4@210° | 5@180° | 5@240° | 6@240° | 7@270° | 8@270° | |
| Pin Arrangements | В | D | F | E | G | Н | N | |
| Description | | | | | | | | |
| Straight handle. | ST303 | ST309 | ST305 | ST304 | ST306 | ST307 | ST308 | |
| Straight handle. 30° twist lock ring fastening, mates with lock flange plugs and receptacles. | ST323 | ST329 | ST325 | ST324 | ST326 | ST327 | ST328 | |
| Right-angle handle. | RA353 | RA359 | RA355 | RA354 | RA356 | RA357 | RA358 | |
| Right-angle handle. 30° twist lock ring fastening, mates with lock flange plugs and receptacles. | RA373 | RA379 | RA375 | RA374 | RA376 | RA377 | RA378 | |

See next page for Pin/Contact arrangements.

PHONE: 773 792-2700


* Please visit the product pages on our website for the most up-to-date product information


MOLDED CABLE ASSEMBLIES WITH DIN PLUGS (continued)


STYLES RA300 AND ST300

DOUBLE-FLATTED HOLE PANEL UP TO 125" (3.18 mm) THICK EXTERNAL CABLE RELIEF


CUTAWAY VIEW OF STYLE ST303







MIDI CABLES



FEATURES AND BENEFITS

- Molded connectors provide superior pull-out retention and greater environmental protection than assembled versions.
- All five pins wired active with high definition Belden Brilliance® cable.
- Can be used with any type MIDI instrument.

SPECIFICATIONS

- Belden Brilliance[®] 24 awg, 4 conductor, braid shielded cable.
- Wiring conforms to MIDI specifications including the clock/sync capabilities on pins 1 and 3.
- Molded 180 degree 5 pin DIN connectors.
- Standard color is black with other colors available on special order.
- PVC molded handles and cable jackets.
- All molded cables are 100% tested for continuity, shorts and voltage breakdown.

ORDERING INFORMATION

- 1. Order by part number.
- 2. Contact Switchcraft for more information.

Belden Brilliance® is a registered trademark of Belden Wire and Cable Company.

MIDI CABLES

| Part number | Length | Color |
|-------------|---------|-------|
| MD3 | 3 foot | Black |
| MD6 | 6 foot | Black |
| MD10 | 10 foot | Black |
| MD15 | 15 foot | Black |

STANDARD PRODUCT

- · Silver-plated pins
- Belden Brilliance® 24 awg, 4 conductor, braid shielded cable
- Black cable
- Black handle

SPECIAL ORDER

- Gold-plated pins
- Other cable types
- Optional lengths
- Color cable
- Color handle

PATCH CORDS & MOLDED CABLE ASSEMBLIES MULTIPIN INTERCONNECTORS


PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MOLDED CABLE ASSEMBLIES WITH MINIATURE, SHIELDED, MOLDED TINI Q-G® PLUGS

STYLE ST600

Tini Q-G® miniature plugs offer 3- through 6-pin/contact connecting with full shielding, small size, RFI-protected termination of analog/digital circuits/equipment. Typical applications are for EIA RS-232C and RS-449 type connections. Plugs retain all Tini Q-G® features, including latchlock, strain relief, flex relief, polarization and "scoop-proof" construction. See Connector Section for details on features and specifications. Shielding of these plugs meets U.S. Navy Tempest requirements with proper cable and mating connector choice.



MOLDED CABLES WITH STRAIGHT FEMALE Tini Q-G® PLUGS (Special Order Only)

Three- through 6-contact plugs are molded into a complete cable assembly per customer requirements. Plug includes latch for secure connection, "through-ground" provision, and external cable flex relief. Plugs are molded onto shielded or unshielded cables of .180" – .215" diameter Standard cable color is gray; black, beige and other colors can also be specified. In addition, UL 94V-0 rated cables can be specified.

Styles ST603, ST604, ST605, ST626 Termination Codes: 603, 604, 605, 626


Note: Reverse gender molded male cable assembly available. Call factory for details.


| Plug Style ² | Description | Mating Receptacles ¹ |
|----------------------------|---|------------------------------------|
| ♦ ST603 | 3-contact straight female plug (molded) | TA3M, TB3M |
| ♦ST604 | 4-contact straight female plug (molded) | TA4M, TB4M |
| ♦ST605 | 5-contact straight female plug (molded) | TA5M, TB5M |
| ♦ST626 | 6-contact straight female plug (molded) | TA6ML, TB6M |

- See Connector Section of Switchcraft's Engineering Design Guide for other mating receptacles.
- Termination code is the same as the numbers in the plug style (e.g. termination code for a ST626 is 626). See multi-pin ordering guide on next page.

IMPORTANT SPECIFYING NOTE

♦ Special 3, 4 and 5 pin/contact patterns can be tooled on special order where production quantities warrant special handling. Contact Switchcraft with your requirements.





MOLDED CABLE ASSEMBLIES FOR MULTI-PIN INTERCONNECTION PART NUMBERING SYSTEM (NOT ALL NUMBERS SHOWN)

- 1. Identify Terminations (both ends)*
- 2. Indicate Color and Type of Cable
- 3. Select the Length of Assembly

MULTI-PIN CABLE ASSEMBLIES

| Termination | Color | Cable ¹ | Length (feet) | Termination (examples) |
|---|------------------------------|------------------------|---|---|
| 303 304 305 306 307 308 309 603 604 605 606 | G-Gray H-Black D-Beige | АВСОЕГ ОНЈКМ О О | 036 (3) 060 (5) 072 (6) 120 (10) | 3 0 3 3 0 4 3 0 5 3 0 6 3 0 7 3 0 8 3 0 9 6 0 3 6 0 4 6 0 5 6 2 6 1 8 4 1 9 0 |

^{1.} See next page for cable descriptions.

• Other cables available on special order. Contact Switchcraft.

TYPICAL PART NUMBERS

| STRAIGHT 3-pin DIN PLUG (#303) TO: | | | | | | | |
|------------------------------------|--------|-------|------------------|--------------------------|--|--|--|
| Termination (other | r end) | Cable | Length (feet) | Part Number ² | | | |
| (3-pin DIN) | #303 | Α | 5 | 303HA060303 | | | |
| (3-pin Tini Q-G®) | #603 | А | 5 | 303HA060603 ³ | | | |
| (Strip and tin) | #184 | Α | 6 | 303HA072184 | | | |
| (Blunt cut) | #190 | А | 6 | 303HA072190 | | | |

^{2.} All cables listed here are black.

STANDARD MULTI-PIN CABLE ASSEMBLY **TERMINATION VS. CABLE CROSS-REFERENCE**

| | | Cal | ole | | | | | | | | | | | |
|---|-------|----------------------------|-----------------------|-----------------------|----------------------------|----------------------------|----------------------------|----------------------------|----------------------------|-----------------------|-----------------------|----------------------------|----------------------------|----------------------------|
| | | W 1 2 0 3 2 | W 1 0 8 9 | W 1 0 7 7 | W 1 2 0 6 # | W 1 2 7 7 6 | W 1 2 3 7 2 | W 1 2 9 1 6 | W 1 2 8 8 2 | W 1 2 7 9 | W 1 2 8 9 | W 1 2 9 0 # | W 1 2 8 4 2 | W 1 4 4 2 1 |
| Т | RA353 | Х | | | | | | Х | | | | | | |
| Ε | RA354 | | | Х | | | | | | Х | | | Х | |
| R | RA355 | | | Х | | | | | | Х | | | Х | |
| M | RA356 | | | | Х | | | | | | Х | | | Х |
| N | RA357 | | | | | Х | | | | | | | | |
| A | RA358 | | | | | | Х | | | | | Х | | |
| Ţ | RA359 | | Х | | | | | | Х | | | | | |
| Ī | RA373 | Х | | | | | | Х | | | | | | |
| O | RA374 | | | Х | | | | | | Х | | | Χ | |
| | RA375 | | | X | | | | | | Х | | | Х | |
| | RA376 | | | | Х | | | | | | Х | | | Х |
| | RA377 | | | | | Х | | | | | | | | |
| | RA378 | | | | | | Х | | | | | Х | | |
| | RA379 | | Х | | | | | | Х | | | | | |
| | ST303 | Х | | | | | | Х | | | | | | |
| | ST304 | | | Х | | | | | | Х | | | Х | |
| | ST305 | | | Х | | | | | | Х | | | Χ | |
| | ST306 | | | | Х | | | | | | Χ | | | Χ |
| | ST307 | | | | | Х | | | | | | | | |
| | ST308 | | | | | | Х | | | | | Χ | | |
| | ST309 | | Х | | | | | | Х | | | | | |
| | ST323 | Х | | | | | | Х | | | | | | |
| | ST324 | | | Х | | | | | | Х | | | Х | |
| | ST325 | | | Х | | | | | | Х | | | Х | |
| | ST326 | | | | Х | | | | | | Χ | | | Х |
| | ST327 | | | | | Х | | | | | | | | |
| | ST328 | | | | | | Х | | | | | Х | | |
| | ST329 | | Х | | | | | | Х | | | | | |
| | ST603 | Х | | | | | | Χ | | | | | | |
| | ST604 | | Х | | | | | | Х | | | | | |
| | ST605 | | | Х | | | | | | Х | | | Χ | |
| | ST626 | | | | | | | | | | X | | | Х |

^{# -} Indicates any number

^{*} Please refer to page 243 for EN3™ weathertight connector options.

^{3. .180&}quot; diameter.

X - Indicates that the cable in this column and the termination in this row can be used together in a standard part number

1. - Other termination/cable combinations may be available or special order.

PATCH CORDS & MOLDED CABLE ASSEMBLIES CABLE GUIDE

PHONE: 773 792-2700


* Please visit the product pages on our website for the most up-to-date product information

STANDARD MULTI-PIN INTERCONNECTION CABLES

FOR MOLDED CABLE ASSEMBLIES ON PAGES 243 THROUGH 251.

| Cable Type | Color | Description | Cable Code |
|---|--------|---|------------|
| W1203-2 | Black | 3 conductor, 22 AWG stranded, unshielded | A |
| 200 2 | 2.00.1 | .18" (4.6 mm) outside diameter, UL style 2960 | ^ |
| W1089-1 | Gray | 4 conductor, 22 AWG stranded, unshielded | D. |
| *************************************** | aray | .18" (4.6 mm) outside diameter, UL style 2960 | В |
| W1077-1 | Gray | 5 conductor, 22 AWG stranded, unshielded | С |
| W1077 1 | Gray | .20" (5.1 mm) outside diameter, UL style 2464 | C |
| W1206-1 | Gray | 6 conductor, 22 AWG stranded, unshielded | <u></u> |
| W1206-2 | Black | .20" (5.1 mm) outside diameter, UL style 2095 | D |
| W1277-6 | Beige | 7 conductor, 22 AWG stranded, unshielded | |
| W1277-0 | Deige | .20" (5.1 mm) outside diameter, UL style 2095 | E |
| W1237-2 | Black | 8 conductor, 22 AWG stranded, unshielded | |
| VV 1201-2 | Diack | .23" (5.8 mm) outside diameter, UL style 2464 | F |
| W1291-6 | Beige | 3 conductor, 24 AWG stranded, foil shielded | |
| W1231-0 | Deige | .18" (4.6 mm) outside diameter | G |
| W1288-2 | Black | 4 conductor, 24 AWG stranded, foil shielded | |
| W 1200 Z | Black | .18" (4.7 mm) outside diameter | Н |
| W1279-1 | Gray | 5 conductor, 24 AWG stranded, foil shielded | |
| W1279-2 | Black | .19" (4.8 mm) outside diameter | J |
| W1279-6 | Beige | .19 (4.0 mm) outside diameter | |
| W1289-2 | Black | 6 conductor, 24 AWG stranded, foil shielded | |
| W1289-6 | Beige | .22" (5.5 mm) outside diameter | K |
| W1290-1 | Gray | 8 conductor, 24 AWG stranded, foil shielded | м. |
| W1290-6 | Beige | .23" (5.7 mm) outside diameter | M |
| W1284-2 | Black | 5 conductor, 22 AWG stranded, braid shielded | 0 |
| VV 1204-2 | DIACK | .23" (5.8 mm) outside diameter | Q |

MOLDED CABLE ASSEMBLIES With Micro Plug® Subminiature Phone Plugs



.453 .47 [II.5I] [II.9] .266 [6.76] .097 [2.46] DIA.

DESIGN FEATURES

- Thermoplastic insulation between tip and sleeve circuits.
- "Pear-shaped" one-piece tip rod.
- Cable clamp connects cable shield (or second conductor) to plug sleeve.

SPECIFICATIONS

PLUG

Tip and Sleeve: Plated copper alloy. **Insulation:** W-1032-1. Molded thermoplastic. **Sleeve Terminal:** Tinned copper alloy.

Molded Handle: Plastic.

Standard Colors: Gray, white, black, brown. Other colors available on special order.

CABLE

Standard Shielded Cable—Type W-1032-1.

NOTE: See Standard Cable Chart on page 260 for details.

Order by part number from guide on page 259.

Special Cable: We will build assemblies on cable furnished by you, .109" (2.77 mm) diameter maximum, or on cable we purchase to your specifications. Jacket must have temperature rating of 60° C minimum.


RA850: Right-angle Micro-Plug® plug with plastic handle. Short body extension. Molded to cables up to .109" (2.77 mm) outside diameter.


ST850: Straight Micro-Plug® plug, small plastic handle, only .47" (11.9 mm) long.

NOTE: Micro-Plug® molded cable assemblies mate with Switchcraft Micro-Jax® TR-2A.

MOLDED CABLE ASSEMBLIES With Tini Plug® Miniature Phone Plugs

PATCH CORDS & MOLDED CABLE ASSEMBLIES MINIATURE PLUGS





SPECIFICATIONS

PLUG

Tip and Sleeve: Nickel-plated copper alloy.

Cable Clamp: Tin-plated steel. Insulation: Rigid plastic. Molded Handle: Plastic.

Standard Colors: Gray, white, black, brown. Other colors available on special order.

CABLE

Shielded—Type W-1000-1 (suitable for ST740 and ST750 due to cable Outside Diameter).

Shielded—Type W-1032-1 (suitable for all types on this page).

Standard Parallel—Type W-1041-1.

NOTE: See Standard Cable Chart on page 260 for details. Order by part number from guide on page 259.

Special Cable: We will build assemblies on cable furnished by you, up to .160" (4.06 mm) (for ST740 and ST750); .120" (3.05 mm) (for ST700, ST710, RA700, RA710) outside diameter, or on cable we purchase to your specifications. Jacket must have temperature rating of 60°C minimum.

DESIGN FEATURES

- "Pear-shaped" one-piece tip rod soldered directly to cable conductor.
- Cable clamp connects cable shield (or second conductor) to the plug sleeve.

RA700: Right-angle Tini Plug® plug with small plastic handle. Short body extension, recommended for slightly recessed jacks. Molded to cables up to .109" (2.77 mm) outside diameter.

RA710: Right-angle Tini-Plug® plug similar to RA700, except longer body extension where equipment jack is deeply recessed. Molded to cables up to .109" (2.77 mm) outside diameter.

ST700: Straight Tini-Plug® plug offering the shortest and smallest handle.


ST710: Same as ST700, except with longer handle.

ST740: Straight Tini-Plug® with larger outside diameter handle desirable.

ST750: Straight Tini-Plug® with same diameter handle as ST740 and longer handle for easier handling.

Inch

MOLDED CABLE ASSEMBLIES With Phono Plugs and Phono Extension Jacks



SPECIFICATIONS

PLUG

Tip (prong): Nickel-plated, copper alloy. **Sleeve Connection:** Plated copper alloy. **Insulation:** Rigid plastic or thermoplastic.

Molded Handle: Thermoplastic.

Standard Colors: Gray, black, brown, red, white, tan, or blue. Other colors available on special order.

EXTENSION JAX

Tip Spring: Nickel-plated, hardened copper alloy.

Sleeve Connection: Plated steel.

Insulation: Rigid plastic.

Molded Handle (both Plug and Jack): Plastic. Standard Colors: Gray, white, black and brown. Other colors available on special order.

CABLES

RA35, ST35, ST40, ST60:

Standard Shielded Cable—Type W-1000-1.

Standard Parallel Cable (lamp cord)—Type W-1033-1.

RA40. RA41:

Standard Shielded Cable—Type W-1000-1 and W-1032-1. Standard Unshielded (Parallel) Cable—Type W-1041-1.

NOTE: See Standard Cable Chart on page 260 for details. Order by part number from guide on page 259.

Special Cable: We will build assemblies on cable furnished by you (maximum diameter varies for types RA35, ST35, ST40) up to .20" (5.08 mm) outside diameter for RA40 and RA41 or on cable we purchase to your specifications. Jacket must have a temperature rating of 60 C minimum.

⟨RA35: Right-angle phono plug with body extension for recessed jack. Cable: .188" (4.78 mm) outside diameter maximum. Completely shielded. (Available on special order only.)

ST35: Straight phono plug with "finger grip" handle. Handle .438" (11.13 mm) outside diameter. Completely shielded.

ST40: Straight phono plug, similar to ST35, except with longer handle.

ST60: Straight extension jack with "finger grip" handle. Handle .438" (11.13 mm) outside diameter. Completely shielded.

RA40: Compact right-angle phono plug with low profile, high quality insulation, and short .281" (7.14 mm) molded handle for audio and RF connections where space is at a minimum.

RA41: Same as RA40, except handle is .531" (13.49 mm) long.

DESIGN FEATURES

- Can be specified with phenolic, nylon, glass-filled Teflon or polypropylene internal insulators. Polypropylene is recommended for RF connecting applications.
- Applications include stereo, PA and intercoms, audio-visual and telecommunications, including RF connections in 2-way radio and paging systems.

Inch (mm

PATCH CORDS & MOLDED CABLE ASSEMBLIES EXTENSION JACKS AND LITTEL® PLUGS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MOLDED CABLE ASSEMBLIES WITH TINI-EXTENSION® JACKS

SPECIFICATIONS

Housing (or Sleeve): Nickel-plated, copper alloy.

Handle: Molded plastic.
Sleeve Terminal: Plated steel.
Tip Spring: Copper alloy.

Insulation: Rigid plastic. Larger design also has a molded

thermoplastic insert.

Standard Colors: Gray white, black, brown. Other colors


available on special order.

CABLE

Standard Shielded: Type W-1032-1. Standard Unshielded: Type W-1041-1.

NOTE: See Standard Cable Chart on page 260 for details.

Order by part number from guide on page 259.



Special Cable: We will build assemblies on cable furnished by you, up to .160" (4.06 ram) outside diameter—or on cable we purchase to your specifications. Jacket must have temperature rating of 60° C minimum.

ST125: Straight Tini-Extension Jax jacks with same features as ST121, on next page (shielded, 2-conductor), except with .406" (10.31 mm) outside diameter, designed to mate with Switchcraft Tini-Plug® plugs.

MOLDED CABLE ASSEMBLIES WITH LITTEL PLUG® PHONE PLUGS

SPECIFICATIONS

PLUG

Tip: Nickel-plated, copper alloy. **Sleeve:** Plated copper alloy. **Insulation:** Rigid plastic. **Internal Shield:** Plated steel. **Molded Handle:** Plastic.

Standard Colors: Gray, white, black and brown.

Other colors available on special order.

CABLE

FOR 2-CONDUCTOR PLUGS:

Standard Shielded Cable—Type W-1000-1. Standard Parallel Cable (lamp cord)—Type W-1033-1.

FOR 3-CONDUCTOR PLUGS:


Standard Shielded Cable-Type W-1021-1.


NOTE: See Standard Cable Chart on page 260 for details. Order by part number from guide on page 259.

Special Cable: We will build assemblies on cable furnished by you, .188" (4.78 mm) diameter maximum, or on cable we purchase to your specifications. Jacket must have a temperature rating of 60°C minimum.

DESIGN FEATURES

- Molded cables with Littel-Plug phone plugs feature one-piece tip rod assembly connecting tip directly to the soldered connection of the cable conductor.
- Unusual dual-purpose clamp terminal provides completely shielded electrical connection and a cable clamp; connects plug sleeve to cable shield or conductor.
- Right-angle phone plugs (RA202, RA203, RA207 and RA208) molded to cables up to .188" (4.78 mm) outside diameter. RA202, RA203, RA207 and RA208 molded to cables with maximum outside diameter up to .260" (6.6 mm).








RA200: Right-angle phone plug with plastic handle. Body extension suitable for recessed jack. Completely shielded.


RA205: Right-angle phone plug, similar to RA200, except short body extension and handle for flush mounted jacks.

MOLDED CABLE ASSEMBLIES WITH LITTEL PLUG® PHONE PLUGS (continued)









RA202: Right-angle phone plug with plastic handle. Body extension suitable where jack is recessed. RA203 is similar to RA202, except 3-conductor plug.


⟨RA207, RA208: Right-angle phone plug, similar to RA202, except short body extension. Recommended use with panel mounted jacks. RA208 is similar to RA207, except 3-conductor plug.

⟨RA217: Special right-angle phone plug, identical to RA200 (previous page); also featuring a unique hook for hanging various types of equipment (such as pillow speakers). Completely shielded. Available on special order only.

ST200: Straight phone plug with "finger grip" handle, but short enough to fit in all equipment.

ST230: Straight 3-conductor phone plug; same features as ST200. Completely shielded.

MOLDED CABLE ASSEMBLIES WITH EXTENSION JAX® PHONE JACKS



ST121: Straight Extension Jax[®] jack is a shielded 2-conductor jack with .50" (12.7 mm) outside diameter. Cable clamp connects shield or second conductor to cable. Mates with .25" (6.35 mm) diameter Switchcraft 2-conductor plugs.

ST131: Straight Extension Jax jack, same as ST121, except 3-conductor. Mates with .25" (6.35 mm) diameter Switchcraft 3-conductor plugs.

SPECIFICATIONS

Housing (or Sleeve): Nickel-plated, copper alloy.

Handle: Molded plastic. Sleeve Terminal: Plated steel. Tip and Ring Springs: Copper alloy.

Insulation: Rigid plastic. Larger design also has a molded

thermoplastic insert.

Standard Colors: Gray, white, black, brown. Other colors available on special order.

CABLE

Standard Shielded-Type W-1000-1 (for ST121).

Type W-1021-1 (for ST131).

Standard Unshielded-Type W-1033-1 (for ST121).

NOTE: See Standard Cable Chart on page 260 for details. Order by part number from guide on page 259.

Special Cables: We will build assemblies on cable furnished by you, up to .260" (6.6 mm) outside diameter, or on cables we purchase to your specifications. Jacket must have temperature rating of 60° C minimum.

PATCH CORDS & MOLDED CABLE ASSEMBLIES CABLE CLAMP BANDS AND Y JUNCTIONS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MOLDED CABLE ASSEMBLIES WITH CABLE CLAMP BANDS

SPECIFICATIONS MOLDED BAND


Housing: Plastic. Inserts can be added to our molds to include customer's name or trademark. Call for details. **Standard Colors:** Gray, white, black, brown. Other colors available on special order.

CABLE³

Standard Parallel Cable (lamp cord)—Type W-1033-1. Standard Shield Cable—Type W-1072.

ST-91 DESIGN FEATURES

- For use on stereo connecting cables and on monaural and stereo headset cables.
- Prevents further separation of individual leads on "Rip" type cordage.
- Can be used as "Y" junction when used with standard shielded cable such as Switchcraft W-1072; or as a cable clamp for general purpose with Switchcraft W-1033 and W-1050.
- Special assemblies can be built to OEM needs, using various terminal lugs, special receptacles to phone plugs or connectors.



*NOTE: See Standard Cable Chart on page 260 for details.

Special Cable: We will build assemblies on cable furnished by you (maximum diameter varies for types) or on cables we purchase to your specifications. Jacket must have temperature rating of 60°C minimum.

MOLDED CABLE ASSEMBLIES WITH "Y" JUNCTIONS

SPECIFICATIONS Y JUNCTION

Housing: Molded Plastic. Inserts can be added to our molds to include customer's name or trademark.


Standard Colors: Gray, white, black, brown. Other colors available on special order.

CABLE*

Standard Shielded Cable-Type W-1000-1. Standard Shielded Cable-Type W-1021-1.

ST-90 DESIGN FEATURES

- For use on binaural and stereophonic headphones.
- Accommodates 1- and 2-conductor shielded cables.
- Durable, strain and humidity resistant.
- Special assemblies can be built to OEM needs, using terminal lugs, special receptacles to phone plugs or connectors.



MOLDED CABLE ASSEMBLIES PART NUMBERING SYSTEM

TO CREATE A PART NUMBER

- 1. Identify Terminations (both ends)
- 2. Indicate Color and Type of Cable
- 3. Select the Length of Assembly

MOLDED CABLE ASSEMBLIES (Not all numbers shown)

| Termi | nation | Color | Cable* | Length (feet) | | | Termi | nation | |
|-------|--------|---------|--------|---------------|---|---|-------|--------|---|
| | | | | | | | | | |
| 0 | 5 | G-Gray | Α | 0 | 1 | 8 | (1.5) | 0 | 5 |
| 1 | 5 | H-Black | В | 0 | 2 | 4 | (2) | 1 | 5 |
| 2 | 5 | D-Beige | С | 0 | 3 | 6 | (3) | 2 | 5 |
| 4 | 0 | W-White | D | 0 | 4 | 8 | (4) | 4 | 0 |
| 8 | 0 | | E | 0 | 7 | 2 | (6) | 8 | 0 |
| 8 | 2 | | F | 1 | 2 | 0 | (10) | 8 | 2 |
| 8 | 3 | | K | | | | . , | 8 | 3 |
| 9 | 9 | | V | | | | | 8 | 4 |
| | | | W | | | | | | |
| | | | Χ | | | | | | |
| | | | Υ | | | | | | |
| | | | Z | | | | | | |

^{*} See "Cable Types" chart on page 260.

Notes:

- Use any 2-number codes on previous pages for termination number.
- Some configurations will be special orders. Contact Switchcraft.
- Some configurations may not be possible.
- Larger plug (#45) will be supplied in place of #40 when used with cable "A".

TYPICAL STANDARD PART NUMBERS

| STRAIGHT 2-CONDUCTOR PHONE PLUG (#05) TO: | | | | | | | | |
|---|--|------------------|--------------------------|--|--|--|--|--|
| Termination (other end) | Cable | Length (feet) | Part Number ¹ | | | | | |
| (phono plug) #05 | Α | 6 | 05HA07205 | | | | | |
| (stripped wires) #84 | Α | 3 | 05HA03684 | | | | | |
| PHONO PLUGS (#25) TO: | PHONO PLUGS (#25) TO: | | | | | | | |
| (phono jack) #82 | Α | 6 | 25HA07282 | | | | | |
| DUAL PHONO PLUGS (#25) TO: | | | | | | | | |
| (dual phono jacks) #82 | (dual phono jacks) #82 F 10 25HF12082 | | | | | | | |
| 3.5mm MINIATURE PLUG (#40) TO: | | | | | | | | |
| (3.5 mm plug) #40 | D | 6 | 40HD07240 | | | | | |

^{1.} All cables listed here are black.

PATCH CORDS & MOLDED CABLE ASSEMBLIES GENERAL CABLE GUIDE

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

STANDARD CABLE GUIDE

FOR MOLDED CABLE ASSEMBLIES ON PAGE 253 THROUGH 259

| Cable Type | Color | Description | Cable Code |
|-------------------------------|------------------------|---|------------|
| W1000 W1000-1 W1000-2 | Beige Gray Black | 50Ω coax, plastic jacket over spiral shield with 22 AWG stranded center conductor; .156" (3.96 mm) outside diameter. Average capacity 31 pF/feet, UL style 1354 | А |
| W1021-1 W1021-1 | Gray Black | 2 conductor, plastic jacket over shield with 2, 22 AWG conductor; .20" (5.2 mm) outside diameter. Average capacity 20 pF/feet between conductor; 55 pF/feet between shorted conductor to shield; 32 pF/feet each conductor to shield, UL style 2092 | В |
| W1013-1 W1013-2 | Gray Black | 2 conductor, plastic unshielded parallel with 2, 18 AWG stranded conductor; .11" (2.8 mm) x .21" (5.3 mm) outside diameter, UL type SPT-1 | К |
| W1032-1 W1032-2 | Gray Black | 48Ω coax, plastic jacket over spiral shield with 25 AWG stranded center conductor; .11" (2.8 mm) outside diameter. Average capacity 35 pF/feet | D |
| W1041-1 W1041-2 | Gray Black | 2 conductor, plastic unshielded tandem cable with 2, 24 AWG stranded conductor; .06" (1.5 mm) x .12" (2.9 mm) | Y |
| W1065-2 | Black | 50Ω coax, plastic jacket over braid shield with 26 AWG stranded center conductor; .1" (2.5 mm) outside diameter. Average capacity 30 pF/feet, RG-174 | Е |
| W1072-1 | Gray | 2 conductor, twin coax, plastic jacket over 2 individually shielded 25 AWG parallel conductor. Average capacity 36 pF/feet, recommended for headset applications | F |
| W1230-1 W1230-4 W1230-5 | Gray Beige White | 2 conductor,plastic unshielded with 2, 18 AWG stranded conductor; .25" (6.4 mm) outside diameter, UL type SVT | V |
| W1243-2 | Black | 75Ω coax, plastic jacket over shield with 27 AWG stranded center conductor; .15" (3.8 mm) outside diameter. Average capacity 20.5 pG/feet, UL style 1354 or 1436 | Х |
| W1033-1 W1033-2 | Gray Black | 2 conductor, plastic unshielded parallel with 2, 20 AWG stranded conductor; .10" (2.54 mm) x .19" (4.7 mm) outside diameter, UL style 2433 | С |
| W1096-2 | Black | 2 conductor, plastic unshielded parallel with 2, 22 AWG stranded conductor; .08" (1.9 mm) x .15" (3.8 mm) outside diameter | Z |

See page 251 for Cable Assembly Termination vs. Cable Cross Reference Table.

CROSS REFERENCE GUIDE

STANDARD CABLE ASSEMBLY TERMINATION vs. CABLE CROSS-REFERENCE

| | | Cal | ole | | | | | | | | | |
|---|--------|-----|--------|--------|---|--------|--------|-------------|---|--------|-------------|-------------|
| | | W | W | W | W | W | W | W | W | W | W | W |
| | | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| | | 0 | 0 2 | 0 1 | 0 | 0 4 | 0 6 | 0 7 2 | 2 | 2 4 | 0 3 3 | 0 |
| | | 0 | 1 | 3 | 3 | 1 | 5 | 2 | 0 | 3 | 3 | 9 6 2 |
| | | # | 1 | # | # | # | 2 | 1 | # | 2 | # | 2 |
| Т | RA40 | Х | | Х | Х | 1 | 1 | 2 | | Х | Х | 1 |
| Е | RA41 | Χ | | Х | 1 | 1 | 1 | 2 | | Х | Х | 1 |
| R | RA200 | Χ | | Х | 1 | 1 | Х | 2 | | Х | 1 | 1 |
| M | RA202 | Χ | | Х | 1 | | | 2 | Х | Х | 1 | 1 |
| Ň | RA205 | Χ | | Χ | 1 | 1 | X | | | | 1 | |
| Α | RA207 | Χ | | Χ | 1 | | | 2 | Χ | Χ | 1 | 1 |
| Ţ | RA700 | | | | Х | Х | X | 2 | | | | |
| O | RA710 | | | | Χ | Χ | Х | 2 | | | | |
| Ň | RA712A | | | Х | | | | | | | 1 | 1 |
| | RA722A | | | Х | | | | | | | 1 | 1 |
| | RA760 | Χ | | Χ | Х | 1 | 1 | 2 | Х | Х | Χ | Х |
| | RA765 | Χ | | Χ | Χ | 1 | 1 | 2 | Х | Х | Χ | Х |
| | RA850 | | | | Χ | Χ | X | 2 | | Х | | Х |
| | ST35 | Χ | Х | Х | Χ | 1 | X | 2 | | Х | Х | 1 |
| | ST40 | Χ | | Х | 1 | 1 | 1 | 2 | | Х | Х | 1 |
| | ST60 | Χ | | Χ | 1 | 1 | 1 | 2 | | Χ | Х | 1 |
| | ST121 | Χ | | Х | 1 | | 1 | 2 | Х | Х | Х | 1 |
| | ST123 | | | | Х | Х | Х | 2 | | | | 3 |
| | ST125 | Χ | | | Х | Х | Х | 2 | | Х | | Х |
| | ST131 | | Х | | | | | | | | | |
| | ST200 | Χ | | Х | 1 | 1 | X | 2 | Х | Х | 1 | 1 |
| | ST230 | | Χ | | | | | | | | | |
| | ST700 | | | | Х | Х | X | 2 | | | | Х |
| | ST710 | | | | Х | Х | X | 2 | | | | Х |
| | ST740 | Χ | | Х | 1 | 1 | 1 | 2 | | Х | Х | Х |
| | ST750 | Χ | | Х | 1 | 1 | 1 | 2 | | Х | Х | Х |
| | ST760 | Χ | | | Х | 1 | 1 | 2 | | Х | Х | 1 |
| | ST760L | | | Х | | | | | Х | | | |
| | ST765 | Χ | | | Х | 1 | 1 | 2 | | Х | Х | 1 |
| | ST765L | | | Х | | | | | Х | | | |
| | ST850 | 3 | | 3 | Х | Х | X | 2 | | 3 | 3 | 3 |
| | ST900 | Χ | Χ | Х | 1 | 1 | 1 | | Х | Х | Х | Х |

- # Indicates any number.
- X Indicates that the cable in this column and the termination in this row can be used together in a standard part number.
- These cable assemblies may use heat shrink tubing under overmolded terminations.
- 2 These cable assemblies have two of the same termination at one end. Each termination is molded in a different color.
- 3 These cable assemblies use a larger overmold than is pictured in the Engineering Design Guide.
- 4 Other termination/cable combinations may be available on special order.

PATCH CORDS & MOLDED CABLE ASSEMBLIES 1/4" TELEPHONE PATCH CORDS AND MIL TYPE 1/4" PATCH CORDS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

1/4" TELEPHONE PATCH CORDS



Switchcraft premium 3-conductor single patch cords are designed for rugged, noise-free performance. **Nickel-plated** plugs eliminate the need for periodical cleaning which keeps your audio signals clear. Color cords provide instant visual identification with a choice of three lengths. All cables are fully shielded with rugged, braided thermoplastic outer jackets. Plug handles are black. Audio patch cords are available with other lengths and brass plugs, if desired. Contact Switchcraft for specifying assistance and cable length tolerances.

MIL TYPE 1/4" PATCH CORDS

Switchcraft Patch Cords are available in a variety of types to meet requirements of communication, industrial and telephone switchboard applications. Patch cords are constructed of high quality bronze tinsel covered with thermoplastic insulating material with braided shield and black thermoplastic braid woven over the insulated conductors.

Switchcraft MIL-type Littel-Plug® and Twin-Plug® phone plugs with brass finish are attached to these quality cords. Design and material used in strict accordance with Specification MIL-P-642(A). Cords have an identifying label on cord and hot stamping on plug handle.

SERIES 20Q 3-CONDUCTOR TELEPHONE-TYPE PATCH CORDS

1/4" diameter plug fingers, black handle, color cable

PART NUMBERING SYSTEM

| 2 0 | Q | | 2 0 | | |
|---------|--|----------------------------|---------|--|---------------------------------------|
| PLUG | CABLE | LENGTH* | PLUG | FINGER FINISH | CABLE COLOR* |
| 3-cond. | Shielded 2-cond. nylon- braid sheath | D - 2' F - 3' H - 4' | 3-cond. | N-Nickel plated B-Natural brass | 0-Black 2-Red 5-Green 6-Blue |

^{*} Contact Switchcraft for other lengths and colors.





SERIES 18Q: Used in broadcasting, studio recording, sound, and other applications where space is at a premium. Utilizes Series 88Q 2-conductor shielded cord, with a Switchcraft 482 Littel-Plug phone plug with red handle (PJ-051) connected to each end. Shield grounded to sleeve of both plugs, and two leads wired tip-to-tip, ring-to-ring. Standard cord color: black. Other lengths and colors: gray, red, green (special order). Series 18Q provides same or greater number of circuits in a given space than cords using "Twin-Plug" dual telephone plugs.

| | Series 18Q, Plug Type 482 | | | | | | |
|------------|---------------------------|-------------|--|--|--|--|--|
| Length | Part | Replacement | | | | | |
| feet (m) | Number | Cord Used | | | | | |
| 0.5 (.152) | 18QA18 | 89QA89 | | | | | |
| 1 (.305) | 18QB18 | 89QB89 | | | | | |
| 2 (.610) | 18QD18 | 89QD89 | | | | | |
| 3 (.914) | 18QF18 | 89QF89 | | | | | |
| 4 (1.219) | 18QH18 | 89QH89 | | | | | |
| 6 (1.829) | 18QK18 | 89QK89 | | | | | |
| 10 (3.048) | 18QN18 | _ | | | | | |

NCE ONLY $\frac{\text{Inch}}{\text{(mm)}}$

COMBINATION PATCH CORDS



Series CPC Combination Patch Cords provide convenient interconnections between standard telephone-type jacks (3-conductor, .25" inside diameter sleeve) and miniature telephone-type jacks (3-conductor, .173" inside diameter). Series CPC cords are ideal for connection in telephone, data processing and other telecommunication applications where both standard and miniature jacks are available for patching.


FEATURES

- Rugged, telephone-quality tinsel conductors, with slate gray, braided thermoplastic jacket with flex relief reinforcements at point of entry into each plug handle.
- Series CPC cords, eliminates the need for a separate adapter or field-fabricated combination cords.
- 3. Switchcraft (on special order) can assemble cords of any practical length.
- ♦ SERIES CPC101: Standard 2-conductor, 413 Twin-Plug (.25" outside diameter finger) on one end; miniature, 3-conductor TT253, TT Twin-Plug (.173" outside diameter finger) on the other end. One twin plug tip to miniature plug ring. All sleeves connected to cable shield. 6, 10, 15, 20 and 25 foot lengths.

- ♦ SERIES CPC103: Standard 2-conductor, 413 Twin-Plug (.25 " outside diameter finger) on one end with cable-connected shield to sleeve; two independent tip circuits. Other end miniature, TT261, TT Twin-Plug (.173" outside diameter finger) in the same wiring. 6, 10, 15, 20 and 25 foot lengths.
- ♦ SERIES CPC104: Standard 3-conductor, 414 Twin-Plug (.25 " outside diameter finger) on one end; miniature 3-conductor, TT263, TT Twin-Plug on other end. Wired at 5-conductor tips-to-tips, rings-to-rings, all sleeves to cable shield. 6, 10, 15, 20 and 25 foot lengths.

| Part Number | Length | Description |
|----------------|----------|---|
| ♦CPC102A | 6 inches | |
| ♦CPC102D | 2 feet | Standard 3-conductor (483) |
| ♦CPC102F | 3 feet | telephone plug (.25" outside |
| ♦CPC102K | 6 feet | diameter finger) on one end; miniature (253) tini-telephone® |
| ♦CPC102N | 10 feet | 3-conductor (.173" outside |
| ♦CPC102R | 15 feet | diameter. finger) plug on |
| ♦CPC102T | 20 feet | other end.(See Schematic). |
| ♦CPC102U | 25 feet | |

♦ Special order only; contact factory for price and delivery.





MIL-TYPE 1/4" TWIN PATCH CORDS

SERIES 22Q: For use in telephone patching, broadcasting, studio recording, high-quality public address systems, telephone, telecommunications, and instrumentation systems. Uses 4-conductor shielded cord with Switchcraft Number 414 Twin-Plug® connected to each end. Shield is grounded to sleeve of each plug and individual leads wired tip-to-tip and ring-to-ring. Twin-Plug 414 is a 6-circuit plug with electrically independent tip circuits and ring circuits, with plug fingers spaced on .625" center to fit standard twin jacks. A self-aligning feature accommodates errors in jack location. Standard lengths: 1 feet to 10 feet; standard color: black. Other lengths and colors are available.

| Part Number | Length, feet (m) | |
|----------------|------------------|--|
| ⊘22QB22 | 1 (.305) | |
| ⊘22QD22 | 2 (.610) | |
| ⊘22QF22 | 3 (.914) | |
| ⊘22QK22 | 6 (1.829) | |
| ⊘22QN22 | 10 (3.048) | |

♦ Special order only; contact factory for price and delivery.

DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm



CABLE AND PLUG FINGER COMBINATIONS

2-Conductor Patch Cord. Two-conductor Bantam-Type® plug, Switchcraft TT251 at each end. Shield (75% coverage) is grounded to each plug sleeve. Tinsel conductor is wired tip-to-tip. Standard color: black. Other colors and lengths are available on special order.

| Part Number | Description | Length, feet (m) |
|---------------|-------------------------------|------------------|
| ♦TT722 | | 1 (.305) |
| ♦TT724 | 2-conductor single, | 2 (.61) |
| ♦TT726 | brass finish on plug fingers, | 3 (.914) |
| ♦TT727 | black handle and cord. | 4 (1.219) |
| ♦TT728 | Identifying label on cord. | 5 (1.524) |
| ♦TT729 | | 6 (1.829) |

3-Conductor Patch Cord. 3-conductor Bantam-Type plug (Switchcraft TT253) at each end. Wiring is the same as TT724, except also has ring-to-ring wiring.


| Part Number | Description | Length, feet (m) |
|----------------|---|------------------|
| ♦TT741 | 3-conductor single, brass finish on plug fingers, black handle and cord. Identifying label on cord. | 0.5 (.152) |
| ♦TT742 | | 1 (.305) |
| ♦ TT744 | | 2 (.61) |
| ♦TT746 | | 3 (.914) |
| ♦TT747 | | 4 (1.219) |
| ♦\tag{TT748} | | 5 (1.524) |
| ♦TT749 | | 6 (1.829) |
| | | |

| Part Number | Description1, 2 | Length, feet (m) |
|-------------|---|------------------|
| ♦TT741N0 | 2 conductor cinals | 0.5 (.152) |
| ♦TT742N0 | 3-conductor single, | 1 (.305) |
| ♦TT744N0 | nickel-plated plug fingers (brass available) black | 2 (.61) |
| ♦TT746N0 | | 3 (.914) |
| ♦TT747N0 | handles and cord. | 4 (1.219) |

3-Conductor Twin Patch Cords. 5-circuit patch cords use two 3-conductor twin Bantam-Type plugs, Switchcraft TT-263, at each end. Sleeve circuits are wired common, and tinsel conductors are wired tip-to-tip and ring-to-ring (see schematic). Polarizing handle notches indicated plug fingers with interconnected tip and rings. Standard color: black. Other colors and lengths are available on special order.

| Part Number | Description | Length, feet (m) |
|---------------|---|------------------|
| ♦TT861 | | 0.5 (.152) |
| ♦TT862 | 3-conductor twin. | 1 (.305) |
| ♦TT864 | brass finish on plug fingers, black handle and cord. Identifying label on cord. | 2 (.61) |
| ♦TT866 | | 3 (.914) |
| ♦TT867 | | 4 (1.219) |
| ♦TT868 | | 5 (1.524) |
| ♦TT869 | | 6 (1.829) |

- 1. For brass fingers, substitute "B" for "N" in part number. Special order only. 2. "0" in part number denotes black handle and cord. Substitute the following
 - for "0" to specify other color cords: 2-Red 5-Green 6-Blue
- \lozenge Special order only; contact Switchcraft for prices and delivery.



DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)

TT100 SERIES

* Please visit the product pages on our website for the most up-to-date product information


MINIATURE TT® MOLDED PATCH CORDS (continued)




| Part N | umbers | Length |
|--------------|--------------|--------------|
| Series TT100 | Series TT120 | feet (m) |
| ♦TT101 | ♦TT121 | 0.5 (.152) |
| ♦TT102 | ♦TT122 | 1.0 (.305) |
| ♦TT103 | ♦TT123 | 1.5 (.457) |
| ♦TT104 | ♦TT124 | 2.0 (.610) |
| ♦TT105 | ♦TT125 | 2.5 (.762) |
| ♦TT106 | ♦TT126 | 3.0 (.914) |
| ♦TT107 | ♦TT127 | 4.0 (1.219) |
| ♦TT108 | ♦TT128 | 5.0 (1.524) |
| ♦TT109 | ♦\tag{TT129} | 6.0 (1.829) |
| ♦TT110 | ♦TT130 | 7.0 (2.134) |
| ♦TT111 | ♦TT131 | 8.0 (2.438) |
| ♦TT112 | ♦TT132 | 9.0 (2.743) |
| ♦TT113 | ♦TT133 | 10.0 (3.05) |
| ♦TT114 | ♦TT134 | 11.0 (3.353) |
| ♦\TT115 | ♦TT135 | 12.0 (3.658) |

| 32.13 1.265 21.97 | "LENGTH" SEE TABLE | - | 3 CONDUCTOR PLUG ASSEMBLY | · \ |
|-------------------------|-----------------------|--|------------------------------|-----------------|
| | J. 5555 3 6 | (1111111111111111111111111111111111111 | | વ્યાવ |
| | | | 7.62 0.300 | (4.39) Ø.173 |
| TT120 SERIE | S | | | |

| Part N | umbers | Length |
|--------------|--------------|--------------|
| Series TT140 | Series TT160 | feet (m) |
| ♦TT141 | ♦TT161 | 0.5 (.152) |
| ♦TT142 | ♦TT162 | 1.0 (.305) |
| ♦TT143 | ♦\tag{TT163} | 1.5 (.457) |
| ♦TT144 | ♦TT164 | 2.0 (.610) |
| ♦TT145 | ♦TT165 | 2.5 (.762) |
| ♦TT146 | ♦TT166 | 3.0 (.914) |
| ♦TT147 | ♦TT167 | 4.0 (1.219) |
| ♦TT148 | ♦TT168 | 5.0 (1.524) |
| ♦TT149 | ♦TT169 | 6.0 (1.829) |
| ♦TT150 | ♦TT170 | 7.0 (2.134) |
| ♦TT151 | ♦TT171 | 8.0 (2.438) |
| ♦TT152 | ♦TT172 | 9.0 (2.743) |
| ♦TT153 | ♦\TT173 | 10.0 (3.05) |
| ♦TT154 | ♦TT174 | 11.0 (3.353) |
| ♦TT155 | ♦TT175 | 12.0 (3.658) |





TELEPHONE COUPLERS AND ADAPTERS

TELEPHONE PATCH COUPLERS

TT-couplers interconnect 2- or 3-conductor patch cords terminated with Switchcraft standard or tini-telephone® plugs, also similar telephone plugs with compatible finger shape and dimensions.

| Part Number | Handle Color | Cond. | Input ID Inch (mm) | Output ID Inch (mm) | |
|----------------|-----------------|-------|-----------------------|------------------------|--|
| ♦ TT281 | Black | 2 | | | |
| ♦ TT282 | Red | 2 | 175 (4.44) | 475 (4 44) | |
| ♦ TT283 | Black | 3 | .175 (4.44) | .175 (4.44) | |
| ♦TT284 | Red | 3 | | | |
| ♦ TT289 | Metal | 3 | .175 (4.44) | .25 (6.35) | |
| 361A | Metal | 2 | 05 (6.05) | 0F (6.0F) | |
| ♦ 362A | Metal | 3 | .25 (6.35) | .25 (6.35) | |

[♦] Special order only; contact factory for prices and delivery.

TT-REPLACEMENT CORDS

Series TT700 cords have bronze tinsel conductors covered with thermoplastic insulation. A braided shield surrounds the conductors, and the cord is finished with a braided black thermoplastic jacket. Cord ends are reinforced to accept the internal threaded end of a TT-Phone Plug® plug. Used as a replacement cord for Series TT720 and TT740 patch cords, and used on TT-Twin Plug® plugs, Series TT260, in dual cable assemblies with 2- and 3-conductor (or combinations) plug fingers requiring independent tip, ring and sleeve circuits, and for single cable assemblies where supplementary cross-over wiring is needed for common tip, ring and/or sleeve circuits.

♦ TT701 - Length 6" (152.4 mm). **♦ TT709** - Length 6' (1.829 m).

PATCH CORDS & MOLDED CABLE ASSEMBLIES VIDEO PATCH CORDS

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

VIDEO PATCH CORDS

Switchcraft new broadcast series video patch cords are available in eight base ten color codes. Our cable is a high performance serial digital 75 Ohm RG59 type. This unique low-loss cable is ideal for "True" 75 Ohm HD patching as well as conventional analog signals.

The jacket is made flexible with very low retract memory.

FEATURES:

- * Rugged nickel-plated handles knurled for positive finger grip.
- * Flexible black "boot" placed on all cable colors for more positive grip and cable strain relief.
- * Overall flexible jacket for easy coil and low retract memory.

SPECIFICATIONS:

Plug Housing: Nickel-plated, copper alloy. Plug Contact Pin: Gold-plated, copper alloy. Conductor: 22 AWG (19 x 34) Cable:

Stranded BC

95% BC Braid

Shield: Dielectric:

.146", 3.70mm, Cellular (Foam) PE

Matte Finish PVC Jacket:

75 Ohm Nom. Imp:



| VP | | | VMP | | |
|-------|--------|-------|-------|--------|-------|
| Video | Length | Cable | Video | Length | Cable |
| Patch | (Feet) | Color | Patch | (Feet) | Color |

| Part Numbering System | | |
|-----------------------|-------------|---------------|
| Video Patch Cords | Video Patch | Length (Feet) |
| Standard .090 WECO | VP | |
| Midsize Video Patch | VMP | |

| Colors | | Color Code | Stock Lengths |
|--------|---|------------|---------------|
| | | | 1' |
| Black | = | BK | 2' |
| Red | = | R | 3' |
| Orange | = | 0 | 4' |
| Yellow | = | Υ | 5' |
| Green | = | GN | 6' |
| Blue | = | BL | 7' |
| Purple | = | Р | 8' |
| Gray | = | GY | 9' |
| | | | 10' |
| | | | |

(Custom lengths are available by request)



Inch

Dual Bantam TT

Single Bantam TT

TTD

* Please visit the product pages on our website for the most up-to-date product information

3-CONDUCTOR TT PATCH CORDS: ANALOG / AES/EBU AUDIO AND RS422 PATCHING

Switchcraft single 3-conductor TT audio patch cords have now been designed with a low capacitance cable which at 110 Ohms is ideal for digital audio AES/EBU and SMPTE Mtime code patching. The overall jacket is now flexible in eight colors. The nickel plated plugs allow for non-tarnishing and the overmolded handle-boot reduces strain off the cable when pulled.

Switchcraft dual 3-conductor TT patch cords have also been redesigned with an overall flexible cable and six colors to choose from. Like the single TT the dual plugs are nickel plated and flexible. These cords work with all Switchcraft TT stereo spaced bays for analog audio and RS422 data patching.

SPECIFICATIONS

Standard plug terminations are single 3-conductor TT. Plug handle is molded thermoplastic.

Plugs: Tip Rod, Ring and Sleeve - Copper Alloy 26 AWG (30x40) OFBC, 110 Ohm Low Cable: Capacitance. Jacket is Matte PVC

| TT Tiny Telephone | Length (Feet) | Cable Color | TTD Tiny Telephone | Length (Feet) | Cable Color |
|-------------------|------------------|----------------|--------------------|---------------|----------------|

| Part Numbering System Video Patch Cords | Video Patch | Length (Feet) | Cable Color |
|--|-------------|---------------|-------------|
| Single Bantam TT | TT | | |
| Dual Bantam TT | TTD | | |

TTD Not available in purple or gray.

| Colors | | Color Code | Stock Lengths |
|--------|---|------------|---------------|
| 001013 | | COIOI COGE | Otock Lengths |
| | | | 1' |
| Black | = | BK | 2' |
| Red | = | R | 3' |
| Orange | = | 0 | 4' |
| Yellow | = | Υ | 5' |
| Green | = | GN | 6' |
| Blue | = | BL | 7' |
| Purple | = | Р | 8' |
| Gray | = | GY | 9' |
| | | | 10' |

(Custom lengths are available by request)



DIMENSIONS ARE FOR REFERENCE ONLY

¹ Foot (12" inches) equals 3.28 meters

MINIATURE KEYBOARD SWITCHES

IBS MINIATURE SWITCHES

SERIES 98000R

Momentary IBS switches provide cost-effective versatility for a wide range of electrical/electronic applications including switching analog and digital signals in business systems, public address, test instruments, medical, EDP (computer), input devices and peripheral equipment, local area network, telecommunication, digital transmission equipment, telephone systems and attachments and calculators. Convenient modular design allows quick assembly to PC boards. These switches are also available in multiple station assemblies (see page 308).

SPECIFICATIONS

MECHANICAL

Switch Actuation: Momentary Plunger Travel: .144" (3.66 mm).

Actuation Force (Full Travel): 12-15 ounce (340-425 grams).

Life: 1 million operations.

ELECTRICAL

UL approved at .25 A @ 28V DC and .125 A @ 125V AC

MATERIALS


Housing: Molded thermoplastic UL 94V-0 Plunger: Molded thermoplastic UL 94V-0.

Contactors: Copper alloy.

Terminals: Copper alloy, solder-plated. Contact Surfaces: Gold-plated.

MOUNTING

Switches have .157" (4 mm) long PC terminals for mounting on single- or double-sided PC boards up to .094" (2.4 mm) thick on 0.394" (10 mm) minimum centers in rows or arrays. 0.394" (10 mm) PC terminals available on special order. Rugged molded-in standoff legs provide stable mounting and clearance for PC board cleaning.



ORDERING STANDARD SWITCHES

Order switches and pushbuttons by part numbers from table. PART NUMBERS

| Part No.1 | Description | Circuit | Dim. A |
|-----------|-------------|---------|-------------------|
| 982A01R | | 1-A | 4.571 |
| 982A03R | Momentary | 1-C | .157" . (4 mm) |
| 982A06R | | 2-C | 1 ('''''') |

¹ Order pushbuttons separately.

ORDERING SPECIAL SWITCHES


Contact your Switchcraft representative with full specifying details.

SPECIAL ORDER FEATURES

- Other circuitry 1B, 2A or 2B
- Longer terminals .394" (10 mm) long.

IBS SWITCH CATALOG NUMBERING SYSTEM 98 X X XX D R SERIES • ♦ D - Make-Before-Break (Shorting Contacts) 98 - 98000R (Use with 03, 06 circuits only when required.) **MECHANICAL FUNCTIONS •** 2 - Momentary CIRCUITS TERMINALS •-A - .157" (4 mm) 01 - 1A 04 - 2A ♦ B - .394" (10 mm) ◊ 02 - 1B ◊05 - 2B 03 - 1C* 06 - 2C

[♦] Special order only; contact Switchcraft for price and delivery.
* Non-shorting (break-before-make) contacts



TERMINAL FUNCTION BY TERMINAL NUMBER

| | | First F | Pole ¹ | | Secon | d Pole |
|---------|------------------|---------|-------------------|------|--------|--------|
| Circuit | N.O. N.C. Common | | N.O. | N.C. | Common | |
| 1-A | 3 | - | 2 | - | - | 5* |
| 1-B | - | 1 | 2 | - | - | 5* |
| 1-C | 3 | 1 | 2 | - | - | 5* |
| 2-A | 3 | - | 2 | 6 | - | 5 |
| 2-B | - | 1 | 2 | - | 4 | 5 |
| 2-C | 3 | 1 | 2 | 6 | 4 | 5 |

^{*}Pin 5 is used as a support pin for switch mounting and has no electrical connection. 1. N.O.= normally open; N.C.= normally close.

RECOMMENDED PC BOARD LAYOUT (.300 x .100) (Component Side) 3 6 2 5 1

KEYBOARD SWITCH PUSHBUTTONS

Pushbuttons designed for IBS switches are available in white, black, red, blue, and gray. Other colors are available on special order. Pushbutton faces are concave for operator convenience and can be mounted either horizontally or vertically. Pushbuttons must be ordered separately, but may be factory installed, if desired, at extra cost.







TYPE II

PART NUMBERS


| Type I | Type II | Color | Type I | Type II | Color |
|---|---|--|--|----------------|---|
| P2936 P2937 P2938 ◊P2939 ◊P2940 | P2951 P2952 P2953 \$\rightarrow{P2954} \$\rightarrow{P2955} | White Black Red Yellow Green | P2941 P2942 \$\rightarrow\$P2943 - - | P2956 P2957 | Blue Gray Brown Cream Tangerine |

[♦] Special order only; contact Switchcraft for price and delivery.

LEGENDS

Engraved letters and numbers are available on special order. A-Z, ON and OFF in Condensed Block typeface are available. Other custom legends may be supplied (please inquire). Refer to drawing and chart for legend data.

| Character Height inches (mm) | Мо | ontal unt . Max.) | HORIZONTAL MOUNT |
|------------------------------------|-----------------------------------|-------------------------|------------------|
| | I | Ш | |
| 1/8" (3.175) | 3 | 4 | |
| 3/32" (2.381) | 4 | 5 | LEGEND |
| 5/64" (1.984) | 4 | 5 | AREA |
| Character Height inches [mm] | Vertical Mount (Char. Max.) | | VERTICAL MOUNT |
| | I | Ш | |
| 1/8" (3.175) | 1 | 1 | |
| 3/32" (2.381) | 2 | 2 | LEGEND AREA |
| 5/64" (1.984) | 2 | 3 | |



UNISWITCH® SWITCHES

SERIES US - Non-illuminated, SERIES LUS - Illuminated

Cost-effective Uniswitch switches are lighted or non-lighted momentary switches featuring snap-in mounting in a single hole and a choice of solder/screw (#5-40), solder/quick-connect (AMP FASTON® 110) 60967-1, or stand-off PC terminals. Molded housing protects internal parts, and bezel functions as built-in escutcheon. Series LUS accepts T 1-3/4 bi-pin lamps. (Lamps not included.) ®FASTON is a registered trademark of AMP INC.

MOUNTING

"Snap-in" mounting is in .617" (15.67 mm) minimum square hole-for row or matrix mounting. Panel thickness: .047" (1.19 mm) to .266" (6.76 mm) maximum. To mount, simply press switch into panel; "Adjusto-Clip" locking tabs engage panel and hold switch securely. Behind panel distance is 1.312" (33.32 mm) minimum.

SPECIFICATIONS

Switch Housing: Molded plastic, charcoal gray only.

"Adjusto-Clip": Copper alloy.

Contactor: Copper alloy plated. Form 1-A rated: 250 mA, 30 W maximum, AC, non-inductive load.

Terminals: Copper alloy, silver-plated. **Pushbuttons:** Molded plastic in 8 colors.

Operating Force: 12 - 16 ounce (340-454 grams).


SPECIAL ORDER FEATURES

- · Other contactor platings.
- Engraved legends (See page 270).
- Other pushbutton colors.
- "Adjusto-Clips" set to positions 2, 3, 4, or 5.

PART NUMBERS (Order switches and pushbuttons separately)

| Terminal Type/Part Number; Series US | | | Tern | ninal Type/Pa Series L | , , |
|---|---------|---------|--------|---------------------------|--------------------------|
| Solder/ Screw | | | | Printed Circuit | Solder/ Quick-Connect |
| US001 | US001PC | US001ST | LUS001 | LUS001PC | LUS001ST |

^{1.} Lamp not included.



"ADJUSTO-CLIP" MOUNTING


| Position Number | Panel Thickness Inch (mm) | | Position Number | Panel Th Inch | |
|--------------------|------------------------------|------------|--------------------|------------------|------------|
| | Min. | Max. | | Min. | Max. |
| 1* | .047 (1.2) | .078 (2.0) | 4 | .188 (4.8) | .219 (5.6) |
| 2 | .094 (2.4) | .125 (3.2) | 5 | .234 (6.0) | .266 (6.8) |
| 3 | .141 (3.6) | .172 (4.4) | | | |

 $^{^{\}star}$ "Adjusto-Clips" normally installed in this position unless otherwise specified.

PUSHBUTTONS* (Pushbuttons ordered separately from switches.)

| Part Number | Color | Part Number | Color |
|-------------|-------|-------------|--------|
| P23491 | Red | P23495 | White |
| P23492 | Black | P23497 | Orange |
| P23493 | Green | P23498 | Yellow |
| P23494 | Blue | ♦P234913 | Amber |

^{*} Extra replacement pushbuttons can be ordered separately.



DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm

 $[\]Diamond$ Special order only; contact Switchcraft for price and delivery.

BOX SWITCH® SWITCHES



BXR013PC

SERIES BXR

Economical momentary, non-illuminated switches feature "Adjusto-Clip" snap-lock mounting and selection of switching. Bezel trims mounting and enclosed construction protects against dust, dirt, and physical damage. Color pushbuttons have concave face for positive "feel".

MOUNTING

Front mount in .620" (15.75 mm) minimum square hole. Solder lug/quick-connect terminals accept AMP FASTON® 110 terminals; PC terminals fit boards up to .281" (7.14 mm) thick. "Adjusto-Clip" permits mounting in panels from .047 ' (1.19 mm) to .281" (7.14 mm) thick.

[®]FASTON is a registered trademark of AMP INC.

SPECIFICATIONS

Housing: Molded plastic, charcoal gray only. Pushbutton: Molded plastic; red, black, green, and

white standard.

"Adjusto-Clip" Mounting Frame: Copper alloy, plated.

Contact Springs: Copper alloy, plated. Contacts: Integral, copper alloy, plated.

1-A, 1-C, 2-C, or 2-A + 2-C

Switching: 250 mA, 30 W max., AC, non-inductive load.

Terminals: Copper alloy, silver-plated.

SPECIAL ORDER FEATURES

- Other contact platings.
- Engraved legends (see page 270).
- Other pushbutton colors.
- "Adjusto-Clips" set to positions 2, 3, 4, or 5.

SHOWN ACTUAL SIZE



Rear view, BXR056 Solder Lug/Quick-Connect Terminals.



Rear view, BXR013PC PC Terminals.

PART NUMBERS


| | | Circuits | | | | | |
|---|--|---|--|--------------------------------|--|--|--|
| Red | Black | Green | White | | | | |
| | Solder Lug/Quick-Connect Terminals | | | | | | |
| BXR011 BXR013 BXR016 BXR0110 | BXR013 BXR023 BXR033 BXR053 BXR016 BXR026 BXR036 BXR056 | | | | | | |
| | | PC Terminals | | | | | |
| ♦BXR011PC ♦BXR013P BXR016PC ♦BXR0110PC | ♦BXR021PC ♦BXR023P BXR026PC ♦BXR0210PC | ♦BXR031PC ♦BXR033PC ♦BXR036PC ♦BXR0310PC | ♦BXR051PC ♦BXR053PC ♦BXR056PC BXR0510PC | 1-A 1-C 2-C 2-A + 2-C | | | |

[♦] Special order only; contact factory for price and delivery.

"ADJUSTO-CLIP" MOUNTING POSITIONS

| Position | Panel Thickness Inch (mm) | | | | |
|----------|---------------------------|------------|--|--|--|
| Number | Minimum | Maximum | | | |
| 1* | .047 (1.2) | .094 (2.4) | | | |
| 2 | .094 (2.4) | .141 (3.6) | | | |
| 3 | .141 (3.6) | .188 (4.8) | | | |
| 4 | .188 (4.8) | .234 (6.0) | | | |
| 5 | .234 (6.0) | .281 (7.1) | | | |

^{* &}quot;Adjusto-Clips" normally installed in this position unless otherwise specified.



DIMENSIONS ARE FOR REFERENCE ONLY

Inch

BUTTON-SWITCH® SWITCHES



SERIES 903, 913, 923, 933

These small momentary switches are completely enclosed in rugged metal housing. Front or rear-panel mount types offer 1-A, 1-B, 1-C, or 1-D switching. Red or black pushbuttons and solder terminals are standard. Series 903 and 913 are front mount in .469" (11.91 mm) diameter hole in panels up to .297" (7.54 mm) thick. Series 923 and 933 are rear mount in .250" (6.35 mm) diameter hole in panels up to .156" (3.96 mm) thick. Mounting hardware is supplied.

SPECIFICATIONS

Body: Copper alloy, plated.

Pushbutton: Molded red or black plastic, integral with shaft.

Insulation: Rigid plastic.

Springs: Integral contacts, plated.

Ratings: 250 mA, 30 W maximum, AC, non-inductive load.

Solder Terminals: Copper alloy, silver-plated.

Locknuts: Copper alloy, plated. Series 903, 913: P-1053-1. Series 923, 933: P-1150-1.

Lockwasher: Series 903, 913: Steel, P-1060-3 Flat Washer: Series 923, 933: Steel, plated, S-1790-1

SPECIAL ORDER FEATURES

• Other pushbutton colors. • Legends.

PART NUMBERS

| Panel Mounting | Pushbutton Cold | or/Part Number | Circuit | Schematic ¹ |
|----------------|-----------------|----------------|---------|------------------------|
| | Red Black | | | |
| Front | 903 | 913 | 1-C | |
| Tiont | ♦903D | ⟨913D | 1-D | 1-C |
| Rear | 923 | 933 | 1-C | ₹ E |
| neai | ♦923D | ♦933D | 1-D | <u>□</u> 1.D |

^{1.} Circuits C or 1-D can be wired for either 1-A or 1-B switching

TINI-SWITCH® SWITCHES



SERIES 950, 960

Momentary Tini-Switch® switches are miniaturized versions of Littel-Switch® switches (see page 274 for construction details). .25 A contacts are intended for low-power switching where contact resistance is not critical. Red or black pushbuttons, solder lug terminals and choice of 1-A, 1-B and 1-C switching is standard.

MOUNTING

Switches mount from rear in .250" (6.35 mm) diameter hole in panels up to .094" (2.39 mm) thick. Mounting washers and locknuts are supplied.

SPECIFICATIONS

Bushing: Copper alloy, plated.

Pushbutton: Molded plastic, integral with shaft.

Insulation: Rigid plastic. **Springs:** Copper alloy.

Contacts: Integral contacts are standard. .25 A, 30 W

maximum, AC, non-inductive load. **Washer:** Steel, plated, S17901. **Locknut:** Copper alloy, plated, P11501.


SPECIAL ORDER FEATURES


• Other pushbutton colors. • Legends.

PART NUMBERS

| Pushbutton Col | or/Part Number | Circuit | Schematic |
|----------------|----------------|-------------------|--------------|
| Red Black | | | |
| 951 | 961 | 1-A, SPST, (N.O.) | 凸 1-A |
| ♦952 | | 1-B, SPST, (N.C.) | <u>出</u> |
| 953 | 963 | 1-C, SPDT | <u>н</u> 1-С |

[♦] Special order only; contact Switchcraft for price and delivery.





Series 950 & 960

Inch


[♦] Special order only; contact Switchcraft for price and delivery.

SWITCHES <u>LITTEL-SWITCH® SWITCH WS SERIES 100,</u> 1008, 200, 2008

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

LITTEL-SWITCH® SWITCHES



SERIES 100, 100S, 200, 200S

Momentary switches feature leaf springs, insulating spacers, notched insulating washers and plated copper alloy bushing assembled into a rugged, reliable, long-life switch for limited space applications. Series 100 and 200 have integral .25 A contacts intended for low power switching where contact resistance is not critical. Series 100S and 200S have 3 A fine silver contact. Red and black pushbuttons, solder lug terminals and choice of 1-A, 1-B or 1-C switching are standard. Shaft and pushbutton molded as one piece. Captive shaft extends through bushing, actuated leaf springs. Notched phenolic washers insulate springs and interlock all members, eliminating possibility of springs shifting. All springs are insulated from bushing.

MOUNTING

Switches mount from rear in panels up to .250" (6.35 mm) thick in .375" (9.52 mm) diameter holes. Locknuts and washers are supplied.

LEGENDS

Switchcraft offers a wide variety of engraved legends on special order. Contact Switchcraft for details.

PART NUMBERS

| Pushbutton Co | lor/Part Number | Circuit | Schematic |
|---------------|-----------------|--------------------|---------------|
| Red | Red Black | | |
| 101 | 201 | 1-A, SPST, (N.O.) | مه |
| ♦101S | ⊘201S | 1-A, 3F31, (N.O.) | 1-A 🖶 |
| | 202 | 1-B, SPST, (N.C.) | ₽ |
| | ⊘202S | 1-b, or or, (N.O.) | 1-B |
| 103 | 203 | - 1-C, SPDT | ~ <u>T</u> to |
| | ⊘203S | 7 1-0, 01 01 | 1-C ±0 |

♦ Special order only; contact Switchcraft for price and delivery.
"S" at the end of part number indicates 3H rated fine silver contacts.

SPECIFICATIONS

Bushing: Copper alloy, plated.

Pushbutton: Molded plastic, integral with shaft.

Insulation: Rigid plastic. **Springs:** Copper alloy.


Contacts: Integral contacts are standard. (Series 100, 200) .250 A, 30 W maximum, AC, non-inductive load. Riveted silver contacts (Series 100S, 200S); 3A, 300 W maximum

AC, non-inductive load. **Washer:** Steel, plated, S10221.

Locknut: Copper alloy, plated, P10001.

SPECIAL ORDER FEATURES

- Other pushbutton colors.
- Legends.
- Welded crossbar palladium contacts for dry circuit.



DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)

HI-D SWITCH® PC MOUNT SWITCHES

SERIES H-100, H-100PC, H-200, H-200PC

Compact, momentary switches mount on .625" (15.87 mm) centers in rows or matrix arrays and are the same height and panel size as Switchcraft's Hi-D Jack. Rugged "box" body protects contact springs against mechanical damage and keys them in precise alignment. Precision springs produce high contact pressure, smoother wear-reducing actuation, and positive "make-break". Recommended where contact resistance is not critical.

MOUNTING

Rear of panel mount in .375" (15.87 mm) diameter hole in panels up to .156" (3.96 mm) thick. Behind panel space: 1.094" (27.79 mm) minimum. Mounting hardware supplied. Switches with PC terminals mount directly to PC boards, and may also be panel mounted with threaded bushing.

SPECIFICATIONS

Switch Housing: Molded plastic.

Mounting Bushing: Copper alloy, plated.

Pushbutton/Actuator: Thermoplastic, red or black with

concave face.

Contact Springs: Copper alloy, silver or gold-plated. **Contacts:** Integral, 1-A, 1-B, 1-C, or 1-D, 0. 25 A, 30 W

maximum, non-inductive load. **Contactor:** Copper alloy, plated.

Locknut: Copper alloy, plated. P10001 (supplied). **Washer:** Steel, nickel-plated. S10221 (supplied).

SPECIAL ORDER FEATURES

- Other pushbutton colors.
- Legends (see page 270).



DA-SWITCH SWITCHES

SERIES DA

Enclosed momentary pushbutton switch. Designed to meet switching requirements of computers, data processors, ground support systems, machine and process controls, test equipment and intercoms. Anodized aluminum body protects switch contacts from dirt, dust and bending during mounting. Terminals accept AMP Series 53 taper pins. Mount in .375" (9.5 mm) hole on .531" (13.5mm) centers. Behind panel depth .938" (23.8mm) minimum.

SPECIFICATIONS

Housing: Aluminum, black anodized. **Button:** Thermoplastic, black.

Terminal Base: Thermoset black phenolic. **Terminals:** Copper alloy, gold-plated. **Contacts:** Integral. 500 mA, 5 W maximum,


non-inductive load.

Contactor: Copper alloy, plated.

Hardware: Supplied with one, ◊P1970 aluminum, black anodized knurled mounting nut, and one,

P1971 parkerized lockwasher.






SERIES H100, H200

PART NUMBERS

| Solder Lug Terminals Pushbutton Color/Part Number | | PC Ten | minals | | |
|---|-------|------------------------------|------------------------------|--------------------------|-----------|
| | | Pushbutton Col | or/Part Number | Circuit | Schematic |
| Red | Black | Red | Black | | |
| H101 | H201 | ♦H101PC ♦H102PC H103PC | ♦H201PC ♦H202PC H203PC | 1-A 1-B 1-C 1-D | See Below |


♦ Special order only; contact factory for price and delivery.



PART NUMBERS

| Series DA | Button Color | Circuit | Schematic |
|----------------|---------------------|---------|---|
| ⊘DA013 | Red | A-B | A-B contacts may be externally wired to |
| ♦ DA023 | Black | A-B | provide a 1-C circuit as illustrated below. |
| ♦ DA033 | Green | A-B | r <u>a</u> • B |
| ♦ DA043 | Blue | A-B | c |
| ♦ DA053 | White | A-B | ○ •A |
| ♦ DA083 | Yellow | A-B | KEY |
| | | | |

 \Diamond Special order only; contact Switchcraft for price and delivery.



DIMENSIONS ARE FOR REFERENCE ONLY



SWITCHES CORD-SWITCH® AND CORDETTE® CORD SERIES SWITCHES

* Please visit the product pages on our website for the most up-to-date product information

CORD-SWITCH® CORD SWITCHES

SERIES E900, ED900, EP900

Momentary cord (pendant) switches can be specified with red or black pushbuttons, 1-C or 1-D switching, solder terminals and metal handle (Series E900), plastic handle (Series EP900), or metal handle with clamp and strain relief (Series ED900).

SPECIFICATIONS

(See page 273 for switch specs.)

SERIES E900, EP900:

Housing: Series E900 - Copper alloy, plated. Series EP900 - Molded black plastic.

Series EP900 - Molded black plastic. **Switch Bushing:** Copper alloy, plated.

Insulation: Rigid plastic.

SERIES ED900:

Housing: Die-cast zinc, plated.

Switch Body and Insert Bushing: Copper alloy, plated.

Insulation: Rigid plastic.

Cable Relief Bushing: Black thermoplastic rubber.

Pressure Plates: Stainless steel.

Cable Relief Screws: Steel, plated.


SPECIAL ORDER FEATURES

Other pushbutton colors.
 Custom legends

PART NUMBERS (examples)

| Pushbutton Color/Part Number | | Maximum Cable Outside Diameter | Circuit | |
|---------------------------------|---------|--------------------------------|---------|--|
| Red | Black | Outside Diameter | | |
| E903 | E913 | .375" [9.5 mm] | | |
| ED903 | ED913 | .375" [9.5 mm] | 1-C | |
| EP903 | EP913 | .250" [6.4 mm] | | |
| ♦E903D | ♦E913D | .375" [9.5 mm] | | |
| ♦ED903D | ♦ED913D | .375" [9.5 mm] | 1-D | |
| ♦EP903D | ♦EP913D | .250" [6.4 mm] | | |

♦ Special order only; contact Switchcraft for price and delivery.



CORDETTE® CORD SWITCHES

PHONE: 773 792-2700



SERIES 921

Momentary, 0.5 A switching combined with 1-piece molded plastic body qualifies Cordette for all types of commercial and industrial usage. The 921 has a phono jack receptacle and a phono jack in handle to fit standard phono plugs. The 921K is molded with 6' (1.8 meter), 2-conductor cable (internal cable clamp).

SPECIFICATIONS

Body: 921 and 921K - Molded gray plastic with contrasting

trim and gray pushbutton.

Switch Contacts: Integral copper alloy, plated, form 1-A, 0.5 A, 50 W maximum, AC, non-inductive load.

Not recommended for high voltage circuits. **Insulation:** Thermoplastic UL 94V-0.


Phono Jack Terminations: (921): Standard phono jack, similar to 3501FP (see Jacks and Plugs Section).

SPECIAL ORDER FEATURES

- 1-B, 1-C, or 1-A + 1-B switching.
- Red, green, blue, white or yellow pushbuttons.
- Legends (see page 270).
- Other body colors.
- ST-900 Custom-molded to any of a large selection of cables (See Molded Cable Assembly Section). Also many cable terminations, i.e., phone plugs, extension jacks, phono plugs, spade lugs, alligator clips, stripped and tinned leads, etc.

PART NUMBERS

| Part Number | Description |
|-------------|--|
| 921 | Cordette switch, phono jack termination. |
| 921K | Same as 921, except with 6' (1.8 meter), 2-conductor cable with stripped and tinned leads. |



DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm

Contacts

CIrcuits

4-C

Terminals

PUSH-LITE® SWITCHES AND INDICATORS

Completely enclosed, lighted pushbutton switches feature long-life, highly-reliable, leaf-springs. Available with or without barriers, full or split-face display. Mounts with clamp-type bracket; no screws, washers or nuts needed. Can be mounted in vertical or horizontal rows and in matrixes. Accepts standard T 1-3/4 flange-base lamp (lamp not furnished with switch) in either 6 V to 28 V rating. Specify 1 lamp for single lamp type or 2 lamps for twin-lamp type

Housing/

Pushbutton Color | Switching

4PDT

when redundant or split-face lighting is required. Barriers and colored filter snap-inserts optional (order separately). Mounting hole (w/o barriers): 1" (25.4 mm) x .875" (22.23 mm); (w/barriers) 1.188" (30.16 mm) x .875" (22.23 mm). Panel thickness: .125" (3.18 mm) maximum. Behind panel depth 1.75" (44.45 mm) (minus panel thickness).

MOMENTARY

Part Number

| SINGLE LAMP | | | | | | | | |
|-------------|--------------|------|------------|-------------|-----|------------|--|--|
| PL103205 | | SPDT | | | 1-C | | | |
| PL106205 | Black/White | DPDT | 2 A, 125 V | Palladium | 2-C | | | |
| PL112205 | Black/vvnite | 4PDT | 2 A, 125 V | Fallaululli | 4-C | | | |
| ♦PL126205 | | DPDT | 8 A, 125V | Silver | 2-C | Solder Lug | | |
| ♦PL403205 | | SPDT | | | 1-C | | | |
| ♦PL406205 | Gray/White | DPDT | 2 A, 125V | | 2-C | | | |
| ♦PL412205 | | 4PDT | 1 | Palladium | 4-C | | | |
| ♦PL706205 | Black/White | DPDT | 2 A, 125 V | | 2-C | DC | | |
| ∆DI 712205 | DIACK/WITHE | 4DDT | 2 A, 123 V | | 1.0 | PC | | |

AC Ratings (max.)

non-inductive



♦PL712205 **TWIN LAMP**

| PL203205 | | SPDT | | | 1-C | |
|-----------|-------------|------|------------|-------------|-----|------------|
| PL206205 | Black/White | DPDT | 2 A. 125 V | Palladium | 2-C | |
| PL212205 | Diack/Wille | 4PDT | 2 A, 125 V | Fallaululli | 4-C | |
| ♦PL226205 | | DPDT | 8 A, 125V | Silver | 2-C | Solder Lug |
| ♦PL503205 | | SPDT | | | 1-C | |
| ♦PL506205 | Gray/White | DPDT | 2 A, 125V | | 2-C | |
| ♦PL512205 | | 4PDT | | Palladium | 4-C | |
| ♦PL803205 | | SPDT | | Fallaululli | 1-C | |
| ♦PL806205 | Black/White | DPDT | 2 A, 125 V | | 2-C | PC |
| ♦PL812205 | | 4PDT | | | 4-C | |

PUSH-LOCK/PUSH-RELEASE

| Part Number | Housing/ Pushbutton Color | Switching | AC Ratings (max.) non-inductive | Contacts | Circuits | Terminals | |
|-------------|------------------------------|-----------|---------------------------------|----------|----------|-----------|--|
| SINGLE LAMP | | | | | | | |
| PI 103705 | | SPDT | | | 1-C | | |

| PL103705 | | SPDT | | | 1-C | |
|-----------|-------------|------|------------|-------------|-----|------------|
| PL106705 | | DPDT | 2 A, 125 V | Palladium | 2-C | |
| PL112705 | Black/White | 4PDT | | | 4-C | |
| ♦PL123705 | | SPDT | 8 A, 125V | Silver | 1-C | Solder Lug |
| ♦PL126705 | | DPDT | 6 A, 125V | Silvei | 2-C | Soluel Lug |
| ♦PL403705 | | SPDT | | | 1-C | |
| ♦PL406705 | Gray/White | DPDT | 2 A, 125V | | 2-C | |
| ♦PL412705 | | 4PDT | | Palladium | 4-C | |
| ♦PL703705 | | SPDT | | Fallaululli | 1-C | |
| ♦PL706705 | Black/White | DPDT | 2 A, 125 V | | 2-C | PC |
| ♦PL712705 | | 4PDT | | | 4-C | |



TWIN LAMP


| ♦PL203705 | | SPDT | | | 1-C | | |
|-----------|------------------------------------|------|------------|-------------|-----|------------|--|
| PL206705 | Black/M/hito | DPDT | 2 A, 125 V | Palladium | 2-C | | |
| PL212705 | Black/White Gray/White Black/White | 4PDT | | ranaarani | 4-C | Coldorlug | |
| ♦PL226705 | | DPDT | 8 A, 125V | Silver | 2-C | Solder Lug | |
| ♦PL506705 | , | DPDT | | | 2-C | | |
| ♦PL512705 | | 4PDT | 2 A, 125V | | 4-C | | |
| ♦PL803705 | | SPDT | | Palladium | 1-C | | |
| ♦PL806705 | | DPDT | 2 A, 125 V | Fallaululli | 2-C | PC | |
| ♦PL812705 | | 4PDT | | | 4-C | | |

[♦] Special order only; contact Switchcraft for price and delivery.

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

PUSH-LITE® SWITCHES AND INDICATORS (continued)



U.L. LISTED, MOMENTARY & PUSH-LOCK/PUSH-RELEASE

| Part Number | Housing/ Pushbutton | Action ¹ | Switching | AC Ratings (max.) non-inductive | Circuit | Listing | Terminals | | |
|----------------|------------------------|----------------------|-----------|------------------------------------|---------|---------|------------|------------|--|
| SINGLE I | _AMP | | | | | | | | |
| ♦26U1003 | | М | SPDT | 8 A, 125 V | | 1-C | UL | | |
| ♦26U1004 | Black/White | Diock/M/hito M | | 8 A, 125V | Silver | 2-C | UL | Solder Lua | |
| ♦26U1007 | biack/vvnite | PL/PR SPDT 8 A, 125V | | Silvei | 1-C | UL | Soluel Lug | | |
| ♦26U1008 | | PL/PR | DPDT | 8 A, 125 V | | 2-C | UL | | |

TWIN LAMP

| ◊26U1005 | | М | SPDT | 8 A, 125 V | | 1-C | UL | |
|----------|-------------|-------|------|------------|----------|-----|----|------------|
| ♦26U1006 | Black/White | М | DPDT | 8 A, 125V | Silver | 2-C | UL | Solder Lua |
| ♦26U1009 | Diack/Wille | PL/PR | SPDT | 8 A, 125V |] Olivei | 1-C | UL | Colder Lug |
| ∆26U1010 | | PL/PR | DPDT | 8 A. 125 V | 1 | 2-C | UL | 1 |

[♦] Special order only; contact Switchcraft for price and delivery. NOTE: 1 M = Momentary; PL/PR = Push-Lock/Push-Release

SERIES PL9000 - PL® INDICATORS

Create unlimited combinations of rows and/or matrix arrays with or without Push-Lite switches. A perfect match for front panel appearance Push-Lite switches - but functions only as a lighted indicator. Mounts same as Push-Lite switches: behind panel depth 1.341" (35.55mm) maximum uses same lamp, color filter, snap inserts, light divider and optional mounting barriers as Push-Lite® switches.



| Part Number | Description |
|----------------|---|
| PL9105 | Black housing; uses 1 or 2 lamps. White screen. |
| ♦PL9205 | Same as PL-9105 except gray housing. |

PUSHBUTTON/INDICATOR SCREENS

Series PL500 Pushbuttons/Indicator Screens are available separately for use with Push-Lite switches or PL Indicators for in-the-field substitution and/or replacement.

| Part Number | Color | Part Number | Color |
|-------------|-------|-------------|--------|
| PL501 | Red | PL508 | Yellow |
| PL503 | Green | PL512 | Clear |
| PL504 | Blue | PL513 | Amber |
| PL505 | White | | |

COLOR FILTER SNAP-INSERTS

Translucent plastic filters for special color coding in Push-Lite switch and PL Indicators. Use with white or clear pushbuttons.

| SERIES PL300 - Full Display Color Filters | | | | | | | | | |
|---|--------|--|--|--|--|--|--|--|--|
| Part Number Color | | | | | | | | | |
| PL303 | Green | | | | | | | | |
| PL305 | White | | | | | | | | |
| PL308 | Yellow | | | | | | | | |

OPTIONAL MOUNTING BARRIERS

Molded plastic barriers separate Push-Lite switches, PL Indicators, or combinations of Push-Lite switches and PL Indicators and prevent accidental operation of adjacent switches. Series PL100: end barrier. Series PL200: center barrier. Two required between adjacently mounted switches. Push-Lite switch is shown with two PL102 end barriers installed.

| Part Number | Description |
|-------------|-----------------------|
| PL102 | End barrier, black |
| ♦PL111 | End barrier, gray |
| PL202 | Center barrier, black |
| ♦PL211 | Center barrier, gray |


 $[\]lozenge$ Special order only; contact Switchcraft for price and delivery.

LIGHT DIVIDER

Light divider for Push-Lite switch pushbuttons and PL Indicator screens; separates lighting from twin lamps. Order light divider for each switch or indicator specified where split-face lighting is desired. **Order PL551.**

BASIC SCHEMATIC

Switch circuitry can be described as combinations of basic schematic circuits as shown below. N.O. means normally open; N.C. means normally closed.





The above are strictly electrical schematics and do not necessarily indicate relative solder lug positions.

DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)


PUSH-LITE® SWITCHES - PART NUMBERING SYSTEM





Black housing

(PC terminals)



stitution/replacement; order from tables. Also, engraving of leg-

ends is available; contact Switchcraft.

RECOMMENDED PC BOARD LAYOUT (Component Side)


SWITCHES PUSH-LITE® SWITCHES — OUTLINE DIMENSIONS


PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

PUSH-LITE® SWITCHES AND INDICATORS (continued)

OUTLINE DIMENSIONS







PUSH-LITE® SWITCHES AND INDICATORS (continued)


OUTLINE DIMENSIONS

SWITCH AND INDICATOR MOUNTING WITH BARRIERS (See Note)



SWITCH AND INDICATOR MOUNTING WITH BARRIERS (SEE NOTE)





NOTE: PANEL OPENINGS FORM MULTIPLE ROW SWITCH MOUNTING

Leave .109" (2.77 mm) minimum width strip between panel-cutouts to assure secure mechanical mounting of adjacent clamp mounting brackets.

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

SLIDE SWITCHES

DESIGN FEATURES

Switchcraft slide switches are completely field tested and proven in electrical/electronic equipment applications. They are among the highest-quality, lowest-cost slide switches available to "cost-to-quality ratio" conscious engineers.

Precision slide switches are designed and constructed to meet or exceed industry standards for reliability, electrical capacity and life characteristics.


Switchcraft's slide action switches are ideal for use in critical military and industrial applications such as: instrumentation, test and ground support equipment, computers, control devices. Their attractive styling will enhance the appearance of modern home entertainment equipment.

UL AND CSA SWITCHES

All slide switches in this catalog with part number suffix "E" are stamped with both UL and CSA marks. Other standard switches are UL recognized (except as noted) and are stamped with the mark.

TERMINALS

Silver-plated terminals are standard; gold-plated terminals are available on special order. Printed circuit terminals in varying lengths from ("A" dimension) .078" (1.98 mm) to 1.25" (31.75 mm) are available on special order. Reference "A" on all switch drawings indicates length of PC terminals. See illustration and notes below for selection of terminals.



SPECIAL ORDER SWITCHES FOR CSA APPLICATIONS

The following series of switches (solder lug type) must be assembled with a fishpaper or phenolic solder guard to be CSA certified and stamped. Available on special order only. Series 46000R, 47000R, 46313R, 49000L, 50000L, Solder guards are not required on these switch series with PC terminals. However, they can only be supplied with CSA stamp on special order. Solder guards are not required on UL only versions. Contact Switchcraft for details.

SWITCH SERIES IDENTIFICATION

| Series | Name | Number of Positions |
|---------------|--------------------------------|------------------------|
| 46000 | General Purpose Slide Switches | 2, 3 |
| 47000 | Tandem Slide Switches | 2; 2 gang |
| 49000 | General Purpose Slide Switches | 3 |
| 50000 | General Purpose Slide Switches | 2 |
| 56200, C56200 | "Tini-Slide" Slide Switches | 2 |
| 56300, C56300 | "Tini-Slide" Slide Switches | 3 |
| C63000 | Miniature Slide Switches | 4 |
| EPS1, EPS2 | European Line Voltage | 2 |
| EPS3, EPS4 | Selector Switches | |

| Series | Description |
|---------------|--------------|
| 46000E | Note 1 |
| 46000R | Notes 1, 3 |
| 47000E | Note 1 |
| 47000R | Notes 1, 3 |
| 49000 | Note 1 |
| 50000 | Notes 1, 3 |
| 56000, C56000 | See page 288 |
| 62000, C62000 | See page 290 |
| C63000 | See page 290 |
| EPS1, EPS2 | See page 291 |
| EPS3, EPS4 | |

NOTES:

1. PC terminal "A" dimension is:

Standard - .078" (1.98)

Special - .109" (2.77), .141" (3.58), .160" (4.06), .180" (4.57), .203" (5.16), .234" (5.94), .266" (6.76), .313" (7.95), .391" (9.93), .400" (10.16), .438" (11.12), .484" (12.29), .609" (15.47), .688" (17.48), .719" (18.26), .813" (20.65), .969" (24.61), 1.25" (31.75)

- 2. 078" (1.98) "A" dimension is not recommended for momentary switches unless clearance hole for return spring is provided in PC board.
- 3. Accepts up to #14 AWG wire.

SLIDE SWITCHES (continued)

DESIGN FEATURES (continued)

SWITCHING

"Double-wipe" slide switches incorporate special "Sliders" to assure wiping action of terminals. This exclusive double wiping action reduces the possibility of oxidation or increased contact resistance. These longer lasting, self-cleaning sliders provide a switch with greater dependability.

The "Sliders", which are formed with precision dies, are U-shaped to give bifurcated contact reliability. "Sliders" are made from a special copper alloy, plated, which assures uniform tensile strength over the entire life of the switch.

Switch terminals are copper alloy, plated. Plating completely encloses the contact area in a silver jacket for positive and continuous electrical operation. A tarnish preventive lubricant coating is applied to the sliders and terminals.


NOTE: "double-wipe" action on all switches except Series 62000 and 46256LFR.

BASIC SCHEMATIC CHART

Standard arrangement is "Break" before "Make" (non-shorting). "Make" before "Break" (shorting) is available on special order in Series 46000R, 47000R, 49000 and 50000.

PART NUMBER SUFFIX LETTERS

| Letter | Description |
|--------|--|
| В | Special pushbutton type. Depressing (rather than sliding) pushbutton operates the switch. |
| С | Tandem switch with 2 knobs; knobs are internally (mechanically) coupled. |
| D | 3-position switch having internal dust shield. |
| E | Molded terminal board. |
| F | Flush actuator. Screwdriver slotted. All series except 47000 series marked standard as "115/230." Other markings available as special order. Call Switchcraft for details. |
| L | Locking action. |
| M | Momentary (non-lock) action. |
| Р | Switch has external plunger. |
| R | Current ratings up to 3A, 125V AC. Phenolic terminal board. |
| S | Shorting type contacts, make-before-break. |
| Т | 3-position switches only. One side of neutral has locking action; the other side has momentary action. |



KNOBS KNOB HEIGHTS Inches (mm)

| Series | Flush | .063 (1.6) | .087 (2.21) | .094 (2.39) | .100 (2.54) | .112 (2.84) | .125 (3.18) | .137 (3.48) | .15 (3.81) | .156 (3.96) | .187 (4.75) | .188 (4.78) | .200 (5.08) | .203 (5.16) | .219 (5.56) | .250 (6.35) | .302 (7.67) | .313 (7.95) | .315 (8) | .328 (8.33) | .344 (8.74) | .375 (9.52) | .406 (10.31) | .440 (11.18) | .453 (11.51) | .469 (11.91) | .487 (12.37) | .500 (12.7) | .531 (13.49) | .563 (14.3) | .594 (15.09) | .719 (18.26) | .750 (19.05) |
|------------------|------------|------------|-------------|-------------|-------------|-------------|-------------|-------------|------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|------------|-------------|-------------|-------------|--------------|--------------|--------------|--------------|--------------|-------------|--------------|-------------|--------------|--------------|--------------|
| 46000E 46000R | * (1) | | | \Q | | | ◊ | | | | | ◊ | | | \Q | \Q | | | | | * | \Q | \Q | | | | | ◊ | \Q | | \Q | ♦ | \Diamond |
| 46300R | \Diamond | \Diamond | | \Diamond | | | | | | \Diamond | | \Diamond | | | \Diamond | | | \Diamond | | | * | \Diamond | | | | \Diamond | | \Diamond | | \Diamond | | \Diamond | \Diamond |
| 47000 | *(1) | | | \Diamond | | | \Diamond | | | | | \Diamond | | | \Diamond | \Diamond | | | | | *(2) | \Diamond | \Diamond | | | | | \Diamond | \Diamond | | \Diamond | | \Diamond |
| 49000 | \Diamond | | | | | | | | | | | | | | \Diamond | | | | | | \Diamond | | | | | | | * | \Diamond | | | | \Diamond |
| 50000 | \Diamond | \Diamond | | | | | | | | | | \Diamond | | | | | | | \Diamond | | | | | | | * | | | | | | \Diamond | |
| 56200 | | | | | \Diamond | | \Diamond | | | | | | * | | | | | | \Diamond | \Diamond | | | | | \Diamond | | | \Diamond | | | | | |
| 56300 | | | \Diamond | | | \Diamond | | \Diamond | \Diamond | | * | | | | | | \Diamond | | \Diamond | | | | | \Diamond | | | \Diamond | | | | | | |
| 62000 (2) | | | | | | | | | | | | | | * | | | | | | \Diamond | | | | | | | | | | | | | |
| C63000 | | | | | | | | | | | | | | * | | | | | | | | | | | | | | | | | | | |
| EPS (3) | * | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |

- * Standard, \Diamond Special order
- 1. Flush screwdriver actuator is standard on numbers 46206LFE, 46206LFR, 46256LFE, 46256LFR and 47227LFR.
- 2. Numbers 62206L and C62206L have side knob actuator (rather than top knob) standard.
- 3. EPS switches not available with raised knobs.

Inch (mm)

SERIES 46200E, 46200R - 2 POSITION

SPECIFICATIONS

Contact Ratings: 0.5A DC and 3A AC, 125V non-inductive. (Also 1.5A, 250V non-inductive for Series 46000E only). Numbers 46206LFR and 46256LFR are not designed to switch more than 125V, and must be set to desired position before power is applied to equipment, appliance, etc.

Listings: UL recognized and CSA certified. Series 46000R switches are CSA marked on special order only. Ref. UL card E40668 and CSA File 28260.

Housing: Steel, plated. Knob: Black thermoplastic.

Terminals and Slider Contacts: Copper alloy, plated.

Insulation: Series 46000E: Thermoplastic.

Series 46000R: Rigid plastic.

Temperature Range: -4°F to +158°F (-20°C to +70°C).

Dielectric Strength: 1 kV rms @ sea level. Insulation Resistance: 1 k M Ω minimum.


SPECIAL ORDER FEATURES

- 1. .344" (8.74 mm) high knobs are standard; other heights available. See chart on page 283.
- 2. #6-32 and #4-40 tapped flanges for mounting available (except 46204MBR and 46206MP).
- 3. P.C. terminals.
- 4. Plunger length on 46206MP Other lengths from .125" (3.18 mm) to 1.844" (46.84 mm) long.
- 5. Series 46000R switches are CSA marked on special order only. See page 282.

PART NUMBERS

| Series 46200E | Series 46200R | Description | Schematic* |
|------------------|------------------|-----------------------|----------------|
| ♦46201ME | 46201MR | SPST NO, Momentary | 1 |
| ♦46202LE | 46202LR | SPST, Locking | II |
| ♦46202ME | ♦46202MR | SPST NC, Momentary | II |
| 46203LE | 46203LR | SPDT, Locking | III |
| ♦46203LSE | ♦46203LSR | SPDT, Locking | III Shorting |
| ♦46203ME | 46203MR | SPDT, Momentary | III |
| 46204LE | ♦46204LR | DPST, Locking | 2-I |
| ♦46204ME | ♦46204MR | DPST NO, Momentary | 2-I |
| 46206LE | 46206LR | DPDT, Locking | 2-III |
| 46206LFE | 46206LFR | DPDT, Locking (1) | 2-III |
| ♦46206LSE | ♦46206LSR | DPDT, Locking | 2-III Shorting |
| ♦46206ME | ♦46206MR | DPDT, Momentary | 2-III |
| - | ♦46206MP | DPDT, Momentary* | 2-III |
| 46256LFE | 46256LFR | DPDT, Locking (1) (2) | V |
| - | ♦C46203LR** | SPDT , Locking | III |
| - | ♦C46204MR** | DPST NO, Momentary | 2-1 |
| - | C46206LR** | DPDT, Locking | 2-III |
| - | C46206LFR** | DPDT, Locking (1) | 2-111 |

- Contacts are non-shorting, except as noted.
- ** "C" prefix specifies .078 inch (1.98) PC terminals, no mounting ears.
- (1) Recommended for power selection, 115-230 legend, screwdriver slotted actuator minimizes tampering.
- (2) Shorting bars installed.
- Special order only; contact Switchcraft



GENERAL PURPOSE SLIDE SWITCHES (continued)





SERIES 46300R - 3-POSITION

Three-position switches offer locking-locking, momentary-momentary and locking-momentary action for talk-listen applications. All switches have positive center detent and shutter type dust cover to prevent dirt and dust from contaminating switch contacts.

SPECIFICATIONS

Contact Ratings: 0.5A DC and 3A AC, 125V non-inductive. **Listings:** UL recognized, card E40688 CSA certified (marked) switches available on special order only.

See page 282.

Housing: Steel, plated.

Detent Spring: Music wire.

Shim: Black vulcanized fiber.

Knob: Black thermoplastic.

Terminals & Slider Contacts: Copper alloy, silver-plated.

Insulation: Phenolic.

Temperature Range: -4°F to +158°F (-20°C to +70°C).

Dielectric Strength: 1 kV rms @ sea level. Insulation Resistance: 1 k $M\Omega$ minimum.

SPECIAL ORDER FEATURES:

- 1. .344" (8.74 mm) high knobs are standard; other heights available. See chart on page 283.
- 2. Series 46000R switches are CSA marked on special order only. See page 282.



| | | Action Positions* | | | |
|------------------|-----------|-------------------|--------|----|-----------|
| Part** Number | Circuitry | #1 | Center | #2 | Schematic |
| 46311LDR | SPTT | L | L | L | VI |
| ◊46311MDR | SPTT | М | L | М | VI |
| ◊46311TDR | SPTT | L | L | М | VI |
| 46313LDR | DPTT | L | L | L | 2-VI |
| 46313MDR | DPTT | М | L | М | 2-VI |
| 46313TDR | DPTT | L | L | М | 2-VI |

 \Diamond Special order only; contact Switchcraft for price and delivery.

* L - Locking; M - Momentary.


SOLDER GUARDS

Insulating Solder Guards, P-2370 (2-position); and $\langle P-2633 \rangle$ (3-position); slip over solder lug terminals and prevent solder splashes from entering interior (contact area) of switch. Made of fishpaper .01" (.25 mm) thick, Solder Guard slips over terminals quickly and easily. Precision punched slots lock onto terminals, and rectangular shape conforms with dimension of switch terminal board. Minimizes costly production line rework.


Solder Guards can be used on:

- General Purpose, Series 46000R
- Tandem, Series 47000R.









^{** &}quot;C" prefix specifies .078" (1.98) PC terminals, no mounting ears.

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

GENERAL PURPOSE SWITCHES - TANDEM











SERIES 47200E, 47200R - 2 POSITION

Space saving, two-gang slide switches are contained in one housing. Switching is locking type with non-shorting contacts.

SPECIAL ORDER FEATURES

- 1. .344" (8.74 mm) high knobs or flush knobs are standard, depending on switch selected; other heights available. See chart on page 283.
- 2. Series 47000R switches are CSA marked on special order only. See page 282.

SPECIFICATIONS

Contact Ratings: 0.5A DC and 3A AC, 125V non-inductive, (Also 1.5A, 250V non-inductive for Series 47000E only.) 47227LFR switches are not designed to switch more than 125V, and must be set to desired position before power is applied to equipment or appliance.

Listings: UL recognized, card E40668, and CSA certified (card 28260). Series 47000R switches are CSA certified on special order only. See page 282.

Housing: Steel, plated. Knob: Black thermoplastic.

Terminals and Slider Contacts: Copper alloy, silver-plated.

Insulation: Series 47000E - Thermoplastic.

Series 47000R - Rigid plastic.

Temperature Range: -4°F to +158°F (-20°C to +70°C).


Dielectric Strength: 1 kV rms @ sea level. Insulation Resistance: 1 k $M\Omega$ minimum.

PART NUMBERS

| Series 47200E | Series 47200R | Description | Sche | matic |
|------------------|------------------|-------------|-------|-------|
| ♦47202LE | ◊47202LR | SPST - SPST | II | II |
| ♦47203LE | ♦47203LR | SPDT - SPDT | III | III |
| ◊47204LE | ◊47204LR | DPST - DPST | 2-I | 2-I |
| ♦47204LCE | ♦47204LCR | DPST - DPST | 2-1 | 2-I |
| ♦47206LE | ◊47206LR | DPDT - DPDT | 2-111 | 2-111 |
| ♦47206LCE | ♦47206LCR | DPDT - DPDT | 2-111 | 2-111 |
| - | ◊47215LR | SPST - SPDT | II | Ш |
| - | ◊47215LCR | SPST - SPDT | II | Ш |
| - | ◊47217LR | SPST - DPST | II | 2-II |
| - | ◊47217LCR | SPST - DPST | II | 2-II |
| - | ◊47221LR | SPDT - DPST | III | 2-II |
| - | ◊47221LCR | SPDT - DPST | III | 2-II |
| | ◊47227LFE | DPDT - DPDT | 2 | -V |
| | ◊47227LFR | DPDT - DPDT | 2- | ٧. |

NOTE: Series 47200E and 47200R - All switches have two independent knobs, except:

- 47204LE, 47204LCR, 47206LCE and 47206LCR have one knob and one flush actuator
- 47227LFE and 47227LFR have internal mechanical coupling and two flush, slotted screwdriver actuators.
- ♦ Special order only; contact Switchcraft



GENERAL PURPOSE SLIDE SWITCHES (continued)







Large, heavy duty, three and four pole slide switches. Standard mounting clearance is .141" (3.58 mm). Series 49300L, non-shorting contacts; Series 49300LS, shorting contacts.

SPECIFICATIONS

Contact Ratings: 0.5A DC and 3A AC, 125V non-inductive. Listings: UL recognized (card E40668); CSA certified (marked) switches available on special order only.

See page 282.

Housing: Steel, plated. Detent Shim: Copper alloy. Knob: Black thermosetting plastic.

Terminals and Slider Contacts: Copper alloy, silver-plated.


Insulation: Rigid plastic.

Temperature Range: -4°F to +158°F (-20°C to +70°C).

Dielectric Strength: 1 kV rms @ sea level. Insulation Resistance: 1 k M Ω minimum.

SPECIAL ORDER FEATURES

- 1..5" (12.7 mm) high knobs are standard; other heights available. See chart on page 283.
- 2. #4-40 extruded and tapped mounting holes available.
- 3. Series 49300L switches are CSA marked on special order only. See page 282.





49331L

PART NUMBERS

| Part Number | UL & CSA Listing | Description | Schematic |
|----------------|---------------------|-----------------|-----------|
| ◊49309L | Yes | 3-PDT, Locking* | 3-VII |
| ♦49309LS | No | 3-PDT, Locking* | 3-VII |
| ◊49329L | Yes | 3-PTT, Locking | 3-VI |
| ♦49329LS | No | 3-PTT, Locking | 3-VI |
| ◊49312L | Yes | 4-PDT, Locking* | 4-VII |
| ♦49312LS | No | 4-PDT, Locking* | 4-VII |
| ◊49331L | Yes | 4-PTT, Locking | 4 -VI |
| ♦49331LS | No | 4-PTT, Locking | 4 -VI |

³rd position is off.

SERIES 50200 - 2 POSITION

A larger 2 position "double wipe" slide switch offering three and four poles of switching and locking or momentary action. Series 50200L and M, non-shorting; Series 50200LS and MS, with shorting contacts.

SPECIFICATIONS

Contact Ratings: 0.5A DC and 3A AC, 125V non-inductive. Listings: UL recognized (card E40668); CSA certified (card 28260). Series 50200L switches are CSA marked on special order only. See page 282.

Housing: Steel, plated. Detent Shim: Copper alloy. Knob: Black thermosetting plastic.

Terminals and Slider Contacts: Copper alloy, plated.


Insulation: Rigid plastic.

Temperature Range: -4°F to +158°F (-20°C to +70°C).

Dielectric Strength: 1 kV rms @ sea level. Insulation Resistance: 1 k MΩ minimum.

SPECIAL ORDER FEATURES

- 1..344" (8.74 mm) high knobs are standard; other heights available. See chart on page 283.
- 2. 50212LF available with flush, screwdriver slotted actuator and has 4 PDT locking action.
- 3. Extruded and tapped 4-40 or 6-32 holes available.
- 4. Series 50200L switches are CSA marked on special order only. See page 282.





50209L

PART NUMBERS

| Part Number | Description | Schematic |
|---------------------|----------------------|-----------|
| ♦50207L | 3PST - Locking | 3-I |
| ♦50207M | 3PST, N.O. Momentary | 3-I |
| ♦50208L | 4PST, Locking | 4-1 |
| 50209L | 3PDT, Locking | 3-111 |
| ♦50209M ♦50209MS | 3PDT, Momentary | 3-11 |
| 50212L | 4PDT, Locking | 4-111 |

[♦] Special order only; contact Switchcraft.

[♦] Special order only; contact Switchcraft.

SWITCHES MINIATURE SLIDE SWITCHES — SERIES 56200 AND C56200

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MINIATURE SLIDE SWITCHES



SPECIAL ORDER







56206L1

C56206L2

C56206L2

SERIES 56200, C56200 - 2 POSITION

"Tini-Slide" slide switches have Exclusive SNAP SLIDE lifting and wiping action. This unique, positive action combines the best features of "snap" and "slide" movements into the design of a superior switch. Pitting, burning and contamination are minimized. Contacts lift through an air gap, drop on stationary contacts, and slide, wiping themselves clean. Subminiature size is ideal where useable space is at a premium.

SPECIFICATIONS

Contact Ratings: 0.5A, 125V AC or DC, non-inductive. Minimum life at rated load 6000 cycles. Resistance after 6000 cycles at rated load is 50 milliohms maximum.

Terminals: PC Type - silver-plated. Each terminal has standoff shoulder for stable mounting and space for board clearance.

Mounting: Flange, (56206L1 and 56206L2) - .1" (2.54 mm) holes for screw or mounting rivet. PC - Direct mounting to PC

boards up to .093" (2.36 mm) thick. **Knob:** Molded thermoplastic (UL 94V-1).

Terminal Board: Molded thermoplastic (UL 94V-0).

Terminals: Copper alloy, silver-plated. **Contact Sliders:** Copper alloy.

Temperature Range: -4°F to +158°F (-20°C to +70°C).


Dielectric Strength: 1 kV rms @ sea level. **Insulation Resistance:** 1 k M Ω minimum.


SPECIAL ORDER FEATURES

- 1..2" (5.08 mm) high knobs are standard; other heights available on special order. See page 283.
- 2. Red and white knobs available.
- 3. Mounting flanges with .1" (2.54 mm) diameter holes on C56206L1 or C56206L2. Flange holes tapped #4-40 on 56206L1 or 56206L2 (where production quantities warrant).
- 4. UL stamped on special order.

PART NUMBERS

| Part Number | Dimension "B" Inch (mm) | Description | Schematic |
|----------------|----------------------------|---------------|-----------|
| 56206L1 | - | DPDT, Locking | 2-III |
| 56206L2 | - | DPDT, Locking | 2-III |
| C56206L1 | .573 (14.55) | DPDT, Locking | 2-III |
| C56206L2 | .352 (8.94) | DPDT, Locking | 2-III |





| 142 THROW | 15.88 | 15.76 | 15.88 | 15.76 | 15.88 | 15.76 | 15.88 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 | 15.76 |

DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)

MINIATURE SLIDE SWITCHES (continued)









56313L1 56313L2

C56313L2 C56313L1

SERIES 56300,C56300 - 3 POSITION

Series 56300 "Tini-Slide" switches provide ultra-reliable 3-position switching. They afford maximum space savings in military, industrial and consumer applications, such as instrumentation, test and ground support equipment, appliances, computers, and control devices.

SPECIFICATIONS

Contact Ratings: 0.5A, 125V AC or DC, non-inductive. Minimum switch life is 6000 cycles. Resistance after 6000 cycles at rated load is 50 milliohms maximum.

Terminals: Solder Lugs - 56313L1 with wrap around notch; 56313L2 with solder lug. PC - .585" (14.68 mm) "B" dimension and .364" (9.24 mm) "B" dimension.

Mounting: Mounting ears for mounting to chassis of panels with screws or rivets (not supplied). Switches with PC terminals have stand-off shoulders for solid PC mount.

Knob: Molded thermoplastic (UL 94HB).

Terminal Board: Molded thermoplastic (UL 94V-0).

Terminals: Copper alloy, silver-plated.

Contact Sliders: Copper alloy.

Temperature Range: -4°F to +158°F (-20°C to +70°C).


Dielectric Strength: 1 kV rms @ sea level. Insulation Resistance: 1 k M Ω minimum.

SPECIAL ORDER FEATURES


- 1...187" (4.75 mm) high knob is standard; Other heights available on special order. See page 283.
- 2. Red and white knobs available.
- 3. Two mounting variations:
 - a. Tapped #4-40 holes on mounting ears for machine screws.
 - b. Mounting ears with .1" (2.54 mm) diameter holes on switches with PC terminals.

PART NUMBERS


| Part Number | Dimension "B" Inch (mm) | Description | Schematic |
|----------------|----------------------------|---------------|-----------|
| 56313L1 | - | DPTT, Locking | 2-VI |
| 56313L2 | - | DPTT, Locking | 2-VI |
| C56313L1 | .585(14.85) | DPTT, Locking | 2-VI |
| C56313L2 | .364 (9.24) | DPTT, Locking | 2-VI |




56313L1



56313L2





RECOMMENDED PC BOARD **LAYOUT (Component Side)**





PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

SIDE-SLIDE®/MINIATURE SLIDE SWITCHES







SERIES 62200 - 2 POSITION

2-position locking action with side knob actuator. Side knob provides low profile, saving space on PC boards.

SPECIFICATIONS

Contact Ratings: 0.5A, 125V AC or DC. **PC Terminals:** Copper alloy, silver plated.

Housing: Steel, plated. Knob: Molded thermoplastic. Terminal Board: Rigid plastic. Sliders: Copper alloy, plated. Dielectric Strength: 1000 V rms.

Insulation Resistance: 1 k $M\Omega$ minimum.

SPECIAL ORDER FEATURES


- 1. Various knob heights available on special order.
- 2. Various lengths available on special order.

PART NUMBERS

| Part Number | Description | Schematic |
|----------------|--------------------------------------|-----------|
| ⊘62206L | DPDT, with mounting ears, Locking | 2-III |
| C62206L | DPDT, without mounting ears, Locking | 2-III |


[♦] Special order only; contact Switchcraft.


MINIATURE SLIDE SWITCHES



SERIES C63200 - 2 POSITION, 4 POLE

C63200 switches designed for applications, such as: instrumentation, test and ground support equipment, computers, data communications and medical equipment. PC mounting on standard industry .100" (2.54 mm) x .200" (5.08 mm) centers. Mounts on PC boards up to .093" (2.36 mm) thick. Molded black thermoplastic knobs. Terminals are copper alloy, gold-plated on contact area, tinned on terminal end.





| Part Number | Action | Switching | Ratings | Schematic | Terminals |
|-------------|---------|-----------|-------------------------|-----------|--|
| C63212L | Locking | 4PDT | 300mA max. 30V AC | 4-111 | Copper alloy, gold-plated on contact area, tinned on terminal end |

DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)

EUROPEAN LINE VOLTAGE SELECTOR SWITCHES















EPS1PC3

EPS2PC2

EPS3SL1

EPS4PC3

SERIES EPS1, EPS2, EPS3, EPS4 - 2 POSITION

European Power Selector Switches are designed for quick, easy programming/selection of 115V-230V primary power. These switches provide OEM designers with an excellent selection of PC and solder lug terminals and ratings up to 10A, 125V AC rating for electrical/electronic equipment and systems headed for the INTERNATIONAL marketplace.

HOUSING AND ACTUATOR

Switches have positive, double detents for "sure" locking into position. Screwdriver slot actuator virtually eliminates the possibility of accidental operation and minimizes tampering. Molded-in legends are: 115-230V. Terminals are staked into housing.

SPECIFICATIONS

Contact Ratings: EPS1, EPS2 - 2A, 250V AC and 4A, 125V AC. EPS3, EPS4 - UL and CSA - 10.1A, 125V; 5A, 250V. VDE - 10A. 250V.

Listings: UL and CSA recognized, UL card E40668; CSAcard 28260. 2A, 250V AC is VDE listed, VDE #13707 (for European applications). Designed to conform to requirements of CEE (International Commission on Rules for the Approval of Electrical Equipment, Publication 24) and the IEC (International Electrotechnical Commission).

Housing: Molded black glass-reinforced plastic. **Actuator and Cover:** Molded thermoplastic. **Terminals:** Copper alloy, silver-plated.

Slider Contacts: EPS1, EPS2 - Bi-Metal, silver on copper alloy. EPS3, EPS4 - Copper alloy with silver cadmium

oxide inlay.

Temperature Range: -4°F to +158°F (-20°C to +70°C).

Dielectric Strength: 2kV rms @ sea level. Insulation Resistance: 1 k $M\Omega$ minimum.

SPECIAL ORDER FEATURES

Series EPS actuators having legends other than 115V and 230V are available on special order.

NOTE: Contact Switchcraft for details.

PART NUMBERS Series EPS1

| Part Number | Terminals | Dimension "B" Inch (mm) | Schematic |
|----------------|----------------|----------------------------|-----------|
| ♦EPS1PC1 | Straight PC | .681 (17.297) | 2-III |
| ♦EPS1PC2 | Straight PC | .719 (18.263) | 2-III |
| EPS1PC3 | Right-Angle PC | - | 2-III |
| EPS1SL1 | Solder Lugs | - | 2-III |

[♦] Special order only; contact Switchcraft.

Series EPS2

| Part Number | Description | Dimension "B" Inch (mm) | Schematic |
|----------------|----------------|----------------------------|-----------|
| EPS2PC1 | Straight PC | .730 (18.542) | 2-III |
| EPS2PC2 | Straight PC | .768 (19.507) | 2-III |
| EPS2PC3 | Right-Angle PC | - | 2-111 |


Series EPS3


| Part Number | Terminals | Dimension "B" Inch (mm) | Schematic |
|----------------|----------------|----------------------------|-----------|
| EPS3PC1 | Straight PC | .681 (17.297) | 2-III |
| EPS3PC2 | Straight PC | .719 (18.263) | 2-III |
| EPS3PC3 | Right-Angle PC | - | 2-III |
| EPS3SL1 | Solder Lugs | - | 2-III |

Series EPS4


| Part Number | Description | Dimension "B" Inch (mm) | Schematic |
|----------------|----------------|----------------------------|-----------|
| EPS4PC1 | Straight PC | .730 (18.542) | 2-III |
| EPS4PC2 | Straight PC | .768 (19.507) | 2-III |
| EPS4PC3 | Right-Angle PC | - | 2-III |

EUROPEAN LINE VOLTAGE SELECTOR SWITCHES (continued)





EUROPEAN LINE VOLTAGE SELECTOR SWITCHES (continued)



PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

LEVER SWITCHES

DESIGN FEATURES

High quality, field-proven Switchcraft® lever switches are available in a wide selection of illuminated and non-illuminated versions, 2- and 3-position, locking and non-locking functions can be provided. Switchcraft illuminated lever switches feature choice of colors, wide selection of switching circuits, single lamp illumination and ease of mounting and lamp replacement.

All switches utilize nickel silver springs without "form" at point of flexing to insure long spring life. The springs are assembled into a conventional stack assembly, insulated from each other by phenolic spacers with plastic tubing press-fit through each stack, insuring correct alignment of contacts and providing high insulation resistance.

APPLICATIONS

Various front panel switching applications on computers, telecommunications systems, industrial control equipment, intercoms, ground support systems, medical electronics, scientific instruments, broadcast consoles and test instrumentation.


CONTACTS

Below are listed the basic contacts available on switches in this catalog:

- Fine silver contacts rated at 2A, 200W (maximum) AC non-inductive load.
- 2. Welded cross bar silver contacts rated at 3A, 300W (maximum) AC non-inductive load.
- 3. Welded cross bar palladium contacts rated at 2A, 200W (maximum) AC non-inductive load.
- Welded cross bar gold alloy contacts rated at up to 1A, 100W (maximum) AC non-inductive load. (Dry circuit applications.)

BASIC CONTACT FORMS

Below are the basic contact forms available standard on all Switchcraft Lever Switches. Specify circuits needed by referring to the letter identification and respective location on frame. See dimensional drawings for stack switch location.



To avoid ordering special switches it is possible to use a larger standard circuit, providing the circuit fulfills your requirements. Circuit Form K is widely used in talk-listen (intercom) function applications. In normal position (neutral), switch does not contact upper or lower contact spring. During typical operation, lever is held in upper (momentary) position while speaking. Releasing lever allows switch to return to neutral. For listening, lever is moved to down (locking) position. Lever is manually returned to neutral when finished.



ORDERING STANDARD SWITCHES

Order lever switches by part number from pages 295 through 298.

LAMP DATA

Lever-Lite® switches use T-1 3/4 flange base lamps which are available from commercial sources.

ORDERING SPECIAL SWITCHES

Lever Switches

Should you desire a special version of any Switchcraft® lever switch not shown here, we require the following information:

- 1. Switch series.
- 2. Number of positions.
- 3. Mechanical action (locking, non-locking, etc.).
- 4. Contact configuration for each position.
- 5. Type of contact material.
- 6. Color sequence (Lever-Lite III).

UL RECOGNIZED LEVER SWITCHES

Seven series of Switchcraft lever switches are UL recognized. These switches are available on special order to fulfill your switching requirements which specifically require UL listed switching devices.

- 1. Series 12000
- 2. Series 41000

NOTE: Refer to switch series in this catalog for full mechanical specifications and additional standard and special features.

LEVER SWITCHES (continued)

LEVER-LITE® III

SERIES 84000 - ILLUMINATED LEVER SWITCHES

Lever-Lite® III illuminated lever switches are designed for front-of-panel mounting, relamping, terminating, color changes and removal. A minimum of time is required to install singly, in rows, or in matrix arrays to meet a wide variety of switching applications. 2- and 3-position types are available in non-locking functions. Mounts on .875" (22.22 mm) horizontal centers or 1.5" (38.1 mm) vertical centers. Talk-listen (intercom) function is also available. Illumination technique provides a different color for each lever position.

LAMPS

Standard T 1-3/4" midget flange-base lamps (not supplied) are available in voltages up to 28V.

SPECIAL ORDER FEATURES


- 1. Talk-Listen (Intercom) function.
- 2. Welded cross bar gold alloy for dry circuit and silver contacts are available. See page 294.




ILLUMINATION

A single internal lamp provides brilliant lever lighting in any color required. Standard factory installed color filters are provided as follows: Series 84000, Multi-Color Illumination 2-position - Amber (neutral position); green (down position). 3-position - Red (up position); amber (neutral position); green (down position). One-color (all positions) and non-illuminated switches can be specified on special order. Switchcraft will install filters for non-standard illumination requirements at nominal cost on special order.


MOUNTING



Grasp fingernail slots on opposite sides of escutcheon and snap out. Next, grasp lever and pull lever assembly free. Insert switch into panel hole.




Turn two internal screws clockwise with screwdriver to securely mount switch to panel.




Replace lever assembly and "snap" escutcheon into place. Installation complete!


RELAMPING/REPLACING COLOR FILTERS



Remove escutcheon and lever assembly. (see "MOUNTING" above) For relamping, pull lamp out of retainer with finger-tip. Replace lamp.



For color filters, use fingernails or small screwdriver to remove. Gently lift (don't pry) up under edge of filter until it "pops" out.



Place new filter in position and press until it "snaps" in. Replace lever assembly and escutcheon. (see "MOUNTING" above)

DIMENSIONS ARE FOR REFERENCE ONLY

Lever-Lite III switches are designed for simplified lamp installation and replacement,

and color filter changes or custom installation in the field or on the OEM production

line. Lamps and filters may be changed at any time with ease and without

SWITCHES <u>LEVER-LITE® ILLUMINATED LEVER SWITCHES</u> — SERIES 84000

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

LEVER SWITCHES (continued)

LEVER-LITE® III SERIES 84000 - ILLUMINATED LEVER SWITCHES

SPECIFYING LEVER-LITE® III SWITCHES

- Basic Switch Refer to Part Number table for ordering switches. For special switches, such as talk-listen (intercom) function, special circuit forms, or non-illuminated switches, contact factory for price and delivery.
- Illumination Supplied with standard color filters installed. Switchcraft will install other combinations at nominal extra cost.
- 3. Lamps Lamps are not supplied with switches.

SPECIFICATIONS

Mounting/Retaining Clips and Covers: Steel, plated. Contact Ratings: Welded cross bar palladium contacts rated at 1A, 200W maximum AC non-inductive load are standard. Other contacts available. See "SPECIAL ORDER FEATURES" on page 295.

PART NUMBERS TWO POSITION

| Part Nu | | |
|---------------|----------------|-----------|
| Non-Locking | Locking | Switching |
| ⊘84206 | 84206L | 2-C |
| ⊘84212 | ⊘84212L | 4-C |

Springs: Copper alloy, plated.

Lamp Terminals: Copper alloy, plated.

Lamp Socket: Zinc, plated.

Terminals: Copper alloy, plated, straight solder lugs. **Housing, Escutcheon, Knob, Actuator and Switching Stacks Insulation:** Molded plastic.

Temperature Range: -22°F to 158°F (-30°C to +70°C).

Dielectric Strength: 1 kV DC.

Leakage Resistance: 1,000 M Ω or greater.

K-131 COLOR FILTER KIT

Kit is available for changing or replacing color filters to meet illumination requirements. Each kit contains 3 filters of each

color: Amber, Blue, Green, Red, White and Yellow.

SWITCHCRAFT PART NUMBER K-131


REPLACEMENT LEVERS

Number G6083 (for locking lever)
Number G6084 (for non-locking lever)

THREE POSITION

| Part Nu | Part Numbers | | Position 2 |
|---------------|--------------|-----|------------|
| ⊘84306 | 84306L | 1-C | 1-C |
| ⊘84312 | 84312L | 2-C | 2-C |
| ⊘84324 | 84324L | 4-C | 4-C |


♦ Special order only; contact Switchcraft.



DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)

LEVER SWITCHES (CONTINUED)





LEV-R® SWITCH SERIES 12000

Electrical

Contact Ratings: Fine silver contacts rated at 3A, 300W maximum AC non-inductive load standard. Other contacts available

Leakage Resistance: 1,000 M Ω or greater

Dielectric Strength: 250 VDC

Material

Frame: Copper alloy, plated (3,000, 13,000); Steel,

plated (12,000)

Bushing and Shaft: Copper alloy, plated

Springs: Copper alloy

Knob: Black molded thermoplastic


Mounting Hardware: Knurled copper alloy locknut T10711, supplied. P10531 hex locknut, special order Insulation: Rigid plastic spacers with plastic tubing through stack. Rigid plastic and/or thermoplastic lifters.

Thermoplastic cam on actuator end


PART NUMBERS TWO POSITION NON-LOCKING*+ THREE POSITION NON-LOCKING*

| Part Number | Stack Hgt. "X" & "Y" (max.) | Switching | Part Number | Stack Hgt. "X" & "Y" (max.) | Swite Pos.1 | ching Pos. 2 |
|---------------|--------------------------------|-----------|---------------|-----------------------------|----------------|-----------------|
| ♦12001 | .719 (18.26) | 1-A | ♦12010 | .703 (17.86) | 1-B | 1-B |
| ♦12002 | .688 (17.48) | 1-B | ♦12011 | .703 (17.86) | 1-B | 1-B |
| ♦12003 | .750 (19.05) | 1-C | ⊘12012 | .766 (19.46) | 1-B | 1-B |
| ♦12003D | .813 (20.65) | 1-D | ⊘12013 | .703 (17.86) | 1-B | 1-C |
| ♦12004 | .906 (23.01) | 2-A | ⊘12014 | .703 (17.86) | 1-B | 1-B |
| ♦12005 | .875 (22.22) | 2-B | ♦12015 | 1.078 (27.49) | 2-B | 2-B |
| ♦12006 | 1.000 (25.40) | 2-C | ♦12016 | .703 (17.86) | 1-B | 1-B |
| ♦12006D | 1.063 (27.00) | 2-D | ♦12017 | .703 (17.86) | 1-B | 1-B |
| | | • | ⊘12033 | .719 (18.26) | 1- | -K |
| | | | ♦12034 | .813 (20.65) | 1-A | 1-A |
| | | | ♦12035 | .750 (19.05) | 1-B | 1-B |
| | | | ♦12036 | .875 (22.22) | 1-C | 1-C |
| | | | ♦12036D | 1.000 (25.40) | 1-D | 1-D |
| | | | ♦12037 | .875 (22.22) | 2- | -K |

12000 SERIES RA LEV-R SWITCHES



12000 SERIES STRAIGHT LEV-R SWITCHES



INTERCOM SWITCHES

| Part Number | Stack Height "X" &"Y" | Switching |
|----------------|-----------------------|-----------|
| ⊘12033T | .719 (18.26) | 1-K |
| ♦12037T | .875 (22.22) | 2-K |

* Add prefix "R" to part number if non-turn mounting is required. (Special order).

+ Add suffix "L" to part number if locking type is required.

♦ Special order only; contact Switchcraft.


| Knobs | | | |
|--------|-------|---------|-------|
| T12742 | Black | T127410 | Ivory |
| T12745 | White | P2912 | Amber |


Knobs must be ordered separately.


 $\frac{\ln n}{m}$


LEVER SWITCHES (CONTINUED)











LT® SWITCH **SPECIFICATIONS**

Frame: Steel, plated.

Bushing and Actuator: Copper alloy, plated.

Springs: Copper alloy.

Contact Ratings: Welded cross bar palladium contacts rated at 2A, 200W maximum, AC non-inductive load are

standard. See "SPECIAL ORDER FEATURES".

Terminals: Tin dipped solder lugs.

Mounting Hardware: Supplied with one copper alloy-plated hex locknut (P10531); and one non-turn washer (P10639). Insulation: Rigid plastic spacers with plastic tubing

the stack assembly. Lifters of thermoplastic.

Lifter-Roller Assembly: Molded plastic.

Knob: Supplied with a paddle style, screw-on black plastic

knob. See "SPECIAL ORDER FEATURES".

Temperature Range: -22°F to 158°F (-30°C to +70°C).

Leakage Resistance: 1,000 M Ω or greater.

MOLDED DUST COVERS

Dust cover is an environment and electrical shield, protecting and improving appearance and increasing switch dependability. Covers enshroud complete switch, preventing build-up of dust, dirt, contamination.

SPECIAL ORDER FEATURES

- 1. Talk-Listen (Intercom) function.
- 2. Fine silver and other alloys available for contacts. See page 294.
- 3. UL recognized switches. See page 294.

LT® SWITCH PART NUMBERS **2 POSITION NON-LOCKING***

| Part Numbers | Switching | Stack Heights Dimension "X" max. |
|---------------|-----------|-------------------------------------|
| ◊41203 | 1-C | .531 (13.49) |
| 41206 | 2-C | .531 (13.49) |
| ◊41208 | 4-A | .615 (15.62) |
| 41212 | 4-C | .750 (19.05) |

3 POSITION NON-LOCKING*

| | Position 1 | Position 2 | Dim. "Y" | Dim. "X" |
|---------------|------------|------------|--------------|--------------|
| ◊41306 | 1-C | 1-C | .531 (13.49) | .531 (13.49) |
| ◊41308 | 2-A | 2-A | .500 (12.7) | .500 (12.7) |
| 41312 | 2-C | 2-C | .531 (13.49) | .531 (13.49) |
| 41324 | 4-C | 4-C | .750 (19.05) | .750 (19.05) |

*Add suffix "L" to part number for locking type.

To avoid ordering special switches, order a larger standard circuit,

providing the circuit meets your requirements.

♦ Special order only; contact Switchcraft.

GENERAL PURPOSE STACK SWITCHES

GENERAL PURPOSE STACK SWITCHES (SPECIAL ORDER ONLY)

Complete general purpose stack switch assemblies are made from a pile-up of various actuator springs, contact springs and lifters. These stack switch assemblies can be used on manually operated control devices where switching is operated by cams, push-buttons and other similar mechanical devices. The stack switch assembly is made up of an actuator spring and various contact springs. These current carrying members are insulated from each other by phenolic spacers with plastic tubing press fitted through the stack; thereby insuring correct alignment of contacts and providing high insulation resistance when mounted.

The types of General Purpose Stack Switch Components available are:

- .375" (9.52 mm) mounting centers
- .250" (6.35 mm) mounting centers
- "Tini-Stack" Switches .188" (4.78 mm) mounting centers
- Telephone Relay Type Switches .250" (6.25 mm) mounting centers

STACK SWITCH COMPONENTS

Switchcraft offers various stack switch components, such as contact springs, spacers, lifters, etc., in many lengths, thicknesses, mounting centers and other details.

Switchcraft can assemble components into innumerable different stack switch assemblies. It is impossible to catalog every type of stack that has been manufactured. Stack switch assemblies can be designed to meet UL requirements, but only as part of equipment.

.375" STACK SWITCHES





Thousands of switching combinations are possible. Switch mounting centers are .375" (9.52 mm) (minimum) with .25" (6.35 mm) wide switch parts. Practical spring length is 2.625" (66.68 mm) (maximum). Contact Switchcraft for selection of contacts and ratings.

MINIATURE .188" (4.78MM) STACK SWITCHES





Many Tini-Stack® switching combinations are possible. Switch mounting centers are .188" (4.78 mm) (minimum). Practical spring length is 1.750" (44.45 mm) (maximum).

SPECIFICATIONS

Springs: Copper alloy, in most standard gauge thicknesses ranging from .006" (0.15 mm) to .016" (0.41 mm). Spacers: Rigid plastic, available in thickness of .015" (0.38 mm), .032" (0.81 mm) and .046" (1.17 mm).

Contacts: Welded cross bar palladium rated at 2A, 200W AC non-inductive load. Gold alloy generally recommended for "dry" circuit applications.

Tubing: Thermoplastic. Lifters: Thermoplastic.

Mounting Hardware: Pressure plate, twin nut and screws:

Steel, plated.

.250" (6.35 MM) STACK SWITCHES





Thousands of switching combinations are possible with slightly smaller parts. Mounting centers are .250" (6.35 mm) (minimum) with .188" (4.78 mm) wide parts. Practical spring length is 2.125" (53.98 mm) (maximum). Contact Switchcraft for selection of contacts and ratings.

TELEPHONE RELAY TYPE SWITCHES





Compact stack switches are particularly suitable for low activating force, such as in relay and magnetic operated devices. Contact Switchcraft for selection of contacts and ratings.

SPECIFICATIONS

Springs: Copper alloy, in thicknesses ranging from

.006" (0.15 mm) to .012" (0.30 mm).

Spacers: Rigid plastic is standard in thickness of .031"

(.79 mm), .047" (1.19 mm) and .063" (1.60 mm).

Contacts: Fine silver or welded cross bar palladium are standard. Palladium or gold alloy are generally recommended for "dry" circuit applications. Other contacts available for varied customer requirements on special order.

Tubing: Thermoplastic. Lifters: Thermoplastic. Bracket: Steel, plated.

Mounting Hardware: Pressure plate, twin nut and screws:

Steel, plated.

SWITCHES GENERAL PURPOSE STACK SWITCHES — COMPONENT SPECIFICATIONS PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

GENERAL PURPOSE STACK SWITCHES (continued)

STACK SWITCH COMPONENT SPECIFICATIONS

- **1. SPRINGS -** Copper alloy in most standard gauge thicknesses of .006" (0.15 mm), .008" (0.20 mm), .010" (0.25 mm), .012" (0.30 mm), .016" (0.40 mm) and .020" (0.50 mm), a few designs can be made up to .031" (.079 mm) thick. All or any contact point hole can be provided; spring can be cut at any point.
- **2. BRACKETS -** Standard brackets are detailed on drawing. Tools are flexible so that various lengths from same width stock can be provided.
- **3. LIFTERS OR PUSHERS -** .125" (3.18 mm) and .188" (4.78 mm) diameter thermoplastic in various lengths staked into one of the contact point holds provides tandem action between blades or to serve as an actuator.
- **4. MOUNTING HARDWARE -** Pressure plates (S1293 and S2300) twin nuts (S1008 and S1431) and screws available for mounting.
- **5. LEAF INSULATORS -** Punched in same shape as springs in .015" (0.38 mm) thickness of fish paper or mylar.
- **6. SPACERS -** Rigid plastic is standard in thicknesses of .015" (0.38 mm), .032" (0.81 mm), .051" (1.30 mm) and .062" (1.57 mm). Thickness of .093" (2.36 mm) is available for .375" (9.52 mm) mounting centers only. For longer surface creepage paths, use both large and standard sized spacers. High temperature insulation also available.
- **7. THERMOPLASTIC TUBING** .375" (9.52 mm) mounting centers pass #5 screw. .250" (6.35 mm) mounting centers pass #3 screw. .188" (4.78 mm) mounting centers pass #2 screw.
- **8. CAM FOLLOWERS -** Two roller bracket designs (G1734 and G2298) available for springs .250" (6.35 mm) wide. Copper alloy standard. Can be furnished in various diameters and materials. Thermoplastic rollers also available.
- **9. CONTACTS -** Welded cross bar contacts are commonly used for cost savings. However, riveted contacts are available. Size and material depend on circuit requirements (supply complete details). For low level audio circuits, we suggest gold alloy or palladium cross bar contacts. Springs can be bifurcated (two contacts per spring).


TYPICAL STACK ASSEMBLY THROW

HOW TO ORDER STACK SWITCHES

Careful consideration of the following suggestions will help specify the most economical and expeditious approach to your switching needs. On initial inquiry or order, supply the following information:

- Simple sketch or drawing. See "Typical Stack Assembly" drawing. Give details checked that are available.
- Current, voltage and type of switching load (resistive or inductive).
- 3. Frequency of operation; life requirements.
- 4. Details of actuator.
- 5. Maximum and minimum movement of actuator blade.
- 6. Any other important specifying details.

It is recommended that data indicated above be forwarded to Switchcraft for comments and recommendations before finalizing your design.






MULTIPLE STATION SWITCHES







SERIES IBS SERIES 65000 DW MULTI-SWITCH

SERIES 66000, 67000 DW MULTI-SWITCH

FEATURES

Switches are designed to meet performance requirements of sophisticated equipment such as: analog and digital computers, analyzers, transmitters and receivers, intercoms, machine and process controls, ground support systems, scientific instruments and test measurement and instrumentation.

STANDARD MECHANICAL FUNCTIONS

INTERLOCK - actuating a button automatically restores to normal the button previously actuated. Lock-out feature, which prevents the mechanical operation of more than one button at a time, is standard on all interlock switches.

NON-LOCK - each button has momentary action. No interaction between buttons. Lock-out available on special order only.

ALL-LOCK - all buttons, except release, lock when depressed (accumulative lock). All buttons restored to normal by activating release button which has momentary action.

PUSH-LOCK/PUSH-RELEASE - pushbutton locks when depressed and is released when again depressed.

LOCK-UP - built-in, electrically operated solenoid locks all stations (in respective positions). Limited to operation of up to 12 stations only and energized from a remote position. Not available in push-lock/push-release.

SPECIAL ORDER MECHANICAL FUNCTIONS

Mechanical functions on selected series can be intermixed on the same frame on special order only. Contact factory for details and availability.

Multi-Switch switches have been designed to readily accommodate "special" functions at nominal cost. Special functions are described at right.

Intermixed functions - the following combinations of standard functions intermixed on the same frame are available:

- Interlock and Non-Lock
- Interlock and Push-Lock/Push-Release
- All-Lock and Non-Lock
- All-Lock and Push-Lock/Push-Release
- Push-Lock/Push-Release and Non-Lock

Lock-out function - Refer to above description under "Interlock."

Push-release cancelling function - Speeds programming

and reprogramming of equipment.

Momentary common release function - Permits one or more momentary common release stations on switch to facilitate special operating and release sequences.

"Split-interlock" function - Two separate groups of inter-lock stations on the same frame offers exceptional design latitude and reduces production line time.

GANGED ASSEMBLIES (Special Order)

Multiple row switching (ganged assemblies) with interaction between rows are available on special order. Space-saving ganged assemblies reduce production line assembly, wiring and testing time. All features of single row switching, including all standard and special features, are available. Contact Switchcraft for specifying assistance.

PUSHBUTTONS

Illuminated and non-illuminated switches can be specified with standard or special pushbuttons. See coverage on individual series for information.

LEGENDS

Legends can be supplied on illuminated and non-illuminated pushbuttons. Contact Switchcraft.

PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MULTIPLE-STATION SWITCHES (continued)



SWITCHES
MULTIPLE-STATION SWITCHES

SERIES 90000, 920000 TINI DW MULTI-SWITCH



SERIES 35000 LITTEL® MULTI-SWITCH



SERIES 37000, 38000 LITTEL® MULTI-SWITCH

CHOOSING THE RIGHT MULTIPLE-STATION SWITCH

| Switch Series | Mechanical Functions¹ | Stations (Maximum) | Switching Per Station (Maximum) | Contact Rating ² | Lighting | Accessories ³ |
|------------------|--------------------------|------------------------------|---------------------------------------|--------------------------------|----------|--------------------------|
| 35000 | ILO, N, A, PL/PR | 18 | 6PDT | 2A AC, 200W | No | C, G, M, P, S, PC/WW |
| 36000 | | | 6PDT | | No | |
| 37000 | ILO, N, A, PL/PR | 18 | 4PDT | 2A AC, 200W | Yes | C, G, M, P, S, |
| 38000 | | | 3PDT | | Yes | PC/WW, LWO |
| 65000 | ILO, N, A, PL/PR | 18 | 4PDT | 3A AC, 0.5A DC | No | C, G, M, S, PC/WW |
| 66000 | ILO, N, A, PL/PR | 18 | 4PDT | 3A AC, 0.5A DC | No | C, G, M, S, PC/WW |
| 67000 | 120, 14, 71, 12,111 | 10 | F 0 | 0/1/10, 0.0/120 | Yes | , O, O, W, O, T O/VVV |
| 90000 92000 | ILO, N, A | 12 - ILO, A 18 - N, PL/PR | 8PDT | 0.5A 28V AC or DC | No | М |
| IBS | I, N | 12 | 2PDT | .125A, 125 VAC or 28 VDC | No | P, M |

^{1.} I = interlock, ILO = interlock with lockout, N = non-lock (momentary), A = all-lock (special order), PL/PR = push-lock/push-release.

ORDERING

Order switches by part number in this section.


For any optional or special order feature, contact Switchcraft.

^{2.} Non-inductive load.

^{3.} C = optional switch contact, G = ganged assemblies, M = special/mixed functions, P = optional pushbuttons, S = solenoid release, PC/WW = PC and wire-wrapping terminals, LWO = lighting wiring options.

MULTIPLE-STATION SWITCHES (continued)

LITTEL® MULTI-SWITCH SERIES 35000



Specify 1 to 18 stations (non-illuminated) with a large selection of mechanical functions, choice of pushbuttons, and up to 6 poles of switching per station. Plungers are on .625" (15.88 mm) centers and are made from .050" (1.27 mm) x .187" (4.75 mm) steel. A square black pushbutton, A592, is supplied with each station. A wide variety of special mechanical functions, features and accessories are also available.

ORDERING INFORMATION STANDARD SWITCHES

Order by part number from tables.

SPECIAL SWITCHES

Many special mechanical functions, features and accessories are available. Contact Switchcraft.

- Ganged Assemblies Pushbuttons
- Special Mechanical Functions Legends
- Switch Stacks Accessories
- PC and Wire-Wrapping Terminals




FIGURE A - PANEL CUTOUT FOR PLUNGER CLEARANCE ONLY






FIGURE B - PANEL CUTOUT FOR SERIES A590 PUSHBUTTON CLEARANCE ONLY

TYPICAL PANELS DIMENSIONS SERIES 35000





PART NUMBERS/2-C PER STATION1

| Interlock with Lock-Out | Non-Lock | Push-Lock/ Push-Release | Number of Stations ² |
|-------------------------|------------------|----------------------------|---------------------------------|
| 35021K206 | ◊35022206 | ◊35027206 | 2 |
| 35041K206 | ⊘35042206 | ◊35047206 | 4 |
| 35061K206 | ◊35062206 | ◊35067206 | 6 |
| 35081K206 | ◊35082206 | ◊35087206 | 8 |
| 35101K206 | ∂35102206 | ◊35107206 | 10 |
| 35121K206 | ◊35122206 | ◊35127206 | 12 |

PART NUMBERS/4-C PER STATION¹

| ♦35021K212 | ◊35022212 | ◊35027212 | 2 |
|-------------------|------------------|------------------|----|
| ♦35041K212 | ♦35042212 | ◊35047212 | 4 |
| ♦35061K212 | ◊35062212 | ◊35067212 | 6 |
| ♦35081K212 | ♦35082212 | ◊35087212 | 8 |
| ♦35101K212 | ◊35102212 | ◊35107212 | 10 |
| ♦35121K212 | ♦35122212 | ♦35127212 | 12 |
| | | | |

- Switches with all-lock function are available on special order. Contact Switchcraft.
- 2. Odd number of stations (3, 5, 7, 9, 11) are available. Switches with 13 through 18 stations are also available. Contact Switchcraft.
- ♦ Special order only; Contact Switchcraft for price and delivery information.

(mm)

SWITCHES LITTEL® MULTI-SWITCH — SERIES 36000, 37000 & 38000 FEATURES

PHONE: 773 792-2700


* Please visit the product pages on our website for the most up-to-date product information

MULTIPLE-STATION SWITCHES (continued)

LITTEL® MULTI-SWITCHES SERIES 36000, 37000, 38000







SERIES 36000 - NON-ILLUMINATED

SERIES 37000 - SINGLE LAMP

SERIES 38000 - TWIN LAMPS

SERIES 36000

Identical to Series 37000, except non-illuminated. Pushbuttons match Series 37000 and 38000 Switching up to 6PDT.

SERIES 37000

Same as Series 35000, but features large, rectangular face pushbuttons, illuminated by one lamp and having large legend area. Switching is up to 4PDT. Switch stations are on .625" (15.88 mm) centers, and depth behind panel is 2.313" (58.75 mm). Black pushbutton housings have white translucent inserts, white legend insert, two support inserts, and transparent display screen. Other pushbuttons and combinations are possible; see pages 316 and 317.

On 2-C per station switches, each station includes two, 83P switch stacks and one H83P lighting stack, and one convenience lighting spring. Contact ratings: 2A, 200W maximum AC non-inductive load.

On 4-C per station switches, each station has 4, 83P switch stacks, one H83P lighting stack, and one convenience lighting spring. "L" and "M" lighting arrangements can be effected by wiring directly to the H83P and H lighting stacks.

Each switch station uses an industry standard T 1-3/4 lamp (not supplied). Special features such as ganged assemblies, solenoid release, and T-1 lamp adapter are available; contact Switchcraft. See pages 316 and 317 for special effects display screen and inserts.

SERIES 38000

Similar to Series 37000, except features twin lamp illumination at each station for redundant or 2-color, split-face (alternate) lighting.

On 2-C per station switches, each station includes 3, H83P lighting switch stacks and 1 lighting spring. This provides up to 3PDT circuitry (1 pole is needed for lighting lamps; lamps not supplied). Contact ratings: 2A, 200W maximum AC non-inductive load.

On 4-C per station switches, each station has three, H83P, two, 83P switching stacks and one lighting spring. This offers

5PDT circuitry (1 pole is required for lighting lamps). two, T 1-3/4 lamps per station are used (lamps are not supplied). Ganged assemblies and solenoid releases are available; contact Switchcraft. See pages 316 and 317 for special effects display screens and inserts.

LIGHTING

Series 37000 and 38000 can be used in control systems where the light is either "ON", or "OFF" or permanently "ON".

One or any combination of the three lighting arrangements listed below can be specified on a switch. NOTE: Standard switches ordered from tables can be wired for "L", "M" or "N" type lighting.

| TYPE | DESCRIPTION |
|------|--|
| "L" | Pushbuttons light in the "IN" position. |
| "M" | Pushbuttons light in the "OUT" position. |
| "N" | Pushbuttons light in the "IN" and "OUT" positions. |

ORDERING STANDARD SWITCHES

Order by part number from tables.

SPECIAL SWITCHES

Many special mechanical functions, features and accessories are available. Contact Switchcraft for special order items.

- Ganged Assemblies
 Special Mechanical Functions
- Special Color Displays
 Pushbuttons
- Legends
 Switch Stacks
- Wiring Lighting Options
 PC and Wire-wrapping Terminals
- Accessories

MULTIPLE-STATION SWITCHES (continued)

LITTEL® MULTI-SWITCHES SERIES 36000, 37000, 38000 (continued)

SERIES 37000

PART NUMBERS / 2-C PER STATION1

| Interlock with Lock-Out | Non-Lock | Push-Lock/ Push-Release | Number of Stations ² |
|----------------------------|-------------------|----------------------------|---------------------------------|
| ⊘37021K1206 | ⊘370221206 | ♦370271206 | 2 |
| ⊘37041K1206 | ⊘370421206 | ♦370471206 | 4 |
| ♦37061K1206 | ⊘370621206 | ♦370671206 | 6 |
| ♦37081K1206 | ⊘370821206 | ♦370871206 | 8 |
| ⊘37101K1206 | ⊘371021206 | ♦371071206 | 10 |
| ⊘37121K1206 | ⊘371221206 | ◊371271206 | 12 |

PART NUMBERS / 4-C PER STATION¹

| ♦37021K1212 | ♦370221212 | ♦370271212 | 2 |
|--------------------|-------------------|-------------------|----|
| ♦37041K1212 | ♦370421212 | ♦370471212 | 4 |
| ♦37061K1212 | ♦370621212 | ◊370671212 | 6 |
| ♦37081K1212 | ♦370821212 | ♦370871212 | 8 |
| ♦37101K1212 | ⊘371021212 | ♦371071212 | 10 |
| ⊘37121K1212 | ◊371221212 | ⊘371271212 | 12 |

- 1. Switches with all-lock function are available on special order. Contact Switchcraft.
- 2. Odd number of stations (3, 5, 7, 9, 11) are available. Switches with 13 through 18 stations also available. Contact Switchcraft.
- ♦ Special order only; Contact Switchcraft for price and delivery information.

TYPICAL PANEL OPENING .625 × NO. OF STATIONS <u>.147</u> DIA. 4 [3.7] HOLES 438 1.0 ...312 + (.625 x NO. OF STATIONS)-

SERIES 38000

PART NUMBERS / 2-C PER STATION1

| Interlock with Lock-Out | Non-Lock | Push-Lock/ Push-Release | Number of Stations ² |
|-------------------------|-------------------|----------------------------|---------------------------------|
| ♦38021K1206 | ◊380221206 | ◊380271206 | 2 |
| ♦38041K1206 | ⊘380421206 | ◊380471206 | 4 |
| ♦38061K1206 | ◊380621206 | ♦380671206 | 6 |
| ♦38081K1206 | ⊘380821206 | ♦380871206 | 8 |
| ♦38101K1206 | ⊘381021206 | ♦381071206 | 10 |
| ⊘38121K1206 | ⊘381221206 | ♦381271206 | 12 |

PART NUMBERS / 4-C PER STATION¹

| ⊘38021K1212 | ♦380221212 | ◊380271212 | 2 |
|--------------------|-------------------|-------------------|----|
| ⊘38041K1212 | ♦380421212 | ◊380471212 | 4 |
| ⊘38061K1212 | ⊘380621212 | ◊380671212 | 6 |
| ⊘38081K1212 | ◊380821212 | ◊380871212 | 8 |
| ⊘38101K1212 | ◊381021212 | ◊381071212 | 10 |
| ⊘38121K1212 | ◊381221212 | ◊381271212 | 12 |
| | | | |

- 1. Switches with all-lock function are available on special order. Contact Switchcraft.
- 2. Odd number of stations (3, 5, 7, 9, 11) are available. Switches with 13 through 18 stations also available. Contact Switchcraft.
- ♦ Special order only; Contact Switchcraft for price and delivery information.

MATERIAL SPECIFICATIONS

Frame: Steel, dry film lubricant.

Plungers, Stack Switch Mounting Brackets and Screws:


Steel, plated.

Stack Switches: Stack switch springs are made of copper

alloy. Solder lugs are hot tin-dipped.

Insulation: Stack switches: rigid plastic spacers with

plastic tubing through stack. Lifters: Thermoplastic.



SWITCHES LITTEL® MULTI-SWITCH — SPECIAL EFFECTS COLOR DISPLAY & INSERTS PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MULTIPLE-STATION SWITCHES (continued)

SPECIAL EFFECTS COLOR DISPLAY SCREENS AND INSERTS

Display screens and inserts are offered in a wide choice of colors for SERIES 37000 and 38000 Littel Multi-Switch switches. Display screens with high-lights are useful in high ambient lighting; or display screens with soft, uniform, and diffused lighting for use under low ambient lighting conditions. Order display screens, inserts and filters separately. See Part Number Chart below.

Series 401 Display Screen Α

Series 404 В Legend insert recesses into display screen. Omit when split-face

Part Number 404 05

inserts are used.

White legend insert has a matte finish on one side suitable for in-the-field marking.

Part Number 404 12 **Retaining Insert**


Clear insert snaps into display screen from rear to retain legend inserts. Omit when split-face inserts are used.

- Series 407 Split-Face Insert D Use with Series 38000
- Series 402 Color Filter Inserts White insert used with blue, white and clear display screens; clear insert used with red, green and yellow. All color filters are omitted where split-face insert is used.

Part Number 402 12 Heat **Shield Insert**

Clear filter insert snaps into push-button housing. Must be used in every pushbutton assembly.

- Part Number 406 Light Divider Recesses into
 - pushbutton housing. For use with Series 38000.
- Series 405 02 Pushbutton Н Housing.



SERIES 401 DISPLAY SCREENS - Display screens with contoured face give a better operation "feel". Rectangular shape provides greater area for engraving legends and symbols. Entire screen is illuminated by single or twin lamp indication. Various brightness and color combinations are possible by use of legend filter and split face inserts.

SERIES 404 LEGEND INSERTS - Small translucent inserts provide special color effects. White colored insert (40405) has a special matte surface for in-the-field identification with ink, pencil or lettering transfers. Special color effects can be accomplished with combination of a colored insert with a clear display screen. IMPORTANT: Order legend insert (40412) with every pushbutton.

SERIES 407 SPLIT-FACE INSERTS - Split-face inserts provide separate control or indicating functions through the use of color. Ideal for use on Series 38000 Littel Multi-Switch switches where each pushbutton can serve as two indicator lights. Up to two lamps can be used per display screen which are split lengthwise by 2-color split-face inserts. Inserts may be hot-stamped. Order (406) light divider when "flip-flop" lighting is specified; or for redundant lighting where a definite visual indication of lamp failure is desired. A frequently used combination is red and green. Red might indicate danger, stop, etc. Green, go, "okay", etc. IMPORTANT: Use (40212) clear insert with a split-face insert.

SERIES 402 FILTER INSERTS – Inserts add greater color definition. Ideal for use under low ambient lighting conditions where brightness of illuminated pushbuttons must be minimized. A white filter insert (40205) is useful in cutting down the brightness of a white color insert and a white or clear display screen. However, it is omitted when color display screen is used. Filters also diffuse light evenly over entire face of display screen with no "hot spots" or darkened corners. IMPORTANT: Order clear insert (40212) for use with every color filter insert. Clear insert snaps in button housing behind a color filter insert and serves as a heat shield.

406 LIGHT DIVIDER – A light divider is used in the standard pushbutton housing to separate the illumination from the twin lamps used in the Series 38000 Littel Multi-Switch switches. Order a light divider for every pushbutton station in the Series 38000 where split-face lighting has been specified.

Series 405 PUSHBUTTON HOUSINGS - One-piece housing for all 37000 and 38000 switches. Accepts Series 401, 402, 404, 406 and 407 components. Standard color is black. Other colors available.

ORDERING - For variations in pushbutton configurations, contact Switchcraft.

| Part No. | Figure | Color |
|---------------|--------|----------------|
| ◊40101 | | Red |
| ◊40103 | | Green |
| ◊40104 | | Blue |
| ◊40105 | Α | White |
| ◊40108 | | Yellow |
| ◊40112 | | Clear |
| ◊40116 | | "Black Screen" |
| ◊40401 | В | Red |

| ♦ Special or | der only; Contact Switchcraft for |
|--------------|-----------------------------------|
| price and | delivery information. |


| | Part No. | Figure | Color |
|---|---------------|--------|--------------------------|
| | ◊40403 | | Green |
| | ◊40404 | В | Blue |
| | ◊40405 | В | White |
| | ◊40408 | | Yellow |
| | | С | Clear (retaining insert) |
| П | | | Red |
| | ◊40203 | Е | Green |
| | ◊40204 | | Blue |
| | ◊40205 | | White |
| | | | L |


| Figure | Color |
|--------|----------------------------|
| Е | Yellow |
| F | Clear (heat shield insert) |
| | Red |
| | Green |
| D | Blue |
| | White |
| | Yellow |
| G | White (light divider) |
| ш | Black (housing) |
| П | White |
| | E F D |

Inch

MULTIPLE-STATION SWITCHES (continued)

LITTEL® MULTI-SWITCH ACCESSORIES





"TINI-STACK" SWITCHES

Many combinations of stack switches are available on special order. Contact Switchcraft for specifying assistance, including clearances for stack heights.

SERIES 80P - Crossbar welded palladium contacts rated: 2A, 200W maximum, AC non-inductive load. For use where contacts of a released station will return to normal before contacts of a newly operated station are actuated. Not recommended for use on push-lock/push/release function.

SERIES 800P - Same as Series 80P but can be used on push-lock/push-release function, or on other functions where contacts of a newly operated station must be actuated before contacts of a released station return to normal.

SERIES 80G - Same as Series 80P, except includes cross-bar welded gold alloy contacts rated at 1A, 100W maximum, AC non-inductive load.

SERIES 800G - Same as Series 80G except for push-lock/push-release and/or other functions as described for Series 800P.

BIFURCATED "TINI-STACK" SWITCH STACKS

Double reliability through use of bifurcated switch stacks featuring bifurcated leaf springs slotted at the contact end and parallel to the long axis of the leaf spring. Separate crossbar gold alloy contacts are welded to leaf springs on each side, doubling the number of contacts on each spring.

SERIES 60BG - Similar to Series 80P, except bifurcated leaf springs with welded crossbar gold alloy contacts rated at 1A, 100W maximum, AC non-inductive load.

SERIES 600BG - Same as Series 60BG, except for use on push-lock/push-release function and/or functions as described under Series 800P.


HIGH CURRENT "TINI-STACK" SWITCH STACKS

Heavy duty switch stacks Series 60W for use in 120V, AC power circuits are available with large, fine silver contacts rated at 5A, non-inductive load. Stack spacer width limits mounting to one stack/station on each side of frame and requires special mounting bracket.

For 10 and 15A switching, contact Switchcraft.


POSITIONING SWITCH STACKS (SERIES 80P, 800P, 80G AND 800G ONLY)

Refer to chart below for proper balancing of the switch stacks mechanical load at each station, "X" denotes correct positioning of the stack on the removable switch stack bracket.



SERIES NJ SOLENOID RELEASE

Solenoid assembly attaches to end of switch frame and provides electrical release of activated stations. Instructions and hardware furnished. Other voltages are available on special order; contact Switchcraft.



PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MULTIPLE-STATION SWITCHES (continued)

LITTEL® MULTI-SWITCH ACCESSORIES

WIRE-WRAPPING TERMINALS

Special order wire-wrapping terminals optimize use of semi-automated termination equipment to save production line time. Terminal shoulders accommodate 1, 2 or 3 wrapped connections per terminal and prevent wrapping tool from "bottoming" (on first wrapped connection) and possibly shorting against other metal parts on switch stack. 4-C switching per station maximum.

NOTE: Stack height dimension will be greater when wire-wrapping terminals are specified. Stack height for 1-A and 1-B circuit is .516" (13.11 mm). For 1-C height is .594" (15.09 mm).


ORDERING: Contact Switchcraft for details.


RECOMMENDED WIRE-WRAPPING TOOLS

| | (Gardner -Denver Co. Part Numbers) | | |
|------------|------------------------------------|-------|--|
| Wire Gauge | Wrapping Bit Sleeve | | |
| #22 & #24 | 500131 | 18840 | |
| #25 | 500131 18840 | | |
| #26 | 37006 17611-2 | | |

RECOMMENDED WIRE-WRAPPING PARAMETERS

| Wire | Number of | Wraps Per | Wire | Number of | Wraps Per |
|------------|-------------|------------|------------|-------------|------------|
| Gauge | Connections | Connection | Gauge | Connections | Connection |
| #22 #24 | 3 | 4 5 | #25 #26 | 3 3 | |





LAMP SOCKETS AND ADAPTERS

LAMP SOCKET T10 \Diamond

Standard on Series 37000, T10 accepts standard midget flange type T1-3/4 lamps.

LAMP SOCKET T12 \Diamond

Standard on Series 38000, the T12 socket accepts standard midget flange type T1-3/4 lamps.


LAMP ADAPTER T1


Converts sockets that accommodate standard T 1-3/4, (P1593) midget flange base lamps to accept T 1 subminiature lamps. Adapter fits T 1-3/4 lamp socket. The 2-piece adapter holds lamp securely in place to assure positive contact of lamp circuit in most environments. If you require extra long-life, specify a T 1 lamp adapter for each T 1-3/4 socket.

PC TERMINALS

Copper alloy PC terminals are integral with associated leaf spring and feature shoulders for proper clearance from PC board and for solid mounting. Contact Switchcraft for details.

 \lozenge Available on special order only; Contact factory for price and delivery information.








MULTIPLE-STATION SWITCHES (continued)

DW MULTI-SWITCH SERIES 65000

Available with up to 18 non-illuminated stations in a single row. Maximum switching per station is 4-C (4PDT). Contacts are rated: 3A, AC, 0.5A DC, 125V, non-inductive load. Integral black button is supplied with each station. Switches mount with #6 screws and nut (not furnished). Contact Switchcraft for special assemblies, with ganged assemblies, solenoid release, PC or wire-wrapping terminals, or escutcheon modules.



PART NUMBERS / 2-C PER STATION¹


| Interlock with Lock-Out | Non-Lock | Push-Lock/ Push-Release | Number of Stations ² |
|-------------------------|------------------|----------------------------|---------------------------------|
| 65021K206 | ◊65022206 | ◊65027206 | 2 |
| 65041K206 | ◊65042206 | ◊65047206 | 4 |
| 65061K206 | ◊65062206 | ◊65067206 | 6 |
| 65081K206 | ◊65082206 | ◊65087206 | 8 |
| 65101K206 | ◊65102206 | ◊65107206 | 10 |
| 65121K206 | ◊65122206 | ◊65127206 | 12 |

- 1. Switches with all-lock function are available on special order. Contact Switchcraft.
- Odd number of stations (3, 5, 7, 9, 11) are available. Switches with 13 through 18 stations also available. Contact Switchcraft.
- \Diamond Special order only; Contact Switchcraft for price and delivery information.

PART NUMBERS / 4-C PER STATION1

| Interlock with Lock-Out | Non-Lock | Push-Lock/ Push-Release | Number of Stations ² |
|-------------------------|------------------|----------------------------|---------------------------------|
| ♦65021K212 | ◊65022212 | ◊65027212 | 2 |
| ♦65041K212 | ◊65042212 | ◊65047212 | 4 |
| ♦65061K212 | ◊65062212 | ◊65067212 | 6 |
| ♦65081K212 | ◊65082212 | ◊65087212 | 8 |
| ♦65101K212 | ◊65102212 | ◊65107212 | 10 |
| ♦65121K212 | ◊65122212 | ◊65127212 | 12 |

- Switches with all-lock function are available on special order. Contact Switchcraft.
- 2. Odd number of stations (3, 5, 7, 9, 11) are available. Switches with 13 through 18 stations also available. Contact Switchcraft.
- ♦ Special order only; Contact Switchcraft for price and delivery information.



DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm -5WILGII — STRIES DOULU & DAULU

* Please visit the product pages on our website for the most up-to-date product information

MULTIPLE-STATION SWITCHES (continued)


DW MULTI-SWITCH SERIES 66000 and 67000



Series 66000 (non-illuminated) and 67000 (illuminated) can be supplied with up to 18 stations, including a square white pushbutton Part Number DW305 at each station. Contacts and ratings are the same as for Series 65000. Lamp sockets (67000) at each station accept 6V to 28V T 1-3/4 flange base lamps (not supplied). Mounts with 2 #6-32 machine screws (not supplied). See page 310 for pushbutton data. Accessories include solenoid release, ganged assemblies, T1 lamp adapter, and metal barriers (between stations). PC and wire-wrapping terminals are also available. Contact Switchcraft.

NON-ILLUMINATED DW MULTI-SWITCH SWITCHES

Switchcraft offers DW Multi-Switch switches, Series 70000 and 71000 with crossbar plungers which accept a wide variety of Switchcraft and industry pushbuttons. Contact Switchcraft for specifying assistance.





Squeeze upper and lower surfaces of pushbutton and pull free of plungers.

SERIES DW40 COLOR INSERTS

Many unusual lighting effects can be created using DW40 color inserts. Molded from dimensionally stable, high-temperature plastic in six standard colors, inserts slip into standard Series DW300 pushbuttons providing unusual latitude in custom designing color and legend effects. With no wear from finger-tips, legend life is virtually unlimited.

| Part No. | Color | Part No. | Color | Part No. | Color |
|---------------|-------|----------|-------|---------------|--------|
| ♦ DW41 | Red | ♦DW44 | Blue | ⊘DW47 | Orange |
| ♦ DW43 | Green | DW45 | White | ♦ DW48 | Yellow |

 $[\]Diamond$ Special order only; Contact Switchcraft for price and delivery information.

SERIES DW300 PUSHBUTTONS (DW305 supplied standard)

| Part No. | Color ¹ | Part No. | Color ¹ | Part No. | Color ¹ |
|----------|--------------------|----------|--------------------|----------|--------------------|
| DW301 | Red | DW304 | Blue | DW312 | Clear |
| DW302 | Black | DW305 | White | DW313 | Amber |
| DW303 | Green | DW308 | Yellow | DW316 | "Black- |
| | | | | | Screen" |

¹ Other colors available on special order. Buttons are 0.594 (15.09) x 0.594 (15.09)


PART NUMBERS/2-C PER STATION¹

| Interlock | | Push-Lock/ | Number of |
|---------------|------------------|------------------|-----------------------|
| with Lock-Out | Non-Lock | Push-Release | Stations ² |
| 67021K506 | ◊67022506 | ◊67027506 | 2 |
| 67041K506 | ◊67042506 | ◊67047506 | 4 |
| 67061K506 | ◊67062506 | ◊67067506 | 6 |
| 67081K506 | ◊67082506 | ◊67087506 | 8 |
| 67101K506 | ◊67102506 | ◊67107506 | 10 |
| 67121K506 | ◊67122506 | ◊67127506 | 12 |
| | | | |

PART NUMBERS/4-C PER STATION¹

| ⊘67021K512 | ⊘67022512 | ◊67027512 | 2 |
|-------------------|------------------|------------------|----|
| ⊘67041K512 | ◊67042512 | ∂67047512 | 4 |
| ⊘67061K512 | ◊67062512 | ∂67067512 | 6 |
| ⊘67081K512 | ◊67082512 | ∂67087512 | 8 |
| ⊘67101K512 | ◊67102512 | ∂67107512 | 10 |
| ⊘67121K512 | ◊67122512 | ∂67127512 | 12 |
| | | | |

- Switches with all-lock function are available on special order. Contact Switchcraft.
- 2. Odd number of stations (3, 5, 7, 9, 11) are available. Switches with 13 through 18 stations also available. Contact Switchcraft.
- ♦ Special order only; Contact Switchcraft for price and delivery information.



Next, grasp lamp with lamp removal tool or fingertips and snapout. Replace lamp and pushbutton. Finished in seconds!

MULTIPLE-STATION SWITCHES (continued)

DW MULTI-SWITCH ACCESSORIES

ESCUTCHEON MODULES, SERIES DW100 AND DW200


Modules are available in colors to match or contrast with Series 65000 pushbutton colors. Modules are simply slipped over the pushbuttons before the switch is mounted on the panel. Flanges on modules overlap the panel cutout and hold modules securely in place while adding only 0.02" (.051 mm) behind panel space.

One module is required for each station. Installation of the Series DW200 Modules (with barrier) is equally simple. First, place one Series DW100 Module over the pushbutton actuator on one end of the row. On the adjacent actuator, place a Series DW200 Module. Position this module so that the barrier overlaps the edge of the Series DW100 Module. Install the remaining Series DW200 modules in the same manner, with the barriers overlapping. The completed escutcheon will have barriers between adjacent pushbutton actuators, but no barriers at the ends of the rows.

| Series DW-100 (without barrier) | Series DW-200 (with barrier) | Color* |
|------------------------------------|---------------------------------|--------|
| ♦ DW101 | ⊘DW201 | Red |
| DW102 | DW202 | Black |
| DW05 | DW205 | White |

^{*} Other colors available on special order.

[♦] Special order only; Contact Switchcraft for price and delivery information.





SPECIAL SWITCHING FORMS

In addition to 2-C and 4-C switching, other circuit forms can be supplied on special order. They are: 1-A, 2-A, 3-A, 4-A, 1-B, 2-B, 3-B, 4-B, 1-C, 3-C, 1-D, 2-D, 3-D, and 4-D.

BARRIERS (SERIES 67000 ONLY)

As an option, (field installable) barriers can be specified and installed. Sturdy wire barriers fit between pushbuttons and prevent accidental simultaneous actuation of adjacent push-buttons. When a pushbutton is depressed, the fingertip is guided away from adjacent pushbuttons, and all pressure is applied to the correct pushbutton.

Switchcraft Part Number $\Diamond P2359$ Barriers (package of 25)

SOLENOID RELEASE

Solenoids provide electromechanical assistance in releasing locked switch stations in switches with up to 12 stations. Release can be effected from a local or remote position. Solenoids are available for use with switches having inter-lock, all-lock, or push-lock/push-release mechanical functions. All solenoids are "pull-type". When ordered separately, solenoids are supplied with all mounting hardware. Brass terminals accept "push-on" type clips (ARK-LES #3500M20C), or wiring can be soldered directly to the lugs.

SPECIFICATIONS

Frame, Latch Bar, and Switch Housing: Steel, plated. Mounting Studs (Series 66000 and 67000):

Same as frame above.

Pushbutton Actuators (Series 65000): Molded thermoplastic. Pushbuttons (Series 66000 and 67000):

Molded thermoplastic.

Terminals: Copper alloy, silver-plated. **Contactors:** Copper alloy, plated. **Terminal Board:** Rigid plastic.

Lamp Socket (Series 67000): Copper alloy, plated.

| Part Number | Switch Function | Mounting* | Voltage | Coil Res. (Ohms) | Duty Cycle |
|----------------|---|-----------|------------------|---------------------|---------------|
| ⊘DW1 | Interlock | Left | 115 AC, 60 Hz | 361 | 20% |
| ⊘DW3 | All-Lock | Right | 115 AC, 60 Hz | 130 | 10% |
| ⊘DW4 | Interlock | Left | 24 DC | 14.2 | 20% |
| ♦DW7 | All-Lock or Push- Lock/Push- Release | Right | 24 DC | 8.96 | 10% |

^{*} Direction indicates side of switch frame solenoid is mounted on (solenoid terminals up).

SWITCHES <u>Tini® DW Multi-Switch — Series 90000 &</u> 92000


PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MULTIPLE-STATION SWITCHES (continued)



SERIES 92000 Switch TDW-F Flip-Flop Pushbutton Installed



TINI® DW MULTI-SWITCH - SERIES 90000, 92000

Subminiature, multiple station switches have pushbuttons on 0.394" (10mm), 0.590" (15mm), or 0.787" (20mm) centers. Four mechanical functions: Interlock, Non-Lock, All-Lock and Push-Lock/Push-Release. Switches mount in panels up to .343" (8.71mm) thick. Switching per station is 2-C (2PDT), 4-C (4PDT), 6-C (6PDT) or 8-C (8PDT). Contact ratings: 0.5A, 28V AC or DC non-inductive. Solder lug or PC terminals.

SERIES 90000 - Up to 18 stations on 0.394" (10mm) centers in a row. Switch mounts with 2, #3 screws (not supplied).

SERIES 92000 - 15mm station centers. Wider spacing permits mounting Series TDWF pushbuttons.

SPECIFICATIONS ELECTRICAL

Switching Module Rating: 0.5A, 28V AC or DC

non-inductive load.

Initial Contact Resistance: 10 milliohms.

MATERIALS

Frame Switch Housing: Steel, plated. Latch Bar: Stainless steel on all-lock function;

zinc alloy on interlock function.

Latch Bar Return Spring: Tinned music wire.

Plunger: Molded thermoplastic.

Plunger Return Spring: Tinned music wire. Terminals/Contacts: Copper alloy, silver-plated.

Contact Sliders: Bifurcated bimetal (silver on copper alloy).

Terminal Board: Molded thermoplastic (UL 94V-0).

Pushbuttons: Molded thermoplastic.

PUSHBUTTONS

| Part Number | Color | Part Number | Color |
|---------------|-------|---------------|--------|
| ◊A6501 | Red | ◊A6504 | Blue |
| ◊A6502 | Black | ◊A6505 | White |
| ◊A6503 | Green | ◊A6508 | Yellow |

Buttons are 0.386 (9.80 mm) x 0.386 (9.80 mm).

 \Diamond Special order only; Contact Switchcraft for price and delivery information.

Pushbuttons for Tini DW Multi-Switch switches must be specified separately, below. Refer to page 316 for data on TWDF pushbuttons.

Series A650 pushbuttons can be specified for both Series 90000 and 92000. Legends can be specified; contact Switchcraft.

PART NUMBERS/2-C PER STATION1

| | Push-Lock/ | Number of |
|------------------|---|---|
| Non-Lock | Push-Release | Stations ² |
| ◊90022B06 | ◊90027B06 | 2 |
| ♦90042B06 | ♦90047B06 | 4 |
| ◊90062B06 | ♦90067B06 | 6 |
| ◊90082B06 | ♦90087B06 | 8 |
| ♦90102B06 | ◊90117B06 | 10 |
| ⊘90122B06 | ♦90127B06 | 12 |
| | ⟨90022B06 ⟨90042B06 ⟨90062B06 ⟨90082B06 ⟨90102B06 | Non-Lock Push-Release ◊90022B06 ◊90027B06 ◊90042B06 ◊90047B06 ◊90062B06 ◊90067B06 ◊90082B06 ◊90087B06 ◊90102B06 ◊90117B06 |

PART NUMBERS/4-C PER STATION1

| ⊘90024B12 | ♦90022B12 | ♦90027B12 | 2 |
|------------------|-----------|------------------|----|
| ♦90044B12 | ♦90042B12 | ♦90047B12 | 4 |
| ♦90064B12 | ♦90062B12 | ♦90067B12 | 6 |
| ♦90084B12 | ♦90082B12 | ♦90087B12 | 8 |
| ♦90104B12 | ♦90102B12 | ♦90117B12 | 10 |
| ◊90124B12 | ♦90122B12 | ♦90127B12 | 12 |


- 1 Switches with all-lock function are available on special order. Contact Switchcraft.
- 2 Odd number of stations (3, 5, 7, 9, 11) are available. Switches with 13 through 18 stations also available. Contact Switchcraft.
- \Diamond Special order only; Contact Switchcraft for price and delivery information.


SPECIFYING NOTE:


Series 90000 Part Numbers are given in table. To order Series 92000 switches, substitute "2" for "0" for second digit of Part Number. Example; Part Number 92024B06 in the Series 92000 version 0.590" (15mm centers) of Part Number 90024B06 0.394" (10mm centers) interlock with lock-out, 2-C switching per station.


MULTIPLE-STATION SWITCHES (continued)


TINI® DW MULTI-SWITCH SERIES 90000 and 92000











PHONE: 773 792-2700

* Please visit the product pages on our website for the most up-to-date product information

MULTIPLE-STATION SWITCHES (continued)







TYPE I 0.388 (9.86) x 0.216 (5.49)

TYPE II 0.464 (11.79) x 0.288 (7.32)

PART NUMBERS/0.394" (10MM) CENTERS¹

| Interlock | Number of Stations ² |
|-----------------------|---------------------------------|
| ♦IBS10B02106AR | 2 |
| ♦IBS10B04106AR | 4 |
| ♦IBS10B06106AR | 6 |
| ♦IBS10B08106AR | 8 |
| ♦IBS10B10106AR | 10 |
| ◊IBS10B12106AR | 12 |

PART NUMBERS/0.590" (15MM) CENTERS¹

| ◊IBS15B02106AR | 2 |
|-----------------------|----|
| ◊IBS15B04106AR | 4 |
| ◊IBS15B06106AR | 6 |
| ◊IBS15B08106AR | 8 |
| ◊IBS15B10106AR | 10 |
| ◊IBS15B12106AR | 12 |
| | |

PART NUMBERS/0.787" (20MM) CENTERS¹

| ◊IBS20B02106AR | 2 |
|-----------------------|----|
| ♦IBS20B04106AR | 4 |
| ♦IBS20B06106AR | 6 |
| ♦IBS20B08106AR | 8 |
| ♦IBS20B10106AR | 10 |
| ♦IBS20B12106AR | 12 |

- Switches with all-lock function are available on special order. Contact Switchcraft.
- 2. Odd number of stations (3, 5, 7, 9, 11) are available. Switches with 13 through 18 stations also available. Contact Switchcraft.
- \Diamond Special order only; Contact Switchcraft for price and delivery information.

PUSHBUTTON PART NUMBERS

| Type I | Type II | Color |
|---------------|---------------|-----------|
| P2936 | P2951 | White |
| P2937 | P2952 | Black |
| P2938 | P2953 | Red |
| ⊘P2939 | ⊘P2954 | Yellow |
| ⊘P2940 | ⊘P2955 | Green |
| P2941 | P2956 | Blue |
| P2942 | P2957 | Gray |
| ⊘P2943 | ⊘P2958 | Brown |
| - | ⊘P2979 | Cream |
| - | ⊘P2992 | Tangerine |

 \Diamond Available on special order only; contact Switchcraft for price and delivery.

IBS MULTI-SWITCH SWITCHES SERIES IBS

Series IBS miniature pushbutton switches are mounted on common frames, up to 12 stations long with center-to-center spacing of 0.394" (10mm), 0.590" (15mm) or 0.787" (20mm). Available with interlock, non-lock (momentary) or push-lock/push-release mechanical functions. .130" (3.30mm) x .130" (3.30mm) square plungers accept a full line of industry standard pushbuttons. Switches are stocked without pushbuttons due to wide variety that can be used. Order pushbuttons separately. Switches have .157" (4mm) long PC terminals for mounting single- or double-sided PC boards up to .094" (2.39mm) thick. Close stacking (centers) permits high density within minimum front panel space.

PUSHBUTTONS

Pushbuttons designed for IBS switches are available in white, black, red, blue and gray. Others colors are available on special order. Pushbutton faces are concave for operator convenience and can be mounted either horizontally or vertically. Pushbuttons must be ordered separately, but may be factory installed, if desired, at nominal extra cost.

SPECIFICATIONS

MECHANICAL

Switch Actuation: Momentary, interlock and push-lock/

push-release.

Plunger Travel: .144" (3.66 mm).

Actuation Force: At .135" (3.43mm) travel: 12-15 oz.

ELECTRICAL

0.125A resistive @ 125 V AC, .25 AMP at 28V DC.

MATERIALS

Housing: Thermoplastic 94V-0. **Plunger:** Thermoplastic UL 94V-0.

Contactors: Copper alloy.

Terminals: Copper alloy, solder plated. Tin-dipped

available on special order.

Contact Surfaces: Plated.

Frame: Copper alloy.

Latch Bar: Thermoplastic.


MULTIPLE-STATION SWITCHES (continued)

IBS MULTI-SWITCH SWITCHES SERIES IBS

IBS PART NUMBERING CODE

| CENTERS FRAME STYLE STATIONS MECHANICAL CIRCUITS TERMINAL 0.394" (10mm) A - Mounting Ears 01 - 12 FUNCTION 01 - 1A LENGTH 0.590" (15mm) B - No Mounting Ears 1 - Interlock 02 - 1B A - 0.157" 0.787" (20mm) 2 - Non-Lock 03 - 1C (4mm) 04 - 2A 05 - 2B | IBS | s xx | X | XX | X | $\mathbf{X}\mathbf{X}^{1}$ | X | R |
|--|-----|--------------------------------|-------------------|----|---------------------------|---|-----------------------------|---|
| 06 - 2C | | 0.394" (10mm) 0.590" (15mm) | A - Mounting Ears | | FUNCTION 1 - Interlock | 01 - 1A 02 - 1B 03 - 1C 04 - 2A 05 - 2B | LENGTH A - 0.157" | |

- 1. See page 269 for individual switch terminal conjunction.



0.394" (10mm) CENTERS **STATIONS** Dimension 10 11 12 2 9 3.880 4.274 4.667 5.061 5.455 1.912 2.305 3.093 3.486 1.518 2.699 (138,56)(38,56)(48,56)(58,55) (68,55)(78,56)(88,54)(98,55)(108,56)(118,54)(128,55)2.057 3.238 4.026 4.419 4.814 5.207 1.270 2.451 2.845 3.632 1.663 В (132,26) (112,24)(122,28)(32, 26)(42,24)(52, 25)(62, 26)(72, 26)(82, 25)(92, 25)(102, 26)2.357 2.750 3.144 3.538 3.931 4.325 4.719 1.569 1.963 1.175 .782 C (119,86) (99,85)(109,86)(19,86) (29,84)(39,85)(49,86)(59,87)(69,85)(79,86)(89,86)2.057 2.451 2.844 3.238 3.632 4.025 4.419 4.813 .876 1.269 1.663 (112,24) (102,24) (122,25) (82,24)(92, 25)(22, 25)(32,23)(42,24)(52, 25)(62, 26)(72,24)

0.590" (15mm) CENTERS

STATIONS

| | | Dimension | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
|------|------|-----------|------|---------|---------|---------|---------|----------|----------|----------|----------|----------|----------|----------|
| | | | In. | 1.715 | 2.305 | 2.896 | 3.486 | 4.077 | 4.667 | 5.258 | 5.848 | 6.439 | 7.030 | 7.620 |
| 90 | | A | (mm) | (43,56) | (58,55) | (73,56) | (88,54) | (103,56) | (118,54) | (133,55) | (148,54) | (163,55) | (178,56) | (193,55) |
| \$ | . | | In. | 1.467 | 2.057 | 2.648 | 3.238 | 3.829 | 4.419 | 5.010 | 5.600 | 6.191 | 6.782 | 7.372 |
| gi l | | В | (mm) | (37,26) | (52,25) | (67,26) | (82,25) | (97,26) | (112,24) | (127,25) | (142,24) | (157,25) | (172,26) | (187,25) |
| Ē | 1 | | In. | .979 | 1.569 | 2.160 | 2.750 | 3.341 | 3.932 | 4.522 | 5.112 | 5.703 | 6.294 | 6.884 |
| - | F 85 | С | (mm) | (24,87) | (39,85) | (54,86) | (69,85) | (84,86) | (99,87) | (114,86) | (129,84) | (144,86) | (159,87) | (174,85) |
| | | | In. | 1.073 | 1.663 | 2.254 | 2.844 | 3.435 | 4.025 | 4.616 | 5.206 | 5.797 | 6.388 | 6.978 |
| | 2 | l D | (mm) | (27,25) | (42,24) | (57,25) | (72,24) | (87,25) | (102,24) | (117,25) | (132,23) | (147,24) | (162,26) | (177,24) |

0.787" (20mm) CENTERS

STATIONS

| | | Dimensio | n | 2 | 3 | 4 | 5 | 6 | 7 | 8 | |
|----------|--------|----------|------|---------|---------|---------|----------|----------|----------|----------|-------|
| | | | In. | 1.911 | 2.699 | 3.486 | 4.274 | 5.061 | 5.848 | 6.636 | |
| 2 | | ^ | (mm) | (48,54) | (68,55) | (88,54) | (108,56) | (128,55) | (148,54) | (168,55) | |
| ₫ | | В | In. | 1.663 | 2.451 | 3.238 | 4.026 | 4.813 | 5.600 | 6.388 | |
| gi | | B | (mm) | (42,24) | (62,26) | (82,24) | (102,26) | (122,25) | (142,24) | (162,25) | |
| 5 | | | ln. | 1.175 | 1.963 | 2.750 | 3.538 | 4.325 | 5.112 | 5.900 | |
| | PES SE | C | (mm) | (29,84) | (49,86) | (69,85) | (89,86) | (109,86) | (129,84) | (149,86) | |
| | | | | ln. | 1.269 | 2.057 | 2.844 | 3.632 | 4.419 | 5.206 | 5.994 |
| 1 | S M | | (mm) | (32,23) | (52,25) | (72,24) | (92,25) | (112,24) | (132,23) | (152,25) | |

MULTIPLE-STATION SWITCHES (continued)

MULTI-SWITCH PUSHBUTTONS

| | III | luminated | | | Non-l | lluminated | | | |
|--------------------------------|----------|-----------|--------------------|----------|--------|------------|--------|--------|---------|
| Switch Series | Fig. 1 | Fig. 2 | Fig. 3 | Fig. 4 | Fig. 5 | Fig. 6 | Fig. 7 | Fig. 8 | Fig. 9 |
| | 9 | | | 8 | | | | | |
| Pushbutton Series ¹ | 400⁴ | 409⁵ | DW300 ⁶ | A-590 | E-590⁵ | A-650 | TDW-F | Type I | Type II |
| 35000 | | | | X-(Std.) | Х | | | | |
| 37000 | X (Std.) | Х | | | | | | | |
| 38000 | X (Std.) | Х | | | | | | | |
| 65000 ² | | | | | | | | | |
| 67000 | | | X (Std.) | | | | | | |
| 90000³ | | | | | | Х | | | |
| 92000³ | | | | | | Х | Х | | |
| IBS ³ | | | | | | | | Х | Х |

- 1. Any pushbutton series can be specified with engraved legends.
- 2. Buttons are an integral part of switch assembly on Series 65000.
- Switches stocked without pushbuttons due to wide variety that can be used. Order buttons separately.
- Display screens and inserts are also available in a wide choice of colors; see "SPECIAL EFFECTS COLOR DISPLAY SCREENS AND INSERTS".
- 5. Double width button
- 6. Colored inserts are available in a wide choice of colors; see "SERIES DW40 COLOR INSERTS".

SPECIFYING NOTE:


Most pushbuttons can be specified in red, black, green, blue, white or yellow. "Black-Screen", amber, clear, and other colors are also possible. Contact Switchcraft with your requirements.

SERIES TDWF - "FLIP-FLOP" PUSHBUTTONS

Unique internal "flip-flop" mechanism permits button face to change colors without electrical energy, lamps or wiring. When pushbutton is operated, highly reflective panels inside housing change position and use ambient light to give a bright illuminated effect. Black pushbuttons are .59" (15mm) high x .63" (16mm) wide. Display window is .315" (8mm) x .374" (9.5mm) wide.

NOTE: "FLIP-FLOP" PUSHBUTTONS ARE DESIGNED FOR USE WITH SERIES 92000 SWITCHES ONLY. Order "flip-flop" pushbuttons with Series 92000 switches. TDW-F "Flip-Flop" Pushbutton Part Numbering

TDW-F "FLIP-FLOP" PUSHBUTTON PART NUMBERING



DIMENSIONS ARE FOR REFERENCE ONLY

Inch (mm)

MULTIPLE-STATION SWITCHES (continued)

MULTI-SWITCH PUSHBUTTONS TDWF PUSHBUTTON LEGENDS (special order)

Horizontally Mounted Switches: Three, .125" (3.18 mm)

high characters, each pushbutton.

Vertically Mounted Switches: Three, .125" (3.18 mm)

high characters, each pushbutton.

LEGEND CHARACTERS AVAILABLE

| 1 tl | hrough 999 | A th | rough ZZZ |
|----------|-----------------|------|-----------|
| | Period | " | Quotes |
| - | Short Dash | _ | Long Dash |
| — | Arrow | & | Ampersand |
| # | Number or Pound | 1 | Slash |
| \$ | Dollar | ¢ | Cent |
| | Vertical Bar | | |

NOTE: Recommended minimum standoff for switches mounted with TDW-F pushbutton is .5" (12.7mm).

SERIES X, Y AND Z "GLO-BUTTON"

Non-illuminated pushbuttons provide a clearly visible legend like illuminated pushbuttons - without lamps, wiring or power. With button depressed, illuminator moves up behind front screen, and legend "lights up" by efficient reflection of external ambient light. With button in "out" position, illuminator retracts and legend appears non-luminous. Series X - specify for horizontal or vertical mount switches. Series Y - legends marked across .625" (15.88 mm) dimension. For horizontal mount switches. Series Z - legends marked across .75" (19.05 mm) dimension. For vertical mount switches.

| Part | | Screen | Illuminator | Size inches (mm) | | | |
|-----------------|--------|--------|-------------|------------------|-----------------|--|--|
| Number | Figure | Color | Color | Width | Height | | |
| X21248◊ | 10 | Black | Orange-Red | .5 | .5 | | |
| X51248◊ | 10 | White | Orange-Neu | (12.7) | (12.7) | | |
| Y21248◊ | 11 | Black | Orange-Red | | | | |
| Y28248 ◊ | 11 | Black | Chartreuse | .625 (15.88) | .75 (19.05) | | |
| Y51248◊ | 11 | White | Orange-Red | (13.00) | (19.03) | | |
| Z21248 ◊ | 12 | Black | Orange-Red | | | | |
| Z28248 ◊ | 12 | Black | Chartreuse | .75 (19.05) | .625 (15.88) | | |
| Z51248 | 12 | White | Orange-Red | (19.05) | (13.00) | | |

MULTI-SWITCH PUSHBUTTON PART NUMBERS

Use the information below to specify colors of the pushbutton series desired. Series TDWF must be specified separately (see page 316).

| PART | | | Overall Siz | e Inch (mm) |
|---------------|--------|--------|---------------|--------------|
| NUMBER | FIGURE | COLOR | Width | Height |
| ◊40001 | | Red | | |
| ◊40002 | | Black | | |
| ◊40003 | | Green | | |
| ◊40004 | 1 | Blue | .594 (15.09) | .974 (24.7) |
| 40005 | | White | | |
| ◊40008 | | Yellow | | |
| 40012 | | Clear | | |
| ◊40901 | | Red | | |
| ◊40902 | | Black | | |
| ◊40903 | | Green | | |
| ◊40904 | 2 | Blue | 1.219 (30.96) | .719 (18.26) |
| ◊40905 | | White | | |
| ◊40908 | | Yellow | | |
| ◊40912 | | Clear | | |
| A591 | | Red | | |
| A592 | | Black | | |
| ♦ A593 | | Green | | |
| ♦ A594 | 4 | Blue | .594 (15.09) | .594 (15.09) |
| A595 | | White | | |
| ♦ A596 | | Brown | | |
| ♦ A598 | | Yellow | | |
| ◊E591 | | Red | | |
| ◊E592 | | Black | | |
| ◊E594 | | Blue | | |
| ◊E595 | 1 | White | 1.234 (31.34) | .594 (15.09) |
| ◊E596 | | Brown | | |
| ◊E598 | | Yellow | | |

[♦] Available on special order only; contact Switchcraft for price and delivery.

FAX: 773 792-2129

* Please visit the product pages on our website for the most up-to-date product information

| 03BL2M | 17 | 112BPC | ΩΩ | 1400 | 203 | 2035 | 274 |
|---------------------------|------------------------|---------------------|----------------|-------------|-------------------|-------------------|---|
| | | | | | | | |
| 05BL3M | | 112BPCS | | 1400301 | | | 46 |
| 05BL5M | | 113 | | 1400315 | | | 262 |
| 05CL3M | 46 | 113B | 98 | 142A | 110 | 220 | 153 |
| 05CL5M | | 113BPC | | | 94 | | 153 |
| | | | | | | | 154 |
| 05DL3M | | 113BPC1M | | | 107 | | |
| 05DL5M | | 113BPCS | | | 107 | | 153 |
| 05GM3M | | 113D | 98 | 152B | 107 | | 153 |
| 05GM5M | 46 | 113DPC | 98 | 153 | 107 | 229 | 153 |
| 05YL3M | | 113E | | 1532A | | | 263 |
| | | | | | | | |
| 05YL5M | | 113EPC | | 1532A301 | | | 263 |
| 06AL5F | | 113EPCS | | 1532B | | | 263 |
| 06EL5F | | 113F | | 1532B301 | | 22QK22 | 263 |
| 09BL4M | 47 | 113FPC | 98 | 1534B | 203 | 22QN22 | 263 |
| 09CL4M | | 113FPCS | | | 107 | | 153 |
| 09DL4M | | 113PC | | | 107 | | 86 |
| | | | | | | | |
| 09GM4M | | 113PCS | | | 48 | | 86 |
| 09YL4M | | 114B | 98 | 15AL8F | 48 | 2332A | 86 |
| 101 | 274 | 114BPC | 98 | 15BL7M | 47 | 2332B | 86 |
| 101S | 274 | 114BPC1M | 98 | 15BL8M | 47 | 2333 | 86 |
| 102 | | 114BPCS | | | 46 | | 153 |
| | | | | | | | |
| 102S | | 120 | | | 46 | | 154 |
| 103 | | 1200 | | | 47 | | 153 |
| 103S | 274 | 12001 | 297 | 15EL8F | 48 | 238 | 153 |
| 11 | | 12002 | | | 46 | | 153 |
| | | 12003 | | | | | 145 |
| 11001 | | | | | 46 | | |
| 11001L | | 12003D | | 15J9068 | | | 205 |
| 11002 | | 12004 | | 15J9076 | | | 205 |
| 11002L | 231 | 12005 | 297 | 15J9077 | 230 | 2432B | 205 |
| 11003 | | 12006 | 297 | 15J9078 | | | 205 |
| 11003D | | 12006D | | | 147 | | 145 |
| | | | | | | | |
| 11003DL | | 12010 | | | 212 | | 109 |
| 11003L | | 12011 | 297 | 1632A | 212 | 25 | 109 |
| 11004 | 231 | 12012 | 297 | | 212 | | 145 |
| 11004L | | 12013 | | | 212 | | 65 |
| | | 12014 | | | | | 65 |
| 11005 | | | | 16J1055 | | | |
| 11005L | | 12015 | | | 147 | | 65 |
| 11006 | | 12016 | 297 | 1700 | 212 | | 205 |
| 11006D | 231 | 12017 | 297 | 172 | 148 | 2532B | 205 |
| 11006DL | | 12033 | | | 152 | | 205 |
| | | | | | | | |
| 11006L | | 12033T | | | 152 | | |
| 11008 | | 12034 | | | 152 | | 205 |
| 11008L | | 12035 | 297 | 176S | 152 | | 205 |
| 11009 | 231 | 12036 | 297 | 177S | 152 | 2544B | 205 |
| 11009L | | 12036D | | | 152 | | 145 |
| | | | | | | | |
| 11012 | | 12037 | | | 212 | | 205 |
| 11012L | | 12037T | | | 152 | | 205 |
| 111 | 98 | 121 | 108 | 181 | 148 | 260 | 145 |
| 111PC | 98 | 1230 | 108 | 182 | 148 | 2600 | 205 |
| 111PCS | | 1238 | | | 147 | | 205 |
| | | | | | | | |
| 11201 | | 125 | | | 147 | | 205 |
| 11201L | | 128 | | | 147 | | 145 |
| 11202 | 231 | 12A | 94 | 184L | 147 | 269 | 145 |
| 11202L | 231 | 12B | | 187 | 149 | 26U1003 | 278 |
| 11203 | | 12BL5M | | | 149 | | 278 |
| | | 12BL6M | | | | | 278 |
| 11203D | | | | | 149 | | |
| 11203DL | | 12CL5M | | | 149 | | 278 |
| 11203L | | 12DL5M | | | 149 | | 278 |
| 11204 | 231 | 12DL6M | 47 | 187L | 149 | 26U1008 | 278 |
| 11204L | | 12GM5M | | | 149 | | 278 |
| 11205 | | 12GM6M | | | | | |
| | | | | 18QA18 | | | 278 |
| 11205L | | 12YL5M | | | 262 | | 145-146 |
| 11206 | | 13 | | 18QD18 | | | 205 |
| 11206D | 231 | 131 | 108 | 18QF18 | 262 | 2732A301 | 205 |
| 11206DL | | 133 | | 18QH18 | | | 205 |
| 11206L | | 1332A | | 18QK18 | | | 205 |
| | | | | | | | |
| 11208 | | 1332B | | | 262 | | 205 |
| 11208L | | 1334B | | | 151 | | 205 |
| 44000 | 231 | 1394RAPC | 58 | 190A | 151 | 2734B301 | 205 |
| 11209 | | 1394SMT | | | 151 | | 205 |
| | 231 | 100 1 0 1V11 | | | 151 | | |
| 11209L | | 13Δ | | | 1:01 | | |
| 11209L 11212 | 231 | 13A | | | | | |
| 11209L | 231 | 13AL5F | 48 | 201 | 274 | 281 | 145-146 |
| 11209L 11212 | 231 | | 48 | 201 | | 281 | 145-146 |
| 11209L 11212 11212L | 231 231 98 | 13AL5F | 48 48 | 201 201S | 274 | 281 282 | 145-146 155 |
| 11209L 11212 11212L | 231 231 98 98 | 13AL5F 13AL6F | 48 48 94 | 201 201S | 274 274 274 | 281 282 285 | 145-146 145-146 155 145-146 145-146 |

| 290 | | 35101K206 | | 370421212 | | | 28 |
|--|-----|--|----------|--------------------------------|----------|--|-----|
| 297 | | 35101K212 | | 370471206 | | | 28 |
| 298 | | 35102206 | 303 | 370471212 | 305 | | 28 |
| 299 | 150 | 35102212 | 303 | 37061K1206 | 305 | 391Q63 | 28 |
| 2BL6M | 47 | 35107206 | 303 | 37061K1212 | 305 | 40 | 147 |
| 2C1072 | | 35107212 | | 370621206 | | | 317 |
| 2P-1216 | | 35121K206 | | 370621212 | | | 317 |
| 2P1248 | | 35121K212 | | 370671206 | | | 317 |
| | | | | | | | |
| 2P1251 | | 35122206 | | 370671212 | | | 317 |
| 2P1298 | | 35122212 | | 37081K1206 | | | 317 |
| 2P1384 | | 35127206 | | 37081K1212 | | | 317 |
| 2P1419 | | 35127212 | | 370821206 | | | 317 |
| 2P1495 | 145 | 3514PC | 123 | 370821212 | 305 | 40101 | 306 |
| 2P1509 | 153 | 3515PC | 123 | 370871206 | 305 | 40103 | 306 |
| 2P1515 | 162 | 3517PC | 123 | 370871212 | 305 | 40104 | 306 |
| 2P1624 | 162 | 352A | 159 | 370A | | | 306 |
| 2P2003 | | 35581 | | 37101K1206 | | | 306 |
| 305HJ084184 | | 35582 | | 37101K1212 | | | 306 |
| | | 35585 | | 371021206 | | | 306 |
| 305KD084184 | | | | | | | |
| 306HK042306 | | 35HDBAU | | 371021212 | | 40201 | |
| 306HK084306 | | 35HDBAUS | | 371071206 | | | 306 |
| 321 | | 35HDBN | | 371071212 | | | 306 |
| 322 | 27 | 35HDBNS | | 37121K1206 | | 40205 | 306 |
| 323 | 27 | 35HDNAU | 156 | 37121K1212 | 305 | 40208 | 306 |
| 324 | 27 | 35HDNAUS | 156 | 371221206 | 305 | 40212 | 306 |
| 32HR*** | | 35HDNN | | 371221212 | | | 306 |
| 330F1 | | 35HDNNS | | 371271206 | | | 306 |
| 330F2 | | 35HDRAAU | | 371271212 | | | 306 |
| 332A | | 35HDRABAU | | 374 | | | 306 |
| | | | | | | | |
| 336A | | 35HDRANN | | 376 | | 40408 | |
| 336B | | 35HR*** | | 377 | | | 306 |
| 33HR*** | | 35PM1 | | 380 | | | 306 |
| 340 | | 35PM2A | | 38021K1206 | 305 | | 306 |
| 345A | 159 | 35RAPC2AH3 | 114, 116 | 38021K1212 | 305 | 406 | 306 |
| 349A | 159 | 35RAPC2AHN2 | 114, 116 | 380221206 | 305 | 40701 | 306 |
| 350 | 148 | 35RAPC2AHN3 | 114 | 380221212 | 305 | 40703 | 306 |
| 3501F | | 35RAPC2AV | | 380271206 | | | 306 |
| 3501FP | | 35RAPC2AV4 | | 380271212 | | | 306 |
| 3501FR | | 35RAPC2AVN4 | | 38041K1206 | | | 306 |
| | | | | | | | |
| 3501M | | 35RAPC2BH3 | | 38041K1212 | | | 317 |
| 3501MC | | 35RAPC2BHN2 | | 380421206 | | | 317 |
| 3502 | | 35RAPC2BHN3 | | 380421212 | | | 317 |
| 35021K206 | | 35RAPC2BV4 | | 380471206 | 305 | | 317 |
| 35021K212 | 303 | 35RAPC2BVN4 | 114 | 380471212 | 305 | 40905 | 317 |
| 35022206 | 303 | 35RAPC3BH3 | 114, 116 | 38061K1206 | 305 | 40908 | 317 |
| 35022212 | 303 | 35RAPC3BHN2 | 114. 116 | 38061K1212 | 305 | 40912 | 317 |
| 35027206 | | 35RAPC3BHN3 | | 380621206 | | | 110 |
| 35027212 | | 35RAPC3BV4 | | 380621212 | | | 141 |
| 3502A | | 35RAPC3BVN4 | | 380671206 | | | 141 |
| | | | | | | — | |
| 3502AAU | | 35RAPC4BH3 | | 380671212 | | | 298 |
| 3502ABAU | | 35RAPC4BHN2 | | 38081K1206 | | | 298 |
| 3502RA | | 35RAPC4BHN3 | | 38081K1212 | | | 298 |
| 3502RAAU | | | 114-115 | 380821206 | 305 | 41212 | 298 |
| 3502RABAU | 161 | 35RAPC4BVN4 | 114 | 380821212 | 305 | 41306 | 298 |
| 3503 | 123 | 35RAPC7J | 112 | 380871206 | 305 | 41308 | 298 |
| 35041K206 | 303 | 35RAPC7JS | 112 | 380871212 | 305 | | 298 |
| 35041K212 | | 35RASMT | | 38101K1206 | | | 298 |
| 35042206 | | 35RASMT2AHNTR | | 38101K1212 | | | 141 |
| 35042212 | | 35RASMT2BHNTR | | 381021206 | | | 141 |
| | | | | | | | |
| 35047206 | | 35RASMT3BHNTR | | 381021212 | | | 138 |
| 35047212 | | 35RASMT4BHNTR | | 381071206 | | | 138 |
| 3504M | | 361A | , | 381071212 | | | 110 |
| 3505F | | 362A | | 38121K1206 | | | 110 |
| 35061K206 | 303 | 363 | 159 | 38121K1212 | 305 | | 65 |
| 35061K212 | 303 | 364A | 159 | 381221206 | 305 | 46201ME | 284 |
| 35062206 | | 365 | | 381221212 | | 46201MR | 284 |
| 35062212 | | 36HR*** | | 381271206 | | | 284 |
| 35067206 | | 37021K1206 | | 381271212 | | | 284 |
| | | | | | | | |
| 35067212 | | 37021K1212 | | 383A | | | 284 |
| 3507 | | 370221206 | | 384A | | | 284 |
| 35081K206 | | 370221212 | | 386A | | | 284 |
| 35081K212 | 303 | 370271206 | 305 | 387A | 28 | | 284 |
| 35082206 | 303 | 370271212 | 305 | 389 | 28 | 46203LSE | 284 |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| 35082206 35082212 35087206 35087212 | 303 | 370271212 37041K1206 37041K1212 370421206 | 305 | 389 390 391Q13 391Q23 | 28 28 | 46203LSE 46203LSR 46203ME 46203MR | |

| 46204LE | 284 | 516-120-000-101 | 178 | 65042212 | 309 | 761K | 162 |
|-----------------|-----|-----------------|-----|-----------|-----|----------|----------|
| 46204LR | | 516-120-000-102 | | 65047206 | | | 162 |
| 46204ME | | 516-290-500 | | 65047212 | | | 162 |
| 46204MR | | | | | | | 162 |
| | | 516-290-590 | | 65061K206 | | | |
| 46206LE | | 520 | | 65061K212 | | | 157 |
| 46206LFE | | 53B | | 65062206 | | | 157 |
| 46206LFR | | 54A | 109 | 65062212 | 309 | 80 | 108 |
| 46206LR | 284 | 54B | 109 | 65067206 | 309 | 820 | 142 |
| 46206LSE | 284 | 55 | 109 | 65067212 | 309 | 830 | 108 |
| 46206LSR | 284 | 5501F | 65 | 65081K206 | 309 | 838 | 108 |
| 46206ME | | 5501M | | 65081K212 | | | 296 |
| 46206MP | | 5501MF | | 65082206 | | | 296 |
| | | | | | | | |
| 46206MR | | 5501MP | | 65082212 | | | 296 |
| 46256LFR | | 55HA2F | | 65087206 | | | 296 |
| 46311LDR | | 56206L1 | | 65087212 | | | 296 |
| 46311MDR | 285 | 56206L2 | 288 | 65101K206 | 309 | 84306L | 296 |
| 46311TDR | 285 | 56313L1 | 289 | 65101K212 | 309 | 84312 | 296 |
| 46313LDR | 285 | 56313L2 | 289 | 65102206 | 309 | 84312L | 296 |
| 46313MDR | | 570 | | 65102212 | | | 296 |
| 46313TDR | | 57GB3F | | 65107206 | | | 296 |
| 47202LE | | 57GB5F | | 65107212 | | | 121, 158 |
| | | | | | | | |
| 47202LR | | 57HB3F | | 65121K206 | | | 158 |
| 47203LE | | 57HB5F | | 65121K212 | | | 158 |
| 47203LR | | 57KD3M | 48 | 65122206 | 309 | | 158 |
| 47204LCE | 286 | 57NC5F | 50 | 65122212 | 309 | 855 | 158 |
| 47204LCR | 286 | 57PC3F | 51 | 65127206 | 309 | 856 | 158 |
| 47204LE | | 57PC3FS | 52 | 65127212 | 309 | 857 | 158 |
| 47204LR | 286 | 57PC5F | | 67021K506 | | | 158 |
| 47206LCE | | 57PC5FS | | 67021K512 | | | 162 |
| | | | | | | | |
| 47206LCR | | 580 | | 67022506 | | | 162 |
| 47206LE | | 581 | | 67022512 | | | 108 |
| 47206LR | | 585 | | 67027506 | | | 158 |
| 47215LCR | 286 | 588 | | 67027512 | 310 | 881 | 158 |
| 47215LR | 286 | 58NC3F | 50 | 67041K506 | 310 | 882 | 158 |
| 47217LCR | 286 | 590 | 146 | 67041K512 | 310 | 883 | 158 |
| 47217LR | | 597 | | 67042506 | | | 151 |
| 47221LCR | | 598 | | 67042512 | | | 312 |
| 47221LR | | 59GB3F | | 67047506 | | | 312 |
| | | | | | | | |
| 47227LFE | | 60 | | 67047512 | | | 312 |
| 47227LFR | | 60GB4F | | 67061K506 | | | 312 |
| 482 | | 60HA4F | | 67061K512 | | | 312 |
| 482N | 140 | 60NC4F | 50 | 67062506 | 310 | 90027B12 | 312 |
| 482NC | 140 | 60PC4F | 51 | 67062512 | 310 | 90042B06 | 312 |
| 483N | 140 | 60PC4FS | 52 | 67067506 | 310 | 90042B12 | 312 |
| 483NC | 140 | 610 | 106 | 67067512 | 310 | 90044B06 | 312 |
| 49101 | | 612 | | 67081K506 | | | 312 |
| 49102 | | 615 | | 67081K512 | | | 312 |
| 49105 | | 61GB5F | | 67082506 | | | 312 |
| 49201 | | | | | | | |
| | | 61GB6F | | 67082512 | | | 312 |
| 49202 | | 61HA5F | | 67087506 | | | 312 |
| 49205 | | 61NC5F | | 67087512 | | | 312 |
| 49301 | | 61PC5F | 51 | 67101K506 | | | 312 |
| 49302 | 232 | 61PC5FS | 52 | 67101K512 | 310 | 90067B06 | 312 |
| 49305 | 232 | 61PC6F | 51 | 67102506 | 310 | 90067B12 | 312 |
| 49309L | 287 | 61PC6FS | 52 | 67102512 | 310 | 90082B06 | 312 |
| 49309LS | | 620 | | 67107506 | | | 312 |
| 49312L | | 62206L | | 67107512 | | | 312 |
| 49312LS | | 62GB7F | | 67121K506 | | | 312 |
| 49312L3 | | 62GB8F | | 67121K500 | | | 312 |
| | | | | | | | |
| 49329LS | | 62HB7F | | 67122506 | | | 312 |
| 49331L | | 62HB8F | | 67122512 | | | 312 |
| 49331LS | 287 | 62NC7F | 50 | 67127506 | 310 | 90102B12 | 312 |
| 50207L | 287 | 62NC8F | 50 | 67127512 | 310 | 90104B06 | 312 |
| 50207M | 287 | 62PC7F | 51 | 70 | 147 | 90104B12 | 312 |
| 50208L | 287 | 62PC7FS | 52 | 712A | 134 | 90117B06 | 312 |
| 50209L | | 62PC8F | | 712RA | | | 312 |
| 50209LS | | 62PC8FS | | 722A | | | 312 |
| 50209L3 | | 65021K206 | | 722RA | | | 312 |
| | | | | | | | |
| 50209MS | | 65021K212 | | 732A | | | 312 |
| 50212L | | 65022206 | | 732RA | | | 312 |
| 50212LS | | 65022212 | | 740 | | | 312 |
| 510 | 106 | 65027206 | | 745 | 157 | 90127B12 | 312 |
| 512 | 106 | 65027212 | 309 | 750 | 157 | 903 | 273 |
| 515 | 106 | 65041K206 | | 755 | 157 | | 273 |
| 516-090-000-301 | 178 | 65041K212 | | 760 | 162 | 9115 | 30 |
| 516-090-000-302 | | 65042206 | | 760K | | | 30 |
| 0.0 000 000 002 | 170 | JOO 12200 | | | 102 | J 120 | 00 |
| | | | | | | | |

| 913 | 273 | Δ5MR | 4 | B6F | 10 | C11 | 94 |
|----------|----------|---------|-----|-----------|-----|-----------|-----|
| 913D | | | | | | | 94 |
| | | | 4 | B6M | | | |
| 9144 | | | 4 | B7F | | | 94 |
| 921 | 245, 276 | A6501 | 312 | B7M | 10 | C1600 | 212 |
| 921K | | Δ6502 | 312 | BD1600 | 212 | | 212 |
| | | | 312 | | | | |
| 923 | | | | BD1632B | | | 145 |
| 923D | | | 312 | BD1634B | 212 | C245 | 145 |
| 9244 | 30 | A6505 | 312 | BD1650 | 212 | C270 | 145 |
| 933 | 273 | A6508 | 312 | BD1700 | 212 | C3F | 10 |
| 933D | | | 4 | BD1795 | | | 10 |
| | | | | | | | |
| 951 | | | 4 | BD1796 | | | 284 |
| 952 | 273 | A6FBAU | 4 | BPJF01 | 123 | C46204MR | 284 |
| 953 | 273 | A6M | 4 | BPJF01AU | 123 | C46206LFR | 284 |
| 961 | | | 4 | BPJF02 | | | 284 |
| | | | | | | | |
| 962 | | | 4 | BPJF02AU | | C4F | 10 |
| 963 | 273 | A7FB | 4 | BPJF03 | 123 | C4M | 10 |
| 97GV*** | 244 | A7FBAU | 4 | BPJF03AU | 123 | C55B | 109 |
| 982A01R | | | 4 | BPJF04 | | C56206L1 | 288 |
| | | | | | | | |
| 982A03R | | | 4 | BPJF04AU | | | 288 |
| 982A06R | 269 | AA3F | 4 | BPJF05 | 123 | C56313L1 | 289 |
| 99GD0726 | 244 | AA3FB | 4 | BPJF05AU | 123 | C56313L2 | 289 |
| 99GV*** | | | 4 | BPJF06 | | | 10 |
| | | | | | | | |
| A1600 | | | 4 | BPJF06AU | | | 10 |
| A1632B | 212 | AA3FL | 4 | BPJJ01 | 123 | C62206L | 290 |
| A1634B | 212 | AA3FLD | 4 | BPJJ01AU | 123 | C63212L | 290 |
| A3F | | | 4 | BPJJ02 | | | 10 |
| | | | | BPJJ02AU | | | |
| A3F01 | | | 4 | | | | 10 |
| A3F02 | 5 | | 4 | BPJJ03 | | | 10 |
| A3F03 | 5 | AA3ML | 4 | BPJJ03AU | 123 | C7M | 10 |
| A3F04 | | | 4 | BPJJ04 | | | 65 |
| A3F05 | | | | BPJJ04AU | | | |
| | | | 4 | | | | 65 |
| A3F06 | | AA4FD | 4 | BPJJ05 | 123 | | 212 |
| A3F07 | 5 | AA4FL | 4 | BPJJ05AU | 123 | CD1634B | 212 |
| A3F08 | 5 | AA4M | 4 | BPJJ06 | 123 | CMT331 | 83 |
| | | | | | | | |
| A3F09 | | | 4 | BPJJ06AU | | | 83 |
| A3FB | 4 | AA5F | 4 | BPJR01 | 123 | CMT332A | 83 |
| A3FBAU | 4 | AA5FB | 4 | BPJR01AU | 123 | CMT332B | 83 |
| A3FD | | | 4 | BPJR02 | | | 84 |
| | | | | | | | |
| A3FL | | | 4 | BPJR02AU | | | 83 |
| A3FS | 4 | AA5M | 4 | BPJR03 | 123 | CMT333A | 83 |
| A3M | 4-5 | AA5MB | 4 | BPJR03AU | 123 | CMT333B | 84 |
| A3M01 | | | 4 | BPJR04 | | | 83 |
| | | | | | | | |
| A3M02 | | | 4 | BPJR04AU | | | 83 |
| A3M03 | 5 | AA6FB | 4 | BPJR05 | 123 | CMT334C | 83 |
| A3M04 | 5 | AA6FD | 4 | BPJR05AU | 123 | CMT334E | 83 |
| A3M05 | | | 4 | BPJR06 | | | 83 |
| | | | 4 | BPJR06AU | | | |
| A3M06 | | | | | | | |
| A3M07 | 5 | | 4 | BXR011 | | | 84 |
| A3M08 | 5 | AA7F | 4 | BXR0110 | 272 | CMT336 | 83 |
| A3M09 | 5 | AA7FR | 4 | BXR011PC | 272 | CMT336A | 83 |
| A3MB | | | 4 | BXR013 | | | 83 |
| | | | | | | | |
| A3MBAU | | | 4 | BXR013P | | | 83 |
| A3ML | 4 | AA7M | 4 | BXR016 | 272 | CMT336D | 83 |
| A3MS | 4 | AA7ML | 4 | BXR016P | 272 | CMT336E | 83 |
| A4F | | | 6 | BXR021 | | | 83 |
| | | | | | | | |
| A4FB | | | 6 | BXR0210 | | | 83 |
| A4FBAU | 4 | AD1600 | 212 | BXR021PC | 272 | CMT339 | 83 |
| A4FD | 4 | AD1632B | 212 | BXR023 | 272 | CMT341 | 84 |
| A4FL | | | 212 | BXR023P | | | 84 |
| | | | | | | | |
| A4M | | | 4 | BXR026 | | | 84 |
| A4MB | | | 4 | BXR026PC | | | 83 |
| A4MBAU | 4 | B1600 | 212 | BXR03 | 272 | CMT346C | 84 |
| A4ML | | B1632B | 212 | BXR0310 | 272 | CMT351C | 83 |
| A591 | | | 212 | BXR0310PC | | | 83 |
| | | | | | | | |
| A592 | | | 212 | BXR031PC | | | 83 |
| A593 | 317 | B1700 | 212 | BXR033 | 272 | CMT358 | 83 |
| A594 | 317 | B1795 | 212 | BXR033PC | 272 | CMT359 | 83 |
| A595 | | | 212 | BXR036 | | | 109 |
| | | | | | | | |
| A596 | | | 10 | BXR036PC | | | 109 |
| A598 | 317 | B3FB | 10 | BXR051 | 272 | CN12B | 109 |
| A5F | 4 | B3M | 10 | BXR0510 | 272 | CN13B | 109 |
| A5FB | | | 10 | BXR051PC | | | 263 |
| | | | | | | | |
| A5FBAU | | | 10 | BXR053 | | | 263 |
| | 1 | B4M | 10 | BXR053PC | 272 | CPC102F | 263 |
| A5FD | 4 | | | | | 0. 0.02 | |
| A5FD | | | 10 | BXR056 | 272 | | 263 |

| CPC102R | 263 | DW3 | 311 | EP913 | 276 | IBS20B12106AR | 314 |
|------------|-----|-----------|-----|-----------------|-----|---------------|-----|
| CPC102T | | DW301 | | EP913D | | J3FS | |
| CPC102U | | DW302 | | EPS1PC1 | | J4MS | |
| D1600 | | DW303 | | EPS1PC2 | | JP012000 | |
| D1632A | | DW304 | | EPS1PC3 | | JP012S32A | |
| D1632B | | DW305 | | EPS1SL1 | | JP012S32B1 | |
| D1634B | | DW308 | | EPS2PC1 | | JP012S34B1 | |
| D1700 | | DW312 | | EPS2PC2 | | JP022000 | |
| D1789 | | DW313 | | EPS2PC3 | | JP022S32A | |
| | | | | | | | |
| D3F | | DW316 | | EPS3PC1 | | JP022S32B | |
| D3FB | | DW4 | | EPS3PC2 | | JP022S34B | |
| D3FBAU | | DW41 | | EPS3PC3 | | JP032000 | |
| D3FD | | DW43 | | EPS3SL1 | | JP032S32A | |
| D3FDB | 9 | DW44 | 310 | EPS4PC1 | 291 | JP032S32B | 207 |
| D3M | 9 | DW45 | 310 | EPS4PC2 | 291 | JP032S34B | 207 |
| D3MB | 9 | DW47 | 310 | EPS4PC3 | 291 | JP042000 | 207 |
| D3MBAU | 9 | DW48 | 310 | F3FRAF | 23 | JP042S32A | 207 |
| D4F | 9 | DW7 | 311 | F3FSTF | 23 | JP042S32B | 207 |
| D4FB | | E*F | | F3MRAF | | JP042S34B | |
| D4FBAU | | E*M | | F3SM3F | | JP052000 | |
| D4M | | E111L | | FA11 | | JP052S32A | |
| D4MB | | E112BL | | FAL11 | | JP052S32B | |
| D4MBAU | | | | | | | |
| | | E591 | | G3MS | | JP052S34B | |
| D5F | | E592 | | G4MS | | JP062000 | |
| D5FB | | E594 | | G6083 | | JP062S32A | |
| D5FBAU | | E595 | | G6084 | | JP062S32B | |
| D5M | | E596 | | H101 | | JP062S34B | |
| D5MB | 9 | E598 | | H101PC | | JP072000 | |
| D5MBAU | 9 | E903 | 276 | H102 | 275 | JP072S32A | 207 |
| D6F | 9 | E903D | 276 | H102PC | 275 | JP072S32B | 207 |
| D6FB | 9 | E913 | 276 | H103 | 275 | JP072S34B | 207 |
| D6FBAU | | E913D | | H103D | | JP082000 | |
| D6FDB | | EAC225 | | H103PC | | JP082S32A | |
| D6M | | EAC227 | | H201 | | JP082S32B | |
| D6MB | | EAC233 | | H201PC | | JP082S34B | |
| | | | | | | | |
| D6MBAU | | EAC233S | | H202 | | JP092000 | |
| D7F | | EAC305 | | H202PC | | JP092S32A | |
| D7FB | | EAC309 | | H203 | | JP092S32B | |
| D7FBAU | | EAC311 | | H203D | | JP092S34B | |
| D7M | | EAC315 | 70 | H203PC | | JP102000 | 207 |
| D7MB | 9 | EAC319 | 70 | H3MS | 26 | JP102S32A | |
| D7MBAU | 9 | EAC323 | 70 | H4MS | 26 | JP102S32B | 207 |
| DA013 | 275 | EAC325 | 70 | HP75BNC1 | 66 | JP102S34B | 207 |
| DA023 | 275 | EAC327 | 70 | HP75BNC10 | 66 | JP112000 | 207 |
| DA033 | 275 | EAC333 | 70 | HP75BNC12 | 66 | JP112S32A | 207 |
| DA043 | | EAC333S | | HP75BNC2 | | JP112S32B | |
| DA053 | | EAC405 | | HP75BNC6 | | JP112S34B | |
| DA083 | | EAC409 | | HP75BNC7 | | JP122000 | |
| DMD*FRA*** | | EAC411 | | HP75BNC9 | | JP122S32A | |
| DS301 | | EAC413 | | | | | |
| | | | | HPCC4F | | JP122S32B | |
| DS302 | | EAC451 | | HPCC4FRA | | JP122S34B | |
| DS303 | | EAC453 | | HPCI4F | | JP312000 | |
| DS306 | | EAC455 | | HPCP*4 | | JP322000 | |
| DS307 | | EAC457 | | HPCPK112F | | JP9902 | |
| DS308 | 236 | ED903 | | HPCPK112F1 | | JP9922 | |
| DS311 | | ED903D | 276 | HPCPK1B | 190 | JP9942 | |
| DS312 | | ED913 | 276 | HPCPK324F | 190 | JPD312000 | 210 |
| DS313 | 237 | ED913D | 276 | HPCPK324F1 | 190 | JPD322000 | 210 |
| DS316 | | EH13942 | 16 | HPCPK3B | | K131 | |
| DS317 | 236 | EHBNC2 | 16 | IBS10B02106AR | 314 | K255 | 5 |
| DS318 | | EHBNCSC | | IBS10B04106AR | | K3FS | |
| DS321 | | EHCAT62 | | IBS10B06106AR | | K459 | |
| DS322 | | EHRCA2 | | IBS10B08106AR | | K460 | |
| DS323 | | EHRCABNC | | IBS10B10106AR | | K4FS | |
| | | | | | | | |
| DS350 | | EHUSB2 | | IBS10B12106AR | | L11 | |
| DS351 | | EN3C** | | IBS15B02106AR | | L112A | |
| DS352 | | EN3CR | | IBS15B04106AR | | L112APC | |
| DS353 | | EN3CRAUTO | | IBS15B06106AR | | L112B | |
| DUSB | 56 | EN3I** | 45 | IBS15B08106AR | 314 | L113B | 98 |
| DW05 | 311 | EN3INS16 | 42 | IBS15B10106AR | 314 | L114B | |
| DW1 | 311 | EN3INS20 | 42 | IBS15B12106AR | 314 | L114BPC | 98 |
| DW101 | | EN3P** | | IBS20B02106AR | | L12A | |
| DW102 | | EN3POS16 | | IBS20B04106AR | | L12B | |
| DW201 | | EN3POS20 | | IBS20B06106AR | | L3MN | |
| DW202 | | EP903 | | IBS20B08106AR | | L4MN | |
| DW205 | | EP903D | | IBS20B10106AR | | L5MN | |
| Dv v Z O O | | Li 300D | 210 | 10020D 10100AIX | 14 | LOIVII V | 00 |
| | | | | | | | |

| L712A | 134 | MT344B | 83 | NL113B | 98 | PJRAS1X3S01 | 126 |
|----------------------------|----------------|--|-----------------|---|--------------------------|--|------------------------|
| L712RA | | MT346 | | NL114B | | PJRAS1X3S02 | |
| L722A | 134 | MT346A | 84 | NL114BPC | 98 | PJRAS1X3U01 | 126 |
| L722RA | | MT346B | | NL114BPCS | | PJRAS2X1S01 | |
| LUS001 | | MT346C | | P2290 | | PJRAS2X1S02 | |
| LUS001PC | | MT352A | | P2315 | | PJRAS2X1302 | |
| | | | | | | | |
| LUS001ST | | MT354B | | P2316 | | PJRAS3X1S01 | |
| M111 | | MT355 | | P23491 | | PJRAS3X1S02 | |
| M112A | 97 | MT356C | | P234913 | 271 | PJRAS3X2S01 | 126 |
| M112APC | 97 | MT357 | 83 | P23492 | 271 | PJRAS3X2S02 | 126 |
| M112B | 97 | MT388 | 85 | P23493 | 271 | PJRAS4X2U01 | 126 |
| M112BPC | 97 | MT389 | 85 | P23494 | 271 | PL102 | 278 |
| M113B | | MT48FN | | P23495 | | PL103205 | |
| M113E | | MT48HN | | P23497 | | PL103705 | |
| M113PPC1M | | MT48K1FN | | P23498 | | PL106205 | |
| M114B | | MT48K1HN | | | | PL106705 | |
| | | | | P2456 | | | |
| M114BPC | | MT48K1NN | | P286301 | | PL111 | |
| M114BPC1M | | MT48K1NS | | P286302 | | PL112205 | |
| M3M | | MT48K3FN | 182 | P286304 | 91 | PL112705 | |
| M4M | 30 | MT48K3HN | 182 | P286305 | 91 | PL123705 | 277 |
| M5M | 30 | MT48K3NN | 182 | P286307 | 91 | PL126205 | 277 |
| MBPK175T | | MT48NN | | P286308 | | PL126705 | |
| MD10 | | MT48NS | | P286401 | | PL202 | |
| | | MT52FN | | | | PL202 PL203205 | |
| MD15 | | | | P286402 | | | |
| MD3 | | MT52HN | | P286404 | | PL203705 | |
| MD6 | | MT52K1FN | | P286405 | | PL206205 | |
| MDPC2A | 121 | MT52K1HN | 182 | P286407 | 91 | PL206705 | 277 |
| MDPC2AR | 121 | MT52K1NN | 182 | P286408 | 91 | PL211 | 278 |
| MDPC2ARA | | MT52K1NS | | P2912 | 297 | PL212205 | |
| MDSL2A | | MT52K3FN | | P2936 | | PL212705 | |
| MDSL2ARA | | MT52K3HN | | P2937 | | PL226205 | |
| | | | | | | | |
| MDSMT2ARATR | | MT52K3NN | | P2938 | -, - | PL226705 | |
| MDSMT2BRATR | | MT52NN | | P2939 | , | PL303 | |
| MDSMT3BRATR | 120 | MT52NS | 184 | P2940 | 270, 314 | PL305 | 278 |
| MDSMT4BRATR | 120 | MTP24K7 | 174 | P2941 | 270, 314 | PL308 | 278 |
| ML112B | 97 | MTP48K1NO | 166 | P2942 | 270, 314 | PL403205 | 277 |
| MN111 | | MTP48K1NS | | P2943 | | PL403705 | |
| MN112A | | MTP48K3BPNS | | P2951 | , | PL406205 | |
| | | | | | , | | |
| MN112APC | | MTP48K3NO | | P2952 | , | PL406705 | |
| MN112B | | MTP48K3NS | | P2953 | | PL412205 | |
| MN112BPC | | MTP48K3PBNO | | P2954 | | PL412705 | |
| MN113B | 97 | MTP48K3SNO | 166 | P2955 | 270, 314 | PL501 | 278 |
| MN113BPC | 97 | MTP52K3BPNO | 174 | P2956 | 270, 314 | PL503 | 278 |
| MN113E | | MTPFA48K1NO | 164 | P2957 | | PL503205 | |
| MN114B | | MTPFA48K1NS | | P2958 | | PL504 | |
| MN114BPC | | MTPH48K1NO | | P2979 | | PL505 | |
| MN122A | | MTPH48K1NS | | P2992 | | PL506205 | |
| | | | | | | | |
| MNL112B | | MTPH48K3NO | | P3F | | PL506705 | |
| MNL113B | | MTPH48K3NS | | P3M | | PL508 | |
| MT331 | 83 | MTPH48K3SNO | 171 | P4F | 8 | PL512 | 278 |
| MT332 | 83 | MVJ*75T | 137 | P4M | 8 | PL512205 | 277 |
| MT332A | | MVJ*NT | | P5F | | PL512705 | |
| MT332B | | MVP32K1*75T | | P5M | | PL513 | |
| MT332C | | MVP32K1*NT | | PC12A | | PL703705 | |
| MT333 | | MVP32K3*75T | | PC12A | | PL706205 | |
| | | | | | | | |
| MT333A | | MVP32K3*NT | | PC712A | | PL706705 | |
| MT333B | | N111 | | PC722A | | PL712205 | |
| MT333E | 83 | N111PC | 98 | PC732A | 134 | PL712705 | 277 |
| MT334A | 83 | N111PCS | 100 | PCL712A | 134 | PL803205 | 277 |
| MT334B | 83 | N112A | 98 | PCL722A | 134 | PL803705 | 277 |
| MT334C | 83 | N112APC | | PD3F*** | | PL806205 | |
| MT334E | | N112APCS | | PD3M*** | | PL806705 | |
| | | N112B | | | | PL812205 | |
| MT334F | | | | PJRAN1X1U01 | | | |
| MT335 | | N112BPC | | PJRAN1X1U02 | | PL812705 | |
| MT335A | | N112BPCS | | PJRAN1X1U03 | | PL9105 | |
| | 83 | N113 | | PJRAN1X1U04 | | PL9205 | |
| MT336 | | N113B | 98 | PJRAN2X1U01 | 126 | PPT | |
| MT336 MT336A | | | | PJRAN2X1U02 | | PQG3F*** | |
| MT336A | 83 | N113BPC | 98 | | | | |
| MT336A MT336B | 83 83 | N113BPC N113BPCS | | | | | |
| MT336A MT336B MT336C | 83 83 83 | N113BPCS | 100 | PJRAN3X1U01 | 126 | PQG3M*** | 18 |
| MT336A | 83 83 83 | N113BPCS N114B | 100 98 | PJRAN3X1U01 PJRAN3X1U02 | 126 126 | PQG3M*** PT1LA | 18 163 |
| MT336A | | N113BPCS N114B N114BPC | 100 98 98 | PJRAN3X1U01 PJRAN3X1U02 PJRAS1X1S01 | 126 126 126 | PQG3M*** PT1LA PT2B | 18 163 163 |
| MT336A | | N113BPCS N114B N114BPC N114BPCS | 98 98 98 | PJRAN3X1U01 PJRAN3X1U02 PJRAS1X1S01 PJRAS1X1S02 | 126 126 126 126 | PQG3M*** PT1LA PT2B QG3F | 18 163 163 25 |
| MT336A | | N113BPCS N114B N114BPC N114BPCS N3MS | | PJRAN3X1U01 PJRAN3X1U02 PJRAS1X1S01 PJRAS1X1S02 PJRAS1X1S03 | | PQG3M*** PT1LA PT2B QG3F QG3FD | 181631632525 |
| MT336A | | N113BPCS N114B N114BPC N114BPCS | | PJRAN3X1U01 PJRAN3X1U02 PJRAS1X1S01 PJRAS1X1S02 | | PQG3M*** PT1LA PT2B QG3F | 181631632525 |
| MT336A | | N113BPCS N114B N114BPC N114BPCS N3MS | | PJRAN3X1U01 PJRAN3X1U02 PJRAS1X1S01 PJRAS1X1S02 PJRAS1X1S03 | | PQG3M*** PT1LA PT2B QG3F QG3FD | |

| QG4FD | 25 | RA760 | 241 | S760K | 162 | SR01 | 5 |
|--------------|-----|------------------------------|-----|------------------|-----|--------|---------|
| QG4M | | RA765 | | S761K | | | 5 |
| QG5F | 25 | RA850 | | S765 | 162 | | 5 |
| QG5FD | | RAPC322 | 78 | S765K | 162 | | 5 |
| QG5M | 25 | RAPC712 | 130 | S766K | 162 | SR05 | 5 |
| QG6F | 25 | RAPC722 | 130 | S830 | 108 | SR06 | 5 |
| QG6FD | 25 | RAPC732 | 130 | SL01 | 61 | SR07 | 5 |
| QG6M | 25 | RAPC732OF | 130 | SL02 | 61 | SR08 | 5 |
| QG7F | | RAPC742 | | SL03 | | | 5 |
| QG7FD | | RAPC742OF | | SL04 | | | 257 |
| QG7M | | RAPC752 | | SL05 | | | 256 |
| QGP322 | | RAPC752S | | SL102F | | ST131 | 257 |
| QGP323 | | RASH712 | 130 | SL102M | | | 257 |
| QGP326 | | RASH722 | | SL103F | | | 257 |
| QGP327 | | RASH732 | | SL103M | | | 247 |
| QGP362 | | RASM712 | | SL104F | | | 247 |
| QGP363 | | RASM722 | | SL104M | | ST305 | 247 |
| QGPK116FB | | RASM732 | | SL105F | | | 247 |
| QGPK116MB | | RASM742TR | | SL105M | | | 246-247 |
| QGPK18M8FB | | RASM752STR | | SL172F | | | 247 |
| QGPK1B | | RASM752TR | | SL173F | | | 247 |
| QGPK332MFB | | RN111PC | | SL173M | | | 247 |
| QGPK3B | | RN112APC | | SL174F | | | 246-247 |
| R3FZ | | RN112BPC | | SL174M | | | 247 |
| R3MZ | | RN113BPC | | SL175F | | | 247 |
| R4FZ | | RN113FPC | | SL175M | | | 247 |
| R4MZ | | RN114BPC | | SL18 | | | 247 |
| R5FZ | | | | SL182F | | | 247 |
| R5MZ | | RS422H48N081 RS422H4N081 | | SL182M | | | 255 |
| | | | | | | | 255 |
| R6FZ | | RS422H4N161 RS422H4N162 | | SL183F SL183M | | | 255 |
| | | | | | | | |
| R7FZ R7MZ | | RS422H4N242 | | SL184F SL184M | | | 250 |
| | | RS422PH4N081 RS422PH4N161 | | SL184W | | | 250 |
| RA200 | | | | | | | 250 |
| RA202 | | RS422PH4N162 | | SL185M | | | 250 |
| RA205 | | RS422PH4N242 | | SL402F | | | 250 |
| RA207 | | RS422PV4N081 | | SL402M | | | 254 |
| RA208 | | RS422PV4N161 | | SL403F | | | 254 |
| RA217 | | RS422PV4N162 | | SL403M | | | 254 |
| RA35 | | RS422PV4N242 | | SL404F | | | 254 |
| RA353 | | RS422PV4N322 | | SL404M | | | 241 |
| RA354 | | RS422V4N081 | | SL405F | | | 241 |
| RA355 | | RS422V4N161 | | SL405M | | | 253 |
| RA356 | | RS422V4N162 | | SL412F | | | 258 |
| RA357 | | RS422V4N242 | | SL413F | | | 245 |
| RA358 | | RS422V4N322 | | SL413M | | | 245 |
| RA359 | | RTT34B01 | | SL414F | | | 258 |
| RA373 | | RTT34B02 | | SL414M | | | 56 |
| RA374 | | RTT34B04 | | SL415F | | | 297 |
| RA375 | | RTT34B05 | | SL415M | | | 297 |
| RA376 | | RTT34B07 | | SMD*FRA*** | | | 297 |
| RA377 | | RTT34B08 | | SN37A11 | | | 9 |
| RA378 | | RTT8701 | | SN37A12A | | | 9 |
| RA379 | | RTT8702 | | SN37A12B | | | 9 |
| RA40 | | RTT8704 | | SN37A14B | | | 9 |
| RA41 | | RTT8705 | | SN49A11 | | | 9 |
| RA49B11 | | RTT8707 | | SN49A12A | | | 9 |
| RA49B12A | | RTT8708 | | SN49A12B | | | 9 |
| RA49B12B | 103 | S11 | 94 | SN49A14B | 103 | | 9 |
| RA49B14B | | S112BPC | | SN49B11 | | | 31 |
| RA49C11 | | S112BPCS | | SN49B12A | | | 31 |
| RA49C12A | 103 | S12A | 94 | SN49B12B | | TA03 | 31 |
| RA49C12B | | S12B | | SN49B14B | 103 | TA04 | 31 |
| RA49C14B | 103 | S13B | 94 | SN49C11 | 103 | TA05 | 31 |
| RA700 | | S230 | | SN49C12A | | | 31 |
| RA70B11 | | S250 | 151 | SN49C12B | 103 | | 31-32 |
| RA70B12A | 103 | S260 | 151 | SN49C14B | 103 | TA3FB | 32 |
| RA70B12B | 103 | S267 | 151 | SN70B11 | 103 | TA3FL | 32 |
| RA70B14B | | S280 | | SN70B12A | | TA3FLB | 32 |
| RA70C11 | | S3F5M | , | SN70B12B | | | 31-32 |
| RA70C12A | | S3FM | | SN70B14B | | | 32 |
| RA70C12B | | S4FM | | SN70C11 | | | 32 |
| RA70C14B | | S580 | | SN70C12A | | | 32 |
| RA710 | | S5F3M | | SN70C12B | | | 32 |
| RA712A | | S5FM | | SN70C14B | | | 32 |
| RA722A | | S760 | | SR00 | | | 32 |
| | | | | | | | |

| TA4MB 32 TT134 265 TT32CDC 87 TT506 TA4ML 32 TT141 265 TT32CFMDC 87 TT507 TA5FL 32 TT141 265 TT32CFMDC 87 TT509 TA5FLB 32 TT142 265 TT33B 87 TT509 TA5ML 32 TT144 265 TT33BC 87 TT510 TA5ML 32 TT145 265 TT33BFM 87 TT5102000 TA5MLB 32 TT145 265 TT33BFMDC 87 TT5102201 TA6FL 32 TT147 265 TT33BFMDC 87 TT5102231 TA6FL 32 TT147 265 TT33FMDC 87 TT5102232A TA7FL 32 TT148 265 TT33FMDC 87 TT5102232B TA7FL 32 TT149 265 TT34A 87 TT5102232B TA7FL 32 TT150 265 | 212 212 212 212 212 212 215, 218 230, 234 217 217 217 217 217 217 217 217 217 217 |
|---|---|
| TA4ML 32 TT135 265 TT32CFM 87 TT507 TA5F 32 TT141 265 TT32CFMDC 87 TT508 TA5FL 32 TT142 265 TT33B 87 TT508 TA5FLB 32 TT144 265 TT33BDC 87 TT51 TA5M 32 TT144 265 TT33BDC 87 TT510 TA5M 32 TT145 265 TT33BFMDC 87 TT5102000 TA5MLB 32 TT146 265 TT33BFMDC 87 TT5102S31 TA6FL 32 TT147 265 TT33PMDC 87 TT5102S32B TA7HL 32 TT148 265 TT33FMDC 87 TT5102S32B TA7HL 32 TT149 265 TT34PMDC 87 TT5102S32B TA7L 32 TT150 265 TT34PMDC 87 TT5102S33B TA7L 32 TT150 265 | 212 212 212 212 215, 218 230, 234 217 217 217 217 217 217 217 217 217 217 |
| TA5F. 32 TT141 265 TT32CFMDC 87 TT508 TA5FL. 32 TT142 265 TT33 87 TT509 TA5FL. 32 TT143 265 TT33B. 87 TT51 TA5M. 32 TT144 265 TT33BFM. 87 TT510. TA5ML. 32 TT145 265 TT33BFMDC. 87 TT5102000 TA5ML. 32 TT146 265 TT33BFMDC. 87 TT5102S32A TA6RL. 32 TT147 265 TT33DC. 87 TT5102S32A TA6RL. 32 TT148 265 TT33PM. 87 TT5102S32A TA7FL. 32 TT149 265 TT33PM. 87 TT5102S33B TA7RL. 32 TT149 265 TT33PM. 87 TT5102S33B TA7RL. 32 TT149 265 TT34A. 87 TT5102S33B TA7ML. 32 TT151 | 212 215, 218 230, 234 217 217 217 217 217 217 217 217 217 217 |
| TA5FL 32 TT142 265 TT33 87 TT509 TA5FLB 32 TT143 265 TT33BC 87 TT510 TA5ML 32 TT144 265 TT33BCM 87 TT510 TA5MLB 32 TT145 265 TT33BFMDC 87 TT5102000 TA5MLB 32 TT146 265 TT33BFMDC 87 TT5102000 TA6FL 32 TT147 265 TT33BFMDC 87 TT5102S32A TA6FL 32 TT148 265 TT33FMDC 87 TT5102S32A TA7FL 32 TT149 265 TT33FMDC 87 TT5102S33B TA7FL 32 TT150 265 TT34AA 87 TT5102S32B TA7L 32 TT150 265 TT34AA 87 TT5102S32B TA7L 32 TT151 265 TT34AA 87 TT5102W32B TA8FL 32 TT151 265 | 212 215, 218 230, 234 217 217 217 217 217 217 217 217 217 217 |
| TA5FLB 32 TT143 265 TT33B. 87 TT51 TA5M 32 TT144 265 TT33BDC 87 TT510. TA5ML 32 TT145 265 TT33BFM. 87 TT5102000 TA5MLB 32 TT146 265 TT33BFMDC 87 TT5102031 TA6FL 32 TT147 265 TT33DC 87 TT5102S32A TA6FL 32 TT148 265 TT33FMDC 87 TT5102S32B TA7FL 32 TT149 265 TT33FMDC 87 TT5102S32B TA7ML 32 TT149 265 TT33FMDC 87 TT5102S32B TA7ML 32 TT150 265 TT34ADC 87 TT5102S33B TA8HL 32 TT151 265 TT34ADC 87 TT5102W32A TA8D 32 TT151 265 TT34DC 87 TT5102W32A TA92 142 TT153 < | 215, 218 230, 234 217 217 217 217 217 217 217 217 217 217 |
| TA5M 32 TT144 265 TT33BDC 87 TT510 TA5ML 32 TT145 265 TT33BFMD 87 TT5102000 TA5MLB. 32 TT146 265 TT33BFMDC 87 TT5102S32A TA6FL 32 TT147 265 TT33DC 87 TT5102S32A TA6ML 32 TT148 265 TT33FMD 87 TT5102S32B TA7FL 32 TT149 265 TT33FMDC 87 TT5102S33B TA7ML 32 TT150 265 TT34A 87 TT5102S34B TA8FL 32 TT151 265 TT34AP 87 TT5102W313 TA8RL 32 TT152 265 TT34APM 87 TT5102W313 TAD2 142 T153 265 TT34APM 87 TT5102W328 TAD3 142 TT153 265 TT34BPM 87 TT5102W328 TB3M 33 TT161 | 230, 234 217 217 217 217 217 217 217 217 217 217 |
| TA5ML 32 TT145 265 TT33BFM 87 TT5102000 TA5MLB 32 TT146 265 TT33BFMDC 87 TT5102S31A TA6FL 32 TT147 265 TT33DC 87 TT5102S32A TA6ML 32 TT148 265 TT33FM 87 TT5102S32B TA7FL 32 TT149 265 TT33FMDC 87 TT5102S33B TA7ML 32 TT150 265 TT34A 87 TT5102S34B TA8FL 32 TT151 265 TT34APM 87 TT5102W32A TA8ML 32 TT152 265 TT34AFMDC 87 TT5102W32A TAD2 142 TT153 265 TT34FMDC 87 TT5102W32A TAD3 142 TT153 265 TT34FMDC 87 TT5102W32B TB3M 33 TT154 265 TT34BFMDC 87 TT5102W32B TB3M 33 TT161 <td>217 217 217 217 217 217 217 217 217 217</td> | 217 217 217 217 217 217 217 217 217 217 |
| TA5MLB. 32 TT146 265 TT33BFMDC 87 TT5102S31 TA6FL 32 TT147 265 TT33DC 87 TT5102S32A TA6ML 32 TT148 265 TT33FMDC 87 TT5102S32B TA7FL 32 TT149 265 TT33FMDC 87 TT5102S33B TA7ML 32 TT150 265 TT34A 87 TT5102S34B TA8FL 32 TT151 265 TT34ADC 87 TT5102S34B TA8RL 32 TT151 265 TT34APC 87 TT5102W32B TAD2 142 T153 265 TT34AFM 87 TT5102W32B TAD3 142 TT154 265 TT34B 87 TT5102W32B TB3M 33 TT151 265 TT34B 87 TT5102W32B TB3MB 33 TT161 265 TT34BDC 87 TT5102W33B TB3MB 33 TT161 | 217 217 217 217 217 217 217 217 217 217 |
| TA6FL 32 TT147 265 TT33DC 87 TT5102S32A TA6ML 32 TT148 265 TT33FM 87 TT5102S32B TA7FL 32 TT149 265 TT33FMDC 87 TT5102S33B TA7ML 32 TT150 265 TT34A 87 TT5102S33B TA8FL 32 TT151 265 TT34ADC 87 TT5102W31 TA8ML 32 TT151 265 TT34APM 87 TT5102W32A TAD2 142 TT153 265 TT34AFMDC 87 TT5102W32B TB3M 33 TT155 265 TT34BDC 87 TT5102W32B TB3M 33 TT161 265 TT34BDC 87 TT5102W32B TB3M 33 TT161 265 TT34BPMDC 87 TT5102W32B TB4M 33 TT161 265 TT34BPMDC 87 TT5112 TB4MB 33 TT162 | 217 217 217 217 217 217 217 217 217 217 |
| TA6ML 32 TT148 265 TT33FM 87 TT5102S32B TA7FL 32 TT149 265 TT33FMDC 87 TT5102S33B TA7ML 32 TT150 265 TT34A 87 TT5102S34B TA8FL 32 TT151 265 TT34ADC 87 TT5102W31 TA8ML 32 TT152 265 TT34AFMDC 87 TT5102W32A TAD2 142 TT153 265 TT34AFMDC 87 TT5102W32B TAD3 142 TT154 265 TT34B 87 TT5102W32B TB3M 33 TT155 265 TT34BDC 87 TT5102W33B TB3MB 33 TT161 265 TT34BTM 87 TT5102W34B TB4M 33 TT161 265 TT34BTM 87 TT5102W34B TB4M 33 TT162 265 TT34BTM 87 TT5121 TB4M 33 TT162 < | 217 217 217 217 217 217 217 217 217 217 |
| TA7FL 32 TT149 265 TT33FMDC 87 TT5102S33B TA7ML 32 TT150 265 TT34A 87 TT5102S34B TA8FL 32 TT151 265 TT34ADC 87 TT5102W31 TA8ML 32 TT152 265 TT34AFM 87 TT5102W32A TAD2 142 TT153 265 TT34AFMDC 87 TT5102W32B TAD3 142 TT154 265 TT34BDC 87 TT5102W32B TB3M 33 TT155 265 TT34BDC 87 TT5102W33B TB3MB 33 TT161 265 TT34BDC 87 TT5102W33B TB3MB 33 TT162 265 TT34BFM 87 TT5102W34B TB4M 33 TT162 265 TT34BFMDC 87 TT5121 TB5M 33 TT162 265 TT34C 87 TT5121 TB5M 33 TT162 | 217 217 217 217 217 217 217 217 217 217 |
| TA7ML 32 TT150 265 TT34A 87 TT5102S34B TA8FL 32 TT151 265 TT34ADC 87 TT5102W31 TABML 32 TT152 265 TT34AFMD 87 TT5102W32A TAD2 142 TT153 265 TT34AFMDC 87 TT5102W32B TAD3 142 TT154 265 TT34BDC 87 TT5102W33B TB3M 33 TT155 265 TT34BDC 87 TT5102W34B TB3MB 33 TT161 265 TT34BDC 87 TT5102W34B TB4M 33 TT161 265 TT34BDC 87 TT5102W34B TB4M 33 TT161 265 TT34BDC 87 TT5102W34B TB4M 33 TT162 265 TT34BDC 87 TT512 TB4MB 33 TT162 265 TT34CDC 87 TT5122 TB5M 33 TT165 26 | 217 217 217 217 217 217 217 217 217 218 218 233 233 233 233 233 233 233 |
| TA8FL 32 TT151 265 TT34ADC 87 TT5102W31 TA8ML 32 TT152 265 TT34AFM 87 TT5102W32A TAD2 142 TT153 265 TT34AFMDC 87 TT5102W32B TAD3 142 TT154 265 TT34BD 87 TT5102W33B TB3M 33 TT155 265 TT34BDC 87 TT5102W34B TB3MB 33 TT161 265 TT34BPM 87 TT5102W34B TB4M 33 TT161 265 TT34BPM 87 TT5102W34B TB4M 33 TT161 265 TT34BPM 87 TT511 TB4MB 33 TT162 265 TT34BPMDC 87 TT5121 TB5M 33 TT163 265 TT34CD 87 TT5122 TB5MB 33 TT165 265 TT34CPM 87 TT5124 TB6M 33 TT166 265 | 217 217 217 217 217 217 217 219 212 233 233 233 233 233 233 233 233 |
| TA8ML 32 TT152 265 TT34AFM 87 TT5102W32A TAD2 142 TT153 265 TT34AFMDC 87 TT5102W32B TAD3 142 TT154 265 TT34B 87 TT5102W33B TB3M 33 TT155 265 TT34BDC 87 TT5102W34B TB3MB 33 TT161 265 TT34BFM 87 TT511 TB4M 33 TT162 265 TT34BFMDC 87 TT512 TB4MB 33 TT163 265 TT34CFMDC 87 TT5121 TB5MB 33 TT163 265 TT34CPM 87 TT5122 TB5MB 33 TT164 265 TT34CPM 87 TT5123 TB6M 33 TT166 265 TT34CPM 87 TT5124 TB7M 33 TT166 265 TT34FMDC 87 TT5125 TB7M 33 TT167 265 < | 217 217 217 217 217 218 219 219 219 233 233 233 233 233 233 233 233 |
| TAD2 142 TT153 265 TT34AFMDC 87 TT5102W32B TAD3 142 TT154 265 TT34B 87 TT5102W33B TB3M 33 TT155 265 TT34BC 87 TT5102W34B TB3MB 33 TT161 265 TT34BFMDC 87 TT511 TB4M 33 TT162 265 TT34BFMDC 87 TT5121 TB4MB 33 TT163 265 TT34C 87 TT5122 TB5M 33 TT164 265 TT34CPMDC 87 TT5123 TB5MB 33 TT166 265 TT34CPMDC 87 TT5124 TB6M 33 TT166 265 TT34CPMDC 87 TT5125 TB7M 33 TT167 265 TT34FDC 87 TT5128 TB8M 33 TT168 265 TT34FDC 87 TT5132 TBA03 37 TT169 265 <td< td=""><td></td></td<> | |
| TAD3. 142 TT154 265 TT34B. .87 TT5102W33B. TB3M. 33 TT155. .265 TT34BDC. .87 TT5102W34B. TB3MB. 33 TT161 .265 TT34BFM. .87 TT511. TB4M. .33 TT162. .265 TT34BFMDC. .87 TT5121. TB4MB. .33 TT163. .265 TT34CDC. .87 TT5122. TB5M. .33 TT164. .265 TT34CPM. .87 TT5123. TB5MB. .33 TT165. .265 TT34CPM. .87 TT5123. TB6M. .33 TT166. .265 TT34CPM. .87 TT5124. TB7M. .33 TT166. .265 TT34CPM. .87 TT5125. TB7M. .33 TT167. .265 TT34FDC. .87 TT5128. TB8M. .33 TT169. .265 TT34FDC. .87 TT5131. TBA03 .37< | |
| TB3M. 33 TT155. 265 TT34BDC. .87 TT5102W34B. TB3MB. 33 TT161. .265 TT34BFM. .87 TT511. TB4M. 33 TT162. .265 TT34BFMDC. .87 TT5121. TB4MB. 33 TT163. .265 TT34CD. .87 TT5122. TB5M. 33 TT164. .265 TT34CPM. .87 TT5123. TB5MB. 33 TT165. .265 TT34CPM. .87 TT5123. TB6M. 33 TT166. .265 TT34CPM. .87 TT5124. TB7M. 33 TT166. .265 TT34CPM. .87 TT5124. TB7M. 33 TT166. .265 TT34FMDC. .87 TT5128. TB8M. 33 TT168. .265 TT34FDC. .87 TT5131. TBA03 37 TT169. .265 TT35DC. .87 TT5132. TBA04 37 | 217 212 233 233 233 233 233 233 233 |
| TB3MB 33 TT161 265 TT34BFM 87 TT511 TB4M 33 TT162 265 TT34BFMDC 87 TT5121 TB4MB 33 TT163 265 TT34C 87 TT5122 TB5M 33 TT164 265 TT34CFM 87 TT5123 TB5MB 33 TT165 265 TT34CFM 87 TT5124 TB6M 33 TT166 265 TT34CFMDC 87 TT5125 TB7M 33 TT167 265 TT34F 87 TT5128 TB8M 33 TT168 265 TT34FDC 87 TT5131 TBA03 37 TT169 265 TT35 87 TT5132 TBA04 37 TT170 265 TT35DC 87 TT5134 TBA05 37 TT171 265 TT36FMDC 87 TT5134 TBA06 37 TT172 265 TT36FMDC | |
| TB4M. 33 TT162 265 TT34BFMDC .87 TT5121 TB4MB 33 TT163 265 TT34C .87 TT5122 TB5M. 33 TT164 265 TT34CPM. .87 TT5123 TB5MB. 33 TT165 265 TT34CFM. .87 TT5124 TB6M. 33 TT166 265 TT34CFMDC .87 TT5125 TB7M. 33 TT167 265 TT34F .87 TT5128 TB8M. 33 TT168 265 TT34FDC .87 TT5131 TBA03 37 TT169 265 TT35 .87 TT5132 TBA04 37 TT170 265 TT35DC .87 TT5133 TBA05 37 TT171 265 TT35FMDC .87 TT5134 TBA06 37 TT172 265 TT36FMDC .87 TT5135 TLP4 33 TT173 265 | |
| TB4MB 33 TT163 265 TT34C .87 TT5122 TB5M 33 TT164 265 TT34CPMC .87 TT5123 TB5MB 33 TT165 265 TT34CFMC .87 TT5124 TB6M 33 TT166 265 TT34CFMDC .87 TT5125 TB7M 33 TT167 265 TT34F .87 TT5128 TB8M 33 TT168 265 TT34FDC .87 TT5131 TBA03 37 TT169 265 TT35 .87 TT5132 TBA04 37 TT170 265 TT35FM .87 TT5133 TBA05 37 TT171 265 TT35FMDC .87 TT5134 TBA06 37 TT172 265 TT36FMDC .87 TT5135 TLP4 33 TT173 265 TT36 .87 TT5138 | 233 233 233 233 |
| TB5M. 33 TT164 265 TT34CDC. .87 TT5123. TB5MB. 33 TT165. .265 TT34CFM. .87 TT5124. TB6M. 33 TT166. .265 TT34CFMDC. .87 TT5125. TB7M. 33 TT167. .265 TT34F .87 TT5128. TB8M. 33 TT169. .265 TT34FDC. .87 TT5131. TBA03. .37 TT169. .265 TT35DC. .87 TT5132. TBA04. .37 TT170. .265 TT35DC. .87 TT5133. TBA05. .37 TT171. .265 TT35FMDC. .87 TT5134. TBA06. .37 TT172. .265 TT35FMDC. .87 TT5135. TLP4. .33 TT173. .265 TT36. .87 TT5138. | |
| TB5MB 33 TT165 265 TT34CFM .87 TT5124 TB6M 33 TT166 .265 TT34CFMDC .87 TT5125 TB7M 33 TT167 .265 TT34F .87 TT5128 TB8M 33 TT168 .265 TT34FDC .87 TT5131 TBA03 .37 TT169 .265 TT35DC .87 TT5132 TBA04 .37 TT170 .265 TT35DC .87 TT5133 TBA05 .37 TT171 .265 TT35FM .87 TT5134 TBA06 .37 TT172 .265 TT35FMDC .87 TT5135 TLP4 .33 TT173 .265 TT36 .87 TT5138 | 233 233 233 |
| TB6M. 33 TT166. 265 TT34CFMDC. .87 TT5125. TB7M. 33 TT167. 265 TT34F. .87 TT5128. TB8M. 33 TT168. 265 TT34FDC. .87 TT5131. TBA03. 37 TT169. .265 TT35DC. .87 TT5132. TBA04. 37 TT170. .265 TT35DC. .87 TT5133. TBA05. 37 TT171. .265 TT35FM. .87 TT5134. TBA06. 37 TT172. .265 TT36FMDC. .87 TT5135. TLP4. 33 TT173. .265 TT36. .87 TT5138. | 233 233 |
| TB7M. 33 TT167. 265 TT34F. 87 TT5128. TB8M. 33 TT168. 265 TT34FDC. 87 TT5131. TBA03 37 TT169. 265 TT35 87 TT5132. TBA04 37 TT170. 265 TT35DC. 87 TT5133. TBA05 37 TT171. 265 TT35FM 87 TT5134. TBA06 37 TT172 265 TT36FMDC 87 TT5135. TLP4 33 TT173 265 TT36 87 TT5138. | 233 |
| TB8M 33 TT168 265 TT34FDC 87 TT5131 TBA03 37 TT169 265 TT35 87 TT5132 TBA04 37 TT170 265 TT35DC 87 TT5133 TBA05 37 TT171 265 TT35FM 87 TT5134 TBA06 37 TT172 265 TT36FMDC 87 TT5135 TLP4 33 TT173 265 TT36 87 TT5138 | |
| TBA03 37 TT169 265 TT35 .87 TT5132 TBA04 37 TT170 265 TT35DC .87 TT5133 TBA05 37 TT171 265 TT35FM .87 TT5134 TBA06 37 TT172 265 TT35FMDC .87 TT5135 TLP4 33 TT173 265 TT36 .87 TT5138 | |
| TBA04 37 TT170 265 TT35DC .87 TT5133 TBA05 37 TT171 265 TT35FM .87 TT5134 TBA06 37 TT172 .265 TT35FMDC .87 TT5135 TLP4 33 TT173 .265 TT36 .87 TT5138 | |
| TBA05 37 TT171 265 TT35FM .87 TT5134 TBA06 37 TT172 265 TT35FMDC .87 TT5135 TLP4 33 TT173 .265 TT36 .87 TT5138 | |
| TBA06 37 TT172 265 TT35FMDC .87 TT5135 TLP4 33 TT173 .265 TT36 .87 TT5138 | |
| TLP4 | |
| | |
| TI DO | |
| | 233 |
| | 233 |
| | 233 |
| | 233 |
| | 233 |
| | 233 |
| | 234 |
| | 234 |
| | 234 |
| | 237 |
| | 237 |
| | 237 |
| | 236 |
| | 218 |
| | 236 |
| | 217 |
| | 217 |
| TT**267 TT254143 TT408230 TT5202W34B | 217 |
| | 236 |
| | 215, 220 |
| | 219 |
| TT104 | 219 |
| TT105 | 219 |
| TT106 | 219 |
| TT107265 TT283265 TT45224230 TT5302W96 | 219 |
| TT108265 TT284265 TT45248230 TT54 | 215, 220 |
| TT109 | 219 |
| TT110 | 219 |
| TT111 | 219 |
| TT112265 TT2W48VCF1223 TT45406230 TT55 | 215, 218 |
| TT113 | 217 |
| TT114 | 217 |
| TT115 | 217 |
| TT121 | 215, 218 |
| | 217 |
| | 217 |
| | 217 |
| | 220 |
| | 215, 220 |
| | 215, 220 |
| | 219 |
| | 219 |
| | 219 |
| | 215, 220 |
| | |
| 1100200 | 219 |

FAX: 773 792-2129

| TRODOWNS | TT6002S89 | 219 | TT91411 | 216 | TTP96K1NN | 180 | W11012 | 231 |
|--|-----------|----------|----------------|-----|---------------|---------|-----------------|-----|
| TRISCOND 219 TISSON | | | | | TTP96K3BPNS | 174 | | |
| TFISTUCIANS | TT61 | 215, 220 | TT92002 | 216 | TTP96K3FN | 180 | W11203 | 231 |
| TRISTON 178005 | TT6102000 | 219 | TT92003 | 216 | TTP96K3HN | 180 | W11203L | 231 |
| TR62 216, 220 TT80208 216 TTPRRKEPNB 174 W11212 231 TTR020589 219 TT80201 216 TTPRRKENN 644 W11212 231 TTR020589 216 TTR0205 216 TTPRRKENN 644 W11212 231 TTR0205 230 TTR | TT6102S89 | 219 | TT92004 | 216 | TTP96K3NN | 180 | W11206 | 231 |
| TREGOZO00 | TT6102W89 | 219 | TT92005 | 216 | TTP96K3NS | 168 | W11206L | 231 |
| TREACOS86 219 TTRE201 216 TTP-ROBKIND 171 W1324 203 203 TTRE201 87 TTRE203 216 TTP-ROBKIND 171 W1324 203 203 TTRE201 87 TTRE203 216 TTP-ROBKIND 171 W1324 203 203 TTRE201 216 TTP-ROBKIND 171 W152401 203 203 TTRE202 87 TTRE203 216 TTP-ROBKIND 171 W152401 203 203 TTRE202 87 TTRE203 216 TTP-ROBKIND 171 W152401 203 203 TTRE203 216 TTP-ROBKIND 171 W152401 203 TTRE203 216 TTRE203 216 TTRE203 217 TTRE203 216 TTRE203 217 TTRE204 217 TTRE | TT62 | 215, 220 | TT92008 | 216 | TTP96K5BPNS | 174 | W11212 | 231 |
| TRESCUNDED TITSQUE | TT6202000 | 219 | TT92011 | 216 | TTPFA96K1NO | 164 | W11212L | 231 |
| TRS21 | TT6202S89 | 219 | TT92201 | 216 | TTPFA96K1NS | 164 | W1332A | 203 |
| TRISQA | TT6202W89 | 219 | TT92202 | 216 | TTPH96K1NO | 171 | W1334B | 203 |
| TRISQA | TT631 | 87 | TT92203 | 216 | TTPH96K1NS | 171 | W1532A301 | 203 |
| Tiss20 | | | | | TTPH96K3NO | 171 | W1532B301 | 203 |
| Trisgo | TT632B | 87 | TT92205 | 216 | TTPH96K3NS | 171 | W1534B | 203 |
| TRS33 | | | | | | | W1534B301 | 203 |
| TRESSB | TT633 | 87 | | | TY3FPC | 37 | | |
| TIESUAL 87 TISSA02 216 TYFFC 37 W253A 226 TISSAC 87 TISSA04 216 TYFFC 37 W253A 226 TISSAC 87 TISSA05 216 TYFFC 37 W253A 226 TISSA 87 TISSA05 216 TYFFC 37 W273A901 226 TISSA 87 TISSA05 216 TYFFC 37 W273A901 226 TISSA 87 TISSA05 216 TYFFC 37 W273A901 226 TISSAC 87 TISSA05 216 TYFFC 8 37 W273A9 226 TISSAC 87 TISSA05 216 TYFFC 8 37 W273A9 226 TISSAC 87 TISSA05 216 TYFFC 8 37 W273A9 226 TISSAC 87 TISSA05 216 TYFFC 8 37 W273A9 226 TISSAC 87 TISSA05 216 TYFFC 8 37 W273A9 226 TISSAC 87 TISSA05 216 TYFFC 8 37 W273A9 226 TISSAC 87 TISSA05 216 TYFFC 8 37 W273A9 226 TITAL 87 TISSA05 216 TYFFC 8 37 W273A9 226 TITAL 87 TISSA05 216 UJAA 99 WAD1634B 212 TITAL 22 24 TISSA05 216 UJAA 99 WAD1634B 212 TITAL 25 TISSA05 216 UJAA 99 WAD1634B 212 TITAL 26 TISSA05 216 UJAA 99 WAD1634B 212 TITAL 27 TISSA05 216 UJAA 99 WAD1634B 212 TITAL 28 | | | | | | | | |
| TIES46 | | | | | | | | |
| TREAD. 87 TT92404 216 TYSFPC 37 W25338 205 87 TT92405 216 TYFEP01 37 W25328 205 17636 87 TT92406 216 TYFEP02 37 W27328301 205 17636 87 TT92406 216 TYFEP02 37 W27328301 205 17636 87 TT92406 216 TYFEP03 37 W27328301 205 17636 87 TT92406 216 TYFEP03 37 W27328301 205 176360CF1 37 W27328301 205 17724 204 TT93006 216 UJA 93 WAD1634B 212 17725 204 TT93006 216 UJA 93 WAD1634B 212 17727 204 TT93006 216 UJA 93 WAD1634B 212 17727 204 TT93006 216 UJA 93 WAD1634B 212 17728 204 TT93006 216 UJA 93 WAD1634B 212 17729 204 TT93006 216 UJA 93 WAD1634B 212 17721 204 TT93006 216 UJA 93 WAD1634B 212 17722 204 TT93006 216 UJA 93 WAD1634B 212 17724 205 TT93006 216 UJA 93 WAD1634B 212 17724 206 TT93006 216 UJA 93 WAD1634B 212 17724 207 WAD164D 216 UJA 93 WAD1634B 212 17724 207 WAD164D 216 UJA 93 WAD1634B 212 17724 207 WAD164D 210 UJA 93 WAD1634B 212 17724 207 WAD164D 210 | | | | | | | | |
| T1636. 87 T192405 216 TYEF01. 37 W27328301 20.6 87 T192411 216 TYEF02. 37 W27328301 20.5 11636. 87 T192411 216 TYEF03. 37 W27328301 20.5 11636. 87 T192411 216 TYEF03. 37 W27328301 20.5 11636. 87 T19301 216 TYEF03. 37 W27328301 20.5 116346MCP1 223 T193003. 216 TYEF06. 37 W2789. 30.5 116346MCP1 223 T193003. 216 TYEF06. 37 W2789. 30.5 116346MCP1 223 T193005. 216 TYEF08. 37 W39M. 2.5 11724. 224 T193006. 216 UUPL. 3.9 WA1634B. 212 11724. 224 T19301 216 UUPL. 3.9 WA1634B. 212 11727. 244 T193031 216 UUPL. 3.9 W1650. 212 11728. 244 T193030. 216 US001. 271 W81796. 212 11729. 244 T193005. 216 US001. 271 W80164B. 212 11729. 244 T193005. 216 US001. 271 W80164B. 212 11724. 254 T193005. 216 US001. 271 W80164B. 212 11724. 254 T193005. 216 US001. 271 W80164B. 212 11744. 254 T193006. 216 US001. 271 W80164 | | | | | | | | |
| TiSSA | | | | | | | | |
| TISSIA | | | | | | | | |
| TIESBOC 87 TTS001 216 TYEF04 37 WZ74B301 205 TTBW48MCNH 223 TTS9002 216 TYEF05 37 WZ799 205 TTBW48MCNH 223 TTS9004 216 TYEF05 37 W3M 25 TTBW48WCNH 223 TTS9005 216 UJ 93 WM634B 212 TTSV 224 TTS9005 216 UJ 93 WM634B 212 TTZ2 264 TTS9005 216 UJ 93 WM634B 212 TTZ2 264 TTS9001 216 UJ 98 93 WF1650 212 TTZ2 264 TTS9001 216 UJ 98 93 WF1650 212 TTZ2 264 TTS9001 216 UJ 98 93 WF1650 212 TTZ2 264 TTS9001 216 UJ 98 93 WF1650 212 TTZ2 264 TTS9001 216 UJ 98 93 WF1650 212 TTZ2 264 TTS9001 216 UJ 98 93 WF1650 212 TTZ2 264 TTS9001 216 US 90 C 211 WS1796 212 TTZ2 27 4 TTS9001 216 US 90 C 211 WS1796 212 TTZ2 28 4 TTS9001 216 US 90 C 211 WS1796 212 TTZ2 28 4 TTS9001 216 US 90 C 211 WS1796 212 TTZ2 28 4 TTS9001 216 US 90 C 211 WS1796 212 TTZ2 28 4 TTS9001 216 US 90 C 216 WS181 TSTS 1 TS 90 WC 90 | | | | | | | | |
| TIEWAMBNCF1 | | | | | | | | |
| TIEWARNCHI 223 TT93004 216 TYEF18 37 W3M 25 TIEWARNCHI 223 TT93004 216 TYEF11 37 W4M 25 TIEWARNCHI 223 TT93008 216 UJ1 99 WA1634B 212 TIT24 264 TT93008 216 UJ2 99 WA1634B 217 TIT24 264 TT93008 216 UJ2 99 WA1634B 217 TIT27 264 TT9301 216 UJ2 99 WB1660 212 TIT27 264 TT93301 216 UJ2 99 WB1660 212 TIT27 264 TT93301 216 UJ2 99 WB1795 212 TIT28 264 TT93303 216 US001 271 WB1786 212 TIT29 264 TT93301 216 US001 271 WB1684B 212 TIT29 264 TT93301 216 US001 271 WB1684B 212 TIT29 264 TT93301 216 US001 271 WB1686 212 TIT41 264 TT93801 216 US001 271 WB1686 212 TIT41 264 TT93801 216 US001 217 WB1684B 217 TIT44 264 TT93601 216 US001 216 US001 217 TIT44 264 TT93601 216 US001 216 US001 217 TIT44 264 TT93601 216 US001 216 US001 217 TIT44 264 TT93602 216 US001 216 US001 217 TIT44 216 US001 216 US0 | | | | | | | | |
| TIEWARKUCFI. 223 TT93005. 216 UJ. 37 W4M. 25 TTTEWARKUCFI. 23 TT93005. 216 UJ. 39 WA1634B. 212 TT722. 264 TT93011. 216 UJ. 39 WA1634B. 212 TT724. 264 TT93011. 216 UJ. 28 99 WA1634B. 212 TT726. 264 TT93011. 216 UJ. 28 99 WA1636B. 212 TT727. 264 TT93302. 216 UJ. 28 99 WB1650. 212 TT728. 264 TT93302. 216 UJ. 29 WB1795. 212 TT729. 264 TT93304. 216 US001PC. 271 WB1796. 212 TT729. 264 TT93304. 216 US001PC. 271 WB1796. 212 TT741. 264 TT93304. 216 US001PC. 271 WB1660. 212 TT741. 264 TT93308. 216 WAPKIHDYST. 199-200 WBD1795. 212 TT741. 264 TT93308. 216 WAPKIHDYST. 199-200 WBD1795. 212 TT741. 264 TT93308. 216 WAPKIHDYST. 199-200 WBD1795. 212 TT741. 264 TT93301. 218 WAPKIHDYST. 199-200 WBD1795. 212 TT741. 264 TT93301. 218 WAPKIHDYST. 199-200 WBD1795. 212 TT744. 264 TT93301. 218 WAPKIHDYST. 199-200 WBD1795. 212 TT744. 264 TT93301. 218 WAPKIHDYST. 199-200 WBD1795. 212 TT744. 264 TT93501. 218 WAPKIHDYST. 199-200 WBD1795. 212 TT744. 264 TT93501. 218 WAPKIHDYST. 199-200 WWM333. 83 TT744. 264 TT93502. 216 WAPKIHDYST. 199-200 WWM3332. 84 TT744. 264 TT93502. 216 WAPKIHDYST. 199-200 WWM3332. 84 TT744. 264 TT93505. 216 WAPKIHDYST. 199-200 WWM3333. 84 TT744. 264 TT95ED. 90 WWM73335. 84 TT744. 264 TT95ED. 90 WWM73335. 84 TT748. 264 TT95ED. 90 WWM73355. 84 TT748. 264 TT95ED. 90 WWM73356. 83 TT866. 264 TT95ED. 90 WWM73356. 83 TT868. 264 TT95ED. 90 WWM73356. 83 TT869. 89 TTD5102000 217 WWM7DYT. 199 WWM3336. 83 TT869. 89 TTD5102000 217 WWM7DYT. 199 WWM3336. 84 TT99100. 216 TTD502000 217 WWM7DYT. 199 WWM3336. 84 TT99100. 216 TTD502000 219 WPP24KINDYT. 199 WWM3336. 84 TT99100. 216 TTD502000 219 WPP24KINDYT. 199 WWM3336. 84 TT99100. 216 TTD502000 21 | | | | | | | | |
| TEMARYCMI | | | | | | | | |
| T1722 | | | | | | | | |
| TT724 | | | | | | | | |
| TT726 | | | | | | | | |
| TT727 | TT724 | 264 | TT93011 | 216 | | | | |
| TT728 | | | | | | | | |
| TT729 | TT727 | 264 | TT93302 | 216 | US001 | 271 | WB1796 | 212 |
| TT741 | TT728 | 264 | TT93303 | 216 | US001PC | 271 | WBD1634B | 212 |
| TT741N0 | TT729 | 264 | TT93304 | 216 | US001ST | 271 | WBD1650 | 212 |
| TT742 | TT741 | 264 | TT93305 | 216 | VAPK1HD*75T | 199-200 | WBD1795 | 212 |
| TT742 | TT741N0 | 264 | TT93308 | 216 | VAPK1HD*NT | 199 | WC1634B | 212 |
| TT742N0 | | | | | | | | |
| TT744 | | | | | | | | |
| TT744N0 | | | | | | | | |
| TT746 | | | | | | | | |
| TT74RN | | | | | | | | |
| TT747 | | | | | | | | |
| TT747N0 | | | | | | | | |
| TT748 264 TT95 90 VJHP'NT 136 WCMT336 83 TT749 264 TT95C 90 VJHP'NT 195 WCMT3368 83 TT861 264 TT95FMDC 90 VJSD'75T 136 WCMT336C 83 TT862 264 TT96EDACNO 178 VJSD'NT 195 WCMT336C 83 TT866 264 TT96EDACNS 178 VJSD'NTX 195 WCMT336E 84 TT866 264 TT96FMDC 90 VMF* 199 WCMT336E 84 TT868 264 TT96FMDC 90 VMF* 266 WD1632B 212 TT869 264 TTD* 267 VWHD'75T 199 WD1789 212 TT89DC 89 TTD5102000 217 VWHD'NT 199 WMT331 83 TT89DC 89 TTD510231 217 VWSD'75T 199 WMT332A 84 TT89FMDC | | | | | | | | |
| TT749 | | | | | | | | |
| TT861 | | | | | | | | |
| TT862 | | | | | | | | |
| TT864 | | | | | | | | |
| TT866 | | | | | | | | |
| TT867 | | | | | | | | |
| TT868 | | | | | | | | |
| TT869 | | | | | | | | |
| TT89 | | | | | | | | |
| TT89DC | | | | | | | | |
| TT89FM | | | | | | | | |
| TTR8PFMDC 89 TTD5202000 217 VP** 266 WMT332C 84 TT91001 216 TTD5202031 217 VPP24K1HD*T5T 193 WMT333 84 TT91002 216 TTD5202W34B 217 VPP24K1HD*NT 193 WMT333B 84 TT91003 216 TTD5302000 219 VPP24K1SD*NT 193 WMT333E 84 TT91004 216 TTD5302S95 219 VPP24K1SD*NT 193 WMT334A 84 TT91005 216 TTD5402000 219 VPP24K3HD*NT 193 WMT334B 83 TT91008 216 TTD5402000 219 VPP24K3HD*NT 193 WMT334C 84 TT91011 216 TTD5402000 219 VPP24K3SD*NT 193 WMT334C 84 TT91201 216 TTD5402096 219 VPP24K3SD*NT 193 WMT334F 84 TT91202 216 TTD5902899 219 VPP26K1HD*NT 193 | | | | | | | | |
| TT91001 216 TTD520231 217 VPP24K1HD*75T 193 WMT333 84 TT91002 216 TTD5202W34B 217 VPP24K1HD*NT 193 WMT333B 84 TT91003 216 TTD5302W00 219 VPP24K1SD*NT 193 WMT334B 84 TT91004 216 TTD5302W96 219 VPP24K1SD*NT 193 WMT334B 83 TT91005 216 TTD5302W96 219 VPP24K3HD*NT 193 WMT334B 83 TT91008 216 TTD5402000 219 VPP24K3SD*NT 193 WMT334C 84 TT91011 216 TTD5402S95 219 VPP24K3SD*NT 193 WMT334E 84 TT91201 216 TTD5402S95 219 VPP24K3SD*NT 193 WMT334F 84 TT91202 216 TTD5902W09 219 VPP26K1HD*75T 193 WMT335A 84 TT91204 216 TTD5902W89 219 VPP26K1SD*NT 193 <td></td> <td></td> <td>TTD5102W34B</td> <td>217</td> <td></td> <td></td> <td></td> <td></td> | | | TTD5102W34B | 217 | | | | |
| TT91002 216 TTD5202W34B 217 VPP24K1HD*NT 193 WMT333B 84 TT91003 216 TTD5302000 219 VPP24K1SD*75T 193 WMT333E 84 TT91004 216 TTD5302S95 219 VPP24K1SD*NT 193 WMT334A 84 TT91005 216 TTD5302W96 219 VPP24K3HD*NT 193 WMT334B 83 TT91008 216 TTD5402000 219 VPP24K3HD*NT 193 WMT334C 84 TT91011 216 TTD5402S95 219 VPP24K3SD*NT 193 WMT334C 84 TT91201 216 TTD5402W96 219 VPP24K3SD*NT 193 WMT334F 84 TT91202 216 TTD5902W96 219 VPP26K1HD*NT 193 WMT335A 84 TT91203 216 TTD5902S89 219 VPP26K1BD*NT 193 WMT336A 84 TT91205 216 TTD60022W99 219 VPP26K1SD*NT 193 </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> | | | | | | | | |
| TT91003 216 TTD5302000 219 VPP24K1SD*75T 193 WMT333E 84 TT91004 216 TTD5302S95 219 VPP24K1SD*NT 193 WMT334A 84 TT91005 216 TTD5302W96 219 VPP24K3HD*NT 193 WMT334B 83 TT91008 216 TTD5402000 219 VPP24K3HD*NT 193 WMT334C 84 TT91011 216 TTD5402S95 219 VPP24K3SD*75T 193 WMT334E 84 TT91201 216 TTD5402W96 219 VPP24K3SD*NT 193 WMT334F 84 TT91202 216 TTD5902W96 219 VPP26K1HD*75T 193 WMT335 84 TT91203 216 TTD5902X89 219 VPP26K1HD*NT 193 WMT335A 84 TT91204 216 TTD5902W89 219 VPP26K1SD*75T 193 WMT336A 83 TT91205 216 TTD6002W89 219 VPP26K1SD*NT 193 </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> | | | | | | | | |
| TT91004 216 TTD5302S95 219 VPP24K1SD*NT 193 WMT334A 84 TT91005 216 TTD5302W96 219 VPP24K3HD*75T 193 WMT334B 83 TT91008 216 TTD5402000 219 VPP24K3HD*NT 193 WMT334C 84 TT91011 216 TTD5402S95 219 VPP24K3SD*NT 193 WMT334E 84 TT91201 216 TTD5402W96 219 VPP24K3SD*NT 193 WMT334F 84 TT91202 216 TTD5902W96 219 VPP26K1HD*75T 193 WMT3355 84 TT91203 216 TTD5902W89 219 VPP26K1HD*NT 193 WMT335A 84 TT91204 216 TTD5902W89 219 VPP26K1SD*75T 193 WMT336A 83 TT91205 216 TTD6002000 219 VPP26K1SD*NT 193 WMT336A 83 TT91208 216 TTD6002W89 219 VPP26K3SD*NT 193 </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> | | | | | | | | |
| TT91005 216 TTD5302W96 219 VPP24K3HD*75T 193 WMT334B 83 TT91008 216 TTD5402000 219 VPP24K3HD*NT 193 WMT334C 84 TT91011 216 TTD5402S95 219 VPP24K3SD*NT 193 WMT334E 84 TT91201 216 TTD5402W96 219 VPP24K3SD*NT 193 WMT334F 84 TT91202 216 TTD5902W96 219 VPP26K1HD*75T 193 WMT335 84 TT91203 216 TTD5902S89 219 VPP26K1HD*NT 193 WMT335A 84 TT91204 216 TTD5902W89 219 VPP26K1SD*75T 193 WMT336A 83 TT91205 216 TTD6002000 219 VPP26K1SD*NT 193 WMT336A 83 TT91208 216 TTD6002S89 219 VPP26K3SD*NT 193 WMT336B 84 TT91401 216 TTEZN**** 177 VPP26K3SD*75T 193 <td>TT91003</td> <td>216</td> <td>TTD5302000</td> <td>219</td> <td>VPP24K1SD*75T</td> <td>193</td> <td></td> <td></td> | TT91003 | 216 | TTD5302000 | 219 | VPP24K1SD*75T | 193 | | |
| TT91008 216 TTD5402000 219 VPP24K3HD*NT 193 WMT334C 84 TT91011 216 TTD5402S95 219 VPP24K3SD*75T 193 WMT334E 84 TT91201 216 TTD5402W96 219 VPP24K3SD*NT 193 WMT334F 84 TT91202 216 TTD5902W00 219 VPP26K1HD*75T 193 WMT335A 84 TT91203 216 TTD5902W89 219 VPP26K1HD*NT 193 WMT335A 84 TT91204 216 TTD5902W89 219 VPP26K1SD*75T 193 WMT336 83 TT91205 216 TTD6002000 219 VPP26K1SD*NT 193 WMT336A 83 TT91208 216 TTD6002S89 219 VPP26K3SD*NT 193 WMT336B 84 TT91211 216 TTD6002W89 219 VPP26K3SD*NT 193 WMT336C 83 TT91401 216 TTEZN**** 177 VPP26K3SD*NT 193 <td>TT91004</td> <td>216</td> <td>TTD5302S95</td> <td>219</td> <td>VPP24K1SD*NT</td> <td>193</td> <td></td> <td></td> | TT91004 | 216 | TTD5302S95 | 219 | VPP24K1SD*NT | 193 | | |
| TT91011 216 TTD5402S95 219 VPP24K3SD*75T 193 WMT334E 84 TT91201 216 TTD5402W96 219 VPP24K3SD*NT 193 WMT334F 84 TT91202 216 TTD5902000 219 VPP26K1HD*75T 193 WMT335 84 TT91203 216 TTD5902S89 219 VPP26K1HD*NT 193 WMT335A 84 TT91204 216 TTD5902W89 219 VPP26K1SD*NT 193 WMT336A 83 TT91205 216 TTD6002000 219 VPP26K1SD*NT 193 WMT336A 83 TT91208 216 TTD6002S89 219 VPP26K1SD*NT 193 WMT336B 84 TT91211 216 TTD6002W89 219 VPP26K3HD*NT 193 WMT336C 83 TT91401 216 TTEZN**** 177 VPP26K3SD*NT 193 WMT336C 83 TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 | TT91005 | 216 | TTD5302W96 | 219 | VPP24K3HD*75T | 193 | WMT334B | 83 |
| TT91201 216 TTD5402W96 219 VPP24K3SD*NT 193 WMT334F 84 TT91202 216 TTD5902000 219 VPP26K1HD*75T 193 WMT335 84 TT91203 216 TTD5902X89 219 VPP26K1HD*NT 193 WMT335A 84 TT91204 216 TTD5902W89 219 VPP26K1SD*75T 193 WMT336A 83 TT91205 216 TTD6002000 219 VPP26K1SD*NT 193 WMT336A 83 TT91208 216 TTD6002S89 219 VPP26K3BD*NT 193 WMT336B 84 TT91211 216 TTD6002W89 219 VPP26K3HD*NT 193 WMT336C 83 TT91401 216 TTEZN**** 177 VPP26K3SD*NT 193 WMT336C 83 TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 WMT336E 84 TT91403 216 TTP96ASNN 186 W11003 231 | TT91008 | 216 | TTD5402000 | 219 | VPP24K3HD*NT | 193 | WMT334C | 84 |
| TT91202 216 TTD5902000 219 VPP26K1HD*75T 193 WMT335 84 TT91203 216 TTD5902S89 219 VPP26K1HD*NT 193 WMT335A 84 TT91204 216 TTD5902W89 219 VPP26K1SD*NT 193 WMT336 83 TT91205 216 TTD6002000 219 VPP26K1SD*NT 193 WMT336A 83 TT91208 216 TTD6002S89 219 VPP26K3HD*75T 193 WMT336B 84 TT91211 216 TTD6002W89 219 VPP26K3HD*NT 193 WMT336C 83 TT91401 216 TTEZN**** 177 VPP26K3SD*NT 193 WMT336D 83 TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 WMT336E 84 TT91403 216 TTP96ASHN 186 W11003 231 WMT342B 83 TT91404 216 TTP96ASNN 186 W11003 231 WMT | TT91011 | 216 | TTD5402S95 | 219 | VPP24K3SD*75T | 193 | WMT334E | 84 |
| TT91203 216 TTD5902S89 219 VPP26K1HD*NT 193 WMT335A 84 TT91204 216 TTD5902W89 219 VPP26K1SD*75T 193 WMT336 83 TT91205 216 TTD6002000 219 VPP26K1SD*NT 193 WMT336A 83 TT91208 216 TTD6002S89 219 VPP26K3HD*75T 193 WMT336B 84 TT91211 216 TTD6002W89 219 VPP26K3HD*NT 193 WMT336C 83 TT91401 216 TTEZN**** 177 VPP26K3SD*75T 193 WMT336D 83 TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 WMT336E 84 TT91403 216 TTP96ASHN 186 W11003 231 WMT342B 83 TT91404 216 TTP96ASNN 186 W11003 231 WMT344B 84 TT91405 216 TTP96K1FN 180 W11006 231 WMT388 85 | | | | | VPP24K3SD*NT | 193 | | |
| TT91203 216 TTD5902S89 219 VPP26K1HD*NT 193 WMT335A 84 TT91204 216 TTD5902W89 219 VPP26K1SD*75T 193 WMT336 83 TT91205 216 TTD6002000 219 VPP26K1SD*NT 193 WMT336A 83 TT91208 216 TTD6002S89 219 VPP26K3HD*75T 193 WMT336B 84 TT91211 216 TTD6002W89 219 VPP26K3HD*NT 193 WMT336C 83 TT91401 216 TTEZN**** 177 VPP26K3SD*75T 193 WMT336D 83 TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 WMT336E 84 TT91403 216 TTP96ASHN 186 W11003 231 WMT342B 83 TT91404 216 TTP96ASNN 186 W11003 231 WMT344B 84 TT91405 216 TTP96K1FN 180 W11006 231 WMT388 85 | | | TTD5902000 | 219 | | | | |
| TT91204 216 TTD5902W89 219 VPP26K1SD*75T 193 WMT336 83 TT91205 216 TTD6002000 219 VPP26K1SD*NT 193 WMT336A 83 TT91208 216 TTD6002S89 219 VPP26K3HD*75T 193 WMT336B 84 TT91211 216 TTD6002W89 219 VPP26K3HD*NT 193 WMT336C 83 TT91401 216 TTEZN**** 177 VPP26K3SD*75T 193 WMT336D 83 TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 WMT336E 84 TT91403 216 TTP96ASHN 186 W11003 231 WMT342B 83 TT91404 216 TTP96ASNN 186 W11003 231 WMT344B 84 TT91405 216 TTP96K1FN 180 W11006 231 WMT388 85 | | | | | | | | |
| TT91205 216 TTD6002000 219 VPP26K1SD*NT 193 WMT336A 83 TT91208 216 TTD6002S89 219 VPP26K3HD*75T 193 WMT336B 84 TT91211 216 TTD6002W89 219 VPP26K3HD*NT 193 WMT336C 83 TT91401 216 TTEZN**** 177 VPP26K3SD*75T 193 WMT336D 83 TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 WMT336E 84 TT91403 216 TTP96ASHN 186 W11003 231 WMT342B 83 TT91404 216 TTP96ASNN 186 W11003 231 WMT344B 84 TT91405 216 TTP96K1FN 180 W11006 231 WMT388 85 | | | | | | | | |
| TT91208 216 TTD6002S89 219 VPP26K3HD*75T 193 WMT336B 84 TT91211 216 TTD6002W89 219 VPP26K3HD*NT 193 WMT336C 83 TT91401 216 TTEZN**** 177 VPP26K3SD*75T 193 WMT336D 83 TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 WMT336E 84 TT91403 216 TTP96ASHN 186 W11003 231 WMT342B 83 TT91404 216 TTP96ASNN 186 W11003 231 WMT344B 84 TT91405 216 TTP96K1FN 180 W11006 231 WMT388 85 | | | | | | | | |
| TT91211 216 TTD6002W89 219 VPP26K3HD*NT 193 WMT336C 83 TT91401 216 TTEZN*** 177 VPP26K3SD*75T 193 WMT336D 83 TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 WMT336E 84 TT91403 216 TTP96ASHN 186 W11003 231 WMT34E 83 TT91404 216 TTP96ASNN 186 W11003 231 WMT344B 84 TT91405 216 TTP96K1FN 180 W11006 231 WMT388 85 | | | | | | | | |
| TT91401 216 TTEZN*** 177 VPP26K3SD*75T 193 WMT336D 83 TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 WMT336E 84 TT91403 216 TTP96ASHN 186 W11003 231 WMT342B 83 TT91404 216 TTP96ASNN 186 W11003L 231 WMT344B 84 TT91405 216 TTP96K1FN 180 W11006 231 WMT388 85 | | | | | | | | |
| TT91402 216 TTP96ASFN 186 VPP26K3SD*NT 193 WMT336E 84 TT91403 216 TTP96ASHN 186 W11003 231 WMT342B 83 TT91404 216 TTP96ASNN 186 W11003L 231 WMT344B 84 TT91405 216 TTP96K1FN 180 W11006 231 WMT388 85 | | | | | | | | |
| TT91403 216 TTP96ASHN 186 W11003 231 WMT342B 83 TT91404 216 TTP96ASNN 186 W11003L 231 WMT344B 84 TT91405 216 TTP96K1FN 180 W11006 231 WMT388 85 | | | | | | | | |
| TT91404 | | | | | | | | |
| TT91405216 TTP96K1FN180 W11006231 WMT388 | | | | | | | | |
| | | | | | | | | |
| 1131400 | | | | | | | | |
| | 1191400 | ∠10 | I I FOOT I TIN | 100 | VV I IUUOL | 231 | V V I V I J O S | రర |

| \A(TT04 |
|--|
| WTT3187 |
| WTT31DC87 |
| WTT31FM87 |
| WTT31FMDC87 |
| WTT32A87 |
| WTT32ADC87 |
| WTT32AFM87 |
| |
| WTT32AFMDC87 |
| WTT32B87 |
| WTT32BDC87 |
| WTT32BFM87 |
| WTT32BFMDC87 |
| WTT32C87 |
| WTT32CDC87 |
| WTT32CFM87 |
| WTT32CFMDC87 |
| WTT3387 |
| |
| WTT33B87 |
| WTT33BDC87 |
| WTT33BFM87 |
| WTT33BFMDC87 |
| WTT33DC87 |
| WTT33FM87 |
| WTT33FMDC87 |
| WTT34A87 |
| WTT34ADC87 |
| WTT34AFM87 |
| |
| WTT34AFMDC87 |
| WTT34B87 |
| WTT34BDC87 |
| WTT34BFM87 |
| WTT34BFMDC87 |
| WTT3587 |
| WTT35DC87 |
| WTT35FM87 |
| WTT35FMDC87 |
| WTT3687 |
| |
| WTT36A87 |
| WTT36ADC87 |
| WTT36AFM87 |
| WTT36AFMDC87 |
| WTT36C87 |
| WTT36CDC87 |
| WTT36CFM87 |
| WTT36CFMDC87 |
| WTT36DC87 |
| WTT36FM87 |
| WTT36FMDC87 |
| |
| |
| WTT63187 |
| WTT63187 WTT632A87 |
| WTT631 |
| WTT631 87 WTT632A 87 WTT632B 87 WTT633 87 WTT633 87 WTT634A 87 WTT634B 87 WTT634C 87 WTT635 87 |
| WTT631 87 WTT632A 87 WTT632B 87 WTT633 87 WTT633B 87 WTT634A 87 WTT634B 87 WTT634C 87 WTT635 87 WTT636 87 |
| WTT631 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633 .87 WTT634A .87 WTT634B .87 WTT634C .87 WTT635 .87 WTT636 .87 WTT636A .87 WTT636C .87 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633 .87 WTT634A .87 WTT634B .87 WTT634C .87 WTT635 .87 WTT636 .87 WTT636A .87 WTT636A .87 WTT636C .87 WTT89 .89 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633 .87 WTT634A .87 WTT634B .87 WTT634C .87 WTT635 .87 WTT636 .87 WTT636A .87 WTT636C .87 WTT89 .89 WTT89DC .89 |
| WTT631 87 WTT632A 87 WTT632B 87 WTT632C 87 WTT633 87 WTT633B 87 WTT634A 87 WTT634B 87 WTT634B 87 WTT634B 87 WTT634B 87 WTT634B 87 WTT636 87 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633 .87 WTT634A .87 WTT634B .87 WTT634C .87 WTT635 .87 WTT636 .87 WTT636A .87 WTT636C .87 WTT89 .89 WTT89DC .89 |
| WTT631 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633 .87 WTT634B .87 WTT634C .87 WTT635 .87 WTT636 .87 WTT636C .87 WTT89 .89 WTT89FM .89 WTT89FMDC .89 WTT89 .90 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633 .87 WTT634B .87 WTT634C .87 WTT635 .87 WTT636 .87 WTT636 .87 WTT636A .87 WTT89 .89 WTT89FMD .89 WTT95D .90 WTT95DC .90 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633 .87 WTT634A .87 WTT634B .87 WTT634C .87 WTT635 .87 WTT636 .87 WTT636 .87 WTT636A .87 WTT89 .89 WTT89FM .89 WTT89FMDC .89 WTT95 .90 WTT95FM .90 WTT95FM .90 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633B .87 WTT634A .87 WTT634B .87 WTT635 .87 WTT636 .87 WTT636 .87 WTT636 .87 WTT636A .87 WTT89 .89 WTT89FM .89 WTT95FMDC .90 WTT95FMDC .90 WTT95FMDC .90 WTT95FMDC .90 |
| WTT631 |
| WTT631 87 WTT632A 87 WTT632B 87 WTT632B 87 WTT633 87 WTT633 87 WTT633B 87 WTT634A 87 WTT634B 87 WTT634C 87 WTT634C 87 WTT636C 87 WTT636C 87 WTT636C 87 WTT89 89 WTT89DC 89 WTT95DC 90 WTT95DC 90 WTT95FMDC 90 |
| WTT631 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633 .87 WTT634B .87 WTT634B .87 WTT635 .87 WTT636 .87 WTT636 .87 WTT636A .87 WTT89 .89 WT189FMDC .89 WT195PMDC .90 WT195FM .90 WT195FM .90 WT196FM .90 WT196FM .90 WT196FMDC .90 WT196FMDC .90 WT196FMDC .90 WT196FMDC .90 WT196FMDC .90 X1332A .203 X1332B .203 |
| WTT631 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633 .87 WTT634B .87 WTT634B .87 WTT635 .87 WTT636 .87 WTT636 .87 WTT636A .87 WTT89 .89 WT189FMDC .89 WT195PMDC .90 WT195FM .90 WT195FM .90 WT196FM .90 WT196FM .90 WT196FMDC .90 WT196FMDC .90 WT196FMDC .90 WT196FMDC .90 WT196FMDC .90 X1332A .203 X1332B .203 |
| WTT631 .87 WTT632A .87 WTT632B .87 WTT632C .87 WTT633 .87 WTT634B .87 WTT634B .87 WTT635 .87 WTT636 .87 WTT636 .87 WTT636A .87 WTT89 .89 WT89FM .89 WT795D .89 WT795D .90 WT795FMDC .90 WT796FMDC .90 WT796FMDC .90 WT796FMDC .90 WT796FMDC .90 WT796FMDC .90 WT732A .203 X1332B .203 X1334B .203 |

| roduct pages on our | WEDSI |
|---------------------|-------|
| X1534B | 203 |
| X1542B315 | 203 |
| X21248 | 317 |
| X2432A | |
| X2432B | 205 |
| X2434B | 205 |
| X2532A | 205 |
| X2532B | 205 |
| X2534B | 205 |
| X2732A | 205 |
| X2732A301 | 205 |
| X2732B | |
| X2732B301 | |
| X2734B | 205 |
| X2734B301 | 205 |
| X2832A | 205 |
| X2932A | |
| X51248 | |
| XMT332A | |
| XMT332B | |
| XMT334B | |
| Y21248 | 317 |
| Y28248 | 317 |
| Y3F | |
| Y3FD | |
| Y3FPC | 22 |
| Y3MPC | 22 |
| Y51248 | |
| YEF01 | |
| YEF02 | |
| YEF03 | 22 |
| YEF04 | |
| YEF05 | |
| YEF08 | |
| YMT332A | |
| YMT332B | |
| YMT334B | |
| Z15J | |
| Z21248 | |
| Z28248 | 317 |
| Z51248 | 317 |

О компании

ООО "ТрейдЭлектроникс" - это оперативные поставки широкого спектра электронных компонентов отечественного и импортного производства напрямую от производителей и с крупнейших мировых складов. Реализуемая нашей компанией продукция насчитывает более полумиллиона наименований.

Благодаря этому наша компания предлагает к поставке практически не ограниченный ассортимент компонентов как оптовыми, мелкооптовыми партиями, так и в розницу.

Наличие собственной эффективной системы логистики обеспечивает надежную поставку продукции по конкурентным ценам в точно указанные сроки.

Срок поставки со стоков в Европе и Америке – от 3 до 14 дней.

Срок поставки из Азии - от 10 дней.

Благодаря развитой сети поставщиков, помогаем в поиске и приобретении экзотичных или снятых с производства компонентов.

Предоставляем спец цены на элементы для создания инженерных сэмплов.

Упорный труд, качественный результат дают нам право быть уверенными в себе и надежными для наших клиентов.

Наша компания это:

- Гарантия качества поставляемой продукции
- Широкий ассортимент
- Минимальные сроки поставок
- Техническая поддержка
- Подбор комплектации
- Индивидуальный подход
- Гибкое ценообразование

Наша организация особенно сильна в поставках модулей, микросхем, пассивных компонентов, ксайленсах (XC), EPF, EPM и силовой электроники.

Большой выбор предлагаемой продукции, различные виды оплаты и доставки, позволят Вам сэкономить время и получить максимум выгоды от сотрудничества с нами!



<u>Перечень производителей, продукцию которых мы поставляем</u> на российский рынок











































































































































гарантия бесперебойности производства и качества выпускаемой продукции

С удовольствием будем прорабатывать для Вас поставки всех необходимых компонентов по текущим запросам для скорейшего выявления групп элементов, по которым сотрудничество именно с нашей компанией будет для Вас максимально выгодным!

С уважением,
Менеджер отдела продаж ООО
«Трейд Электроникс»
Шишлаков Евгений
8 (495)668-30-28 доб 169
manager28@tradeelectronics.ru

http://www.tradeelectronics.ru/